

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: September 20, 2016  
Date of Addendum: September 7, 2016

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
103	47-0202-108	PCC PAVEMENT - GRADE AND NEW	IDA	NHSN-020-2(108)--2R-47 NHSN-020-2(120)--2R-47 NHSN-020-2(142)--2R-47 NHSN-020-2(143)--2R-81 NHSN-020-2(145)--2R-81	20sep103a02

Make the following changes to the PROPOSAL SPECIAL PROVISIONS TEXT:

Replace the existing ‘NON-POINT 25 UTILITY DATA’ with the attached.



**UTILITY BID ATTACHMENT**

County:

**Ida**

Project Classification:

**Non-Point 25**

Project No.:

**NHSN-020-2(113)--2R-81 (ROW)**

**NHSN-020-2(108)--2R-47 (CONST)**

District Utility Coordinator:

**Doug Manley**

**Iowa Department of Transportation**

**District Utility Coordinator**

Highway Route Number or Name:

**US 20**

**2800 Gordon Dr.**

**Sioux City, IA 51102-0987**

Segment or Section:

**W of Adams Ave to W of US 71**

**Utilities:**

**This project also comes under Specifications section 1107.15, that details the contractors responsibilities for utility facilities and services.**

*1107.15 CONTRACTOR'S RESPONSIBILITY FOR UTILITY FACILITY AND SERVICES.*

*A. The Contracting Authority will endeavor to have all necessary adjustments made to public or private utilities within or adjacent to the limits of construction prior to construction activities, except those requiring coordination with the Contractor. Utility facilities have been plotted from available surveys and records, and shall be considered approximate. Other utilities may exist and their location may not be presently known or identified on the plans. The Contractor shall notify Iowa One-Call at 1.800.292.8989 to identify the location of all underground utility facilities within the construction area.*

*B. The Contractor shall determine the exact location of all public and private utility facilities located within the construction area to avoid damage in accordance with Section 480.4, Code of Iowa. The Contractor shall have considered in their bid all permanent and temporary utility appurtenances in their present or adjusted positions as shown in the contract documents.*

*C. Where existing utility facilities are shown in the contract documents or encountered within the construction area, the Contractor shall notify the utility company prior to beginning construction activities. The Contractor shall be responsible for notifying utilities and conducting work near utility facilities, required by Iowa Code 480.4.*

Additional detailed information regarding the location of relocated utility facilities is available on the permits issued to the utility companies. These permits can be viewed at the District office during normal working hours. Contact the **District Utility Coordinator at 712-276-1451.**

A Utility Conflict Matrix for underground utilities is available in the Bid Document efiles. Vast Broadband Conflict Matrix was not generated because the utility was expected to have relocation work completed prior to letting of this project.

Relocation Plans that were available from the utility companies are available in the efiles for this project.

This document represents information provided by the utility companies as of ~~July 18~~ September 2, 2016. **Potential bidders are encouraged to contact the utility companies for any updates that may be available.**

**Facilities- Affected:**

**Magellan Midstream Partners (Gas):**

Relocation work will start or was started in October 2016.

Relocation will require coordination with contractor: Single crossing of US 20 ROW by ammonia pipeline near Sta. 12196. Expected completion in fall or early winter of 2016, weather permitting.

Contact: Caitlyn Moser: 918-574-7266, email: caitlyn.moser@magellanlp.com.

**North West Rural Electric Cooperative (Electric):**

Relocation work will start or was started 9/12/2016.

Relocation will require coordination with contractor: Relocation of overhead electric line along south ROW line and several crossings between the beginning of project and Buchanan Avenue are expected to be completed in early October 2016.

Contact: Derrick Haak: 712-707-4935, email: dhaak@nwrec.coop.

**Raccoon Valley Electric Cooperative (Electric):**

Relocation work will start or was started 7/13/2016.

Relocation will require coordination with contractor: Several overhead line crossings of US 20 between Cory Avenue and end of project have begun and are expected to be completed in early October 2016.

Contact: Mitch McKeever: 712-662-4275, email: mitchm@rvec.coop

**Schaller Telephone Company (Telephone):**

Relocation work will start or was started 6/1/2016.

Relocation will require coordination with contractor: All new fiber placement is completed. Utility is in the process of switching customers from the existing service lines to the new fiber. Work is expected to be completed in October 2016.

Contact: Jim Kestel: 712-275-4211, email: [jmkestel@schallertel.net](mailto:jmkestel@schallertel.net)

**MidAmerican Energy Company (Electric Distribution):**

Relocation work will start or was started 9/12/2016.

Relocation will require coordination with contractor: Relocation will begin after the ROW Parcel 327 is obtained by the Department in September 2016. Relocation is expected to be completed in early October 2016.

Contact: Nick Nation: 515-574-5040, email: [njnation@midamerican.com](mailto:njnation@midamerican.com).

**Corn Belt Power Cooperative (Electric):**

Relocation work will start or was started 7/13/2016.

Relocation has been completed.

Contact Dan Shiflett: 515-890-7562, email: [dan.schiflett@cbpower.coop](mailto:dan.schiflett@cbpower.coop).

**Frontier Communications of Iowa (Telephone):**

Relocation work will start or was started 7/1/2016.

Relocation has been completed.

Contact: Trent Flockhart: 515-573-1268, email: [trent.flockhart@ftr.com](mailto:trent.flockhart@ftr.com)

**MidAmerican Energy - Wind (Electric):**

Relocation work will start or was started 7/20/2016.

Relocation has been completed.

Contact: John Bentz: 515-972-4103, email: [jgbentz@midamerican.com](mailto:jgbentz@midamerican.com).

**MidAmerican Energy Company (Electric Transmission):**

Relocation work will start or was started 7/25/2016.

Relocation has been completed.

Contact: Nate Johnson: 563-333-8648, email: nljohnson@midamerican.com.

**MidAmerican Energy Company (Gas Distribution):**

Relocation work will start or was started 8/30/2016.

Relocation of the US 20 crossing has been completed.

The gas line which parallels US 20 between Adams Avenue and Pioneer Avenue will be UAC. Minimal topsoil stripping (only as necessary for fill areas) should be exercised when working over and around this line.

Contact: Dean Burger; 712-233-4865, email: dmburger@midamerican.com.

**Vast Broadband (Local Fiber Optic):**

Relocation work will start or was started 6/1/2016.

Relocation has been completed.

Utility relocated along county road system north of US 20. No facilities currently operating in this project area.

Contact: Kody Bratzel: 605-951-7516, email: kody.bratzel@vastbroadband.com

**Western Iowa Networks (Telephone):**

Relocation work will start or was started 6/1/2016.

Relocation work has been completed.

Contact Mike Ludwig: 712-673-2311, email: mludwig@westianet.com

-- END --