

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: October 18, 2016
Date of Addendum: September 27, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
101	06-0214-027	PCC OVERLAY - UNBONDED	BENTON	STPN-021-4(27)--2J-06	18OCT101A01

Make the following changes to the PLAN:

On sheet C.1 in Estimate Reference Information add the note below to all 3 of the following bid items:

2102-2713070 Excavation, Class 13 Roadway and Borrow
2301-1003005 Standard or Slip-Form Portland Cement Concrete Pavement, QM-C, Class 3
durability, 9.5 in.
2310-5151620 Portland Cement Concrete Pavement, QM-C, Placement Only (Unbonded)

Estimate Reference Note to be added:

The Contractor will be allowed the option to construct at 2% cross slope, the outer most 4 feet of proposed PCC paved shoulders that are shown on typical sections PCC-1 sheet B.1 and 7308B sheet B.2.

This option includes excavating the bottom trenches at 2% cross slope verses 4% as shown in said typicals. No adjustments to plan quantities will be made if this option is used.