MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 14-0713-501

Proposed Contract Period: Late Start Date of 09/05/17 with 35 WORK DAYS

Project(s):

Project No: MB-071-3(501)112--77-14

County: CARROLL

Type of Work: DECK JOINT REPAIR

Route: U.S. 71 Length: 0.00 miles Location: UP RR AND RD 0.2 MI S OF US 30 IN CARROLL

Item No. Item Description ______

Quantity/Unit

SECTION NO. 0001

DESIGN NO. 0117; RTEPAIRS TO A 453'-8 X 40'-0 PRETENSIONED

PRESTRESSED CONCRETE BEAM BRIDGE

2403-0100000 STRUCT CONC (MISCELLANEOUS) 2404-7775005 REINFORC STEEL, EPOXY COATED

5 CY

405 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 22-C022-084

Proposed Contract Period: Late Start Date of 06/26/17 with 80 WORK DAYS

Project(s):

Project No: BROS-C022(084)--8J-22

County: CLAYTON

Type of Work: BRIDGE REPLACEMENT - CCS
Route: KEYSTONE ROAD Length: 0.00 miles

Location: ON KEYSTONE RD, OVER SNY MAGILL, FROM LARIAT RD SOUTH 400 FE

ET TO BRIDGE, AT NW S22 T94 R03

Item No. Item Description Quantity/Unit ------

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 690 CY 551 CY 119,976 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 24-C024-113

Proposed Contract Period: Late Start Date of 07/03/17 with 75 WORK DAYS

Project(s):

Project No: BROS-C024(113)--5F-24

County: CRAWFORD

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: O AVE Length: 0.00 miles

Location: O AVE: FROM 130TH ST TO 140TH ST.

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 12' X 12' X 54' REINFORCED CONCRETE BOX

CULVERT

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 3,298 CY

 2403-0100020
 STRUCT CONC (RCB CULV)
 446 CY

 2404-7775000
 REINFORC STEEL
 61,339 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 25-0803-218

Proposed Contract Period: Late Start Date of 09/25/17 with 20 WORK DAYS

Project(s):

Project No: IMN-080-3(218)110--0E-25

County: DALLAS

Type of Work: PPCB REPAIR

Route: I-80 Length: 0.00 miles

Location: US 169 INTERCHANGE

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 27-C027-065

Proposed Contract Period: Late Start Date of 06/12/17 with 105 WORK DAYS

Project(s):

Project No: BRS-C027(65)--60-27

County: DECATUR

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: VARIOUS LOCATIONS Length: 0.30 miles

Location: R30 OVER EAST FORK BIG CREEK R34 OVER TRIB TO GRAND RIVER R4

6 OVER TRIB TO LITTLE RIVER

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN10' X 6' X 62' REINFORCED CONCRETE BOX

CULVERT - R30 OVER EAST FORK BIG CREEK

2102-2625000 EMBANKMENT-IN-PLACE 1,605 CY
2303-1031750 HMA ST BASE, 3/4" 190 TON
2303-1033500 HMA ST SURF, 1/2", NO FRIC 193 TON
2403-0100020 STRUCT CONC (RCB CULV) 561 CY
2404-7775000 REINFORC STEEL 82,375 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 33-C033-108

Proposed Contract Period: Late Start Date of 09/18/17 with 30 WORK DAYS

Project(s):

Project No: BROS-C033(108)--5F-33

County: FAYETTE

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: OUTER ROAD Length: 0.00 miles

Location: OUTER RD: OVER UNNAMED STREAM

Item No. Item Description

Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 12'-0 X 8'-0 X 40'-0 REINFORCED CONCRETE

BOX CULVERT

2403-0100020 STRUCT CONC (RCB CULV) 2404-7775000 REINFORC STEEL

201 CY

30,882 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 44-C044-082

Proposed Contract Period: Late Start Date of 07/10/17 with 25 WORK DAYS

Project(s):

Project No: FM-C044(82)--55-44

County: HENRY

Type of Work: BRIDGE REHABILITATION

Route: W55 Length: 0.10 miles

Location: ON W55 AT OAKLAND MILLS

Item No. Item Description

Quantity/Unit

______ SECTION NO. 0001

ITEMS FOR A 520'-6 X 28' CONTINUOUS STEEL I-BEAM BRIDGE

2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 25 CY

3,578 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 50-0801-507

Proposed Contract Period: Late Start Date of 08/28/17 with 30 WORK DAYS

Project(s):

Project No: MBIN-080-1(507)150--0M-50

County: JASPER

Type of Work: ABUTMENT REPAIR

Route: I-80 Length: 0.00 miles

Location: OVER W. 148TH ST. SOUTH 1 MILE E. OF CO. RD. S-27

 Item No.
 Item Description
 Quantity/Unit

 SECTION NO. 0001

 DESIGN NO. 0616; TWIN 125'-10 X 40

 2403-0100000
 STRUCT CONC (MISCELLANEOUS)
 4 CY

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 288 LB

 SECTION NO. 0002

 DESIGN NO. 0716; TWIN 125'-10 X 40

 2403-0100000
 STRUCT CONC (MISCELLANEOUS)
 4 CY

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 288 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 50-3897-601

Proposed Contract Period: Late Start Date of 08/07/17 with 50 WORK DAYS

Project(s):

Project No: BROS-3897(601)--8J-50

County: JASPER

Type of Work: BRIDGE REPLACEMENT - CCS
Route: INDIGO AVENUE Length: 0.10 miles

Location: IN THE CITY OF KELLOGG, ON INDIGO AVE., OVER COON CREEK IN S

EC 25 T80-N, R-18W

Item No. Item Description Quantity/Unit ------

SECTION NO. 0001

ITEMS FOR A 70'-0 X 24' CONTINUOUS CONCRETE SLAB BRIDGE

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 225 CY 113 SY 168 CY 32,861 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 75-C075-147

Proposed Contract Period: Late Start Date of 07/17/17 with 60 WORK DAYS

Project(s):

Project No: BROS-C075(147)--8J-75

County: PLYMOUTH

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 310TH ST Length: 0.10 miles

Location: ON 310TH ST BETWEEN SEC 13/24-90-45: OVER MUDDY CREEK

Item No. Item Description

Quantity/Unit

SECTION NO. 0001

ITEMS FOR 100' X 30' CONTINUOUS CONCRETE SLAB BRIDGE

2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL

251 CY

59,523 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 75-0752-087-A

Proposed Contract Period: Late Start Date of 08/14/17 with 30 WORK DAYS

Project(s):

Project No: BRFN-075-2(87)--39-75

County: PLYMOUTH

Type of Work: BRIDGE DECK OVERLAY

Route: U.S. 75 Length: 0.00 miles

Location: US 75 (SB) OVER DRY CREEK 3.4 MI N OF JCT. SR C60

Item No.	Item Description	Quantity/Unit
	NO. 0001	
2413-0698074	DESIGN NO. 117; A 40'-0 X 30'-0 I-BEAM BRIDGE DECK REPAIR, CL A NO. 0002	63 SY
	ALTERNATE 'AA' OPTION 1: DECK OVERLAY (CLASS 0 PCC)	
I	BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOS	EN
	DECK OVERLAY (CL O PCC)	142 SY
	NO. 0003	
	ALTERNATE 'AA' OPTION 2: DECK OVERLAY (CLASS HPC-0-1	•
E	BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOS	EN
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	142 SY
SECTION	NO. 0004	
F	ROADWAY ITEMS	
2303-0101000	HMA WEDGE/LEVEL/STRENGTH	500 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 79-C079-049

Proposed Contract Period: Late Start Date of 08/21/17 with 45 WORK DAYS

Project(s):

Project No: BRS-C079(49)--60-79

County: POWESHIEK

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: F29 Length: 0.00 miles

Location: ON F29, OVER STREAM, FROM 190TH STREET EAST 0.5 MILES, AT S1

9 T80 R13

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 12' X 7' X 4' SINGLE REINFORCED BOX CULVERT

 2102-2625000
 EMBANKMENT-IN-PLACE
 318 CY

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 611 CY

 2301-1033080
 STD/S-F PCC PAV'T, CL C CL 3, 8"
 1,400 SY

 2403-0100020
 STRUCT CONC (RCB CULV)
 193 CY

 2404-7775000
 REINFORC STEEL
 25,884 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 81-C081-067

Proposed Contract Period: Approx Start Date of 07/01/17 with 65 WORK DAYS

Proposal Note:

*** WORK RESTRICTION ***

ONLY ONE PROJECT MAY BE UNDER CONSTRUCTION AT A TIME DUE TO

THE NEED FOR ACCESS TO MULTIPLE RESIDENCES AND AN

AGRICULTURAL FEEDING OPERATION BETWEEN THESE TWO PROJECTS.

Project(s):

Project No: BRS-C081(67)--60-81

County: SAC

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: M43 Length: 0.00 miles Location: ON M43 OVER STREAM 0.4 MILES SOUTH OF 200TH STREET

Project No: FM-C081(68)--55-81

County: SAC

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: M43 Length: 0.00 miles

Location: ON M43, OVER STREAM, FROM 0.8 MILES SOUTH OF 200TH STREET, S

28 T89 R37

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A PRECAST 20' X 8' REINFORCED CONCRETE BOX CULVERT BRS-C081(67)--60-81

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 2404-7775005 REINFORC STEEL, EPOXY COATED 195 SY

2,138 LB

SECTION NO. 0002

ITEMS FOR A PRECAST 20' X 7' REINFORCED CONCRETE BOX CULVERT FM-C081(68)--55-81

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 544 CY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 195 SY 2404-7775005 REINFORC STEEL, EPOXY COATED 2,138 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 96-C096-140

Proposed Contract Period: Late Start Date of 05/22/17 with 105 WORK DAYS

Project(s):

Project No: FM-C096(132)--55-96

County: WINNESHIEK
Type of Work: PIPE CULVERTS

Route: W34 Length: 8.00 miles

Location: ON W34, FROM US HWY 52 TO CO. RD. A14, AT S28 T100 R08

Project No: BHOS-C096(140)--5N-96

County: WINNESHIEK

Type of Work: RECONSTRUCTION - RCB CULVERT EXT-TRIPLE
Route: W34 Length: 0.00 miles
Location: ON W34, OVER CANOE CREEK, S9 T99 R08

Project No: BHOS-C096(141)--5N-96

County: WINNESHIEK

Type of Work: RCB CULVERT EXTENSION - TWIN BOX

Route: W34 Length: 0.00 miles

Location: ON W34, OVER CANOE CREEK TRIBUTARY, S21 T99 R08

Item No. Item Description Quantity/Unit

SECTION NO. 0002

ITEMS FOR A TRIPLE 18' X 12' REINFORCED CONCRETE BOX

CULVERT EXTENSION - BHOS-C096(140)--5N-96

 2102-2625000
 EMBANKMENT-IN-PLACE
 1,382 CY

 2403-0100020
 STRUCT CONC (RCB CULV)
 479 CY

 2404-7775000
 REINFORC STEEL
 76,248 LB

SECTION NO. 0004

ITEMS FOR A TWIN 12' X 10' REINFORCED CONCRETE BOX

CULVERT EXTENSION - BHOS-C096(141)--5N-96

2102-2625000 EMBANKMENT-IN-PLACE 2,048 CY 2403-0100020 STRUCT CONC (RCB CULV) 172 CY 2404-7775000 REINFORC STEEL 24,843 LB

SECTION NO. 0005

ROADWAY ITEMS

FM-C096(132)--55-96

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2,329 SY 2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT) 542 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 56 EACH

SECTION NO. 0006

ITEMS FOR A 8' X 4' X 58' REINFORCED CONCRETE BOX CULVERT

FM-C096(132)--55-96

 2102-2625000
 EMBANKMENT-IN-PLACE
 31 CY

 2403-0100020
 STRUCT CONC (RCB CULV)
 68 CY

 2404-7775000
 REINFORC STEEL
 10,433 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 97-C097-112

Proposed Contract Period: Late Start Date of 06/19/17 with 85 WORK DAYS

Project(s):

Project No: BRS-C097(112)--60-97

County: WOODBURY

Type of Work: BRIDGE REPLACEMENT - CCS

Route: D25 Length: 0.10 miles

Location: D-25: OVER BIG WHISKEY CREEK

Item No.	Item Description	Quantity/Unit
	NO. 0001	
I	TEMS FOR A 90' X 30-6 CONTINUOUS CONCRETE SLA	B BRIDGE
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,682 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	3,038 SY
2403-0100010	STRUCT CONC (BRIDGE)	204 CY
2404-7775000	REINFORC STEEL	124 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	53,089 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 97-C097-129

Proposed Contract Period: Late Start Date of 07/24/17 with 60 WORK DAYS

Project(s):

Project No: BROS-C097(129)--5F-97

County: WOODBURY

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: L43 Length: 0.10 miles Location: L43: FROM 190TH STREET TO 200TH STREET

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 67'-6 X 30'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

 2102-2625000
 EMBANKMENT-IN-PLACE
 1,327 CY

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 49 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 129 CY

 2404-7775000
 REINFORC STEEL
 78 LB

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 31,344 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 97-7057-688

Proposed Contract Period: Late Start Date of 07/10/17 with 80 WORK DAYS

Project(s):

Project No: EDP-7057(688)--7Y-97

County: WOODBURY

Type of Work: BRIDGE NEW - OTHER

Route: FLOYD RIVER TRAIL Length: 0.35 miles

Location: FLOYD RIVER TRAIL, FROM OUTER DRIVE NORTH TO UPRR AND CONNE

CTION TO LEWIS BLVD ALONG FLOYD RIVER

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
R	OADWAY ITEMS	
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	53,171 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	348 CY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	2,223 SY
SECTION	NO. 0002	
I	TEMS FOR A 271'-0 X 12'-0 PRE-ENGINEERED STEEL	TRUSS
R	ECREATIONAL TRAIL BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	92 CY
2404-7775000	REINFORC STEEL	3,430 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	9,602 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 018 Proposal ID: 99-C099-087

Proposed Contract Period: Late Start Date of 09/11/17 with 30 WORK DAYS

Project(s):

Project No: BROS-C099(87)--8J-99

County: WRIGHT

Type of Work: BRIDGE REPLACEMENT - OTHER

Route: R35 Length: 0.00 miles

Location: ON R35, OVER EAGLE CREEK-D D 36, 0.1 MILES, S35 T93 R25

Item No. Item Description Quantity/Unit

______ SECTION NO. 0001

ITEMS FOR A 40'-0 X 12' CONCRETE ARCH CULVERT

2403-0100020 STRUCT CONC (RCB CULV) 2404-7775000 REINFORC STEEL 106 CY 7,900 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 06-8017-611

Proposed Contract Period: Late Start Date of 07/10/17 with 55 WORK DAYS

Project(s):

Project No: STP-U-8017(611)--70-06

County: BENTON

Type of Work: PCC PAVEMENT - REPLACE

Route: 3RD ST Length: 0.00 miles

Location: IN THE CITY OF VINTON, ON 3RD STREET, FROM 3RD AVE TO 9TH AV

Ε

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 4,504 CY 2301-1033070 STD/S-F PCC PAV'T, CL C CL 3, 7" 10,028 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 11-7422-615-A

Proposed Contract Period: Late Start Date of 08/01/17 with 35 WORK DAYS

Project(s):

Project No: STP-U-7422(615)--70-11

County: BUENA VISTA

Type of Work: PCC PAVEMENT - REPLACE

Route: E RICHLAND ST Length: 0.75 miles

Location: IN THE CITY OF STORM LAKE, E RICHLAND ST: FROM FLINDT DRIVE

TO INDUSTRY STREET

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 718 CY 4,310 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 25-C025-107

Proposed Contract Period: Late Start Date of 08/28/17 with 30 WORK DAYS

Project(s):

Project No: HSIP-S-C025(107)--6C-25

County: DALLAS

Type of Work: PCC PAVEMENT - REPLACE

Route: F90 Length: 0.27 miles

Location: ON F90, FROM WEST APPROACH OF THE BULGAR CREEK BRIDGE EAST A

PPROX. 0.27 MILES TO IA 169, ON NLINE S36 T78 R28

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 3,079 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 34-C034-096

Proposed Contract Period: Late Start Date of 05/22/17 with 100 WORK DAYS

Project(s):

Project No: STP-S-C034(96)--5E-34

County: FLOYD

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: T26 Length: 6.50 miles

Location: ON T26, FROM B45(210TH STREET) TO NORTH CITY LIMITS OF MARBL

E ROCK, AT S20 T95 R17

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 18,833 CY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 78,662 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 45-C045-079

Proposed Contract Period: Late Start Date of 06/26/17 with 65 WORK DAYS

Project(s):

Project No: TAP-R-C045(79)--8T-45

County: HOWARD

Type of Work: PCC SIDEWALK/TRAIL

Route: WAPSI GREAT WESTERN Length: 7.46 miles

Location: ON WAPSI GREAT WESTERN TRAIL PAVING, FROM TRAIL HEAD (RICEVI

LLE) TO ACME

Item No. Item Description Quantity/Unit ------

SECTION NO. 0001

PCC TRAIL ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2511-0302500 RECREATIONAL TRAIL, PCC, 5"

87 CY

34,298 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 50-C050-114

Proposed Contract Period: Late Start Date of 07/10/17 with 65 WORK DAYS

Project(s):

Project No: STP-S-C050(114)--5E-50

County: JASPER

Type of Work: PCC OVERLAY - UNBONDED

Route: F36 Length: 5.50 miles

Location: ON COUNTY ROAD F36, FROM COUNTY ROAD S52 EAST 5.5 MILES TO C

HERRY CREEK BRIDGE

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
R	OADWAY ITEMS	
2301-1034090	STD/S-F PCC PAV'T, CL C CL 31, 9"	5,268 SY
2310-5151040	PCC OVERLAY, FURN ONLY	16,225 CY
2310-5151251	PCC OVERLAY PLACE ONLY (UNBONDED)	79 , 929 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,083 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	186 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 53-0165-605

Proposed Contract Period: Late Start Date of 07/31/17 with 50 WORK DAYS

Project(s):

Project No: STP-U-0165(605)--70-53

County: JONES

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: ELM STREET Length: 0.00 miles

Location: IN THE CITY OF ANAMOSA, ON S. ELM, FROM W. MAIN ST. TO WAPSI

PINICON BRIDGE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2301-1034080 STD/S-F PCC PAV'T, CL C CL 3I, 8" 2303-1031500 HMA ST BASE, 1/2" 2303-1033500 HMA ST SURF, 1/2", NO FRIC 6,079 SY 70 TON

35 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 62-C062-088

Proposed Contract Period: Late Start Date of 08/14/17 with 60 WORK DAYS

Project(s):

Project No: STP-S-C062(88)--5E-62

County: MAHASKA

Type of Work: PCC PAVEMENT - REPLACE

Route: G5T Length: 2.16 miles

Location: ON G5T/T33, FROM SO. SKUNK RIVER NE 1.76 MI TO PEORIA CHESTN

UT ST; AND G5T FROM T33 E 0.30 MI

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 14,307 CY 2301-1034090 STD/S-F PCC PAV'T, CL C CL 3I, 9" 30,780 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 74-C074-102

Proposed Contract Period: Late Start Date of 05/22/17 with 95 WORK DAYS

Project(s):

Project No: STP-U-2395(606)--70-74

County: PALO ALTO

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: COLLEGE DRIVE Length: 0.25 miles

Location: IN THE CITY OF EMMETSBURG, COLLEGE DR: FROM INT N LAWLER AND

COLLEGE DRIVE N AND E .25 MILES

Project No: FM-C074(99)--55-74

County: PALO ALTO

Type of Work: PCC PAVEMENT - GRADE & REPLACE
Route: B55 Length: 4.25 miles
Location: B53 RODMAN ST TO HIGHWAY 15

Project No: STP-S-C074(102)--5E-74

County: PALO ALTO

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: N40 Length: 1.25 miles

Location: N40: GOLF COURSE N 1.25 MI

2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8"

______ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS STP-U-2395(606)--70-74 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1032080 STD/S-F PCC PAV'T, CL C CL 2, 8" 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 4,110 CY 5,334 SY 28 SY SECTION NO. 0002 ROADWAY ITEMS FM-C074(99)--55-74 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 71,503 CY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 59,608 SY SECTION NO. 0003 ROADWAY ITEMS STP-S-C074(102)--5E-74 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 12,915 CY

15,197 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 110 Proposal ID: 75-C075-148

Proposed Contract Period: Late Start Date of 06/19/17 with 70 WORK DAYS

Project(s):

Project No: STP-S-C075(148)--5E-75

County: PLYMOUTH

Type of Work: PCC OVERLAY - BONDED

Route: C60 Length: 6.25 miles

Location: ON C60 FROM HWY 140 WEST 6.25 MI:

______ Item No. Item Description Quantity/Unit ______ SECTION NO. 0001 ROADWAY ITEMS - DIVISION 1 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 2,848 CY 33,887 SY 321 TON 2310-5151040 PCC OVERLAY, FURN ONLY 13,484 CY 2310-5151551 PCC OVERLAY PLACE ONLY (WHITE TOPPING) 60,363 SY 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 70 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 8 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 111 Proposal ID: 90-5825-643

Proposed Contract Period: Late Start Date of 06/12/17 with 100 WORK DAYS

Project(s):

Project No: STP-U-5825(643)--70-90

County: WAPELLO

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: EAST MAIN STREET Length: 0.35 miles

Location: IN THE CITY OF OTTUMWA, ON EAST MAIN STREET, FROM JEFFERSON

STREET SE 0.35 MILES TO S VINE STREET

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,007 CY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 10,078 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 12-0112-603

Proposed Contract Period: Late Start Date of 08/21/17 with 30 WORK DAYS

Project(s):

Project No: STP-U-0112(603)--70-12

County: BUTLER

Type of Work: HMA RESURFACING

Route: MAIN ST Length: 1.54 miles

Location: MAIN ST, IA-14 TO 6TH ST; 6TH ST, MAIN ST TO LOCUST ST; LOCU

ST ST, 6TH ST TO 7TH ST; 7TH ST, LOCUST ST TO LINDEN ST

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-0001000 HMA WEDGE/LEVEL/STRENGTH 131 TON 2303-1032500 HMA ST INTERMEDIATE, 1/2" 320 TON 2303-1033500 HMA ST SURF, 1/2", NO FRIC 3,900 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 14-0713-706

Proposed Contract Period: Late Start Date of 09/18/17 with 15 WORK DAYS

Project(s):

Project No: MP-071-3(706)112--76-14

County: CARROLL

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 71 Length: 0.55 miles

Location: FROM N OF W 15TH ST TO 0.15 MI N OF W 20TH ST IN CARROLL

Item No.	Item Description	Quantity/	/Unit
SECTION	NO. 0001		
R	COADWAY ITEMS		
2303-1042500	HMA HT INTERMEDIATE, 1/2"	1,036	TON
2303-1043502	HMA HT SURF, 1/2", FRIC L-2	987	TON
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	107	SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	1	EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 20-C020-111

Proposed Contract Period: Late Start Date of 08/28/17 with 15 WORK DAYS

Project(s):

Project No: STP-S-C020(111)--5E-20

County: CLARKE

Type of Work: HMA RESURFACING

Route: J-12 Length: 1.71 miles

Location: ON J-12, FROM HWY. 69 EAST 1.71 MILES TO WELDON, ALONG SLINE

S32-33 T71 R25

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-1032750 HMA ST INTERMEDIATE, 3/4" 2,815 TON 2303-1033500 HMA ST SURF, 1/2", NO FRIC 2,855 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 23-C023-107

Proposed Contract Period: Late Start Date of 08/14/17 with 25 WORK DAYS

Project(s):

Project No: FM-C023(107)--55-23

County: CLINTON

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: Y4E Length: 4.08 miles

Location: Y4E: HWY 30 TO BIG ROCK

Item No. Item Description Quantity/Unit ______

SECTION NO. 0001

ROADWAY ITEMS

2303-1031500 HMA ST BASE, 1/2" 2303-1033500 HMA ST SURF, 1/2", NO FRIC 4,673 TON 5,265 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 27-C027-062-A

Proposed Contract Period: Late Start Date of 09/25/17 with 25 WORK DAYS

Project(s):

Project No: FM-C027(62)--55-27

County: DECATUR

Type of Work: HMA PAVEMENT - REPLACE

Route: SOUTH SMITH STREET Length: 1.05 miles

Location: ON S SMITH ST

Item No. Item Description	Quantity/Unit
SECTION NO. 0001 ROADWAY ITEMS	
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	2,015 CY
2303-1031750 HMA ST BASE, 3/4" 2303-1033500 HMA ST SURF, 1/2", NO FRIC	2,025 TON 1,625 TON
2511-0302600 RECREATIONAL TRAIL, PCC, 6"	12 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 31-1363-048

Proposed Contract Period: Late Start Date of 08/07/17 with 50 WORK DAYS

Project(s):

Project No: STP-136-3(48)--2C-31

County: DUBUQUE

Type of Work: HMA RESURFACING

Route: IOWA 136 Length: 0.59 miles

Location: IN THE CITY OF WORTHINGTON, ON HWY 136, FROM MILEPOST 81.71

TO MILEPOST 82.30

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 585 CY

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 585 CY
2303-1031750 HMA ST BASE, 3/4" 341 TON
2303-1032500 HMA ST INTERMEDIATE, 1/2" 859 TON
2303-1033500 HMA ST SURF, 1/2", NO FRIC 888 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 35-C035-096

Proposed Contract Period: Late Start Date of 08/21/17 with 35 WORK DAYS

Project(s):

Project No: FM-C035(96)--55-35

County: FRANKLIN

Type of Work: HMA RESURFACING WITH MILLING

Route: S25 Length: 7.00 miles

Location: ON S25 (HEATHER AVENUE), FROM HARDIN STREET (C73) NORTH 8 MI

LES TO 100TH STREET (C47)

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-1033500 HMA ST SURF, 1/2", NO FRIC 12,047 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 43-0304-714

Proposed Contract Period: Late Start Date of 10/02/17 with 10 WORK DAYS

Project(s):

Project No: MP-030-4(714)9--76-43

County: HARRISON

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 30 Length: 0.15 miles Location: FROM JUST WEST OF JOLIET AVE EAST 0.15 MI

Item No. Item Description Quantity/Unit

291 SY

SECTION NO. 0001

ROADWAY ITEMS

2303-1143504 HMA HT SURF, 1/2", FRIC L-4

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 49-0521-110

Proposed Contract Period: Late Start Date of 08/07/17 with 55 WORK DAYS

Project(s):

Project No: HSIPX-052-1(110)--3L-49

County: JACKSON

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 52 Length: 10.10 miles Location: 600 FT SE OF 395TH AVE TO DUBUQUE CO LINE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

HSIP FUNDING

2303-1131500 HMA ST BASE, 1/2"

13,453 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 57-C057-126

Proposed Contract Period: Late Start Date of 05/22/17 with 105 WORK DAYS

Project(s):

Project No: FM-C057(126)--55-57

County: LINN

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: MOUNT VERNON ROAD Length: 2.42 miles

Location: ON MT VERNON RD, FROM 44TH STREET TO HWY 13, AT S25 T83 R07

Item No.	Item Description	Quantity/Unit
	NO. 0001	
I	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	11,690 CY
2303-1041750	HMA HT BASE, 3/4"	14,946 TON
2303-1043500	HMA HT SURF, 1/2", NO FRIC	11,303 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,011 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	5 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 59-C059-044

Proposed Contract Period: Late Start Date of 09/05/17 with 35 WORK DAYS

Project(s):

Project No: STP-S-C059(44)--5E-59

County: LUCAS

Type of Work: HMA RESURFACING

Route: S-45 Length: 3.60 miles

Location: S-45: FROM IOWA HIGHWAY 14 TO MARION COUNTY LINE

Item No. Item Description Quantity/Unit ______ SECTION NO. 0001 ROADWAY ITEMS 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 2303-1032500 HMA ST INTERMEDIATE, 1/2" 2303-1033500 HMA ST SURF, 1/2", NO FRIC 2,273 TON

5,140 TON 5,140 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 97-C097-131

Proposed Contract Period: Late Start Date of 08/14/17 with 40 WORK DAYS

Project(s):

Project No: FM-C097(131)--55-97

County: WOODBURY

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: L37 Length: 6.00 miles

Location: L37: FROM HWY 20 TO D38

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 293 CY 2303-1032500 HMA ST INTERMEDIATE, 1/2" 7,410 TON 2303-1033500 HMA ST SURF, 1/2", NO FRIC 7,000 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 05-0444-707

Proposed Contract Period: Late Start Date of 08/28/17 with 15 WORK DAYS

Project(s):

Project No: MP-044-4(707)36--76-05

County: AUDUBON

Type of Work: HMA JOINT & CRACK SEALING

Route: IOWA 44 Length: 9.74 miles

Location: KIMBALLTON TO U.S. 71

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 10-1506-705

Proposed Contract Period: Late Start Date of 07/17/17 with 20 WORK DAYS

Project(s):

Project No: MP-150-6(705)40--76-10

County: BUCHANAN
Type of Work: HMA PATCHING

Route: IOWA 150 Length: 1.88 miles Location: IN INDEPENDENCE, FROM U.S. 20 TO NEAR NCL

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 13-0071-704

Proposed Contract Period: Late Start Date of 05/22/17 with 95 WORK DAYS

Project(s):

Project No: MP-169-1(701)122--76-08

County: BOONE

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 169 Length: 15.60 miles

Location: FROM JUST N. OF W. JCT U.S. 30, NORTH TO JUST SOUTH OF THE E

JCT IOWA 175 IN WEBSTER CO.

Project No: MP-007-1(704)57--76-13

County: CALHOUN

Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 7 Length: 15.90 miles
Location: ECL OF MANSON EAST TO THE JCT. WITH U.S. 169

IN WEBSTER CO.

Project No: MP-017-1(706)56--76-40

County: HAMILTON

Type of Work: LONGITUDINAL JOINT REPAIR

Route: IOWA 17 Length: 13.00 miles

Location: FROM JUST SOUTH OF E. JCT IOWA 17/D20, N. TO SCL EAGLE GROVE

IN WRIGHT CO.

Project No: MP-020-1(713)136--76-40

County: HAMILTON

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 20 Length: 4.20 miles Location: FROM THE W. IOWA 17 INTRCHG TO THE E. IOWA 17 INTRCHG

(WBL'S ONLY; WORK INCLUDES ALL 8 RAMPS)

Project No: MP-169-1(708)156--76-94

County: WEBSTER

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 169 Length: 0.90 miles

Location: FROM 2.3 MI. NORTH OF U.S. 20 TO THE JCT. W. BUSINESS 20 AT

U.S. 169 IN THE CITY OF FORT DODGE (SBLS ONLY)

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 15-0801-413

Proposed Contract Period: Late Start Date of 10/02/17 with 10 WORK DAYS

Project(s):

Project No: IMN-080-1(413)50--0E-15

County: CASS

Type of Work: PCC PATCHING

Route: I-80 Length: 0.00 miles Location: FROM POTTAWATTAMIE CO. LINE E. TO I-35

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 750 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 84 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 23-C023-105

Proposed Contract Period: Late Start Date of 08/07/17 with 10 WORK DAYS

Project(s):

Project No: FM-C023(105)--55-23

County: CLINTON
Type of Work: FOG SEAL

Route: Y44 Length: 4.88 miles Location: ON Y44, FROM E-63 TO US 30, S5 T81 RE2

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 26-C026-101

Proposed Contract Period: Late Start Date of 07/10/17 with 35 WORK DAYS

Project(s):

Project No: FM-C026(101)--55-26

County: DAVIS

Type of Work: HMA CRACK FILLING

Length: 33.56 miles Route: 215TH STREET

Location: ON 215TH ST, FLORIS ROAD, LILAC AVE, NUTHATCH AVE & TIMBER A

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 36-0024-714

Proposed Contract Period: Late Start Date of 10/02/17 with 15 WORK DAYS

Project(s):

Project No: MP-002-4(714)18--76-36

County: FREMONT

Type of Work: PCC PATCHING

Route: IOWA 2 Length: 10.59 miles Location: FROM APPROX 2.2 MI E OF U.S. 275 TO U.S. 59

_				
	Item No.	Item Description	Quantity,	/Unit
	SECTION 1	NO. 0001		
	R	OADWAY ITEMS		
	2303-1033500	HMA ST SURF, 1/2", NO FRIC	69	TON
	2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	106	SY
	2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	480	SY
	2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4	EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 38-0202-703

Proposed Contract Period: Late Start Date of 09/18/17 with 15 WORK DAYS

Project(s):

Project No: MP-020-2(703)215--76-38

County: GRUNDY

Type of Work: PCC JOINT & CRACK FILLING

Route: U.S. 20 Length: 6.33 miles

Location: FROM WEST OF DIKE, EAST TO BLACK HAWK COUNTY LINE.

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 209 Proposal ID: 43-0295-235

Proposed Contract Period: Late Start Date of 09/25/17 with 25 WORK DAYS

Project(s):

Project No: IMN-029-5(235)72--0E-43

County: HARRISON
Type of Work: PCC PATCHING

Route: I-29 Length: 0.00 miles

Location: FROM POTTAWATTAMIE CO. LINE N. TO SOUTH DAKOTA

STATE LINE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-1053502 HMA VT SURF, 1/2", FRIC L-2 857 TON
2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 333 SY
2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 31 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 210 Proposal ID: 48-0066-712

Proposed Contract Period: Late Start Date of 09/11/17 with 25 WORK DAYS

Project(s):

Project No: MP-006-6(712)232--76-48

County: IOWA

Type of Work: PCC PATCHING

Route: U.S. 6 Length: 8.80 miles Location: FROM THE E. JCT U.S. 151 TO E OF KENT PARK

Project No: MP-149-6(704)50--76-48

County: IOWA

Type of Work: PCC PATCHING
Route: IOWA 149 Length: 15
Location: FROM KEOKUK COUNTY LINE TO I-80. Length: 15.90 miles

Project No: MP-151-6(708)0--76-48 County: IOWA

Type of Work: PCC PATCHING

Route: U.S. 151 Length: 9.62 miles

Location: I-80 TO N OF THE IOWA RIVER

Project No: MP-212-6(704)12--76-48

County: IOWA

Type of Work: PCC PATCHING

Length: 0.72 miles Route: IOWA 212

Location: NEAR THE WCL MARENGO TO U.S. 6

2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT

Item No. Item Description	Quantity/Ur	Jnit
SECTION NO. 0001		
ROADWAY ITEMS		
IOWA COUNTY MP-006-6(712)232-	76-48	
2529-5070110 PATCH, FULL-DEPTH FINISH, B	BY AREA 412 SY	ЗΥ
2529-5070120 PATCH, FULL-DEPTH FINISH, B	BY COUNT 45 EA	CACE
SECTION NO. 0002		
ROADWAY ITEMS		
IOWA COUNTY MP-149-6(704)50		
2529-5070110 PATCH, FULL-DEPTH FINISH, B		. –
2529-5070120 PATCH, FULL-DEPTH FINISH, B	BY COUNT 45 EA	LACE
SECTION NO. 0003		
ROADWAY ITEMS		
IOWA COUNTY MP-151-6(708)07		
2529-5070110 PATCH, FULL-DEPTH FINISH, B		. –
2529-5070120 PATCH, FULL-DEPTH FINISH, B	BY COUNT 63 EA	LACE
SECTION NO. 0004		
ROADWAY ITEMS		
IOWA COUNTY MP-212-6(704)12		
2529-5070110 PATCH, FULL-DEPTH FINISH, B	BY AREA 267 SY	Ϋ́

42 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 211 Proposal ID: 50-0801-707

Proposed Contract Period: Late Start Date of 07/17/17 with 20 WORK DAYS

Project(s):

Project No: MPIN-080-1(707)160--0N-50

County: JASPER

Type of Work: HMA PAVED SHOULDER - FOG SEAL

Route: I-80 Length: 4.64 miles

Location: FROM 0.7 MI E OF F48, EAST TO 0.8 MI E OF IOWA 224

Project No: MPIN-080-1(707)184--0N-79

County: POWESHIEK

Type of Work: HMA PAVED SHOULDER - FOG SEAL

Route: I-80 Length: 9.15 miles Location: FROM1.0 MI E OF IOWA 146, EAST TO 1.1 MI E OF U.S. 63

______ Item Description

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 212 Proposal ID: 57-0306-724

Proposed Contract Period: Late Start Date of 07/10/17 with 40 WORK DAYS

Project(s):

Project No: MP-030-6(724)245--76-57

County: LINN

Type of Work: PCC PATCHING

Route: U.S. 30 Length: 23.30 miles Location: FROM MORGAN CREEK TO CEDAR COUNTY LINE

Project No: MP-151-6(726)25--76-57

County: LINN

Type of Work: PCC PATCHING
Route: U.S. 151
Location: AT W JCT U.S. 30 Length: 0.44 miles

Project No: MP-151-6(727)30--76-57 County: LINN

Type of Work: PCC PATCHING

Route: U.S. 151 Length: 7.71 miles Location: FROM E JCT U.S. 30 TO N JCT IOWA 13

Project No: MP-922-6(720)0--76-57

County: LINN

Type of Work: PCC PATCHING

Route: IOWA 922 Length: 2.09 miles Location: FROM U.S. 30 TO 16TH AVENUE SW IN CEDAR RAPIDS

Item No.	Item Description		Quantity/Unit
SECTION	NO. 0001		
R	OADWAY ITEMS		
M	IP-030-6(724)24576-57		
2529-5070110	PATCH, FULL-DEPTH FINISH,	BY AREA	727 SY
2529-5070120	PATCH, FULL-DEPTH FINISH,	BY COUNT	90 EACH
SECTION	NO. 0002		
R	OADWAY ITEMS		
M	IP-151-6(726)2576-57		
2529-5070110	PATCH, FULL-DEPTH FINISH,	BY AREA	104 SY
2529-5070120	PATCH, FULL-DEPTH FINISH,	BY COUNT	15 EACH
SECTION	NO. 0003		
R	OADWAY ITEMS		
M	IP-151-6(727)3076-57		
2529-5070110	PATCH, FULL-DEPTH FINISH,	BY AREA	692 SY
2529-5070120	PATCH, FULL-DEPTH FINISH,	BY COUNT	97 EACH
SECTION	NO. 0004		
R	OADWAY ITEMS		

MP-922-6(720)0--76-57

481 SY 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 59 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 213 Proposal ID: 57-1516-725

Proposed Contract Period: Late Start Date of 07/10/17 with 45 WORK DAYS

Project(s):

Project No: MP-020-6(715)245--76-10

County: BUCHANAN
Type of Work: PCC PATCHING

Route: U.S. 20 Length: 7.29 miles

Location: BLACK HAWK CO LINE TO IOWA AVE IN INDEPENDENCE

Project No: MP-013-6(713)45--76-28

County: DELAWARE

Type of Work: PCC PATCHING

Route: IOWA 13 Length: 9.14 miles
Location: FROM NORTH OF MANCHESTER TO SOUTH JCT IOWA 3

Project No: MP-020-6(706)283--76-28

County: DELAWARE
Type of Work: PCC PATCHING

Route: U.S. 20 Length: 37.27 miles

Location: FROM ECL OF DELAWARE TO JULIEN DUBUQUE BRIDGE IN DUBUQUE.

Project No: MP-151-6(725)38--76-57

County: LINN

Type of Work: PCC PATCHING

Route: U.S. 151 Length: 56.73 miles

Location: FROM IOWA 13 TO U.S. 61

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

BUCHANAN COUNTY MP-020-6(715)245--76-10

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 678 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 112 EACH

SECTION NO. 0002

ROADWAY ITEMS

DELAWARE COUNTY MP-013-6(713)45--76-28

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 681 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 63 EACH

SECTION NO. 0003

ROADWAY ITEMS

DELAWARE COUNTY MP-020-6(706)283--76-28

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 415 SY 2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT) 440 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 26 EACH

SECTION NO. 0004

ROADWAY ITEMS

LINN COUNTY MP-151-6(725)38--76-57

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 830 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

SECTION NO. 0004

ROADWAY ITEMS

LINN COUNTY MP-151-6(725)38--76-57

2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)
2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT

95 SY 60 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 214 Proposal ID: 67-0293-718

Proposed Contract Period: Late Start Date of 08/14/17 with 10 WORK DAYS

Project(s):

Project No: MPIN-029-3(718)106--0N-67

County: MONONA

Type of Work: HMA PAVED SHOULDER - FOG SEAL

Route: I-29 Length: 8.06 miles

Location: FROM N OF E60 TO IOWA 175 (SB)

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 215 Proposal ID: 73-0024-709

Proposed Contract Period: Late Start Date of 08/28/17 with 15 WORK DAYS

Project(s):

Project No: MP-002-4(709)29--76-73

County: PAGE

Type of Work: HMA CRACK FILLING

Route: IOWA 2 Length: 19.50 miles

Location: FROM U.S. 59 TO ECL OF CLARINDA

Project No: MP-059-4(706)11--76-73

County: PAGE

Type of Work: HMA JOINT & CRACK SEALING
Route: U.S. 59 Length:
Location: FROM SOUTH OF IOWA 2 TO J18 Length: 9.08 miles

Item Description

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 216 Proposal ID: 78-0064-715

Proposed Contract Period: Late Start Date of 10/16/17 with 5 WORK DAYS

Project(s):

Project No: MP-006-4(715)4--76-78

County: POTTAWATTAMIE
Type of Work: PCC PATCHING

Route: U.S. 6 Length: 4.27 miles

Location: FROM 6TH ST TO JUST E OF I-80 IN COUNCIL BLUFFS

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 211 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 19 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 217 Proposal ID: 92-0925-707

Proposed Contract Period: Late Start Date of 10/09/17 with 10 WORK DAYS

Project(s):

Project No: MP-092-5(707)218--76-92

County: WASHINGTON Type of Work: PCC PATCHING

Route: IOWA 92 Length: 11.92 miles

Location: FROM KEOKUK COUNTY TO IOWA 1

Item No. Item Description Quantity/Unit ______ SECTION NO. 0001 ROADWAY ITEMS 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT) 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 173 SY 30 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 07-3802-509

Proposed Contract Period: Late Start Date of 08/07/17 with 55 WORK DAYS

Project(s):

Project No: MBIN-380-2(509)71--0M-07

County: BLACK HAWK
Type of Work: REVETMENT

Route: I-380 Length: 0.00 miles

Location: CEDAR RIVER 0.4 MI E OF W JCT US 20

Item No. Item Description Quantity/Unit

80 CY

SECTION NO. 0001

ROADWAY ITEMS

2102-2625000 EMBANKMENT-IN-PLACE

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 31-0209-234

Proposed Contract Period: Late Start Date of 07/17/17 with 20 WORK DAYS

Project(s):

Project No: NHSN-020-9(234)--2R-31

County: DUBUQUE
Type of Work: GRADING

Route: U.S. 20 Length: 0.00 miles

Location: 0.5 MI E OF IA 136 IN DYERSVILLE - PARK AND RIDE PARKING

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 288 CY 2301-1032060 STD/S-F PCC PAV'T, CL C CL 2, 6" 53 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 67-1751-069

Proposed Contract Period: Late Start Date of 10/16/17 with 10 WORK DAYS

Project(s):

Project No: STPN-175-1(69)--2J-67

County: MONONA

Type of Work: PIPE CULVERTS

Route: IOWA 175 Length: 0.00 miles

Location: NEAR OAK AVE IN TURIN

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-861

Proposed Contract Period: By individual sites.

Site 01: STANDARD TIME FRAME

Late Start Date of 07/31/17 with 20 WORK DAYS

Site 02: ACCELERATED TIME FRAME

Late Start Date of 05/29/17 with 5 WORK DAYS

Project(s):

Project No: NHSN-000-S(861)--2R-00

County: STATEWIDE Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 00-000S-893

Proposed Contract Period: Late Start Date of 08/07/17 with 60 WORK DAYS

Project(s):

Project No: NHSN-000-S(893)--2R-00

County: STATEWIDE
Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 1

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 59-C059-057

Proposed Contract Period: Late Start Date of 09/18/17 with 30 WORK DAYS

Project(s):

Project No: HSIP-S-C059(57)--6C-59

County: LUCAS

Type of Work: PAVEMENT MARKINGS

Route: VARIOUS ROUTES Length: 51.41 miles Location: ON VARIOUS PAVED ROUTES, 51.41 MILES

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 354 Proposal ID: 69-C069-060

Proposed Contract Period: Late Start Date of 08/21/17 with 20 WORK DAYS

Project(s):

Project No: HSIP-C069(60)--8X-69

County: MONTGOMERY

Type of Work: PAVEMENT MARKINGS

Route: VARIOUS Length: 19.41 miles

Location: VARIOUS ROUTES ON H54, H34, M37, 205TH STREET & GINKO AVE

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 06-0306-245

Proposed Contract Period: Approx Start Date of 06/26/17 with 20 WORK DAYS

Project(s):

Project No: NHSN-030-6(245)--2R-06

County: BENTON

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 30 Length: 0.00 miles

Location: PARCEL 74A, 2365 73RD ST, VAN HORNE

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 402 Proposal ID: 16-0308-046

Proposed Contract Period: Approx Start Date of 06/26/17 with 10 WORK DAYS

Project(s):

Project No: NHSN-030-8(46)--2R-16

County: CEDAR

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 30 Length: 6.03 miles Location: PARCEL 102, 238 ADAMS AVENUE, LISBON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 97-0772-022

Proposed Contract Period: Late Start Date of 06/19/17 with 40 WORK DAYS

Project(s):

Project No: BRFN-077-2(22)--39-97

County: WOODBURY

Type of Work: BRIDGE CLEANING

Route: U.S. 77 Length: 0.00 miles

Location: IN THE CITY OF SIOUX CITY OVER THE MISSOURI RIVER

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 602 Proposal ID: 97-1296-039

Proposed Contract Period: Late Start Date of 06/19/17 with 40 WORK DAYS

Project(s):

Project No: IMN-129-6(39)0--0E-97

County: WOODBURY

Type of Work: BRIDGE CLEANING

Route: I-129 Length: 0.00 miles

Location: MISSOURI RIVER BRIDGE IN SIOUX CITY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 18, 2017 10:00 A.M.

Proposed Bid Order: 981 Proposal ID: 97-0293-716

Proposed Contract Period: Late Start Date of 09/25/17 with 25 WORK DAYS

Project(s):

Project No: MPIN-029-3(716)134--0N-97

County: WOODBURY
Type of Work: FENCING

Route: I-29 Length: 2.81 miles

Location: FROM NORTH OF K25 (SALIX INT) NORTH TO 1.4 MI NORTH OF D51.