

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 06-C006-080

Proposed Contract Period: Late Start Date of 08/15/11 with 45 WORK DAYS

Project(s):

Project No: BROS-C006(80)--5F-06

County: BENTON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 13TH AVENUE Length: 0.00 miles

Location: OVER PRAIRIE CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 80'-0 X 30-6 CCS BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	175 CY
2404-7775000	REINFORC STEEL	45,513 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 07-C007-120

Proposed Contract Period: Late Start Date of 08/08/11 with 55 WORK DAYS

Project(s):

Project No: FM-C007(120)--55-07

County: BLACK HAWK

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: EAGLE ROAD Length: 0.00 miles

Location: HWY 63 TO KIMBALL AVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
2102-2710070	ITEMS FOR A TWIN 8' X 6' X 66' PRECAST CONC BOX CULVERT EXCAVATION, CL 10, RDWY+BORROW	873 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 07-0206-059

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Proposal Note:

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING
=====

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS
LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL
PROPOSALS AS SHOWN BELOW:

B.O.	PROPOSAL ID	COUNTY	PROJECT NO.
====	=====	=====	=====
XXX	07-0206-059-M	BLACK HAWK	BRFN-020-6(59)--39-07
.			BRFN-027-7(02)--39-07
AND			
XXX	07-0206-059	BLACK HAWK	BRFN-020-6(59)--39-07
XXX	07-0277-002	BLACK HAWK	BRFN-027-7(02)--39-07

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Project(s):

Project No: BRFN-020-6(59)--39-07
 County: BLACK HAWK
 Type of Work: BRIDGE RAIL RETROFIT
 Route: U.S. 20 Length: 0.00 miles
 Location: IN THE CITY OF WATERLOO AT 8 LOCATIONS ON
 US 20/I-380

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0411; REPAIRS TO A 383'-4 X 26' PPCB	
	RETROFIT RAIL	BRFN-020-6(59)--39-07
2403-010000	STRUCT CONC (MISCELLANEOUS)	43 CY
SECTION NO. 0002		
ROADWAY ITEMS		
		BRFN-020-6(59)--39-07
2102-2625000	EMBANKMENT-IN-PLACE	1,880 CY
2122-5190007	PAVED SHLD, PCC, 7"	387 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 07-0277-002

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Proposal Note:

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING
=====

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS
LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL
PROPOSALS AS SHOWN BELOW:

B.O.	PROPOSAL ID	COUNTY	PROJECT NO.
====	=====	=====	=====
XXX	07-0206-059-M	BLACK HAWK	BRFN-020-6(59)--39-07
.			BRFN-027-7(02)--39-07
AND			
XXX	07-0206-059	BLACK HAWK	BRFN-020-6(59)--39-07
XXX	07-0277-002	BLACK HAWK	BRFN-027-7(02)--39-07

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Project(s):

Project No: BRFN-027-7(2)--39-07
County: BLACK HAWK
Type of Work: BRIDGE RAIL RETROFIT
Route: IOWA 27 Length: 0.00 miles
Location: IN THE CITY OF CEDAR FALLS AT 4 LOCATIONS
ON IA. 58/27

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 1111; REPAIRS TO A DUAL 2857'-6 X VARIES PCCB	
	RETROFIT RAIL	BRFN-027-7(2)--39-07
2403-010000	STRUCT CONC (MISCELLANEOUS)	3 CY
SECTION NO. 0002		
	ROADWAY ITEMS	
		BRFN-027-7(2)--39-07
2102-2625000	EMBANKMENT-IN-PLACE	300 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 16-C016-081

Proposed Contract Period: Late Start Date of 07/05/11 with 75 WORK DAYS

Project(s):

Project No: BROS-C016(81)--8J-16

County: CEDAR

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: STONE MILL ROAD Length: 0.10 miles

Location: OVER ROCK CREEK, APPROX. 3 MILES SOUTHWEST OF TIPTON

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 151'-4 X 30'-6 PPCB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,048 CY
2403-0100010	STRUCT CONC (BRIDGE)	227 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	57,796 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 24-C024-097

Proposed Contract Period: Late Start Date of 07/18/11 with 70 WORK DAYS

Project(s):

Project No: BROS-C024(97)--5F-24

County: CRAWFORD

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: M27 Length: 0.00 miles

Location: OVER BIG CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 12' 72' RCB CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,423 CY
2403-0100020	STRUCT CONC (RCB CULV)	411 CY
2404-7775000	REINFORC STEEL	55,050 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 26-C026-073

Proposed Contract Period: Late Start Date of 08/01/11 with 65 WORK DAYS

Project(s):

Project No: BROS-C026(73)--5F-26

County: DAVIS

Type of Work: BRIDGE REPLACEMENT - CCS

Route: LILAC AVENUE Length: 0.00 miles

Location: OVER CHEQUEST CREEK, 3 MI NORTH OF BLOOMFIELD.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110'-0 X 24'-0 CCS BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,710 CY
2403-0100010	STRUCT CONC (BRIDGE)	217 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	55,094 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 31-C031-050

Proposed Contract Period: Late Start Date of 06/20/11 with 80 WORK DAYS

Project(s):

Project No: EDP-C031(50)--7Y-31

County: DUBUQUE

Type of Work: STRUCTURES (MISCELLANEOUS)

Route: MRT/HERITAGE TRAIL Length: 0.10 miles

Location: RUPP HOLLOW RD TO SOUTH JOHN DEERE RD

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	1,400 CY
SECTION NO. 0002		
ITEMS FOR A 136'-7 X 12'-0 STEEL TRUSS PEDESTRIAN BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,309 CY
2403-0100010	STRUCT CONC (BRIDGE)	52 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	11,698 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 31-C031-062

Proposed Contract Period: Late Start Date of 07/25/11 with 65 WORK DAYS

Project(s):

Project No: BRS-C031(62)--60-31

County: DUBUQUE

Type of Work: BRIDGE AND APPROACHES - CCS

Route: C64(PETERSBURG ROAD) Length: 0.00 miles

Location: OVER COFFEE CREEK, ALONG WCL OF NEW VIENNNA

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110'-0 X 30'-6 CCS BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,319 CY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	65 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	60 TON
2403-0100010	STRUCT CONC (BRIDGE)	256 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	66,341 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 00A Proposal ID: 07-0206-059-M

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Proposal Note:

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING
=====

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS
LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL
PROPOSALS AS SHOWN BELOW:

B.O.	PROPOSAL ID	COUNTY	PROJECT NO.
====	=====	=====	=====
XXX	07-0206-059-M	BLACK HAWK	BRFN-020-6(59)--39-07
.			BRFN-027-7(02)--39-07
AND			
XXX	07-0206-059	BLACK HAWK	BRFN-020-6(59)--39-07
XXX	07-0277-002	BLACK HAWK	BRFN-027-7(02)--39-07

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Project(s):

Project No: BRFN-020-6(59)--39-07
 County: BLACK HAWK
 Type of Work: BRIDGE RAIL RETROFIT
 Route: U.S. 20 Length: 0.00 miles
 Location: IN THE CITY OF WATERLOO AT 8 LOCATIONS ON
 US 20/I-380

Project No: BRFN-027-7(2)--39-07
 County: BLACK HAWK
 Type of Work: BRIDGE RAIL RETROFIT
 Route: IOWA 27 Length: 0.00 miles
 Location: IN THE CITY OF CEDAR FALLS AT 4 LOCATIONS
 ON IA. 58/27

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	DESIGN NO. 0211; REPAIRS TO A 264'-6 X 84' PPCB	
	RETROFIT RAIL	BRFN-0206-6(59)--39-07
2403-0100000	STRUCT CONC (MISCELLANEOUS)	43 CY
	SECTION NO. 0002	
	ROADWAY ITEMS	
		BRFN-020-6(59)--39-07
2102-2625000	EMBANKMENT-IN-PLACE	1,880 CY
2122-5190007	PAVED SHLD, PCC, 7"	387 SY
	SECTION NO. 0003	
	DESIGN NO. 1311; REPAIRS TO A DUAL 632'-6 X VARIES PPCB	
	RETROFIT RAIL	BRFN-027-7(2)--39-07

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0003

DESIGN NO. 1311; REPAIRS TO A DUAL 632'-6 X VARIES PPCB

RETROFIT RAIL

BRFN-027-7(2)--39-07

2403-0100000 STRUCT CONC (MISCELLANEOUS)

3 CY

SECTION NO. 0004

ROADWAY ITEMS

BRFN-027-7(2)--39-07

2102-2625000 EMBANKMENT-IN-PLACE

300 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 39-0254-038

Proposed Contract Period: Late Start Date of 05/23/11 with 90 WORK DAYS

Project(s):

Project No: FSSN-025-4(38)--3T-39

County: GUTHRIE

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: IOWA 25 Length: 0.00 miles

Location: OVER MASON CREEK
1.0 MILE SOUTH OF IA 44

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 111; A 163'-10 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	497 CY
2404-7775000	REINFORC STEEL	16,212 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	76,734 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5,377 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	84 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 46-C046-050

Proposed Contract Period: Late Start Date of 09/12/11 with 25 WORK DAYS

Project(s):

Project No: BROS-C046(50)--8J-46

County: HUMBOLDT

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: 260TH STREET Length: 0.00 miles

Location: 0.1 MI E OFNW COR SEC 25 T91N R27W NORWAY TWP

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 47-C047-047

Proposed Contract Period: Late Start Date of 07/11/11 with 70 WORK DAYS

Project(s):

Project No: BRS-C047(47)--60-47

County: IDA

Type of Work: BRIDGE AND APPROACHES - CCS

Route: M25 Length: 0.00 miles

Location: OVER ELK CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 140'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,526 CY
2403-0100010	STRUCT CONC (BRIDGE)	369 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	87,438 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 49-C049-049

Proposed Contract Period: Late Start Date of 06/06/11 with 90 WORK DAYS

Project(s):

Project No: BRS-C049(49)--60-49

County: JACKSON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 150TH STREET Length: 0.50 miles

Location: OVER BRUSH CREEK,

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 140'-0 X 30'-6 CCS BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	12,581 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	4,600 SY
2403-0100010	STRUCT CONC (BRIDGE)	369 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	86,891 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 53-C053-060

Proposed Contract Period: Late Start Date of 05/23/11 with 120 WORK DAYS

Project(s):

Project No: BROS-C053(60)--5F-53

County: JONES

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 80TH STREET Length: 0.10 miles

Location: OVER TRIBUTARY TO WAPSIPINICON RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 70' X 30'-6 CCS BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	21,685 CY
2108-5025000	OVERHAUL	3,265 ST-Y
2403-0100010	STRUCT CONC (BRIDGE)	160 CY
2403-0100020	STRUCT CONC (RCB CULV)	241 CY
2404-7775000	REINFORC STEEL	73,709 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 86-C086-078

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Project(s):

Project No: BHOS-C086(78)--5N-86

County: TAMA

Type of Work: RECONSTRUCTION - BRIDGE WIDENING

Route: C AVENUE Length: 0.10 miles

Location: NEW WIDER DECK ON BRIDGE OVER IOWA RIVER

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR A 520'-6 X 20'-0 CONTINUOUS STEEL I-BEAM BRIDGE		
WIDENING TO 30' ROADWAY		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,246 CY
2403-0100010	STRUCT CONC (BRIDGE)	523 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	158,919 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 96-C096-103

Proposed Contract Period: Late Start Date of 08/15/11 with 45 WORK DAYS

Project(s):

Project No: BHS-C096(103)--63-96

County: WINNESHIEK

Type of Work: BRIDGE REHABILITATION

Route: W14 Length: 0.00 miles

Location: OVER BOHEMIAN CREEK, SOUTH OF B16 INTERSECTION IN SPILLVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 107' X 26' PPCB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	20 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,384 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 96-C096-104

Proposed Contract Period: Late Start Date of 06/27/11 with 80 WORK DAYS

Project(s):

Project No: BROS-C096(104)--8J-96

County: WINNESHIEK

Type of Work: RCB CULVERT NEW - TWIN BOX

Route: RANCH RD Length: 0.00 miles

Location: 125' S. OF INT. WITH OLD STAGE RD.

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR A TWIN 10' X 10' X 84' RCB CULVERT		
2102-2625000	EMBANKMENT-IN-PLACE	160 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	22,433 CY
2403-0100020	STRUCT CONC (RCB CULV)	337 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	45,056 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 018 Proposal ID: 97-C097-099

Proposed Contract Period: Late Start Date of 06/27/11 with 85 WORK DAYS

Project(s):

Project No: BROS-C097(99)--5F-97

County: WOODBURY

Type of Work: BRIDGE AND APPROACHES - CCS

Route: D38 Length: 0.07 miles

Location: JUST E. OF MICHIGAN AVE.
KEDRON TWP SECTION 34.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 150'-0 X 30'-6 CCS BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,747 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	749 SY
2403-0100010	STRUCT CONC (BRIDGE)	421 CY
2404-7775000	REINFORC STEEL	144 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	95,793 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 019 Proposal ID: 97-0311-034

Proposed Contract Period: Late Start Date of 08/29/11 with 40 WORK DAYS

Project(s):

Project No: STPN-031-1(34)--2J-97

County: WOODBURY

Type of Work: RCB CULVERT EXTENSION - SINGLE BOX

Route: IOWA 31 Length: 0.00 miles

Location: 3.4 MILES N. OF IA. 141

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 2111; 5' X 5' X 37' RCB EXTENSION WITH FLUME RT.		
2403-0100020	STRUCT CONC (RCB CULV)	70 CY
2404-7775000	REINFORC STEEL	9,144 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,715 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 07-1185-643

Proposed Contract Period: Late Start Date of 08/29/11 with 30 WORK DAYS

Project(s):

Project No: SRTS-U-1185(643)--8U-07

County: BLACK HAWK

Type of Work: PCC SIDEWALK/TRAIL

Route: ROWND STREET Length: 0.00 miles

Location: IN THE CITY OF CEDAR FALLS, SIDEWALK FROM BICENTENNIAL
DRIVE TO HAWTHORNE DRIVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	50 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 07-2187-202

Proposed Contract Period: Late Start Date of 08/15/11 with 40 WORK DAYS

Project(s):

Project No: HSIPX-218-7(202)--3L-07

County: BLACK HAWK

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: U.S. 218 Length: 0.01 miles

Location: CO. RD. C-57 INTERSECTION 2 MILES S. OF BREMER CO.
LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	8,000 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	6,900 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 11-7422-612

Proposed Contract Period: Late Start Date of 07/11/11 with 65 WORK DAYS

Project(s):

Project No: STP-U-7422(612)--70-11

County: BUENA VISTA

Type of Work: PCC PAVEMENT - GRADE AND NEW

Route: VESTAL STREET Length: 0.73 miles

Location: FROM WEST 10TH ST. NORTH TO C49

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	15,336 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	10,940 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 17-7967-600

Proposed Contract Period: Late Start Date of 05/23/11 with 190 WORK DAYS

Project(s):

Project No: STP-U-7967(600)--27-17
 County: CERRO GORDO
 Type of Work: PCC PAVEMENT - GRADE & REPLACE
 Route: MAIN & LAKE ST. Length: 0.00 miles
 Location: IN THE CITY OF VENTURA, HWY 18 TO SCL OF VENTURA

Project No: STP-E-7967(601)--8V-17
 County: CERRO GORDO
 Type of Work: PCC PAVEMENT - GRADE & REPLACE
 Route: MAIN & LAKE ST. Length: 0.50 miles
 Location: IN THE CITY OF VENTURA, FISHING JETTY ON MAIN STREET TO HWY
 18 INCLUDING LAKE ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - BASE BID - STP-U-7967(600)--27-17		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	11,410 CY
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	14,086 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	13,445 SY
2303-0121500	HMA (300K ESAL) BASE, 1/2"	72 SY
2303-0122500	HMA (300K ESAL) I-S, 1/2", NO FRIC	144 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	90 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	1 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 23-1415-618

Proposed Contract Period: Late Start Date of 06/20/11 with 80 WORK DAYS

Project(s):

Project No: HDP-1415(618)--71-23

County: CLINTON

Type of Work: PCC PAVEMENT - GRADE AND NEW

Route: 19TH AVENUE Length: 0.00 miles

Location: IN THE CITY OF CLINTON, FROM SPRINGDALE DR. TO WEST OF
RANDALL COURT

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	57,320 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	10,925 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	2,763 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 33-C033-110

Proposed Contract Period: Late Start Date of 08/15/11 with 30 WORK DAYS

Project(s):

Project No: STP-E-C033(110)--5K-33

County: FAYETTE

Type of Work: PCC SIDEWALK/TRAIL

Route: CANOE & GREAT RIVER Length: 3.00 miles

Location: ELGIN TO CLERMONT TO NIMS BRIDGE

PART OF ECN TRAIL - MULTI PURPOSE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	21,963 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 37-0042-039

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Project(s):

Project No: STPN-004-2(39)--2J-37

County: GREENE

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: IOWA 4 Length: 0.25 miles

Location: IN THE CITY OF JEFFERSON-N GRIMMEL RD/ W
CENTRAL AVE/NEW BACKAGE RDS;IA 4 DETOUR

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	20,240 CY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	1,945 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	26,700 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 50-0805-293

Proposed Contract Period: Late Start Date of 05/31/11 with 90 WORK DAYS
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.
Late Start Date of 05/31/11 with 4 WORK DAYS
Site 02: SEE SITE NUMBER 02 DESCRIPTION BELOW.
Late Start Date of 06/06/11 with 40 WORK DAYS

Proposal Note:

*** SITE NUMBER 01 ***

TO COMPLETE THE INSIDE SHOULDER STRENGTHENING FROM STA.
2725+27 TO 2747+95.5 EASTBOUND AND STA. 2724+17.3 TO 2749+50
WESTBOUND

*** SITE NUMBER 02 ***

TO COMPLETE THE WEST SIDE RAMP EXTENSIONS (EB EXIT AND WB
ENTRANCE).

Project(s):

Project No: IMX-080-5(293)168--02-50

County: JASPER

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: I-80 Length: 1.30 miles

Location: IOWA SPEEDWAY DR. INTERCHANGE 4 MILES E. OF IA. 14

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	18,498 CY
2301-1034120	STD/S-F PCC PAV'T, CL C CL 3I, 12"	6,924 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 52-5557-616-A

Proposed Contract Period: Approx Start Date of 06/13/11 with 35 WORK DAYS

Project(s):

Project No: STP-E-5557(616)--8V-52

County: JOHNSON

Type of Work: PCC SIDEWALK/TRAIL

Route: DUBUQUE STREET TRAIL Length: 1.53 miles

Location: IN THE CITY OF NORTH LIBERTY, SOUTH CITY LIMIT TO NORTH CITY
LIMIT

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,630 CY
2403-0100020	STRUCT CONC (RCB CULV)	10 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,290 LB
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	9,055 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 110 Proposal ID: 57-C057-114

Proposed Contract Period: Late Start Date of 08/22/11 with 35 WORK DAYS

Project(s):

Project No: FM-C057(114)--55-57

County: LINN

Type of Work: PCC OVERLAY - UNBONDED

Route: SPRINGVILLE ROAD Length: 1.84 miles

Location: MARTELLE RD TO U.S.151

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	230 TON
2310-5151040	PCC OVERLAY, FURN ONLY	4,743 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	24,242 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 111 Proposal ID: 66-C066-053

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Project(s):

Project No: STP-S-C066(53)--5E-66
 County: MITCHELL
 Type of Work: PCC OVERLAY - UNBONDED
 Route: T64 & B17 Length: 10.25 miles
 Location: A46 FROM IA 9 TO T64, T64 FROM A46 TO
 SCL, & B17 FROM T64 TO ECL

Project No: FM-C066(54)--55-66
 County: MITCHELL
 Type of Work: PCC OVERLAY - UNBONDED
 Route: MONUMENT AVENUE Length: 4.50 miles
 Location: S SEC 30-100-16 TO NW SEC 8-100-16

Project No: L-LPPCC-1--73-66
 County: MITCHELL
 Type of Work: PCC OVERLAY - UNBONDED
 Route: T46 & A19 Length: 5.10 miles
 Location: W 1/4 COR SEC 36-100-16 TO N 4.5 MILES T
 O NW COR SEC 12-100-16

Project No: L-LPPCC-2--73-66
 County: MITCHELL
 Type of Work: PCC OVERLAY - UNBONDED
 Route: A46 Length: 5.15 miles
 Location: HWY9/360TH EAST 5.2 MILES TO NE COR SEC
 25-98-15

Project No: L-LPPCC-4--73-66
 County: MITCHELL
 Type of Work: PCC OVERLAY - UNBONDED
 Route: T36 Length: 3.90 miles
 Location: W 1/4 SEC 23-99-17 NORTH 4 MILES TO W 1/
 4 COR SEC 35-100-17

Project No: L-LPPCC-5--73-66
 County: MITCHELL
 Type of Work: PCC OVERLAY - UNBONDED
 Route: B17 Length: 5.00 miles
 Location: US HWY 218 EAST 5 MILES ON 320TH TO NE C
 OR SEC 17-97-15

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
2310-5151040	ROADWAY ITEMS - STP-S-C066(53)--5E-66 PCC OVERLAY, FURN ONLY	14,070 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001		
ROADWAY ITEMS - STP-S-C066(53)--5E-66		
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	113,284 SY
SECTION NO. 0002		
ROADWAY ITEMS - FM-C066(54)--55-66		
2310-5151040	PCC OVERLAY, FURN ONLY	6,149 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	49,633 SY
SECTION NO. 0003		
ROADWAY ITEMS - L-LPPCC-1--73-66		
2310-5151040	PCC OVERLAY, FURN ONLY	8,300 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	66,672 SY
SECTION NO. 0004		
ROADWAY ITEMS - L-LPPCC-2--73-66		
2310-5151040	PCC OVERLAY, FURN ONLY	7,884 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	63,700 SY
SECTION NO. 0005		
ROADWAY ITEMS - L-LPPCC-4--73-66		
2310-5151040	PCC OVERLAY, FURN ONLY	6,491 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	52,353 SY
SECTION NO. 0006		
ROADWAY ITEMS - L-LPPCC-5--73-66		
2310-5151040	PCC OVERLAY, FURN ONLY	7,651 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	61,930 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 112 Proposal ID: 75-C075-126

Proposed Contract Period: Late Start Date of 07/11/11 with 60 WORK DAYS

Project(s):

Project No: STP-S-C075(126)--5E-75

County: PLYMOUTH

Type of Work: PCC OVERLAY - UNBONDED

Route: C38 Length: 10.00 miles

Location: K-64 TO CHEROKEE COUNTY LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2301-1032090	STD/S-F PCC PAV'T, CL C CL 2, 9"	3,244 SY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	600 TON
2310-5151040	PCC OVERLAY, FURN ONLY	26,465 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	126,031 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 113 Proposal ID: 75-4257-626

Proposed Contract Period: Late Start Date of 09/06/11 with 30 WORK DAYS

Proposal Note:

*** WORK RESTRICTION ***

WORK ON THE 6TH AVENUE INTERSECTION CANNOT BEGIN BEFORE JUNE
6, 2011. THE PUBLIC SCHOOL THAT IS LOCATED SOUTH ON
6TH AVENUE WILL BE IN SESSION UNTIL SUMMER BREAK BEGINS.

Project(s):

Project No: STP-U-4257(626)--70-75

County: PLYMOUTH

Type of Work: PCC PAVEMENT WIDENING

Route: LINCOLN ST/LAKE AVE Length: 0.00 miles

Location: IN THE CITY OF LE MARS, WIDENING TURN LANES AT 4TH ST. SW;
6TH ST. SW; 12TH ST. SW; 21ST ST SW; 24TH ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,084 CY
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	229 SY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	3,459 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 114 Proposal ID: 77-8260-626

Proposed Contract Period: Late Start Date of 05/23/11 with 105 WORK DAYS

Project(s):

Project No: STP-U-8260(626)--70-77

County: POLK

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: GRAND AVENUE Length: 0.54 miles

Location: IN THE CITY OF WEST DES MOINES FROM INTERSTATE 35 RAMPS
THROUGH SOUTH 50TH STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	16,234 CY
2301-1032090	STD/S-F PCC PAV'T, CL C CL 2, 9"	13,423 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	1,751 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 115 Proposal ID: 82-0741-160

Proposed Contract Period: Late Start Date of 05/23/11 with 240 WORK DAYS

Project(s):

Project No: IM-074-1(160)1--13-82
 County: SCOTT
 Type of Work: PCC PAVEMENT - GRADE & REPLACE
 Route: I-74 Length: 0.00 miles
 Location: IN THE CITY OF DAVENPORT AT I74/53RD ST. INTERCHANGE

Project No: IM-074-1(168)1--13-82
 County: SCOTT
 Type of Work: RECONSTRUCTION - BRIDGE WIDENING
 Route: I-74 Length: 0.00 miles
 Location: 1.1 MI E I-80
 53RD STREET OVER I-74 IN DAVEMPORT

Project No: IM-074-1(190)1--13-82
 County: SCOTT
 Type of Work: TRAFFIC SIGNS
 Route: I-74 Length: 0.00 miles
 Location: IN THE CITY OF DAVENPORT AT 53RD ST. INTERCHANGE

Project No: IM-074-1(191)1--13-82
 County: SCOTT
 Type of Work: LIGHTING
 Route: I-74 Length: 0.00 miles
 Location: IN THE CITY OF DAVENPORT AT 53RD ST. INTERCHANGE

Project No: IM-074-1(192)1--13-82
 County: SCOTT
 Type of Work: TRAFFIC SIGNALS
 Route: I-74 Length: 0.00 miles
 Location: IN THE CITY OF DAVENPORT AT 53RD ST. INTERCHANGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - IM-074-1(160)1--13-82		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	165,413 CY
2122-5190010	PAVED SHLD, PCC, 10"	4,735 SY
2301-1034100	STD/S-F PCC PAV'T, CL C CL 3I, 10"	62,541 SY
2303-0021500	HMA (300K ESAL) BASE, 1/2"	211 TON
2303-0133500	HMA (1M ESAL) SURF, 1/2", NO FRIC	35 SY
SECTION NO. 0002		
ALTERNATE 'AA' OPTION 1: PCC SHOULDER - (160)		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	3,505 SY
SECTION NO. 0004		
DESIGN NO. 0111; A 468'-0 X VAR. HEIGHT REINFORCED CONCRETE		
RETAINING WALL - IM-074-1(160)1--13-82		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0004

DESIGN NO. 0111; A 468'-0 X VAR. HEIGHT REINFORCED CONCRETE
RETAINING WALL - IM-074-1(160)1--13-82

2403-0100000	STRUCT CONC (MISCELLANEOUS)	406 CY
2404-7775000	REINFORC STEEL	26,665 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	37,578 LB

SECTION NO. 0005

DESIGN NO. 1608; A TWIN 10'-0 X 12'-0 REINF. CONCRETE BOX
CULVERT EXTENSION - IM-074-1(160)1--13-82

2403-0100020	STRUCT CONC (RCB CULV)	324 CY
2404-7775000	REINFORC STEEL	43,058 LB

SECTION NO. 0007

DESIGN NO. 1108; WIDEN EXISTING BRIDGE TO A 253'-8 X 87'-0
WITH 10' SIDEWALK - IM-074-1(168)1--13-82

2403-0100010	STRUCT CONC (BRIDGE)	430 CY
2404-7775000	REINFORC STEEL	5,733 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	95,697 LB
2413-0698074	DECK REPAIR, CL A	102 SY

SECTION NO. 0008

ALTERNATE 'BB' OPTION 1: CL O PCC - (168)
BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN

2413-0698066	DECK OVERLAY (CL O PCC)	2,339 SY
--------------	-------------------------	----------

SECTION NO. 0009

ALTERNATE 'BB' OPTION 2: CL HPC-O PCC - (168)
BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN

2413-0698067	DECK OVERLAY (CL HPC-O PCC)	2,339 SY
--------------	-----------------------------	----------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 116 Proposal ID: 84-C084-135

Proposed Contract Period: Late Start Date of 07/11/11 with 60 WORK DAYS

Project(s):

Project No: L-9-08PAV--73-84
 County: SIOUX
 Type of Work: PCC PAVEMENT - NEW
 Route: 390TH STREET Length: 1.00 miles
 Location: EAST OF SIOUX CENTER

Project No: STP-S-C084(135)--5E-84
 County: SIOUX
 Type of Work: PCC OVERLAY - UNBONDED
 Route: L14 Length: 8.00 miles
 Location: HWY #18 AT BOYDEN, IA TO SOUTH TO S6-T95
 N-R43W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - L-9-08PAV--73-84		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	275 CY
2301-1032000	STD/S-F PCC PAV'T, CL C CL 2, VAR THICK	13,487 SY
SECTION NO. 0002		
ROADWAY ITEMS - STP-S-C084(135)--5E-84		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5 CY
2310-5151040	PCC OVERLAY, FURN ONLY	15,726 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	102,923 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 117 Proposal ID: 95-4135-603

Proposed Contract Period: Late Start Date of 09/06/11 with 20 WORK DAYS

Project(s):

Project No: SRTS-U-4135(603)--8U-95

County: WINNEBAGO

Type of Work: PCC SIDEWALK/TRAIL

Route: URBAN TRAIL SYSTEM Length: 0.73 miles

Location: SIDEWALKS ON S WINNEBAGO, S LAKE, S 10TH
AVE E, S GRANT AND S LINCOLN

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	750 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 04-C004-084

Proposed Contract Period: Late Start Date of 07/18/11 with 65 WORK DAYS

Project(s):

Project No: FM-C004(83)--55-04
 County: APPANOOSE
 Type of Work: HMA RESURFACING
 Route: 230TH AVENUE Length: 0.35 miles
 Location: 230TH AVE W 0.35 MI

Project No: STP-S-C004(84)--5E-04
 County: APPANOOSE
 Type of Work: HMA RESURFACING
 Route: J-46 Length: 6.00 miles
 Location: HWY 5 WEST TO NUMA

Project No: FM-C004(91)--55-04
 County: APPANOOSE
 Type of Work: HMA RESURFACING
 Route: 244TH AVENUE Length: 2.00 miles
 Location: MORAVIA CL TO SH5

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		FM-C004(83)--55-04
2303-0021750	HMA (300K ESAL) BASE, 3/4"	878 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	657 TON
SECTION NO. 0002		
ROADWAY ITEMS		
		STP-S-C004(84)--5E-04
2303-0021750	HMA (300K ESAL) BASE, 3/4"	8,337 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	6,866 TON
SECTION NO. 0003		
ROADWAY ITEMS		
		FM-C004(91)--55-04
2303-0021750	HMA (300K ESAL) BASE, 3/4"	2,771 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	2,358 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 07-C007-106

Proposed Contract Period: Late Start Date of 09/12/11 with 25 WORK DAYS

Project(s):

Project No: STP-S-C007(106)--5E-07

County: BLACK HAWK

Type of Work: HMA RESURFACING WITH MILLING

Route: UNION ROAD Length: 5.00 miles

Location: CEDAR FALL CL TO WINSLOW RD C-55

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	7,865 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,585 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 08-C008-055

Proposed Contract Period: Late Start Date of 09/19/11 with 15 WORK DAYS

Project(s):

Project No: FM-C008(55)--55-08

County: BOONE

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: E-26 Length: 2.50 miles

Location: KALE ROAD TO EAST AND SOUTH 2.5 MILES

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	5,931 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 18-0032-056

Proposed Contract Period: Late Start Date of 07/25/11 with 45 WORK DAYS

Project(s):

Project No: STP-003-2(56)--2C-18

County: CHEROKEE

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 3 Length: 2.39 miles

Location: FROM US 59 SE TO E. JCT. CO. RD. C-38

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	200 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	4,538 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	4,278 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	93 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 20-0352-397

Proposed Contract Period: Late Start Date of 06/20/11 with 80 WORK DAYS

Project(s):

Project No: IMX-035-2(397)33--02-20

County: CLARKE

Type of Work: HMA RESURFACING

Route: I-35 Length: 9.24 miles

Location: FROM JUST N. OF US 34 INTERCHANGE N. TO WARREN CO. LINE
(SBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	30 CY
2122-5190110	PAVED SHLD, PCC, 11"	1,242 SY
2301-1034110	STD/S-F PCC PAV'T, CL C CL 3I, 11"	1,867 SY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	9,081 TON
2303-0062500	HMA (30M ESAL) INTERMEDIATE, 1/2"	15,050 TON
2303-0063502	HMA (30M ESAL) SURF, 1/2", FRIC L-2	12,040 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 23-1361-063

Proposed Contract Period: Late Start Date of 05/23/11 with 100 WORK DAYS

Project(s):

Project No: STP-136-1(63)--2C-23

County: CLINTON

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 136 Length: 16.53 miles

Location: FROM 16TH ST. NW IN CLINTON NW. TO
JUST W. OF CHARLOTTE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	3,005 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	3,454 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	29,318 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	44 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	6 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 36-C036-058

Proposed Contract Period: Late Start Date of 09/19/11 with 20 WORK DAYS

Project(s):

Project No: FM-C036(58)--55-36

County: FREMONT

Type of Work: HMA PAVEMENT - NEW

Route: M-16

Length: 3.00 miles

Location: 190TH ST TO 160TH ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0021750	HMA (300K ESAL) BASE, 3/4"	6,876 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 36-0291-079

Proposed Contract Period: By individual sites.

Site 02: TO COMPLETE WORK AFTER SWITCHING TO NORMAL TRAFFIC
Approx Start Date of 10/03/11 with 15 WORK DAYS

Proposal Note:

*** SITE 01 A+B BIDDING ***

ARTICLE 1112 A+B BIDDING SHALL APPLY TO SITE 01 WITH THE
FOLLOWING CONDITIONS:

DAILY ROAD USER COST: \$5,000.00/DAY.

MAXIMUM NUMBER OF CALENDAR DAYS ALLOWED: 120

THE ROAD USER COST PER CALENDAR DAY (DAILY ROAD USER COST)
SHOWN IN THE PROPOSAL INCLUDES COSTS TO THE TRAVELING PUBLIC
AND DAMAGES TO THE CONTRACTING AUTHORITY WHEN TRAFFIC ON
I-29 IS HEAD-TO-HEAD.

THE DOLLAR AMOUNT 'LIQUIDATED DAMAGES' FOR THE TIME BID
SITE IS EQUAL TO THE DAILY ROAD USER COST. THE DISINCENTIVE
ASSESSMENT/INCENTIVE PAYMENT IS EQUAL TO THE DAILY ROAD USER
COST.

*** CRITICAL CLOSURE ACTIVITY ***

THE CRITICAL CLOSURE ACTIVITY IS WHEN THE I-29 TRAFFIC IS
HEAD-TO-HEAD.

Project(s):

Project No: IMX-029-1(79)10--02-36

County: FREMONT

Type of Work: HMA RESURFACING

Route: I-29

Length: 5.90 miles

Location: FROM IA. 2 N. TO 1.5 MILE N. OF CO. RD. J-26(NBL ONLY)

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	12,782 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	15,039 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	7,717 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	2,307 TON
2303-0062500	HMA (30M ESAL) INTERMEDIATE, 1/2"	30,079 TON
2303-0063502	HMA (30M ESAL) SURF, 1/2", FRIC L-2	14,188 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 39-1415-017

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Project(s):

Project No: STP-025-4(37)--2C-39
 County: GUTHRIE
 Type of Work: HMA RESURFACING
 Route: IOWA 25 Length: 1.09 miles
 Location: FROM JUST W. OF IA. 141 N. TO CO. RD. E-63

Project No: STP-141-5(17)--2C-39
 County: GUTHRIE
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: IOWA 141 Length: 16.10 miles
 Location: FROM SCL OF COON RAPIDS E. TO JUST W. OF
 N. JCT. IA.4

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - STP-025-4(37)--2C-39		
2102-2625000	EMBANKMENT-IN-PLACE	120 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	1,371 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	3,949 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	3,915 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	696 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0003		
ROADWAY ITEMS - STP-141-5(17)--2C-39		
2102-2625000	EMBANKMENT-IN-PLACE	821 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	210 TON
2303-0031500	HMA (1M ESAL) BASE, 1/2"	17,910 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	38,292 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	21,972 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	57 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	5 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 41-C041-102

Proposed Contract Period: Late Start Date of 08/15/11 with 35 WORK DAYS

Project(s):

Project No: L-C02011--73-41
County: HANCOCK

Type of Work: HMA RESURFACING

Route: JEWEL AVENUE Length: 0.00 miles

Location: FROM THE INTERSECTION OF JEWELL AVENUE & 220TH ST., NORTH IN
VARIOUS LOC. TO THE END OF 7TH AVE. IN THE CITY OF BRITT

Project No: FM-C041(102)--55-41
County: HANCOCK

Type of Work: HMA RESURFACING

Route: R-18 Length: 3.50 miles

Location: 120TH STREET NORTH 3.5 MI TO INTERSECTIO
N OF ELM STREET

Project No: FM-C041(103)--55-41
County: HANCOCK

Type of Work: HMA RESURFACING

Route: B-63 Length: 8.50 miles

Location: IOWA #17 EAST TO W CORP LINE KANAWHA

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		L-C02011--73-41
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	1,655 TON
SECTION NO. 0002		
ROADWAY ITEMS		
		FM-C041(102)--55-41
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	6,245 TON
SECTION NO. 0003		
ROADWAY ITEMS		
		FM-C041(103)--55-41
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	15,999 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 51-0348-143

Proposed Contract Period: Late Start Date of 07/11/11 with 70 WORK DAYS

Project(s):

Project No: NHSX-034-8(143)--3H-51

County: JEFFERSON

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 34 Length: 7.25 miles

Location: FROM CEDAR AVE. NEAR BATAVIA EAST TO BENTON AVE. NEAR ROME
(VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	660 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	1,183 TON
2303-0031750	HMA (1M ESAL) BASE, 3/4"	5,916 TON
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	14,088 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	15,707 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	32 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 53-0165-604

Proposed Contract Period: Late Start Date of 06/27/11 with 60 WORK DAYS
Site 01: TO COMPLETE WORK ON OLD DUBUQUE ROAD
Late Start Date of 06/27/11 with 30 WORK DAYS

Proposal Note:

SITE 01

TO COMPLETE ALL WORK ON OLD DUBUQUE ROAD.

Project(s):

Project No: STP-U-0165(604)--70-53

County: JONES

Type of Work: HMA RESURFACING WITH MILLING

Route: OLD DUBUQUE ROAD Length: 2.00 miles

Location: ALSO ON FORD ST., THIRD ST/SCOTT ST. AND
OLD DUBUQUE RD.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	3,900 SY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	875 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	3,750 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	4,200 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 163 Proposal ID: 75-0752-084

Proposed Contract Period: Late Start Date of 08/01/11 with 45 WORK DAYS

Project(s):

Project No: NHSN-075-2(84)--2R-75

County: PLYMOUTH

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 75 Length: 0.75 miles

Location: US 75 FROM NEAR SCL OF HINTON N. TO 0.25 MILE N. OF
NCL OF HINTON

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	55 CY
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	2,659 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	2,532 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 164 Proposal ID: 77-1601-010

Proposed Contract Period: Late Start Date of 07/11/11 with 70 WORK DAYS

Project(s):

Project No: STP-160-1(10)--2C-77
 County: POLK
 Type of Work: HMA RESURFACING
 Route: IOWA 160 Length: 1.03 miles
 Location: IN THE CITY OF ANKENY FROM IOWA 415 E. TO
 SE PEACHTREE DR.

Project No: STP-415-1(48)--2C-77
 County: POLK
 Type of Work: HMA RESURFACING
 Route: IOWA 415 Length: 1.03 miles
 Location: IN THE CITY OF ANKENY FROM NW 72ND PL. TO
 900' E. OF SW IRVINEDALE DR.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
STP-160-1(10)--2C-77		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	1,036 CY
2303-0041500	HMA (3M ESAL) BASE, 1/2"	260 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	6,001 TON
2303-0043502	HMA (3M ESAL) SURF, 1/2", FRIC L-2	6,001 TON
SECTION NO. 0003		
ROADWAY ITEMS		
STP-415-1(48)--2C-77		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	269 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	7,119 TON
2303-0043502	HMA (3M ESAL) SURF, 1/2", FRIC L-2	7,119 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 33-0562-704

Proposed Contract Period: Late Start Date of 06/27/11 with 40 WORK DAYS

Project(s):

Project No: MP-056-2(704)0--76-33

County: FAYETTE

Type of Work: SEAL COAT

Route: IOWA 56

Length: 22.55 miles

Location: FROM FRANKLIN ST. IN THE CITY OF WEST UNION TO THE WCL OF
ELKADER.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	4,045 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
 (for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 50-0061-706

Proposed Contract Period: Late Start Date of 06/27/11 with 55 WORK DAYS

Project(s):

Project No: MP-014-1(710)115--76-38
 County: GRUNDY

Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 14 Length: 0.52 miles
 Location: TWO SPOT LOCATIONS NEAR WOLF CREEK BRIDGE

Project No: MP-065-1(704)139--76-42
 County: HARDIN

Type of Work: HMA JOINT & CRACK SEALING
 Route: U.S. 65 Length: 8.08 miles
 Location: FROM N. JCT. OF IOWA 175 TO SCL OF IOWA FALLS.

Project No: MP-006-1(706)171--76-50
 County: JASPER

Type of Work: HMA JOINT & CRACK SEALING
 Route: U.S. 6 Length: 15.87 miles
 Location: FROM ECL OF NEWTON TO GRINNELL.

Project No: MP-030-1(702)172--76-64
 County: MARSHALL

Type of Work: HMA JOINT & CRACK SEALING
 Route: U.S. 30 Length: 6.40 miles
 Location: FROM STATE CENTER, EAST TO NEAR THE JCT. OF S-70.

Project No: MP-330-1(708)21--76-64
 County: MARSHALL

Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 330 Length: 4.50 miles
 Location: FROM THE U.S. 30 INTERCHANGE NORTH TO THE JCT. OF E-29

Project No: MPIN-080-1(702)184--0N-79
 County: POWESHIEK

Type of Work: HMA JOINT & CRACK SEALING
 Route: I-80 Length: 9.21 miles
 Location: FROM 1 MI. E. OF IOWA 146 TO 1 MI. E. OF US 63(WBL) INCLUDES
 RAMPS AT INTERCHANGES WITH U.S. 63, IOWA 21 & V18.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 52-0806-705

Proposed Contract Period: Late Start Date of 09/12/11 with 35 WORK DAYS

Project(s):

Project No: MPIN-080-6(705)249--0N-52
County: JOHNSON
Type of Work: HMA PATCHING
Route: I-80 Length: 0.00 miles
Location: AT HERBERT HOOVER INTERCHANGE (EXIT 249)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	3,379 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 57-3806-708

Proposed Contract Period: Late Start Date of 08/01/11 with 10 WORK DAYS

Project(s):

Project No: MPIN-380-6(708)30--0N-57

County: LINN

Type of Work: FOG SEAL

Route: I-380

Length: 13.42 miles

Location: FROM 1 MI. NORTH OF E-34 TO IOWA 150.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 71-0593-704

Proposed Contract Period: Late Start Date of 09/30/11 with 35 WORK DAYS

Project(s):

Project No: MP-086-3(708)0--76-30

County: DICKINSON

Type of Work: HMA CRACK FILLING

Route: IOWA 86 Length: 7.65 miles

Location: FROM JCT. OF U.S. 71 NORTH TO THE JCT. OF IOWA 9.

Project No: MP-059-3(704)194--76-71

County: OBRIEN

Type of Work: HMA CRACK FILLING

Route: U.S. 59 Length: 21.72 miles

Location: FROM THE W. JCT. OF U.S. 18, NORTH TO MINNESOTA STATE LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 77-0061-715

Proposed Contract Period: Late Start Date of 09/19/11 with 25 WORK DAYS

Project(s):

Project No: MP-006-1(715)127--76-77

County: POLK

Type of Work: PCC PATCHING

Route: U.S. 6 Length: 5.04 miles

Location: IN THE CITY OF CLIVE FROM THE I-80 INTERCHANGE E. & N. TO
DOUGLAS AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	598 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	54 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 77-0351-707

Proposed Contract Period: Late Start Date of 07/18/11 with 20 WORK DAYS

Project(s):

Project No: MPIN-035-1(707)98--0N-77

County: POLK

Type of Work: HMA PAVED SHOULDER - FOG SEAL

Route: I-35 Length: 39.03 miles

Location: FROM 1.25 MI. NORTH OF F-22 TO D-25 INTERCHANGE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 77-0691-707

Proposed Contract Period: Late Start Date of 08/01/11 with 35 WORK DAYS

Project(s):

Project No: MP-017-1(708)20--76-08
 County: BOONE
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 17 Length: 15.00 miles
 Location: FROM JCT. OF U.S. 30 NORTH & EAST TO 2.5 MI. S. OF STANHOPE.

Project No: MP-069-1(707)84--76-77
 County: POLK
 Type of Work: HMA JOINT & CRACK SEALING
 Route: U.S. 69 Length: 7.09 miles
 Location: IN THE CITY OF DES MOINES FROM DES MOINES RIVER BRIDGE
 N. TO SCL OF ANKENY

Project No: MP-415-1(708)15--76-77
 County: POLK
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 415 Length: 2.00 miles
 Location: FROM SAYLORVILLE LAKE BRIDGE TO IOWA 141

Project No: MP-210-1(701)14--76-85
 County: STORY
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 210 Length: 1.30 miles
 Location: IN THE CITY OF SLATER FROM WCL TO ECL INCLUDES
 JCT. IOWA 210 AT U.S. 69.

Project No: MP-175-1(706)117--76-94
 County: WEBSTER
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 175 Length: 4.90 miles
 Location: FROM GOWRIE TO HARCOURT

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 209 Proposal ID: 82-0066-708

Proposed Contract Period: Late Start Date of 09/26/11 with 20 WORK DAYS

Project(s):

Project No: MP-038-6(704)17--76-16
 County: CEDAR
 Type of Work: PCC PATCHING
 Route: IOWA 38 Length: 2.06 miles
 Location: FROM THE W. JCT. OF I-80, N. TO CO. RD. F-44.

Project No: MP-067-6(710)42--76-23
 County: CLINTON
 Type of Work: PCC PATCHING
 Route: U.S. 67 Length: 5.58 miles
 Location: FROM STOCKWELL LN. IN CLINTON, NORTH TO CO. RD. E-50.

Project No: MP-006-6(708)304--76-82
 County: SCOTT
 Type of Work: PCC PATCHING
 Route: U.S. 6 Length: 6.00 miles
 Location: FROM FAIRMOUNT ST. TO UTICA RIDGE RD. IN DAVENPORT.

Project No: MP-022-6(704)89--76-82
 County: SCOTT
 Type of Work: PCC PATCHING
 Route: IOWA 22 Length: 4.35 miles
 Location: IN THE CITY OF BUFFALO FROM Y-40 E. TO ECL.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
CEDAR COUNTY MP-38-6(704)17--76-16		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	230 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	25 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
CLINTON COUNTY MP-67-6(710)42--76-23		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	322 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	27 EACH
SECTION NO. 0003		
ROADWAY ITEMS		
SCOTT COUNTY MP-6-6(708)304--76-82		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	450 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	49 EACH
SECTION NO. 0004		
ROADWAY ITEMS		
SCOTT COUNTY MP-22-6(704)89--76-82		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	175 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	22 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 210 Proposal ID: 82-0746-705

Proposed Contract Period: Late Start Date of 10/03/11 with 20 WORK DAYS

Project(s):

Project No: MPIN-074-6(705)0--0N-82

County: SCOTT

Type of Work: LONGITUDINAL JOINT REPAIR

Route: I-74 Length: 5.36 miles

Location: FROM I-80, SOUTH TO MISSISSIPPI RIVER

Project No: MPIN-080-6(706)280--0N-82

County: SCOTT

Type of Work: HMA CRACK FILLING

Route: I-80 Length: 0.00 miles

Location: FROM Y-30 TO MIDDLE ROAD (RAMPS)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 211 Proposal ID: 97-0203-712

Proposed Contract Period: Late Start Date of 10/03/11 with 40 WORK DAYS

Project(s):

Project No: MP-007-3(706)15--76-11
County: BUENA VISTA

Type of Work: HMA CRACK FILLING

Route: IOWA 7 Length: 2.01 miles

Location: IN THE CITY OF STORM LAKE FROM BARTON STREET TO NORTH OF
LAKE SHORE DR.

Project No: MP-175-3(702)40--76-47
County: IDA

Type of Work: HMA CRACK FILLING

Route: IOWA 175 Length: 10.51 miles

Location: WOODBURY COUNTY LINE EAST TO W. JCT. OF U.S. 59.

Project No: MP-020-3(712)0--76-97
County: WOODBURY

Type of Work: HMA CRACK FILLING

Route: U.S. 20 Length: 12.75 miles

Location: FROM BEGINNING OF RT. E. TO ECL OF LAWTON.

Project No: MP-140-3(701)0--76-97
County: WOODBURY

Type of Work: HMA CRACK FILLING

Route: IOWA 140 Length: 25.36 miles

Location: FROM U.S. 20 NORTH TO IOWA 3.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 212 Proposal ID: 97-0293-707

Proposed Contract Period: Late Start Date of 08/29/11 with 45 WORK DAYS

Project(s):

Project No: MPIN-029-3(707)127--0N-97

County: WOODBURY

Type of Work: HMA CRACK FILLING

Route: I-29 Length: 13.99 miles

Location: FROM THE MONONA CO. LINE TO SOUTH OF THE SERGEANT BLUFF
INTERCHANGE. (SB LANES)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 04-0051-052

Proposed Contract Period: Late Start Date of 10/17/11 with 10 WORK DAYS

Project(s):

Project No: ER-005-1(52)--28-04

County: APPANOOSE

Type of Work: REVETMENT

Route: IOWA 5 Length: 0.00 miles

Location: 2 MILES N. OF CINCINNATI

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 04-0051-053

Proposed Contract Period: Late Start Date of 09/19/11 with 25 WORK DAYS

Project(s):

Project No: ER-005-1(53)--28-04

County: APPANOOSE

Type of Work: REVETMENT

Route: IOWA 5 Length: 0.00 miles

Location: SHOAL CREEK 2 MILES N. OF CINCINNATI

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 43-C043-066

Proposed Contract Period: Late Start Date of 05/23/11 with 120 WORK DAYS

Project(s):

Project No: STP-S-C043(66)--5E-43

County: HARRISON

Type of Work: GRADING

Route: L16

Length: 3.73 miles

Location: NCL WOODBINE TO INTERS. W/ 155TH ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	179,922 CY
2108-5025000	OVERHAUL	921,760 ST-Y
2403-0100000	STRUCT CONC (MISCELLANEOUS)	6 CY
2403-0100020	STRUCT CONC (RCB CULV)	391 CY
2404-7775000	REINFORC STEEL	54,587 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 86-0306-195

Proposed Contract Period: Late Start Date of 05/23/11 with 110 WORK DAYS

Project(s):

Project No: NHSN-030-6(195)--2R-86

County: TAMA

Type of Work: FENCING

Route: U.S. 30 Length: 0.00 kilometers

Location: US 30 TAMA BYPASS FROM 0.7 KM E. OF MESQUAKIE
CASINO E. TO 2.45 KM E. OF L AVE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 93-0651-024

Proposed Contract Period: Late Start Date of 10/17/11 with 10 WORK DAYS

Project(s):

Project No: ER-065-1(24)--28-93

County: WAYNE

Type of Work: REVETMENT

Route: U.S. 65

Length: 0.00 miles

Location: 4 MILES S. OF IA. 2

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 306 Proposal ID: 93-0651-025

Proposed Contract Period: Late Start Date of 10/17/11 with 10 WORK DAYS

Project(s):

Project No: ER-065-1(25)--28-93

County: WAYNE

Type of Work: REVETMENT

Route: U.S. 65 Length: 0.00 miles

Location: S. CALEB CREEK APPROX. 6 MILES S. OF IA. 2

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 307 Proposal ID: 93-0651-026

Proposed Contract Period: Late Start Date of 10/10/11 with 15 WORK DAYS

Project(s):

Project No: ER-065-1(26)--28-93

County: WAYNE

Type of Work: REVETMENT

Route: U.S. 65 Length: 0.00 miles

Location: N. CALEB CREEK APPROX. 6 MILES S. OF IA. 2

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-442

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE DIVISION 1 SIGNS
Completion Date of 09/30/11

Site 02: TO COMPLETE DIVISION 2 SIGNS
Late Start Date of 05/23/11 with 25 WORK DAYS

Project(s):

Project No: NHSN-000-S(442)--2R-00

County: STATEWIDE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 16-0807-102

Proposed Contract Period: Late Start Date of 06/20/11 with 90 WORK DAYS

Project(s):

Project No: IMN-080-7(102)254--0E-16

County: CEDAR

Type of Work: TRAFFIC SIGNS

Route: I-80 Length: 0.00 miles

Location: JOHNSON COUNTY LINE EAST TO THE MISSISSIPPI RIVER
(VARIOUS INTERCHANGES)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 16-0808-272

Proposed Contract Period: Late Start Date of 08/15/11 with 50 WORK DAYS

Project(s):

Project No: IHSIPX-080-8(272)271--08-16

County: CEDAR

Type of Work: GUARDRAIL

Route: I-80 Length: 0.00 miles

Location: FROM E. JCT. IA. 38 E. TO CO. RD. Y-30

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	5,664 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 354 Proposal ID: 19-C019-079

Proposed Contract Period: Late Start Date of 07/11/11 with 45 WORK DAYS

Project(s):

Project No: L-2011--73-19
County: CHICKASAW

Type of Work: PAVEMENT MARKINGS
Route: MULTIPLE ROUTES Length: 0.00 miles
Location: VARIOUS LOCATIONS IN CHICKASAW COUNTY

Project No: FM-C019(79)--55-19
County: CHICKASAW

Type of Work: PAVEMENT MARKINGS
Route: MUTIPLE ROUTES Length: 0.00 miles
Location: VARIOUS LOCATIONS IN CHICKASAW COUNTY

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 355 Proposal ID: 25-0803-170

Proposed Contract Period: Late Start Date of 06/06/11 with 90 WORK DAYS

Project(s):

Project No: IHSIPX-080-3(170)110--08-25

County: DALLAS

Type of Work: GUARDRAIL

Route: I-80 Length: 0.00 miles

Location: FROM US 169(DE SOTO) E. TO I-35

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	9,607 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 356 Proposal ID: 52-3806-276

Proposed Contract Period: Late Start Date of 06/20/11 with 80 WORK DAYS

Project(s):

Project No: IHSIPX-380-6(276)0--08-52

County: JOHNSON

Type of Work: GUARDRAIL

Route: I-380

Length: 0.00 miles

Location: FROM I-80 N. TO 1.2 MILES N. OF LINN CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	8,711 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 357 Proposal ID: 82-0615-139

Proposed Contract Period: Late Start Date of 09/12/11 with 35 WORK DAYS

Project(s):

Project No: NHSN-061-5(139)--2R-82

County: SCOTT

Type of Work: TRAFFIC SIGNS

Route: U.S. 61 Length: 0.00 miles

Location: BUSINESS U.S. 61 IN DAVENPORT

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 90-0348-151

Proposed Contract Period: Late Start Date of 07/25/11 with 15 WORK DAYS

Project(s):

Project No: NHSN-034-8(151)--2R-90

County: WAPELLO

Type of Work: WETLAND MITIGATION REMEDIATION

Route: U.S. 34 Length: 0.00 miles

Location: BATAVIA BORROW REMEDIATION

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
MITIGATION REMEDIATION ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	980 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 57-3806-542-B

Proposed Contract Period: Late Start Date of 05/23/11 with 60 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE:

- . BRIDGE NO. 5210.90380:
- . (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
- . {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
- . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
- . (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
- . 5210.9{o}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
- . (ALPHA VALUES;
- . O = OVER, R = RIGHT, L = LEFT,
- . A = RAMP, S = SINGLE)
- . 5210.9o{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES:

- . 5719.7L380 5719.7R380 5720.0A380

Project(s):

Project No: MBIN-380-6(542)20--0M-57
 County: LINN
 Type of Work: BRIDGE PAINTING
 Route: I-380 Length: 0.00 miles
 Location: 3RD AVE. IN CEDAR RAPIDS

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 602 Proposal ID: 97-0772-013

Proposed Contract Period: Late Start Date of 06/20/11 with 40 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{o}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.9o{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES:

. 5719.7L380 5719.7R380 5720.0A380

Project(s):

Project No: BRFN-077-2(13)--39-97
County: WOODBURY
Type of Work: BRIDGE CLEANING
Route: U.S. 77 Length: 0.00 miles
Location: IN THE CITY OF SIOUX CITY OVER MISSOURI RIVER

Item No. Item Description Quantity/Unit

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 19, 2011 10:00 A.M.

Proposed Bid Order: 603 Proposal ID: 97-1296-033

Proposed Contract Period: Late Start Date of 06/20/11 with 40 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS
AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{o}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.9o{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE
FOLLOWING BRIDGES:

. 5719.7L380 5719.7R380 5720.0A380

Project(s):

Project No: IMN-129-6(33)00--0E-97
County: WOODBURY
Type of Work: BRIDGE CLEANING
Route: I-129 Length: 0.00 miles
Location: IN THE CITY OF SIOUX CITY OVER MISSOURI RIVER

Item No. Item Description Quantity/Unit
