

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: May 17, 2011
Date of Addendum: May 3, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
101	09-0637-106	PCC Pavement - Grade & New	BREMER	NHSX-063-7(52)--3H-09 NHSX-063-7(101)--3H-09 NHSX-063-7(102)--3H-09 NHSX-063-7(105)--3H-09 NHSX-063-7(106)--3H-09	17may101.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Attached is a SCHEDULE OF PRICES for the following item:

Line No. 1521 2401--204000 REMOVAL OF EXISTING BRIDGE, US 63 STA.
23+75.7, 14.0 RT. 8.53 x 36.58 CONC. BRIDGE

Bid this item as instructed and submit the bid for this item with the Bid Proposal.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Line No. 0490 2107--100200 COMPACTION WITH MOISTURE CONTROL
from 62,852.000 M3 to 327,472.000 M3.

Change Line No. 0530 2111--100000 GRANULAR SUBBASE from 239,747.900 M2 to
238,177.900 M2.

Delete Line No. 0570 2122--220001 PAVED SHOULDER, PORTLAND CEMENT
CONCRETE (PAVED SHOULDER PANEL FOR BRIDGE END DRAIN)

Change Line No. 0600 2301--103260 STANDARD OF SLIP-FORM PORTLAND
CEMENT CONCRETE PAVEMENT QM-C, CLASS 3 DURABILITY 260 MM from
206,543.500 M2 to 208,073.500 M2.

Change Line No. 0640 2301--990000 QUALITY MANAGEMENT - CONCRETE
(QM-C) from 53,702.000 M3 to 54,099.100 M3.

For Line No. 0700 change the Item Description from REMOVAL OF EXISTING BRIDGE to REMOVAL OF EXISTING BRIDGE, IA 3 STA. 1025+02.2, 39.2 LT. 7.93 x 36.57 CONC. STEEL BEAM BRIDGE. The Item Number, Item Quantity and Unit remain the same.

If the above changes are not made on the proposal form, they will be made as shown here.

Make the following change to Plan Sheet C.2, Item Codes 2301--103260 and 2301--133260:

Replace:

See Tab. 100-24 for locations and details.

With:

See Tab. 100-24 and Tab. 102-3 for locations and details.

Make the following change to Plan Sheet C.3, Item Code 2401--204000:

Replace:

Includes 2 bridges:

Stage 2 removal: IA 3 Sta. 1025+02.2, 39.2 7.93 x 36.57 Conc. Steel Beam Bridge.

Stage 3 removal: US 63 Sta. 23+75.7, 14.0 Rt. 8.53 x 36.58 Conc. Bridge.

With:

Stage 2 removal: IA 3 Sta. 1025+02.2, 39.2 7.93 x 36.57 Conc. Steel Beam Bridge.

A SCRAPE SAMPLE WAS TAKEN FROM AN AREA OF THIS BRIDGE TO GET AN INDICATION OF THE EXISTENCE OF AND LEVEL OF TOTAL CHROMIUM AND TOTAL LEAD. ANALYSIS OF TOTAL LEAD ON THIS SAMPLE WAS 1600 PARTS PER MILLION (PPM). ANALYSIS OF TOTAL CHROMIUM ON THIS SAMPLE WAS 290 PPM. THESE ANALYSES SHOW THE EXISTENCE OF THESE TWO TOXIC CONSTITUENTS. LEVELS INDICATED BY THESE TESTS COULD CREATE CONDITIONS ABOVE REGULATORY LIMITS FOR HEALTH AND SAFETY REQUIREMENTS. NO OTHER CONSTITUENTS WERE ANALYZED. THE BIDDER SHOULD NOT RELY ON THE DEPARTMENT'S TESTING AND ANALYSIS FOR ANY PURPOSE OTHER THAN AS AN INDICATION OF THE EXISTENCE OF THESE TWO TOXIC CONSTITUENTS.

Make the following change to Plan Sheet C.4:

For Item Code 2401--204000, Add the following note:

Stage 3 removal: US 63 Sta. 23+75.7, 14.0 Rt. 8.53 x 36.58 Conc. Bridge.

Note: The above change is the Estimate Reference Information for Proposal Line No. 1521

Make the following change to Plan Sheet C.10:

Replace Tabulation 104-8A with the attached Tabulation 104-8A.

Make the following change to Plan Sheet C.11 and C.12:

Replace Tabulation 100-24 with the attached Tabulation 100-24.

PROPOSAL ADDENDUM - SCHEDULE OF PRICES

Proposal ID No.: 09-0637-106
 Primary Work Type: PCC PAVEMENT - GRADE AND NEW
 Primary County: BREMER

Bid Order No.: 101
 Letting Date: May 17, 2011
 10:00 A.M.

ITEMS LISTED ON THIS PAGE ARE ADDED BY ADDENDUM 17MAY101.A01

Line No	Item Number Item Description	Item Quantity and Unit	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Cts
Section 0007 (CONTINUED)						
ROADWAY ITEMS - NHSX-063-7(106)--3H-09						
1521	2401--204000 REMOVAL OF EXISTING BRIDGE, US 63 STA. 23+75.7, 14.0 RT. 8.53 X 36.58 CONC. BRIDGE	LUMP	.		.	
Total Bid			.		.	

