



Iowa Department of Transportation

LOCAL LETTING INFORMATION

Howard County -- L-(T68)--73-45
 Proposal Guarantee: \$125,000.00
 April 04, 2011 - 10:00 AM
 County Engineer's Office, Cresco, IA
 PCC Pavement - Replace, 5.45 miles
 Contact # 563-547-2620 FAX # 563-547-2576

1511.120	SY	BRIDGE APPROACH, RK-19
1.000	LS	CONSTRUCTION SURVEY
5253.540	CY	EXCAVATION, CL 10, RDWY+BORROW
7.000	EACH	FLAGGER
8937.710	TON	GRANULAR SHLD, TYPE B
1.000	LS	MOBILIZATION
11668.050	CY	MODIFIED SUBBASE, PLACE ONLY
762.520	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
1.000	LS	PCC PAV'T SAMPLE
70289.921	SY	RMVL+CRUSH OF PAV'T
3.000	EACH	RUMBLE STRIP PANEL (PCC SURF)
11.000	EACH	SAFETY CLOSURE
68891.699	SY	STD/S-F PCC PAV'T, CL C CL 3, 6.5"
1.000	LS	TRAFFIC CONTROL

Keokuk County Secondary Road Department County -- PP-9011(1)-54
 Proposal Guarantee: \$6,500.00
 April 4, 2011 - Sigourney - Keokuk County Board of Supervisors, IA - 9:30 a.m.
 Bid Turn-in Location: Keokuk County Auditor Office
 P.C.C. PAVEMENT PATCHING
 Contact # 641-622-2610 FAX # 641-622-3637

1	LS	Mobilization
1	LS	Traffic Control
684.44	SY	Patches, Full depth by area
38	EA	Patches, Full depth by count
684.44	SY	Subbase, (Patches) - 6

Washington County Secondary Road Department County -- 2011 Tied Grading Projects, Part 2
 Proposal Guarantee: \$50,000.00
 April 12, 2011 - Supervisors Room, Washington Co Court House, Washington, IA - 9:00 A.M.
 Bid Turn-in Location: Court House, Washington Co Auditors Office, 222 W Main St, Washington
 2 Tied Grading Projects L-H-164: 2.966 miles grading & surfacing on Underwood Ave from the City of Ainsworth to G36 (220th St)
 L-H-184: 3.013 miles grading & surfacing on Spruce Ave form Hwy 92 to G36 (220th St)
 Sites: 2
 TIED with: L-H-164, L-H-184
 Contact # 319-653-7731 FAX # 319-653-7730

30255	cy	Excavation, Class 10 Roadway & Borrow
9027	cy	Reclaiming Present Surface Material
19229	ton	Choke Stone Base
20731	ton	Macadam Stone Base
775	ton	Surfacing, Driveway, Class A Crushed Stone
1032	cy	Excavation, Class 20, for Roadway Pipe Culvert
2618	lf	Corrugated Metal Entrance Pipe
902	lf	Corrugated Metal Driveway Pipe



Iowa Department of Transportation

LOCAL LETTING INFORMATION

Marshall County Secondary Road Department County -- 2011 Granular Resurfacing

Proposal Guarantee: \$ Varies by District

April 12, 2011 - Council Chambers, 10 W State St, 2nd Floor, Marshalltown, IA - 9:00 AM

Bid Turn-in Location: Auditor's Office, Courthouse

Maintenance - Granular resurfacing of roads in Marshall County.

Contact # 641-754-6343 FAX # 641-754-6384

20,819	ton	Division 1 Crushed Stone
31,584	ton	Division 2 Crushed Stone
Varies	ton	Division 3 Gravel or Crushed Stone
8,996	ton	Division 4 Crushed Stone

Winnebago County -- LFM-(A44)--7X-95

Proposal Guarantee: \$75,000.00

April 12, 2011 - County boardroom, Forest City , IA - 11:00 AM

367-PCC Paving, PCC (Whitetopping) Resurfacing

Contact # 641-585-2905 FAX # 641-585-2891

1.000	LS	CONSTRUCTION SURVEY
18.000	EACH	FLAGGER
10000.000	TON	GRANULAR SHLD, TYPE B
631.000	STA	GROOVE CUT - PAV'T MARK
1.000	LS	MOBILIZATION
631.000	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
54668.000	SY	PCC OVERLAY PLACE ONLY (WHITE TOPPING)
9111.000	CY	PCC OVERLAY, FURN ONLY
1.000	LS	PCC PAV'T SAMPLE
3200.000	SY	RMVL OF PAV'T
8.000	EACH	RUMBLE STRIP PANEL (PCC SURF)
180.000	LF	SAW CUTTING
1.000	LS	SIGNING
3200.000	SY	STD/S-F PCC PAV'T, CL C CL 3, 8"
1.000	LS	TRAFFIC CONTROL

Lee County Secondary Road Department County -- M2011-4, M2011-5, M2011-6, M2011-7

Proposal Guarantee: \$6,250.00

April 13, 2011 - Fort Madison - Lee County Board Room; Fort Madison, IA - 10:30 am

Bid Turn-in Location: Lee County Auditor's Office; Fort Madison, IA

Emergency Repair - Erosion; Embankment-In-Place, Retevment, and related items at 4 bridge sites.

Sites: 1. On 175th Ave, 1.3 miles east of W55. 2. On 140th Ave, 0.8 miles south of J40. 3. On 194th Ave, 680 feet east of US 27. 4.

On 241st Ave, 0.3 miles north of Peach Orchard Road.

TIED with: M2011-4, M2011-5, M2011-6, M2011-7

Contact # 319-372-2541 FAX # 319-372-7033

297.80	CY	EMBANKMENT-IN-PLACE
7.00	CY	FLOWABLE MORTAR
1118.5	SY	ENGINEER FABRIC
1208.70	TON	REVTMENT, CLASS B
2.51	ACRE	MULCH
2.51	ACRE	SEED+FERTILIZE



Iowa Department of Transportation

LOCAL LETTING INFORMATION

Franklin County -- LFM-01-081(11)E8--RI-35
 Proposal Guarantee: \$200,000.00
 April 14, 2011 - Courthouse, Hampton , IA - 2:00 PM
 PCC Paving, 8
 Contact # 641-456-4671 FAX # 641-456-3219

1740.000	LF	Crack Stitching (Bonded Overlay)
10500.000	CY	EXCAVATION, CL 10, RDWY+BORROW
8400.000	TON	GRANULAR SHLD, TYPE B
4535.000	CY	MODIFIED SUBBASE
9070.000	CY	MODIFIED SUBBASE, PLACE ONLY
1049.810	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
465.000	SY	PATCH, FULL-DEPTH REPAIR
37410.000	SY	PCC OVERLAY, PLACE ONLY (BONDED)
63955.000	SY	RMVL+CRUSH OF PAV'T
65310.000	SY	STD/S-F PCC PAV'T, CL C CL 3, 8"

Carroll County Secondary Road Department County -- LFM-127--7X-14, LFM-128--7X-14, LF5--73-14
 Proposal Guarantee \$ 25000
 APRIL 18, 2011 - Carroll - Carroll County Board of Supervisors Meeting Room, Court House Carroll, Iowa - A.M.
 Bid Turn-in Location: Carroll County Auditor, Court House, Carroll, Iowa 51401
 3 PRECAST BOX CULVERTS
 Sites: VARIOUS LOCATIONS IN CARROLL COUNTY
 TIED with: LFM-127--7X-14, LFM-128--7X-14, LF5--73-14
 Contact # 712-792-3603 FAX # 712-792-3611

581	cy	Excavation - Class 10
2187	cy	Excavation - Class 20
44	lf	PRECAST CONC BOX CULV 14X13
120	lf	PRECAST CONC BOX CULV 10X10
60	lf	PRECAST CONC BOX CULV, TWIN CELL12X12



Iowa Department of Transportation

BULLETIN REPORTING FORM

County: <u>Sioux</u>	Project No.: <u>L-7-2011--73-84</u>
Proposal Guarantee: <u>\$4,000 or Bid Bond</u>	DBE or TSB Goal: <u>None</u> %
Date of Letting: <u>April 12, 2011</u>	Time of Letting: <u>10:00 A.M.</u>
Bid Turn-In Location: <u>Sioux County Auditor</u>	Type of Project: <u>Structure Culvert</u>
Contact Phone #: <u>712-737-2248</u>	Contact Fax #: <u>712-737-2757</u>

Specific Description of Project: Twin 154" x 100" Structural Plate Pipe Arch Culvert. Located 2.5 miles south of US Hwy. 18 on Dove Avenue, near Rock Valley, IA.

QUANTITY	UNIT	DESCRIPTION
1	L.S.	Removal of Existing Structure
393	C.Y.	Excavation, Class 20,Rdwy Pipe
28	C.Y.	Structural Concrete (Misc)
1505	Lbs	Reinforcing Steel
108	L.F.	Culv Str. Plate Arch 154"x100"
1	L.S.	Mobilization

Date: 3/11/2011 Local Agency Official: Douglas G. Julius, P.E.

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts at DOT.Contracts@DOT.iowa.gov



Iowa Department of Transportation

BULLETIN REPORTING FORM

County: Sioux Project No.: L-4-2010--73-84
 Proposal Guarantee: \$6,250 or Bid Bond DBE or TSB Goal: None %
 Date of Letting: April 12, 2011 Time of Letting: 10:00 A.M.
 Bid Turn-In Location: Sioux County Auditor Type of Project: Structure Culvert
 Contact Phone #: 712-737-2248 Contact Fax #: 712-737-2757

Specific Description of Project: Triple 150" x 95" Structural Plate Pipe Arch Culvert. Located 1.5 miles west of Co. Blacktop L22 on 380th Street.

QUANTITY	UNIT	DESCRIPTION
1	L.S.	Removal of Existing Structure
898	C.Y.	Excavation, Class 20,Rdwy Pipe
43	C.Y.	Structural Concrete (Misc)
2704	Lbs	Reinforcing Steel
177	L.F.	Culv Str. Plate Arch 154"x100"
1	L.S.	Mobilization

Date: 3/11/2011 Local Agency Official: Douglas G. Julius, P.E.

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts at DOT.Contracts@DOT.iowa.gov



Iowa Department of Transportation

BULLETIN REPORTING FORM

County: <u>Sioux</u>	Project No.: <u>L-4-2011--73-84</u>
Proposal Guarantee: <u>\$4,000 or Bid Bond</u>	DBE or TSB Goal: <u>None</u> %
Date of Letting: <u>April 12, 2011</u>	Time of Letting: <u>10:00 A.M.</u>
Bid Turn-In Location: <u>Sioux County Auditor</u>	Type of Project: <u>Structure Culvert</u>
Contact Phone #: <u>712-737-2248</u>	Contact Fax #: <u>712-737-2757</u>

Specific Description of Project: Twin 150" x 95" Structural Plate Pipe Arch Culvert. Located 13/4 mile east of Co. Blacktop K64 on 360th Street.

QUANTITY	UNIT	DESCRIPTION
1	L.S.	Removal of Existing Structure
437	C.Y.	Excavation, Class 20,Rdwy Pipe
30	C.Y.	Structural Concrete (Misc)
1701	Lbs	Reinforcing Steel
110	L.F.	Culv Str. Plate Arch 150"x95"
1	L.S.	Mobilization

Date: 3/11/2011 Local Agency Official: Douglas G. Julius, P.E.

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts at DOT.Contracts@DOT.iowa.gov



Iowa Department of Transportation

BULLETIN REPORTING FORM

County: Sioux Project No.: L-2-98--73-84
 Proposal Guarantee: \$4,000 or Bid Bond DBE or TSB Goal: None %
 Date of Letting: April 12, 2011 Time of Letting: 10:00 A.M.
 Bid Turn-In Location: Sioux County Auditor Type of Project: Structure Culvert
 Contact Phone #: 712-737-2248 Contact Fax #: 712-737-2757

Specific Description of Project: Twin 152" x 97" Structural Plate Pipe Arch Culvert. Located 3/4 mile east of the intersection of Kingbird Avenue and 430th Street near Alton, IA.

QUANTITY	UNIT	DESCRIPTION
1	L.S.	Removal of Existing Structure
599	C.Y.	Excavation, Class 20,Rdwy Pipe
29	C.Y.	Structural Concrete (Misc)
1627	Lbs	Reinforcing Steel
104	L.F.	Culv Str. Plate Arch 152"x97"
1	L.S.	Mobilization

Date: 3/11/2011 Local Agency Official: Douglas G. Julius, P.E.

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts at DOT.Contracts@DOT.iowa.gov



Iowa Department of Transportation

BULLETIN REPORTING FORM

County: Sioux Project No.: L-12-2007--73-84
 Proposal Guarantee: \$25,000 or Bid Bond DBE or TSB Goal: None %
 Date of Letting: April 12, 2011 Time of Letting: 10:00 A.M.
 Bid Turn-In Location: Sioux County Auditor Type of Project: Structure Culvert
 Contact Phone #: 712-737-2248 Contact Fax #: 712-737-2757

Specific Description of Project: 90' x 30' Cont. Concrete Slab Bridge located 1/2 mi. east of Co. Blacktop K64 on 470th Street near Orange City, IA.

QUANTITY	UNIT	DESCRIPTION
899	C.Y.	Excavation, Class 10 (Channel)
1	Lump Sum	Removal of Existing Structure
41	C.Y.	Excavation, Class 20
227	C.Y.	Concrete, Structural (Bridge)
5110	LBS	Reinforcing Steel
47197	LBS	Reinforcing Steel Epoxy
202	L.F.	Concrete Open Rail
1680	L.F.	Piles, Steel HP 10X42
171	L.F.	Conc. Encase of Steel HP10x42
4	Each	Steel Beam G.Rail TransSection
4	Each	Steel Beam G.Rail End Bolted
4	Each	Steel Beam G.Rail End Terminal
1	Lump Sum	Mobilization

Date: 3/15/2011 Local Agency Official: Douglas G. Julius, P.E.

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts at DOT.Contracts@DOT.iowa.gov