



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

Winnebago County -- LFM-(A14)--7X-95

Proposal Guarantee \$ 25,000.00

Courthouse, Forest City , IA, May 24, 2011, 11:00 AM

366-HMA Paving, HMA Resurfacing

Contact # 641-585-2905 FAX # 641-585-2891

414.000	TON	ASPH BINDER, PG 58-28
2.058	MILE	CLEAN+PREPARATION OF BASE
1.000	LS	CONSTRUCTION SURVEY
25.000	EACH	FLAGGER
3100.000	TON	GRANULAR SHLD, TYPE B
341.000	STA	GROOVE CUT - PAV'T MARK
2100.000	TON	HMA (3M ESAL) BASE, 1/2"
2400.000	TON	HMA (3M ESAL) INTERMEDIATE, 1/2"
2400.000	TON	HMA (3M ESAL) SURF, 1/2", NO FRIC
1.000	LS	HMA PAV'T SAMPLE
1.000	LS	MOBILIZATION
341.000	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
4.000	EACH	RUMBLE STRIP PANEL (HMA SURF)
1.000	LS	TRAFFIC CONTROL

Winnebago County -- LFM-(R50)--7X-95

Proposal Guarantee \$ 100,000.00

Courthouse, Forest City , IA, May 24, 2011, 11:00 AM

366-HMA Paving, 4

Contact # 641-585-2905 FAX # 641-585-2891

1260.000	TON	ASPH BINDER, PG 58-28
79900.000	GAL	ASPH STABILIZING AGENT(STD ASPH EMULSION
6.374	MILE	CLEAN+PREPARATION OF BASE
82410.000	SY	COLD IN-PLACE RECYCLED ASPH PAV'T
1.000	LS	CONSTRUCTION SURVEY
45.000	EACH	FLAGGER
9600.000	TON	GRANULAR SHLD, TYPE B
1093.000	STA	GROOVE CUT - PAV'T MARK
6400.000	TON	HMA (3M ESAL) BASE, 1/2"
7300.000	TON	HMA (3M ESAL) INTERMEDIATE, 1/2"
7300.000	TON	HMA (3M ESAL) SURF, 1/2", NO FRIC
1.000	LS	HMA PAV'T SAMPLE
1.000	LS	MOBILIZATION
465.000	CY	MODIFIED SUBBASE
1474.000	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
978.000	SY	PAV'T, SCARIFICATION
1955.000	SY	RMVL OF PAV'T
8.000	EACH	RUMBLE STRIP PANEL (HMA SURF)
1.000	LS	SIGNING
1955.000	SY	STD/S-F PCC PAV'T, CL C CL 3, 8"
1.000	LS	TRAFFIC CONTROL



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

-----

Winnebago County -- LFM-(R34)--7X-95  
 Proposal Guarantee \$ 12,500.00  
 Courthouse, Forest City , IA, May 24, 2011, 11:00 AM  
 359-Miscellaneous, Asphalt Microsurfacing  
 Contact # 641-585-2905 FAX # 641-585-2891

923.520	TON	AGG - MICROSURFACING
27705.000	GAL	EMULSIFIED ASPH - MICROSURFACING
12.000	EACH	FLAGGER
1.000	LS	MOBILIZATION
1012.000	STA	PAINTED PAV'T MARK, WATERBORNE/SOLVENT
7.124	MILE	PREPARATION OF SURF - MICROSURFACING
6.000	EACH	RUMBLE STRIP PANEL (HMA SURF)
1.000	LS	TRAFFIC CONTROL

-----

Mills County Secondary Road Department County -- L-B244615--73-65  
 Proposal Guarantee \$ 5000.00  
 May 24, 2011 Glenwood, Iowa - Board of Supervisors Mills County Court House 418 Sharp Street Glen, Iowa 51534, IA 9:00 AM  
 Bid Turn-in Location: Mills County Engineers Office 403 Railroad Ave. Glenwood, Iowa 51534  
 10.0'x 8.0' Twin RCB Culvert, 15° Skew  
 Contact # 712-527-4873 FAX # 712-527-5124

1	ls	Clearing And Grubbing
197.0	cy	Excavation, Class 10 Roadway and Borrow
80.0	cy	Excavation, Class 10, Channel
150.0	ton	Granular surfacing on road, Class D Roadstone
1.0	ls	Removal of Existing Bridge
43.5	cy	Granular Backfill
800.0	cy	Excavation - Class 20
182.4	cy	Structural Concrete (RCB Culvert)
25,564.0	lb	Reinforcing Steel
1.0	ea	Apron, Conc. 36
30.0	lf	Culv. Conc. Entrance Pipe, 36
356.7	sy	Engineering Fabric
118.8	ton	Revetment, Class E
2.0	ea	Safety Closure
1.0	ls	Construction Survey
1.0	ls	Traffic Control
1.0	ls	Mobilization
1.0	ls	Removal and Reinstall Fence
1.0	ls	Temporary fence
1.0	ls	Temporary Stream Crossing
0.9	Acres	Mulch
0.9	Acres	Seeding and Fertilizing (Rural)



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

Mills County Secondary Road Department County -- L-221S--73-65

Proposal Guarantee \$ 5000.00

May 24, 2011 Glenwood, Iowa - Board of Supervisors, Mills County Court House 418 Sharp Street Glenwood, Iowa 51534, IA 9:30 AM

Bid Turn-in Location: Mills County Engineers Office 403 Railroad Ave. Glenwood, Iowa

Culvert Replacement - RCB

Contact # 712-527-4873 FAX # 712-527-5124

0.3	acre	Clearing And Grubbing
1,576.2	cy	Excavation, Class 10 Channel
1.0	ls	Removal of Existing Structures
313.3	ton	Granular Backfill
115.1	cy	Structural Concrete (RCB)
19,345.0	lb	Reinforcing Steel
1.0	ea	Aprons, Concrete, 24
41.5	lf	Culvert, Concrete entrance Pipe, 24
1.0	ea	Aprons, Metal 24
60.0	lf	Culvert, Corrugated Metal Entrance pipe, 24
94.4	cy	Flowable Mortar
266.7	sy	Engineering Fabric
109.0	lf	Removal and reinstall of fence, Barbed Wire
1.0	ls	Construction Survey
1.0	ls	Traffic Control
2.0	ea	Flaggers
1.0	ls	Mobilization
0.3	Acre	Mulching
0.3	Acre	Seeding and Fertilizing (Rural)

Cherokee County Secondary Road Department County -- L-58-B-11

Proposal Guarantee \$ 1500.00

May 31, 2011 Cherokee - Cherokee County Board of Supervisor's Room, IA 0930 A.M.

Bid Turn-in Location: Cherokee County Auditor's office, 520 W. Main, Cherokee, IA

Replace bridge on J Ave. approximately 1/2 mile north of C-44. Replacement Bridge will be an Oden bridge.

Sites: Between 560 & 570'th streets on J Ave.

Contact # 712-225-6712 FAX # 712-225-6715

713	CY	EMBANKMENT-IN-PLACE
1	LS	REMOVAL OF EXISTING BRIDGE
320	CY	EXCAVATION, CLASS 20
136	SY	ENGINEERING FABRIC
120	TON	REVTMENT, CLASS E
2	EACH	SAFETY CLOSURE
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
44.7	TON	GRANULAR SURFACE ON RD. CL A STONE
72.5	CY	GRANULAR SUBBASE
72.5	CY	GRANULAR SUBBASE, PLACE ONLY
1.76	CY	STRUCTURE CONCRETE (BRIDGE-PAVING BLOCKS)
1	LS	FURNISH ODEN ENTERPRISES BRIDGE
1	LS	INSTALL ODEN ENTERPRISES BRIDGE



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

-----

Cherokee County Secondary Road Department County -- L-58-B-11  
 Proposal Guarantee \$ 1500.00  
 May 31, 2011 Cherokee, IA - 520 W. Main, IA 930 A.M.  
 Bid Turn-in Location: Cherokee County Auditor's Office  
 Replace damaged bridge with Oden Enterprises Precast deck bridge  
 Contact # 712-225-6712 FAX # 712-225-6715

- 1.76 cy Structural Concrete
- 713 cy Embakment in-place
- 285 sy Granular Subbase
- 285 sy Granular Subbase- place only
- 44.7 ton Granular Surface, Class A
- 1 LS Removal of Existing Bridge
- 320 cy Excavation - Class 20
- 136 sy Engineering Fabric
- 120 Ton Revetment, Class E
- 2 Each Safety Closures
- 1 LS Traffic Control
- 1 LS Mobilization
- 1 LS Furnish Oden Enterprises Bridge
- 1 LS Install Oden Enterprises Bridge

-----

Wright County -- L-B061856--73-99  
 Proposal Guarantee \$ 12,500.00  
 Courthouse, Clarion , IA, June 02, 2011, 10:00 AM  
 320-Bridges, Bridge Replacement  
 Contact # 515-532-3597 FAX # 515-532-6063

- 1.000 LS Furnish 34' x 28' 6" Oden Bridge As Per Plan
- 1.000 LS Install 34' x 28' 6" Oden Bridge As Per Plan

-----

Bremer County -- M-01-2011 Contract rock  
 Proposal Guarantee \$ 1,000.00  
 Courthouse, Waverly , IA, June 06, 2011, 11:00 AM  
 Granular surfacing on road, crushed stone, Division I 44.00 Miles, 11,150 ton Division II 42.75 Miles, 10,250 ton Division III 20.25 miles, 5,000 ton Division IV 56.00 miles, 13,225 ton  
 Contact # 319-352-4302 FAX # 319-352-4326

39625.000 TON GRANULAR SURF ON RD, CL A CR STONE



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

Bremer County -- L-9-311

Proposal Guarantee \$ 12,500.00

County boardroom, Waverly, IA, June 06, 2011, 11:30 AM

Grading & Culverts, Culvert project with associated grading work on 270th Street and Garden Avenue.

Contact # 319-352-4302 FAX # 319-352-4326

2.000	EACH	APRON, CONC, 36"
2.000	EACH	APRON, CONC, 42"
1218.000	LF	CLEAN-OUT OF SILT FENCE
251.000	LF	CLEAN-OUT OF SILT FENCE-DITCH CHECK
3.488	ACRE	CLEAR+GRUBB
42.000	LF	CULV, CMP ENT, 18"
40.000	LF	CULV, CONC RDWY PIPE, 36"
54.000	LF	CULV, CONC RDWY PIPE, 42"
38.880	SY	ENGINEER FABRIC
69.000	TON	EROSION STONE
13003.000	CY	EXCAVATION, CL 10, RDWY+BORROW
595.000	CY	EXCAVATION, CL 20, RDWY PIPE CULV
1764.000	TON	GRANULAR SURF ON RD, CL A CR STONE
1.000	LS	MOBILIZATION
3.488	ACRE	MULCH
1.000	LS	RMVL OF EXIST STRUCT
4.000	EACH	SAFETY CLOSURE
3.488	ACRE	SEED+FERTILIZE (RURAL)
1218.000	LF	SILT FENCE
251.000	LF	SILT FENCE-DITCH CHECKS
1094.000	CY	TOPSOIL, STRIP, SALVAGE+SPREAD
1.000	LS	TRAFFIC CONTROL
2.000	EACH	TWIN PRECAST CONC BOX CULV ST END SEC, _12' x 4' _____
32.000	LF	TWIN PRECAST CONC BOX CULV, _12' x 4' _____

Buena Vista County Secondary Road Department County -- Buena Vista Co. Salt Storage Shed

Proposal Guarantee \$ 3000.00

June 7, 2011 Storm Lake, IA - Buena Vista County Board Room, IA 11:00 A.M.

Bid Turn-in Location: Buena Vista County Auditor's Office

The construction of 8in. reinforced poured concrete walls for a 40'x70' bulk salt storage building and a 50'x70' bulk salt/sand storage building. Buildings to be constructed at the Buena Vista County Maintenance Facility on the east side of Storm Lake, IA. (At the Intersections of Radio Rd (120th Ave) and East Richland)

Sites: Storm Lake, IA

Contact # 712-749-2540 FAX # 712-749-2704

1	LS	Removal & Disposal of Existing Structure
1	LS	40'x70', 8
1	LS	50'x70', 8



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

Kossuth County -- LFM-B971003--7X-55

Proposal Guarantee \$ 25,000.00

Courthouse, Algona , IA, June 07, 2011, 11:00 AM

320-Bridges, Removal of existing 36' x 24' Steel I-Beam Bridge on high timber abutments and the construction of 100' x 30' C.C.S. Bridge, 15° Skew, non-monolithic piers & integral abutments. Located approximately 0.3 miles South of NW Corner Section 10, Lincoln Township, Kossuth County, Iowa.

Contact # 515-295-3320 FAX # 515-295-4973

222.200	LF	CONC OPEN RAIL, TL-4
510.000	CY	EXCAVATION, CL 10, CHANNEL
828.000	LF	PILE, PRESTRESS CONC, 16" (P10L TYPE 2)
700.000	LF	PILE, STEEL, HP 10X42
59856.000	LB	REINFORCE STEEL, EPOXY COATED
2.000	EACH	SAFETY CLOSURE
4.000	EACH	STEEL BEAM G'RAIL BARRIER TRANS SECTION
245.200	CY	STRUCT CONC (BRIDGE)
1.000	LS	TRAFFIC CONTROL

Kossuth County -- LFM-B081310--7X-55

Proposal Guarantee \$ 25,000.00

Courthouse, Algona , IA, June 07, 2011, 11:00 AM

320-Bridges, Removal of existing 68' x 30' Steel I-Beam Bridge on high timber abutments and the construction of 80' x 30' C.C.S. Bridge, 0° Skew, non-monolithic piers & integral abutments. Located approximately 0.1 miles East of NW Corner Section 13, Springfield Township, Kossuth County, Iowa.

Contact # 515-295-3320 FAX # 515-295-4973

182.000	LF	CONC OPEN RAIL, TL-4
75.000	CY	EXCAVATION, CL 10, CHANNEL
225.000	LF	INSTALLATION OF G'RAIL
928.000	LF	PILE, PRESTRESS CONC, 16" (P10L TYPE 2)
1100.000	LF	PILE, STEEL, HP 10X42
46704.000	LB	REINFORCE STEEL, EPOXY COATED
2.000	EACH	SAFETY CLOSURE
189.400	CY	STRUCT CONC (BRIDGE)
1.000	LS	TRAFFIC CONTROL

Butler County Secondary Road Department County -- LFM-T55/220th--73-12

Proposal Guarantee \$ 37500

June 14th, 2011 Allison - County Boardroom, IA 10:00 A.M.

Bid Turn-in Location: County Auditor

Full Depth Reclamation, Grading & Structures work on 220th Street - Earth Shoulders & Structures on T55

Contact # 319-267-2630 FAX # 319-267-2625

61500	cy	Excavation - Class 10
3820	cy	Modified Subbase, Place Only
2500	ton	Base Choke Stone
216	lf	Concrete Roadway Pipe, 24
134	lf	Concrete Roadway Pipe, 30
58	lf	Concrete Roadway Pipe, 36
194	lf	Concrete Roadway Pipe, 42
84	lf	Concrete Roadway Pipe, 54
19380	sy	Removal & Crushing of Pavement
1	ls	Traffic Control
3400	lf	Silt Fence



# Iowa Department of Transportation

## LOCAL LETTING INFORMATION

-----  
Clay County -- Tied LST Bridge Replacements (PRECAST OPTION)

Proposal Guarantee \$ 37,500.00

Clay County Admin Bldg / Boardroom, Spencer, IA, June 28, 2011, 9:00 AM

Bridge Replacement w/ Box Culverts, LST-5812C-1 (MB16-2) Twin 12x10x40 15° Skew LST-5812C-1 (MB17-1) Twin 12x10x40 30° Skew LST-5712C-2 (LB31-2) Single 12x10x40 0° Skew LST-6512C-3 (HB24-2) Twin 10x12x40 15° Skew

Contact # 712-262-2825 FAX # 712-262-4114

28.200	UNIT	CLEAR+GRUBB
660.000	CY	EXCAVATION, CL 10, CHANNEL
40.000	CY	EXCAVATION, CL 12, BOULDER/ROCK FRAGMENT
2446.000	CY	EXCAVATION, CL 13, RDWY+BORROW
705.000	CY	EXCAVATION, CL 20
387.000	CY	EXCAVATION, CL 23
758.000	TON	GRANULAR MAT'L
4.000	LS	MOBILIZATION
128387.000	LB	REINFORCE STEEL
4.000	LS	RMVL OF EXISTING BRIDGE
931.400	CY	STRUCT CONC (RCB CULV)



# Iowa Department of Transportation

## BULLETIN REPORTING FORM

County: Winnebago Project No.: L-(E8WB)  
 Proposal Guarantee: \$12,500 DBE or TSB Goal: \_\_\_\_\_ %  
 Date of Letting: May 24, 2011 Time of Letting: 11:15 A.M.  
 Bid Turn-In Location: County Engineer Type of Project: 332- Box Culvert  
 Contact Phone #: 6415852905 Contact Fax #: 6415852891

Specific Description of Project: Replace existing timber bridge with a twin 10'x10'x58' cast in place box culvert with end sections and flared wingwalls.

QUANTITY	UNIT	DESCRIPTION
1800	CY	EXCAVATION, CL. 10, RDWY & BRW
1	LS	QUALITY MANAGEMENT-CONCRETE
150	TON	GRAN. SURF. ON ROAD, CL. A.
1	LS	REMOVAL OF EXISTING BRIDGE
200	TON	GRANULAR BACKFILL
400	CY	EXCAVATION, CL. 20
255	CY	STRUC. CONC. (RCB CULVERT)
35100	LB	REINFORCING STEEL
150	TON	REVTMENT, CL. E
2	EACH	SAFETY CLOSURE
1	LS	CONSTRUCTION SURVEY
1	LS	TRAFFIC CONTROL
1	LS	MOBILIZATION
2	EACH	TILE RELOCATION
0.8	ACRE	MULCHING
0.8	ACRE	FERTILIZE & SEED (RURAL)
80	LF	SILT FENCE

Date: 4/29/2011 Local Agency Official: Jim Witt

Notices must be in the Ames Office by 5:00 p.m. the Friday before the first publication in which advertising is desired. E-mail completed forms to Iowa Department of Transportation, Office of Contracts at DOT.Contracts@DOT.iowa.gov