

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: July 19, 2011
Date of Addendum: June 23, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
009	61-C061-092	Abutment Repair	Madison	ER-C061(92)--58-61	19jul009.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Attached is a SCHEDULE OF PRICES for the following item:

Line No. 0141 2408-7800000 STRUCTURAL STEEL

Bid this item as instructed and submit the bid for this item with the Bid Proposal.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Line No. 0060 2409-4200001 MISCELLANEOUS HARDWARE from 149.850 LB to **199.850 LB**.

Change Line No. 0070 2409-4575001 TREATED TIMBER AND LUMBER from 4.262 MFBM to **4.858 MFBM**.

If the quantities are not changed on the proposal form, the bid amounts will be extended using the unit price times the correct quantities as shown here.

Make the following change to the plan:

SHEET 2:

Add the following note to the reference notes for the item 2408-7800000, STRUCTURAL STEEL:

The Bid Item Structural Steel includes: New diaphragms (W6X12) X 2.25' (x15) = 405 lbs. Cut off existing diaphragms 4" from beam. (C10x30) x14' (x4) c-channel for abutment caps = 1680 lbs. 1/4"pl x 14" x 14' (x2) top plate for abutment caps = 334 lbs.

Add the following text to the reference note for the item 2409-4200001 MISCELLANEOUS HARDWARE:

The bid item Galvanized Hardware has been increased to include: 60d nails (450 total = 50 lbs.) To be used to re-deck the superstructure.

Add the following text to the reference note for the item 2409-4575001
TREATED TIMBER AND LUMBER:

The bid item Treated Lumber has been increased to include: 4x12x14 (x4), 3x12x14 (x6), replace existing 3x6 nailers with 3x12, 3x12x20 (x2).

Delete the reference note and replace with the following note for the item 2401-6750001 REMOVALS, AS PER PLAN:

The superstructure of the existing bridge has been removed from the existing substructure and is located on the project site. The superstructure of the existing bridge shall be replaced on the new substructure. This work shall be incidental to the Bid Item Removals, As Per Plan.

Proposal ID No.: 61-C061-092
 Primary Work Type: ABUTMENT REPAIR
 Primary County: MADISON

Bid Order No.: 009
 Letting Date: JULY 19, 2011
 10:00 A.M.

ITEMS LISTED ON THIS PAGE ARE ADDED BY ADDENDUM 19jul009.a01

UNIT BIDS MUST BE TYPED OR SHOWN IN INK OR THE BID WILL BE REJECTED.

Line No	Item Number Item Description	Item Quantity and Unit	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Cts
Section 0001 (continued)						
ITEMS FOR A 28'-0 X 14'-0 I-BEAM BRIDGE WITH TIMBER DECK						
0141	2408-7800000 STRUCTURAL STEEL	2,419.000 LB	.		.	
Total Bid					.	