

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: November 15, 2011
Date of Addendum: October 26, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
352	77-C077-185	Traffic Signs	Polk	FM-TSF-C077(185)--5B-77 FM-TSF-C077(186)--5B-77	15nov352.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the Proposal:

Delete SP-090120, March 15, 2011

SPECIAL PROVISIONS FOR LIGHTING INTENDED FOR: SCOTT COUNTY
IM-074-1(191)1--13-82, from the Proposal Special Provisions Text and the Proposal
Special Provisions List.

Add the attached SP-091020, November 15, 2011

SPECIAL PROVISIONS FOR CONTINUOUS OPERATING SINGLE HEAD SOLAR
BEACON ON WARNING SIGN POST Polk County FM-TSF-C077(185)--5B-77 & FM-TSF-
C077(186)--5B-77 to the Proposal Special Provisions Text and the Proposal Special Provisions
List.



**SPECIAL PROVISIONS
FOR
CONTINUOUS OPERATING SINGLE HEAD SOLAR BEACON ON WARNING SIGN POST**

Polk County

Project Numbers
FM-TSF-C077(185)--5B-77 & FM-TSF-C077(186)--5B-77

Effective Date
November 15, 2011

THE STANDARD SPECIFICATIONS, SERIES 2009, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

091020.01 DESCRIPTION**A. Summary.**

This work includes the supply and installation of a continuous operating single head solar powered flashing beacon on a warning sign post, including providing the post. Each unit shall consist of a self-contained solar engine, LED signal module and signal housing, and mounting hardware such that the entire assembly mounts to the top of the post. The solar engine shall contain all electronics, batteries and solar panels. No additional cabinet is required. The system shall conform to all provisions of the MUTCD, Chapter 4L, Flashing Beacons.

B. Quality Assurance.

The product must be Federal Communication Commission (FCC) certified to comply with all of 47 Code of Federal Regulations (CFR) FCC Part 15 Subpart B Emission requirements. The system, including battery packs, solar panel, LED modules and all components, shall be guaranteed for a minimum of three years. Manufacturer must be International Organization for Standardization (ISO) 9001 certified.

091020.02 MATERIAL**A. Mechanical Specifications.**

1. The solar engine shall be constructed from powder coated aluminum, and shall be no greater in size than 4.75" x 15" x 32". The Solar panels shall be integrated to the solar engine. All batteries and electronics shall be mounted in the solar engine, with no external control cabinet or battery cabinet required. The solar engine shall be vented to provide cooling of the battery and electronic system. Venting shall be covered by wire mesh to prevent intrusion of insects.
2. The solar engine shall have the provision to mount an external device for remote activation. System must have capability to power such device. Solar engine must contain sufficient space to house third party device inside a sealed enclosure located inside the solar engine.
3. The overall weight of the assembly, including mounting hardware, signal housings, LED modules, and solar engine shall not exceed 75 lbs.
4. The solar engine shall have the provision to be tilted and oriented south with additional mounting hardware, or mounted completely flat to the ground such that mounting in any orientation will keep the solar engine level.

B. Mounting.

The entire assembly, including solar engine, signal housing and LED module, and bracket shall be provided with hardware for mounting on to the top of a post designed to meet the minimum requirements to withstand 110 mph wind loads in conformance with the requirements of the AASHTO publication, "Standard Specifications for Structural Supports of Highway Signs, Luminaires and Traffic Signals", 5th Edition 2009, including latest revisions and errata in affect at time of letting. Mounting hardware shall be standard traffic signal mounting hardware.

C. Solar / Battery System.

1. The solar engine shall include two 10-watt solar panels no larger than the footprint of the housing. The solar engine shall house two, field replaceable sealed lead acid batteries no greater than 24 Ah each.

The solar panel and battery system shall be 12 Volt DC.

SP-091020 page 3 of 4

2. The solar panel shall meet the design qualification and type approval of photovoltaic modules in accordance with International Electrotechnical Commission (IEC) 61215. This specification includes radiation testing, thermal testing, and mechanical testing for environmental conditions such as UV-exposure, thermal cycling, as well as degradation of maximum power output.
3. The solar panel shall consist of no more than two solar panels, mounted to the solar engine with an aluminum flashing.
4. The batteries shall be mechanically secured into the housing. A battery bracket shall enclose each battery in a manner to restrict the thermal expansion of the battery.
5. System shall have an auxiliary 12 Volt DC power output to power third party devices such as wireless radios or sensing equipment.

D. Signal Housing.

The solar engine shall not overhang the signal head, so as not to restrict mounting a signal head back plate. The signal head shall be easily removable from the assembly. The bracket assembly shall be constructed such that the signal heads can be removed easily in the field without removing the solar engine. The bracket assembly shall be designed to take the torsion and bending load of the solar engine. The signal head shall not be subjected to the torsional or bending load of the solar engine.

E. Posts.

The post used to support the entire assembly, including solar engine, signal housing, LED module, and bracket shall be breakaway type design and meet the requirements to withstand 110 mph wind loads and be in conformance with the requirements of the AASHTO publication, "Standard Specifications for Structural Supports of Highway Signs, Luminaires and Traffic Signals", 5th Edition, including latest revisions and errata in affect at time of letting. Contractor shall submit shop drawings of post design to the Engineer for approval prior to ordering posts. Cost for preparation of shop drawings shall be considered incidental to price bid for each unit installed.

091020.03 OPERATIONAL SPECIFICATIONS

- A. The system shall conform to all standards for flashing beacons as required in the accepted Manual of Uniform Traffic Control Devices and current versions.
- B. The beacon shall flash at a rate of not less than 50 or more than 60 times per minute. The illuminated period of each flash shall not be less than one-half and not more than two-thirds of the total cycle.
- C. The beacon shall have a night dimming feature.
- D. The beacon shall have a minimum operating autonomy of 30 days.
- E. The beacon shall automatically reduce light output in case of low battery situations, reducing risk that the beacons will fail entirely under conditions of poor solar insulation.

091020.04 ACTIVATION

The beacon shall operate continuously when the battery is connected. The beacon shall have the option to be turned on by a third party switch or third party device with a compatible contact closure output.

091020.05 ENVIRONMENTAL SPECIFICATIONS

A. The system shall be able to withstand and operate at temperature extremes of -40 deg. F to +122 deg. F.

B. The system shall be designed and constructed to withstand 110 mph wind loads in conformance with the requirements of the AASHTO publication, "Standard Specifications for Structural Supports of Highway Signs, Luminaires and Traffic Signals", 5th Edition 2009, including latest revisions and errata in affect at time of letting.

C. The electronic circuit board housing, wire harnessing and connectors shall be designed and tested in accordance to IEC International Standard 60529, Ingress Protection IP67 requiring that the enclosure be dust tight and remain completely sealed when immersed in water to a depth of 1 meter for 1 hour.

091020.06 ELECTRICAL STANDARDS

Integrated solar charger shall be approved to Canadian Standards Association (CSA) and Underwriters Laboratories, Inc. (UL) standards.

091020.07 METHOD OF MEASUREMENT

The quantity of Single Head Solar Beacon on Warning Sign Post will be measured by each beacon assembly and post installed in accordance with the contract documents. Warning signs to be installed on post to be paid under other items.

091020.08 BASIS OF PAYMENT

The Contractor will be paid the contract unit price for each Single Head Solar Beacon on Warning Sign Post, measured as described above.