

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 001                      Proposal ID: 02-C002-057

Proposed Contract Period: Late Start Date of 08/27/12 with 50 WORK DAYS

Project(s):

Project No: BRS-C002(57)--60-02

County: ADAMS

Type of Work: RCB CULVERT NEW - SINGLE BOX

Route: 183RD STREET                      Length: 0.20 miles

Location: OVER A SMALL STREAM, 0.2 MI. EAST OF HWY 148.

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 12'-0 X 10'-0 SINGLE RCB CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	6,395 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	733 SY
2403-0100020	STRUCT CONC (RCB CULV)	220 CY
2404-7775000	REINFORC STEEL	37,029 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 002                      Proposal ID: 06-C006-083

Proposed Contract Period: Late Start Date of 08/13/12 with 55 WORK DAYS

Project(s):

Project No: BROS-C006(83)--8J-06

County: BENTON

Type of Work: BRIDGE AND APPROACHES - PPCB

Route: BENTON IOWA ROAD              Length: 0.00 miles

Location: OVER A SMALL STREAM, APPROX. 4 MILES SE OF LUZERNE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 90'-0 X 30'-0 PPCB BRIDGE AND APPROACHES		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	62 CY
2403-0100010	STRUCT CONC (BRIDGE)	150 CY
2404-7775000	REINFORC STEEL	35,380 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 003                      Proposal ID: 06-C006-084

Proposed Contract Period: Late Start Date of 07/23/12 with 65 WORK DAYS

Project(s):

Project No: BROS-C006(84)--5F-06

County: BENTON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 50TH STREET                      Length: 0.00 miles

Location: OVER SPRING CREEK

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 100'-0 X 30'-6 CCS BRIDGE REPLACEMENT		
2403-0100010	STRUCT CONC (BRIDGE)	227 CY
2404-7775000	REINFORC STEEL	57,361 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 09-C009-050

Proposed Contract Period: Late Start Date of 06/18/12 with 80 WORK DAYS

Project(s):

Project No: BROS-C009(50)--8J-09

County: BREMER

Type of Work: BRIDGE AND APPROACHES - CCS

Route: 150TH STREET Length: 0.00 miles

Location: SOUTH .5 MI. OF SUMNER ON YUKON THEN  
WEST .25 MI. ON 150TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 220'-0 X 24'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	453 CY
2404-7775000	REINFORC STEEL	104,813 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,290 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 005                      Proposal ID: 18-C018-059

Proposed Contract Period: Late Start Date of 07/16/12 with 60 WORK DAYS

Project(s):

Project No: BRS-C018(59)--60-18

County: CHEROKEE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: M21                                      Length: 0.00 miles

Location: OVER PITCHER CREEK APPROXIMATELY 5 MILES SOUTH OF AURELIA

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 90'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,500 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	157 SY
2403-0100010	STRUCT CONC (BRIDGE)	198 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	52,522 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 33-C033-109-A

Proposed Contract Period: Late Start Date of 06/18/12 with 70 WORK DAYS

Project(s):

Project No: STP-E-C033(109)--5K-33

County: FAYETTE

Type of Work: BRIDGE NEW - PPCB

Route: RECREATIONAL TRAIL Length: 0.00 miles

Location: OVER TURKEY RIVER

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 283'-0 X 12'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	321 CY
2404-7775000	REINFORC STEEL	20,270 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	52,633 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 37-0042-038

Proposed Contract Period: Specified Start Date of 03/05/12 with 140 WORK DAYS

Project(s):

Project No: HDP-004-2(38)--71-37

County: GREENE

Type of Work: BRIDGE NEW - PPCB

Route: IOWA 4 Length: 0.40 miles

Location: IN THE CITY OF JEFFERSON OVER UP R.R.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0111; A 1094'-0 X 54'-0 PPCB BRIDGE WITH 10'-0 SIDEWALK		
2403-0100010	STRUCT CONC (BRIDGE)	3,837 CY
2404-7775000	REINFORC STEEL	289,385 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	687,115 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	14,209 CY
2122-5190009	PAVED SHLD, PCC, 9"	572 SY
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	780 SY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	463 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	2,522 SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	6,590 SY
2404-7775005	REINFORC STEEL, EPOXY COATED	38,049 LB
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	1,172 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 38-C038-082

Proposed Contract Period: Late Start Date of 04/02/12 with 120 WORK DAYS

Project(s):

Project No: BROS-C038(82)--8J-38

County: GRUNDY

Type of Work: BRIDGE AND APPROACHES - PPCB

Route: 230TH STREET Length: 0.33 miles

Location: OVER BLACK HAWK CREEK  
SECTION 12, T87N, R15W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 304' - 0 X 30' - 0 PPCB		
2403-0100010	STRUCT CONC (BRIDGE)	491 CY
2404-7775000	REINFORC STEEL	122,372 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	51,686 CY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 009                      Proposal ID: 42-C042-112-A

Proposed Contract Period: Late Start Date of 08/20/12 with 40 WORK DAYS

Project(s):

Project No: BRS-C042(112)--60-42

County: HARDIN

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: D20                                      Length: 0.00 miles

Location: 0.4 MI E. OF S15, OVER DRAINAGE DITCH  
LATERAL 3, DRAINAGE DISTRICT BIG 4

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 10' X 10' X 62' TWIN RCB CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	385 CY
2301-1032090	STD/S-F PCC PAV'T, CL C CL 2, 9"	278 SY
2403-0100020	STRUCT CONC (RCB CULV)	257 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	34,590 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 43-0301-119

Proposed Contract Period: Late Start Date of 05/29/12 with 105 WORK DAYS

Project(s):

Project No: NHSX-030-1(119)--3H-43

County: HARRISON

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: U.S. 30 Length: 0.00 miles

Location: OVER SMALL NATURAL STREAM 3.6 MILES E. OF  
CO. RD. F-32

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 109; A 122' - 2 X 53' - 0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	396 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	79,318 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,092 CY
SECTION NO. 0003		
ALTERNATE 'AA' OPTION 1: PCC SHOULDERS BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	1,034 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 52-C052-089

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE STAGES 1 THROUGH 6 AS SHOWN ON J.01

Late Start Date of 04/02/12 with 100 WORK DAYS

Site 02: TO COMPLETE STAGES 7 THROUGH 12 AS SHOWN ON J.01

Approx Start Date of 04/15/13 with 85 WORK DAYS

Project(s):

Project No: STP-S-C052(89)--5E-52

County: JOHNSON

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: OAKDALE BOULEVARD Length: 0.63 miles

Location: GOLDS GYM TO DUBUQUE STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	75,507 CY
2301-1032090	STD/S-F PCC PAV'T, CL C CL 2, 9"	8,698 SY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	462 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	447 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	495 TON
2403-0100000	STRUCT CONC (MISCELLANEOUS)	445 CY
2404-7775000	REINFORC STEEL	34,677 LB
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	2,842 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 012                      Proposal ID: 55-C055-133

Proposed Contract Period: Late Start Date of 07/09/12 with 55 WORK DAYS

Project(s):

Project No: BROS-C055(133)--5F-55

County: KOSSUTH

Type of Work: BRIDGE REPLACEMENT - CCS

Route: B-30                                      Length: 0.00 miles

Location: OVER LOTTS CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 90'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	223 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	53,530 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 013                      Proposal ID: 60-C060-085

Proposed Contract Period: Late Start Date of 05/28/12 with 100 WORK DAYS

Project(s):

Project No: BHOS-C060(85)--5N-60

County: LYON

Type of Work: RECONSTRUCTION - BRIDGE WIDENING

Route: K60                                      Length: 0.00 miles

Location: APPROX. 1/3 MILE SOUTH OF 220TH STREET  
WHEELER TWP. SECTION 7.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 205'-0 X 20'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE WIDENING TO 30'-0 ROADWAY		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,011 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	1,225 SY
2403-0100010	STRUCT CONC (BRIDGE)	347 CY
2404-7775000	REINFORC STEEL	11,544 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	68,445 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 63-C063-102

Proposed Contract Period: Late Start Date of 07/09/12 with 80 WORK DAYS

Project(s):

Project No: BROS-C063(102)--8J-63

County: MARION

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: 140TH AVENUE Length: 0.01 miles

Location: OVER HICKORY CREEK APPROXIMATELY 10 MILES SOUTH OF KNOXVILLE

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 176'-4 X 24'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	16,090 CY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	10 CY
2403-0100010	STRUCT CONC (BRIDGE)	253 CY
2404-7775000	REINFORC STEEL	59,849 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 015                      Proposal ID: 75-0122-017

Proposed Contract Period: Late Start Date of 07/09/12 with 80 WORK DAYS

Project(s):

Project No: BRFN-012-2(17)--39-75

County: PLYMOUTH

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: IOWA 12                      Length: 0.00 miles

Location: OVER A DRAINAGE DITCH, IN SECTION 24-9-49, 5.6 MILES SOUTH  
OF IOWA 3.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 110, A 12'-0 X 8'-0 X 95'-0 RCB SINGLE CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	225 CY
2404-7775000	REINFORC STEEL	37,920 LB
SECTION NO. 0002		
ROADWAY ITEMS FOR DESIGN NO. 110		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,823 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	41 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	54 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	74 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 016                      Proposal ID: 77-C077-173

Proposed Contract Period: Late Start Date of 04/02/12 with 240 WORK DAYS  
Site 01: TO COMPLETE PHASE 1 AS SHOWN ON PLAN SHEET J.01.  
Late Start Date of 04/02/12 with 100 WORK DAYS

Project(s):

Project No: STP-S-C077(173)--5E-77  
County: POLK  
Type of Work: RETAINING WALL -- CAST-IN-PLACE  
Route: AURORA AVE.                      Length: 0.50 miles  
Location: IN THE CITY OF DES MOINES FROM AURORA  
AVE. NORTH TO I-80

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	13,942 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	750 SY
2303-0042750	HMA (3M ESAL) INTERMEDIATE, 3/4"	4,279 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	2,202 TON
2403-0100000	STRUCT CONC (MISCELLANEOUS)	246 CY
2404-7775000	REINFORC STEEL	28,528 LB



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 017                      Proposal ID: 78-0293-080

Proposed Contract Period: Completion Date of 10/04/13

Project(s):

Project No: IM-NHS-029-3(80)52--03-78

County: POTTAWATTAMIE

Type of Work: BRIDGE NEW - STEEL GIRDER

Route: I-29                                      Length: 0.00 miles

Location: IN THE CITY OF COUNCIL BLUFFS ON NE CONNECTOR SB I-29  
TO I-29/80 OVER I-80 & RAMPS

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
DESIGN NO. 0612; A 2166'-0 X VARIES CONTINUOUS WELDED CURVED GIRDER BRIDGE		
2102-2625000	EMBANKMENT-IN-PLACE	810 CY
2403-0100010	STRUCT CONC (BRIDGE)	873 CY
2404-7775000	REINFORC STEEL	384,810 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	1,603,705 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 018                      Proposal ID: 80-C080-054

Proposed Contract Period: Late Start Date of 04/30/12 with 15 WORK DAYS

Project(s):

Project No: ER-C080(54)--58-80

County: RINGGOLD

Type of Work: PERMANENT SCOUR COUNTERMEASURES

Route: P33                                      Length: 0.00 miles

Location: AT WEST FORK GRAND RIVER  
APPROX. 0.5 MILES S. OF DIAGONAL

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 019 Proposal ID: 85-C085-113

Proposed Contract Period: Late Start Date of 04/02/12 with 45 WORK DAYS

Project(s):

Project No: BRS-C085(113)--60-85

County: STORY

Type of Work: RCB CULVERT NEW - TWIN BOX

Route: E18 Length: 0.10 miles

Location: .35 MILES WEST OF US HIGHWAY 69

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR TWIN 10' X 8' X 80' RCB CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	590 CY
2301-1012080	STD/S-F PCC PAV'T, CL A CL 2, 8"	278 SY
2403-0100020	STRUCT CONC (RCB CULV)	271 CY
2404-7775000	REINFORC STEEL	34,257 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 020 Proposal ID: 85-0305-229

Proposed Contract Period: Late Start Date of 06/25/12 with 75 WORK DAYS

Project(s):

Project No: BRFN-030-5(229)--39-85

County: STORY

Type of Work: ABUTMENT REPAIR

Route: U.S. 30 Length: 0.00 miles

Location: OVER UP R.R. 0.2 MILES W. OF CO. RD. S-14  
(WBL/EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0212; REPAIRS TO A TWIN 200'-0 X 30'-0 CONTINUOUS I-BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	168 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	15,983 LB
2413-0698074	DECK REPAIR, CL A	70 SY
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	140 CY
SECTION NO. 0003		
ALTERNATE 'AA' OPTION 1: PCC PAVED SHOULDERS BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	889 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 021 Proposal ID: 90-5825-636

Proposed Contract Period: Late Start Date of 08/27/12 with 45 WORK DAYS

Project(s):

Project No: BRM-5825(636)--8N-90

County: WAPELLO

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: SOUTH MILNER ST. Length: 0.10 miles

Location: IN THE CITY OF OTTUMWA  
OVER JEFFERSON DRAINAGE DITCH

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 8'-0 X 6'-0 REINFORCED CONCRETE BOX CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	518 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	860 SY
2403-0100020	STRUCT CONC (RCB CULV)	197 CY
2404-7775000	REINFORC STEEL	26,716 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 022 Proposal ID: 91-C091-079

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE THE FIRST RCB

Late Start Date of 06/04/12 with 25 WORK DAYS

Site 02: TO COMPLETE THE SECOND RCB

Approx Start Date of 07/23/12 with 25 WORK DAYS

Proposal Note:

\*\*\*SITE 01 AND 02\*\*\*

ONE RCB IS TO BE COMPLETED AND THE ROAD OPENED TO TRAFFIC  
BEFORE WORK CAN BEGIN ON THE OTHER RCB. THE CONTRACTOR CAN  
CHOOSE WHICH RCB TO BUILD FIRST.

Project(s):

Project No: BROS-C091(79)--8J-91

County: WARREN

Type of Work: RCB CULVERT NEW - SINGLE BOX

Route: 143RD AVE Length: 0.20 miles

Location: 3.5 MI NORTH OF INDIANOLA ON 143RD AVE

Project No: BROS-C091(80)--8J-91

County: WARREN

Type of Work: RCB CULVERT NEW - SINGLE BOX

Route: 143RD AVE Length: 0.20 miles

Location: 1.25 MI NORTH OF INDIANOLA ON 143RD AVE  
8-76-23

Item No.	Item Description	Quantity/Unit
	SECTION NO. 0001	
	ITEMS FOR SINGLE 10' X 10' X 54'-0 PRECAST CULVERT BROS-C091(79)--8J-91	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,783 CY
	SECTION NO. 0002	
	ITEMS FOR SINGLE 12' X 8' X 72'-0 PRECAST CULVERT BROS-C091(80)--8J-91	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,579 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 023 Proposal ID: 97-0297-042

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE ALL WORK THROUGH STAGE 2C AND (37)&(38) BRIDGES.  
Completion Date of 11/21/12

Proposal Note:

\*\*\*MISSOURI RIVER WAGE DECISION\*\*\*

WAGE DECISION IA10-31.12 SHALL APPLY ONLY TO PROJECT  
IM-029-7(41)149--13-97.

\*\*\* NO EXCUSE ROAD OPENING BONUS FOR 2012 WORK \*\*\*

THE CONTRACTOR WILL BE PAID THE PREDETERMINED LUMP SUM  
AMOUNT SHOWN IN THE PROPOSAL SCHEDULE OF PRICES FOR THE BID  
ITEM 'NO EXCUSE ROAD OPENING BONUS' FOR COMPLETING ALL  
WORK FOR STAGE 1 THROUGH STAGE 2C AS SHOWN ON SHEET J.1 OF  
THE PLANS ON OR BEFORE THE CALENDAR DATE SHOWN. ANY OTHER  
DELAYS DUE TO WEATHER, CHANGE ORDERS, OVERRUNS OF  
QUANTITIES, UTILITY DELAYS, OR ANY OTHER DELAYS WILL NOT BE  
CONSIDERED AS JUSTIFICATION TO MODIFY THE CALENDAR DATE.

\*\*\* INCENTIVE/DISINCENTIVE FOR 2013 WORK \*\*\*

SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR  
INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL  
APPLY TO WORK IN 2013 WITH THE FOLLOWING CONDITIONS:  
CLOSURE DAYS: 180  
MAXIMUM INCENTIVE: NONE  
INCENTIVE RATE PER DAY: \$2,000.00  
DISINCENTIVE RATE PER DAY: \$2,000.00  
THE CRITICAL CLOSURE ACTIVITY INCLUDES COMPLETION OF ALL  
CONTRACT ITEMS THAT ARE INVOLVED IN COMPLETING STAGES 3A  
THROUGH 4 AS SHOWN ON PLAN SHEET J.1B. THE  
INCENTIVE/DISINCENTIVE AMOUNT WILL BE PAID/COLLECTED BY THE  
CONTRACTING AUTHORITY UPON COMPLETION OF THE CRITICAL  
CLOSURE ACTIVITY.

Project(s):

Project No: IM-NHS-029-7(37)149--03-97

County: WOODBURY

Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER

Route: I-29 Length: 3.15 miles

Location: IN THE CITY OF SIOUX CITY ON WESLEY PARKWAY (US 77)  
OVER I-29

Project No: IM-029-7(38)149--13-97

County: WOODBURY

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: I-29 Length: 3.15 miles

Location: IN THE CITY OF SIOUX CITY ON WESLEY PARKWAY (US 77)  
OVER TRI-VIEW AVE./BNSF R.R.

Project No: IM-029-7(41)149--13-97

County: WOODBURY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Type of Work: BRIDGE RAIL RETROFIT  
Route: I-29 Length: 3.15 miles  
Location: IN THE CITY OF SIOUX CITY ON WESLEY PKY.(US 77) OVER  
MISSOURI RIVER

Project No: IM-029-7(42)149--13-97  
County: WOODBURY

Type of Work: PCC PAVEMENT - GRADE & REPLACE  
Route: I-29 Length: 0.39 miles  
Location: IN THE CITY OF SIOUX CITY ON WESLEY PKY. FROM  
JUST N. OF 3RD ST. S. TO MISSOURI RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 1711; A 152'-0 X 104'-0 WELDED GIRDER BRIDGE WITH 10'-11.5 SIDEWALK - IM-NHS-029-7(37)149--03-97		
2403-0100010	STRUCT CONC (BRIDGE)	296 CY
2404-7775000	REINFORC STEEL	4,583 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	241,753 LB
SECTION NO. 0002		
DESIGN NO. 1811; A 202'-0 X VARIES PPCB BRIDGE WITH 10'-11.5 SIDEWALK - IM-029-7(38)149--13-97		
2403-0100010	STRUCT CONC (BRIDGE)	688 CY
2404-7775000	REINFORC STEEL	102,953 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	288,778 LB
SECTION NO. 0003		
DESIGN NO. 2211; A 592'-0 X VARIES CONTINUOUS WELDED PLATE GIRDER - IM-029-7(41)149--13-97		
2404-7775005	REINFORC STEEL, EPOXY COATED	30,435 LB
SECTION NO. 0004		
ROADWAY ITEMS IM-029-7(42)149--13-97		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	125,265 CY
2122-5190010	PAVED SHLD, PCC, 10"	851 SY
2301-1034100	STD/S-F PCC PAV'T, CL C CL 3I, 10"	16,465 SY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	46 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	13,390 LB
SECTION NO. 0007		
CONTRACT ITEMS		
2528-5160000	NO EXCUSE ROAD OPENING BONUS, _____	Lump Sum LUMP
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1 CDAY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 101                      Proposal ID: 31-2405-602

Proposed Contract Period: Late Start Date of 05/14/12 with 30 WORK DAYS

Project(s):

Project No: STP-E-2405(602)--8V-31

County: DUBUQUE

Type of Work: PCC SIDEWALK/TRAIL

Route: EPWORTH TRAIL                      Length: 0.53 miles

Location: FROM 600 FT W OF BIERMAN RD E ON JACOBY  
TO 2100 FT N ALONG BIERMAN RD IN THE CI

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	PCC SIDEWALK/TRAIL	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,638 CY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	2,410 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 102                      Proposal ID: 57-1187-756

Proposed Contract Period: Approx Start Date of 06/11/12 with 30 WORK DAYS

Project(s):

Project No: SRTS-U-1187(756)--8U-57

County: LINN

Type of Work: PCC SIDEWALK/TRAIL

Route: E & C AVENUES NE              Length: 0.48 miles

Location: IN THE CITY OF CEDAR RAPIDS, FROM 19TH STREET TO 20TH STREET

Item No.	Item Description	Quantity/Unit
-----		
	SECTION NO. 0001	
	PCC SIDEWALK ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	240 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 103                      Proposal ID: 78-0293-086

Proposed Contract Period: Late Start Date of 04/16/12 with 240 WORK DAYS  
Site 01: SEE PROPOSAL NOTE FOR SITE 01  
Late Start Date of 04/16/12 with 100 WORK DAYS

Proposal Note:

\*\*\*SITE 01\*\*\*  
TO COMPLETE WORK IN STAGE 1A, 1B, 1C.3, 1C.4, 1C.5, 2.2,  
2.3, 2.4, 2.5, AND 2.9 AS SHOWN IN THE STAGING NOTES ON  
SHEET C.10 OF IM-NHS-29-3(86)52--03-78.

Project(s):

Project No: IM-NHS-029-3(86)52--03-78  
County: POTTAWATTAMIE  
Type of Work: PCC PAVEMENT - GRADE AND NEW  
Route: I-29                                      Length: 1.20 miles  
Location: IN THE CITY OF COUNCIL BLUFFS FROM JUST S. OF NEBRASKA  
AVE. TO JUST W. OF 24TH ST.(I-29 SB)

Project No: IM-NHS-029-3(94)52--03-78  
County: POTTAWATTAMIE  
Type of Work: TRAFFIC SIGNS  
Route: I-29                                      Length: 0.00 miles  
Location: IN THE CITY OF COUNCIL BLUFFS FROM W. OF W. MIXMASTER  
TO E. OF INDIAN CREEK & ON I-29 TO N. OF UP R.R.

Project No: IM-NHS-029-3(95)52--03-78  
County: POTTAWATTAMIE  
Type of Work: LIGHTING  
Route: I-29                                      Length: 0.00 miles  
Location: IN THE CITY OF COUNCIL BLUFFS FROM E. OF MO. RIVER TO E.  
OF INDIAN CR. & I-29 SB FR 24TH ST TO E. OF INDIAN CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - IM-NHS-029-3(86)52--03-78		
2102-2625000	EMBANKMENT-IN-PLACE	67,643 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	887,705 CY
2122-5190012	PAVED SHLD, PCC, 12"	22,584 SY
2301-1004120	STD/S-F PCC PAV'T, QM-C CL 3I, 12"	48,232 SY
SECTION NO. 0006		
TRAFFIC SIGN ITEMS - IM-NHS-029-3(94)52--03-78		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	59 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	7,032 LB
SECTION NO. 0007		
LIGHTING ITEMS - IM-NHS-029-3(95)52--03-78		
2404-7775000	REINFORC STEEL	29,686 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 151                      Proposal ID: 23-0672-058

Proposed Contract Period: Late Start Date of 06/25/12 with 80 WORK DAYS

Project(s):

Project No: STP-067-2(58)--2C-23

County: CLINTON

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: U.S. 67                      Length: 7.39 miles

Location: FROM CO. RD. E-50 N. TO IA. 64

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	1,558 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	11,383 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	11,521 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	120 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	3 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 152                      Proposal ID: 49-C049-054

Proposed Contract Period: Late Start Date of 08/27/12 with 35 WORK DAYS

Project(s):

Project No: FM-C049(54)--55-49

County: JACKSON

Type of Work: HMA RESURFACING WITH MILLING

Route: CAVES RD & 150TH ST. Length: 4.92 miles

Location: FROM 98TH STREET TO 200' WEST  
OF 50TH AVENUE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	610 TON
2303-0013500	HMA (100K ESAL) B-I-S, 1/2", NO FRIC	10,639 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
 (for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 50-1171-021

Proposed Contract Period: Late Start Date of 06/11/12 with 90 WORK DAYS  
 Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.  
                         No Start Date Specified with 10 WORK DAYS  
 Site 02: SEE SITE NUMBER 02 DESCRIPTION BELOW.  
                         No Start Date Specified with 10 WORK DAYS

Proposal Note:

\*\*\* SITE NUMBER 01 \*\*\*

TO COMPLETE ALL WORK REQUIRING THE TEMPORARY TRAFFIC SIGNALS  
 AT STATION 30+00.

\*\*\* SITE NUMBER 02 \*\*\*

TO COMPLETE ALL WORK REQUIRING THE TEMPORARY TRAFFIC SIGNALS  
 AT STATION 474+85.

Project(s):

Project No: STP-117-1(21)--2C-50  
 County: JASPER  
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING  
 Route: IOWA 117 Length: 11.09 miles  
 Location: FROM JCT. F48 W. TO S. WALNUT ST. AND FROM N. APPROACH OF  
 S. SKUNK RIVER BRIDGE N. TO NEAR JCT. US65/IA330

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5,268 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	4,061 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	17,192 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	16,926 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	49 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	10 EACH
SECTION NO. 0002		
DESIGN NO. 0410; A 215'-5 X 28'-0 PPCB RAIL RETROFIT		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	4 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	688 LB
SECTION NO. 0003		
DESIGN NO. 0510; A 120'-0 X 28'-0 CCS RAIL RETROFIT		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	3 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	652 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 154                      Proposal ID: 57-C057-108

Proposed Contract Period: Late Start Date of 05/14/12 with 85 WORK DAYS  
Site 01: TO COMPLETE CULVERT AND ROADWAY WORK ON LAFAYETTE ROAD  
Late Start Date of 05/14/12 with 35 WORK DAYS

Proposal Note:

\*\*\*SITE 01\*\*\*

TO COMPLETE THE CULVERT AND ALL ROADWAY WORK ASSOCIATED WITH  
LAFAYETTE ROAD.

Project(s):

Project No: STP-ES-E-C057(108)--8T-57

County: LINN

Type of Work: HMA SIDEWALK/TRAIL

Route: C. V. NATURE TRAIL    Length: 6.80 miles

Location: CO HOME RD TO LAFAYETTE & FISHEL RD TO  
SCHULTZ RD

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	13,598 CY
2511-0301600	RECREATIONAL TRAIL, HMA, 6"	611 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	857 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 155                      Proposal ID: 59-0142-033

Proposed Contract Period: Late Start Date of 04/16/12 with 120 WORK DAYS

Project(s):

Project No: STP-014-2(33)--2C-59  
 County: LUCAS  
 Type of Work: HMA RESURFACING WITH MILLING  
 Route: IOWA 14                      Length: 4.54 miles  
 Location: CHARITON N. TO WILLIAMSON

Project No: STP-014-3(41)--2C-63  
 County: MARION  
 Type of Work: HMA RESURFACING WITH MILLING  
 Route: IOWA 14                      Length: 7.64 miles  
 Location: CO. RD. G-76 N. TO NEAR IA. 5/92 IN KNOXVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
LUCAS CO STP-14-2(33)--2C-59		
2102-2625000	EMBANKMENT-IN-PLACE	380 CY
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	9,039 TON
SECTION NO. 0004		
ROADWAY ITEMS		
MARION CO STP-14-3(41)--2C-63		
2102-2625000	EMBANKMENT-IN-PLACE	840 CY
2303-0041750	HMA (3M ESAL) BASE, 3/4"	8,113 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	22,840 TON



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 156                      Proposal ID: 67-C067-070

Proposed Contract Period: Late Start Date of 08/20/12 with 35 WORK DAYS

Project(s):

Project No: FM-C067(70)--55-67

County: MONONA

Type of Work: HMA RESURFACING WITH MILLING

Route: K45                                      Length: 6.60 miles

Location: ONAWA TO SOUTH LINE OF BLENCOE  
FROM 235TH ST. TO 300TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0023750	HMA (300K ESAL) I-S, 3/4", NO FRIC	20,850 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 74-0183-083

Proposed Contract Period: Late Start Date of 09/10/12 with 20 WORK DAYS

Project(s):

Project No: STPN-004-5(35)--2J-74  
 County: PALO ALTO  
 Type of Work: HMA RESURFACING WITH MILLING  
 Route: IOWA 4 Length: 0.57 miles  
 Location: IN THE CITY OF EMMETSBURG FROM E. JCT. US 18  
 TO S. OF 12TH ST.

Project No: NHSN-018-3(83)--2R-74  
 County: PALO ALTO  
 Type of Work: HMA RESURFACING WITH MILLING  
 Route: U.S. 18 Length: 0.60 miles  
 Location: IN THE CITY OF EMMETSBURG FROM LAKE ST. TO HURON ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
STPN-004-5(35)--2J-74		
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	941 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	896 TON
SECTION NO. 0002		
ROADWAY ITEMS		
NHSN-018-3(83)--2R-74		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	203 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	483 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	460 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	322 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	19 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 158                      Proposal ID: 82-0671-116

Proposed Contract Period: Late Start Date of 09/10/12 with 25 WORK DAYS

Project(s):

Project No: NHSN-067-1(116)--2R-82

County: SCOTT

Type of Work: HMA RESURFACING

Route: U.S. 67                      Length: 0.40 miles

Location: IN BETTENDORF FROM WCL N. TO 6TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	792 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	918 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	104 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	6 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 159                      Proposal ID: 91-C091-083

Proposed Contract Period: Late Start Date of 10/08/12 with 15 WORK DAYS

Project(s):

Project No: HRRR-C091(83)--5R-91

County: WARREN

Type of Work: HMA PAVED SHOULDER - NEW

Route: R63                                      Length: 4.25 miles

Location: HWY 92 TO HWY G-24

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 96-0525-036

Proposed Contract Period: Late Start Date of 04/02/12 with 130 WORK DAYS

Project(s):

Project No: MP-052-2(704)134--76-96  
 County: WINNESHIEK  
 Type of Work: HMA RESURFACING WITH MILLING  
 Route: U.S. 52 Length: 1.32 miles  
 Location: IN THE CITY OF OSSIAN AT VARIOUS LOCATIONS.

Project No: NHSX-052-5(36)--3H-96  
 County: WINNESHIEK  
 Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING  
 Route: U.S. 52 Length: 9.52 miles  
 Location: FROM JUST N. OF NORTH ST. IN CALMAR N. TO JUST S. OF  
 IA. 9 IN DECORAH

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		MP-52-2(704)134--76-96
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	1,330 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,330 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	42 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	7 EACH
SECTION NO. 0003		
ROADWAY ITEMS		
		NHSX-052-5(36)--3H-96
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	3,320 CY
2303-0041750	HMA (3M ESAL) BASE, 3/4"	11,520 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	32,935 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	16,540 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	160 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 22-0189-101

Proposed Contract Period: Late Start Date of 09/10/12 with 15 WORK DAYS

Project(s):

Project No: HSIPX-018-9(101)--3L-22

County: CLAYTON

Type of Work: MILLED RUMBLE STRIPS

Route: U.S. 18 Length: 0.00 miles

Location: FROM ECL OF POSTVILLE E. TO NEAR MARQUETTE

Project No: HSIPX-009-8(39)--3L-96

County: WINNESHIEK

Type of Work: MILLED RUMBLE STRIPS

Route: IOWA 9 Length: 0.00 miles

Location: FROM RIDGEWAY E. TO WAUKON

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 24-0393-701

Proposed Contract Period: Late Start Date of 04/02/12 with 70 WORK DAYS

Project(s):

Project No: MP-030-3(708)81--76-14  
County: CARROLL

Type of Work: HMA CRACK FILLING  
Route: U.S. 30 Length: 1.25 miles  
Location: IN THE CITY OF CARROLL FROM W. 8TH STREET TO EAST OF GRANT ROAD.

Project No: MP-141-3(707)87--76-14  
County: CARROLL

Type of Work: HMA CRACK FILLING  
Route: IOWA 141 Length: 2.40 miles  
Location: FROM THE E. JCT. OF U.S. 71 TO E60.

Project No: MP-030-3(704)70--76-24  
County: CRAWFORD

Type of Work: HMA CRACK FILLING  
Route: U.S. 30 Length: 11.31 miles  
Location: FROM PARK ST. IN WESTSIDE TO JCT. U.S. 71 IN CARROLL.

Project No: MP-039-3(701)0--76-24  
County: CRAWFORD

Type of Work: HMA CRACK FILLING  
Route: IOWA 39 Length: 24.40 miles  
Location: FROM JCT. OF U.S 59 IN DENISON TO JCT. OF IA 175 IN ODEBOLT.

Project No: MP-071-3(707)142--76-81  
County: SAC

Type of Work: HMA CRACK FILLING  
Route: U.S. 71 Length: 7.60 miles  
Location: FROM THE W. JCT. OF IOWA 175 TO THE S. JCT. OF U.S. 20.

Project No: MP-196-3(700)0--76-81  
County: SAC

Type of Work: HMA CRACK FILLING  
Route: IOWA 196 Length: 7.76 miles  
Location: FROM JCT. OF U.S. 71, NORTH TO JCT. U.S. 20.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 203                      Proposal ID: 97-0313-706

Proposed Contract Period: Late Start Date of 04/02/12 with 45 WORK DAYS

Project(s):

Project No: MP-020-3(713)13--76-97

County: WOODBURY

Type of Work: HMA CRACK FILLING

Route: U.S. 20                      Length: 8.50 miles

Location: FROM LAWTON TO MOVILLE (EB LANES) AND MOVILLE TO END OF  
FOUR-LANE (WB LANES).

Project No: MP-031-3(706)20--76-97

County: WOODBURY

Type of Work: HMA CRACK FILLING

Route: IOWA 31                      Length: 19.70 miles

Location: FROM SOUTH OF CORRECTIONVILLE TO JCT. OF U.S. 59.

Project No: MP-140-3(702)0--76-97

County: WOODBURY

Type of Work: HMA CRACK FILLING

Route: IOWA 140                      Length: 9.59 miles

Location: FROM JCT. OF U.S. 20 IN MOVILLE TO 1ST STREET AND MAIN  
IN KINGSLEY.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 301                      Proposal ID: 36-0291-098

Proposed Contract Period: Late Start Date of 04/02/12 with 20 WORK DAYS

Project(s):

Project No: ER-029-1(98)0--06-36

County: FREMONT

Type of Work: DITCH IMPROVEMENT

Route: I-29                                      Length: 10.00 miles

Location: FROM MISSOURI STATE LINE NORTH TO IA. 2  
INTERCHANGE (VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
	SECTION NO. 0001	
	ROADWAY ITEMS - SEGMENT 1	
2102-2625000	EMBANKMENT-IN-PLACE	2,190 CY
	SECTION NO. 0002	
	ROADWAY ITEMS - SEGMENT 3	
2102-2625000	EMBANKMENT-IN-PLACE	6,754 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 36-0291-099

Proposed Contract Period: Late Start Date of 04/02/12 with 30 WORK DAYS

Project(s):

Project No: ER-029-1(99)10--06-36

County: FREMONT

Type of Work: DITCH IMPROVEMENT

Route: I-29 Length: 0.00 miles

Location: FROM IA. 2 INTERCHANGE N. TO BARTLET INTERCHANGE  
(VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
	SECTION NO. 0001	
	ROADWAY ITEMS - SEGMENT 5	
	I-29 MP 10.1 TO MP 15.5	
2102-2625000	EMBANKMENT-IN-PLACE	6,910 CY
	SECTION NO. 0002	
	ROADWAY ITEMS - SEGMENT 6	
	I-29 MP 15.5 TO MP 20.0	
2102-2625000	EMBANKMENT-IN-PLACE	1,777 CY
	SECTION NO. 0003	
	ROADWAY ITEMS - SEGMENT 7	
	I-29 MP 20.0 TO MP 25.0	
2102-2625000	EMBANKMENT-IN-PLACE	1,500 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 303                      Proposal ID: 36-0291-100

Proposed Contract Period: Late Start Date of 04/16/12 with 15 WORK DAYS

Project(s):

Project No: ER-029-1(100)24--06-36

County: FREMONT

Type of Work: GRADING

Route: I-29

Length: 0.00 miles

Location: FROM N. OF BARTLET INTERCHANGE N. TO US 275 INTERCHANGE &  
US 34 FROM MISSOURI RIVER TO I-29(VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	2,230 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 83-0442-043

Proposed Contract Period: Late Start Date of 04/16/12 with 40 WORK DAYS

Project(s):

Project No: ER-044-2(43)--28-83

County: SHELBY

Type of Work: SLIDE REPAIR

Route: IOWA 44 Length: 0.00 miles

Location: 1.1 MILES E. OF PORTSMOUTH (N. SIDE)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0002		
DESIGN NO. 111; A 10'-0 X 10'-0 RCB CULVERT EXTENSION		
2403-0100020	STRUCT CONC (RCB CULV)	81 CY
2404-7775000	REINFORC STEEL	11,512 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 97-0296-240

Proposed Contract Period: Late Start Date of 06/25/12 with 75 WORK DAYS

Project(s):

Project No: IM-NHS-029-6(240)147--03-97

County: WOODBURY

Type of Work: GRADING (MISCELLANEOUS)

Route: I-29 Length: 0.00 miles

Location: IN THE CITY OF SIOUX CITY FROM N. OF BACON ST. BRIDGE N.  
TO S. OF FLOYD RIVER BRIDGE(SBL) MSE RET. WALL

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,834 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 501                      Proposal ID: 77-0654-136

Proposed Contract Period: Late Start Date of 04/16/12 with 30 WORK DAYS

Project(s):

Project No: NHSN-065-4(136)--2R-77

County: POLK

Type of Work: LANDSCAPING

Route: U.S. 65                      Length: 0.00 miles

Location: FROM SE 64TH ST. N. TO US 6

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 502                      Proposal ID: 84-0602-083

Proposed Contract Period: Late Start Date of 03/12/12 with 50 WORK DAYS

Project(s):

Project No: NHSN-060-2(83)--2R-84

County: SIOUX

Type of Work: LANDSCAPING

Route: IOWA 60                      Length: 0.00 miles

Location: ALTON BY-PASS FROM 470TH ST. INTERCHANGE TO 450TH ST.  
INTERCHANGE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 503                      Proposal ID: 86-0306-086

Proposed Contract Period: Late Start Date of 04/16/12 with 75 WORK DAYS

Project(s):

Project No: NHSN-030-6(86)--2R-86

County: TAMA

Type of Work: EROSION CONTROL

Route: U.S. 30                      Length: 13.58 kilometers

Location: TAMA BYPASS FROM 0.7 KM E. OF MESQUAKI  
CASINO E. TO 2.45 KM E. OF "L" AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102--100100	CL 10 EXCAVATION RDWY+BORROW	400 M3



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 601                      Proposal ID: 00-0006-501

Proposed Contract Period: Late Start Date of 05/07/12 with 40 WORK DAYS

Project(s):

Project No: MB-000-6(501)0--77-00

County: STATEWIDE

Type of Work: BRIDGE CLEANING

Route: MULTIPLE ROUTES                      Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 6

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 602                      Proposal ID: 33-0032-500

Proposed Contract Period: Late Start Date of 05/07/12 with 25 WORK DAYS

Project(s):

Project No: MB-003-2(500)243--77-33

County: FAYETTE

Type of Work: BRIDGE PAINTING

Route: IOWA 3                                      Length: 0.00 miles

Location: OVER LITTLE WAPSI RIVER 0.2 MILE W. OF V-68

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: December 20, 2011 10:00 A.M.

Proposed Bid Order: 603                      Proposal ID: 57-3806-539

Proposed Contract Period: Late Start Date of 05/07/12 with 60 WORK DAYS

Project(s):

Project No: MBIN-380-6(539)31--0M-57

County: LINN

Type of Work: BRIDGE PAINTING

Route: I-380                                      Length: 0.00 miles

Location: OVER 1ST ST., 2ND AVE. SW, 3RD AVE. SW & 3RD ST. NW IN CEDAR  
RAPIDS, UNDER BOAR ROAD & URBANA ROAD NEAR CEDAR POINT.

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

