

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: December 20, 2011  
Date of Addendum: December 2, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
023	97-0297-042	Bridge Replacement - Steel Girder	Woodbury	IM-NHS-029-7(37)149--03-97 IM-029-7(38)149--13-97 IM-029-7(41)149--13-97 IM-029-7(42)149--13-97	20dec023.a01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Attached is a SCHEDULE OF PRICES for the following items:

Line No. 0581 2595-0000105 BNSFRR INSURANCE PROVISIONS  
Line No. 1941 2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.  
Line No. 1942 2513-0001040 CONCRETE BARRIER, BA-104

Bid these items as instructed and submit the bid for these items with the Bid Proposal.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Line No. 1370 2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN., from  
546.700 SY to **480.100 SY**.  
Change Line No. 1380 2511-7528101 DETECTABLE WARNINGS, from 50.000 SF to  
**10.000 SF**.  
Change Line No. 1390 2513-0001030 CONCRETE BARRIER, BA-103, from 1685.900  
LF to **427.500 LF**.

If the quantities are not changed on the proposal form, the bid amounts will be extended using the unit price times the correct quantities as shown here.

Make the following changes to the plans for Project No. IM-029-7(42)149--13-97:

SHEET C.2:

Add Reference Note for the item 2513-0001040, CONCRETE BARRIER, BA-104:

Refer to Tab 108-18B on C Sheets.

SHEET C.8

Add the following to Standard Note 203-2:

IM-29-7(53)149--13-97 - Traffic Signs

SHEET C.15:

Replace: Tab. 108-18B CONCRETE BARRIER AT SIDE LOCATIONS,  
Dated 10-18-11

With attached: Tab. 108-18B CONCRETE BARRIER AT SIDE LOCATIONS,  
Dated 10-18-11

SHEET C.28:

Replace: Tab. 113-1 SIDEWALKS, Dated 10-18-11

With attached: Tab. 113-1 SIDEWALKS, Dated 10-18-11

\*\*\*\*\*

Proposal ID No.: 97-0297-042  
 Primary Work Type: BRIDGE REPLACEMENT - STEEL GIRDER  
 Primary County: WOODBURY  
 Bid Order No.: 023  
 Letting Date: DECEMBER 20, 2011 10:00 A.M.

ITEMS LISTED ON THIS PAGE ARE ADDED BY ADDENDUM 20dec023.a01

UNIT BIDS MUST BE TYPED OR SHOWN IN INK OR THE BID WILL BE REJECTED.

Line No	Item Number	Item Description	Quantity and Unit	Unit Price Dollars   Cts	Bid Amount Dollars   Cts
Section 0002 (continued)					
DESIGN NO. 1811; A 202'-0 X VARIES PPCB BRIDGE WITH 10'-11.5 SIDEWALK - IM-029-7(38)149--13-97					
0581	2595-0000105	BNSFRR INSURANCE PROVISIONS	LUMP	LUMP	.
Section 0004 (continued)					
ROADWAY ITEMS					
IM-029-7(42)149--13-97					
1941	2511-7526006	SIDEWALK, P.C. CONCRETE, 6 IN.	4.600 SY	.	.
1942	2513-0001040	CONCRETE BARRIER, BA-104	1,282.600 SY	.	.
Total Bid					.

### CONCRETE BARRIER AT SIDE LOCATIONS

Refer to BA-102, BA-103, BA-104, BA-105, BA-106, BA-107, and BA-150.  
Lane(s) to which the installation is adjacent.

No.	Location		Side Barrier					Remarks		
	Direction of Traffic	Station to Station	Side	L2 Offset	Barrier Type (BA-102, BA-103, or BA-104)	Length of Barrier	BA-105 Transition Section		BA-107 End Section	Reinforced Paved Shoulder (Required?)
	Wesley									
	SB	407+66.1	408+22.1	RT	12.0	BA-103	56.0			BA-108 MOD (U.4), North End
	SB	410+08.0	411+28.1	LT	3.0	BA-103	121.0			BA-108 MOD (U.5), Both Ends
	SB	419+26.2	419+96.6	RT	1.4-13.9	BA-103	61.0	1		BA-105 On S End, Change In Taper
	SB	419+96.6	420+43.0	RT	13.9-9.2	BA-103	46.7			BA-108 MOD (U.7), North End
	SB	420+00.0	421+42.7	LT	3.0	BA-103	142.8			BA-108 BOD (U.8), Both Ends
	SB Frnt Rd 2									
	EB/SB	3516+50.5	3519+15.0	LT	4.0	BA-104	267.2		165.7	TBR Connection, West End
	NB Frnt Rd 2									
	WB/NB	3516+39.8	3516+72.7	LT	8.1-4	BA-104	33.0		32.5	
	WB/NB	3516+72.7	3519+73.7	LT	4.0	BA-104	299.4		177.7	TBR Connection, West End
	WB/NB	3516+42.0	3516+85.9	RT	20.9-4	BA-104	48.3		58.4	
	WB/NB	3516+85.9	3519+73.7	RT	4.0	BA-104	289.4		179.4	TBR Connection, West End
	Wesley Ramp B									
	WB/NB	2514+00.0	2515+10.9	LT	4.0	BA-104	109.8		70.7	TBR Conn. East, BA-107 MOD (U.3) West
	WB/NB	2514+00.0	2514+75.2	RT	4.0	BA-104	75.9		47.1	TBR Connection, East End
	WB/NB	2514+75.2	2515+03.5	RT	4-14.7	BA-104	31.0	1	39.8	BA-107 MOD (U.3), West End
	Wesley Ramp C									
	EB/SB	3514+01.8	3514+40.4	LT	6-10.3	BA-104	38.8		56.8	TBR Conn. East, BA-108 MOD (U.6) West
	EB/SB	3514+01.8	3514+66.9	RT	6.0	BA-104	65.6		55.3	TBR Connection, East End
	EB/SB	3514+66.9	3514+90.9	RT	6-7.6	BA-104	24.2	1	60	BA-107 MOD (U.3), West End
			Totals				427.5	1	3	943.3
							1282.6			

**SIDEWALKS**

See MI-220 and L Sheets

Road Identification	Station to Station		Side	4" PCC Sidewalk	6" PCC Sidewalk	Detectable Warnings	Remarks
				SY	SY	SF	
Wesley	407+66.9	413+40.0	RT	350.9		10	
Wesley	413+40.0	413+50.8	RT		4.6		
Wesley	419+67.9	422+00.5	RT	129.2		0	
TOTAL				480.1	4.6	10	