

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: December 20, 2011
Date of Addendum: December 16, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
007	37-0042-038	BRIDGE NEW - PPCB	GREENE	HDP-004-2(38)--71-37	20DEC007.A03

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the PROPOSAL SCHEDULE OF PRICES:

Change Line No. 0210 2408-7800000 STRUCTURAL STEEL from 75,074.000 LB to 84,870.000 LB.

For Line No. 0530 change the Item Number and Unit from 2402-0425031 GRANULAR BACKFILL, TON to 2402-0425030 GRANULAR BACKFILL, CY. The Item Description and Item Quantity remain the same.

Change Line No. 0540 2404-7775005 REINFORCING STEEL, EPOXY COATED from 38,049.000 LB to 14,636.000 LB.

If the above changes are not made on the proposal form, they will be made as shown here.

Make the following change to the plan:

Sheet Number 55:

All Sole Plates: PL 7 x 1 x 2'-4 1/2, ASTM A514 GRADE B

Sheet U.17, Add the following note:

Disregard barrier rail reinforcing spacing shown on sheet U.17 and follow reinforcing spacing shown on sheet U.18. All steel shown in barrier rail is to be considered incidental to the barrier rail.

Sheet U.18, Delete the following note:

All barrier rail reinforcing steel is to be included with the superstructure reinforcing steel.

Add the following note:

Total reinforcing steel included in barrier rail is 16,391 lb.

Sheet U.19, Delete the following:

All barrier rail reinforcing steel is to be included with the superstructure reinforcing steel.

Add the following note:

Total reinforcing steel included in barrier rail is 23,413 lb.