

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: April 17, 2012
Date of Addendum: April 5, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
209	58-0929-142	Milled Rumble Strips	Louisa	HSIPX-092-9(142)--3L-58	17apr209.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the Plan Sheet C.1

Tab. 232-3A EROSION CONTROL (RURAL SEEDING) :

Replace 232-3A Dated 04-17-12
with attached 232-A MODIFIED

EROSION CONTROL (RURAL SEEDING)

Following the completion of work in a disturbed area, place seed, fertilizer, and mulch on the portion of the area lying 8 feet adjacent to shoulder as follows:

SEEDING:

3 lbs. of Fescue or Fawn per 1000 sq. ft.

FERTILIZER:

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

MULCH:

70 lbs. of dry cereal straw per 1000 sq. ft. Consolidate all mulch into the soil using a mulch stabilizer.

Preparing the seedbed and furnishing and applying seed, fertilizer, and mulch is incidental to mobilization and will not be paid for separately.