

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: April 17, 2012  
Date of Addendum: April 13, 2012

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
301	18-0032-059	SLIDE REPAIR	CHEROKEE	STPN-003-2(59)--2J-18	17APR301.A01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to plan sheet C.2:

Replace Standard Note 232-3A with attached Standard Note 232-3A.

## **EROSION CONTROL (RURAL SEEDING)**

Following the completion of work in a disturbed area, place seed, fertilizer, and mulch on the portion of the area lying 8 feet adjacent to shoulder as follows:

**SEEDING:**

3 lbs. of Fescue or Fawn per 1000 sq. ft.

**FERTILIZER:**

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

**MULCH:**

70 lbs. of dry cereal straw per 1000 sq. ft. Consolidate all mulch into the soil using a mulch stabilizer.

Preparing the seedbed and furnishing and applying seed, fertilizer, and mulch is incidental to mobilization and will not be paid for separately.