

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: April 17, 2012
Date of Addendum: April 13, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
303	27-0691-040	SLIDE REPAIR	DECATUR	ER-069-1(40)--28-27	17APR303.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to plan sheet C.2:

Replace Standard Note 232-3A with attached Standard Note 232-3A.

EROSION CONTROL (RURAL SEEDING)

Following the completion of work in a disturbed area, place seed, fertilizer, and mulch on the portion of the area lying 8 feet adjacent to shoulder as follows:

SEEDING:

3 lbs. of Fescue or Fawn per 1000 sq. ft.

FERTILIZER:

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

MULCH:

70 lbs. of dry cereal straw per 1000 sq. ft. Consolidate all mulch into the soil using a mulch stabilizer.

Preparing the seedbed and furnishing and applying seed, fertilizer, and mulch is incidental to mobilization and will not be paid for separately.