

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: May 15, 2012  
Date of Addendum: May 11, 2012

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
152	12-0147-036	HMA RESURFACING WITH MILLING	BUTLER	HDP-014-7(036)--3C-12	15MAY152.A04

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the PROPOSAL SCHEDULE OF PRICES:

Change Line No. 0950 2599-9999005 ('EACH' ITEM) LIGHTING UNIT from 14.000  
EACH to 16.000 EACH.

If the quantity is not changed on the proposal form, the bid amount will be extended using the unit price times the correct quantity as shown here.

Make the following change to SP-090211:

For 090211.02 MATERIALS, A ,2, b:

Replace:

Provide nursery grown plants grown in the same climatic zone as the project.

With:

Plant material quality shall comply with Article 4170.02, Item 5, a through d, "Quality of Plant Material".

Make the following change to plan sheet O.22, Native Plant (Plug) Notes:

Replace:

5. ALL PLANTS SHALL BE NURSERY GROWN IN A SIMILAR CLIMATIC ZONE AS THIS PROJECT; COLLECTION OF PLANTS FROM THE WILD IS NOT ACCEPTABLE. PLANTS SHALL BE THOSE LISTED IN THE PLANT SCHEDULE; DERIVATIVES/HYBRIDS OF THE PLANTS WILL NOT BE ALLOWED.

With:

5. All Plants shall be nursery grown in a similar climatic zone as this project. Whenever possible, the plant material shall be furnished from the same plant hardiness zone as where the project site is located or in a plant hardiness zone north of the project site (colder zone), and shall originate from within a 150 mile radius of the project site. Collection of plants from the wild is not acceptable. Plants shall be those listed in the plant schedule; derivatives/hybrids of the plants will not be allowed.

Make the following change to plan sheet P.9:

Tabulation 108-1, Add the following Lighting Installations:

A101, Sta. 8+25.98, 17.5' LT

A102, Sta. 7+86.87, 26.7' LT