

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: June 19, 2012
Date of Addendum: June 7, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
360	91-0352-409	Guardrail	Warren	IHSIPX-035-2(409)42--08-91	19jun360.a02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Add the following note to the PROPOSAL NOTES, page 2:

*****HIGH TENSION CABLE GUARDRAIL INSTALLATIONS*****
FOR EACH HIGH TENSION CABLE GUARDRAIL INSTALLATION, ONCE THE PLACEMENT OF POSTS INTO SOCKETS HAS BEGUN, THE CABLES MUST BE TENSIONED AND FULLY FUNCTIONAL WITHIN 15 WORKING DAYS. INSTALLATION MEANS THE ENTIRE LENGTH OF HIGH TENSION CABLE GUARDRAIL BETWEEN TWO END ANCHORS.

Add to: PLAN SHEET C.1, ESTIMATE REFERENCE INFORMATION,
TAB 100-4A-10-29-02:

ITEM NO.16 2505-6000111 HIGH TENSION CABLE GUARDRAIL

WHERE HIGH TENSION CABLE GUARDRAIL IS INSTALLED ON A CURVE, USE MANUFACTURER'S RECOMMENDED REDUCED POST SPACING. HOWEVER, REDUCED POST SPACING WITHIN THE CURVE SHALL NOT EXCEED 10 FEET. CURVES WHERE REDUCED POST SPACING APPLIES (APPROX.): STA 600+00, STA 660+00, STA 780+00, STA 860+00, STA 950+00, STA 1000+00.