

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: June 19, 2012
Date of Addendum: June 13, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
152	17-4822-630	HMA Resurfacing with Milling	Cerro Gordo	STP-U-4822(630)--70-17	19jun152.a02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the plan:

ESTIMATE REFERENCE INFORMATION:

SHEET C.2

ITEM NO. 12 2435-0130148 MANHOLE, SANITARY SEWER, SW-301, 48 IN. Replace TAB WHKS-1, SANITARY SEWER MANHOLES on SHEET C.3 with (attached) Tabulation. WHKS-1

SHEET C.2

ITEM NO. 30 2512-1725256 CURB AND CUTTER, P.C. CONCRETE, 2.5 FT.: Add the following note to Tabulation 100-4A, Estimates Reference Information. PAVEMENT DEPTH FOR CURB AND GUTTER TO BE 7 INCHES.

SANITARY SEWER MANHOLES

No.	Location	Type	Top Elev.		Remarks
			Ø	Bottom Elev.	
9-3	46+08.1	SW-301	1108.1	1098.78	Install 8' of 8" San. Sewer to connect main to MH
9-4	48+70.9	SW-301	1106.4	1100.7	Install 8' of 8" San. Sewer to connect main to MH
-27A	50+06.0	SW-301	1104.9	1099.5	Install 8' of 8" San. Sewer to connect main to MH
3-27	53+33.5	SW-301	1105.52	1098.17	Install 8' of 8" San. Sewer to connect main to MH
3-26	56+83.6	SW-301	1104.2	1095.9	Install 8' of 8" San. Sewer to connect main to MH
3-25	60+33.6	SW-301	1100.5	1087.25	Install 16' of 12" San. Sewer to connect main to MH
3-29	66+72.2	SW-301	1095.65	1089.1	Install 8' of 8" San. Sewer to connect main to MH
4-51	91+71.2	SW-301	1082.92	1075	Install 8' of 8" San. Sewer to connect main to MH
4-52	95+72.0	SW-301	1080.99	1075.36	Install 8' of 8" San. Sewer to connect main to MH
4-53	98+65.8	SW-301	1081.26	1076.13	Install 8' of 8" San. Sewer to connect main to MH