

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: June 19, 2012
Date of Addendum: June 15, 2012

| B.O. | Proposal ID | Proposal Work Type | County | Project Number | Addendum |
|-------------|--------------------|---------------------------|---------------|-----------------------|-----------------|
| 105 | 27-C027-032 | PCC Pavement - Replace | Decatur | STP-S-C027(32)--5E-27 | 19jun105.a01 |

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Add the following note to the plan:

GENERAL NOTES:

SHEET B.01

The existing pavement is a nominally 6" Type B non-reinforced PCC pavement with 1/2" x 3" centerline dowels at 48" centers. There is also a 3" HMA overlay on top of the existing PCC pavement.