

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 31-0522-090

Proposed Contract Period: Late Start Date of 04/01/13 with 240 WORK DAYS

Project(s):

Project No: NHSX-052-2(83)--3H-31  
 County: DUBUQUE  
 Type of Work: PCC PAVEMENT - GRADE & REPLACE  
 Route: U.S. 52 Length: 1.37 miles  
 Location: IN THE CITY OF DUBUQUE FROM US 61/151 N. TO  
 GRANDVIEW AVE.(CATFISH CREEK)

Project No: BRF-052-2(90)--38-31  
 County: DUBUQUE  
 Type of Work: BRIDGE REPLACEMENT - PPCB  
 Route: U.S. 52 Length: 0.00 miles  
 Location: IN THE CITY OF DUBUQUE OVER  
 CATFISH CREEK/CC R.R.

Project No: NHSN-052-2(91)--2R-31  
 County: DUBUQUE  
 Type of Work: LIGHTING  
 Route: U.S. 52 Length: 0.00 miles  
 Location: IN THE CITY OF DUBUQUE AT US 61/151/  
 GRANDVIEW AVE. INTERSECTION

Project No: NHSN-052-2(112)--2R-31  
 County: DUBUQUE  
 Type of Work: TRAFFIC SIGNS  
 Route: U.S. 52 Length: 1.23 miles  
 Location: IN THE CITY OF DUBUQUE JUST S. OF GRANDVIEW AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
DIVISION 1		
		NHSX-052-2(83)--3H-31
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	88,679 CY
2122-5190010	PAVED SHLD, PCC, 10"	18,945 SY
2301-1003100	STD/S-F PCC PAV'T, QM-C CL 3, 10"	48,329 SY
SECTION NO. 0002		
DESIGN NO. 211; FOR A 623'-8 X VARIOUS HEIGHT SOLDIER PILE		
	RETAINING WALL	NHSX-052-2(83)--3H-31
2403-0100000	STRUCT CONC (MISCELLANEOUS)	498 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	32,086 LB
SECTION NO. 0003		
DESIGN NO. 311; FOR A 658'-10 X VARIOUS HEIGHT REINFORCED		
	CONCRETE RETAINING WALL	NHSX-052-2(83)--3H-31
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1,220 CY
2404-7775000	REINFORC STEEL	48,666 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	81,320 LB
SECTION NO. 0005		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

DESIGN NO. 111; FOR A 518'-0 X 40'-0 DUAL PRETENSIONED  
PRESTRESSED CONCRETE BEAM BRIDGE      BRF-052-2(90)--38-31

2403-0100010	STRUCT CONC (BRIDGE)	3,607 CY
2404-7775000	REINFORC STEEL	191,057 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	524,637 LB

SECTION NO. 0007

ROADWAY ITEMS - SIGNING  
NHSN-052-2(112)--2R-31

2403-0100000	STRUCT CONC (MISCELLANEOUS)	11 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,120 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 42-0571-021

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Project(s):

Project No: BRF-057-1(15)--38-42  
 County: HARDIN  
 Type of Work: PCC PAVEMENT - GRADE & REPLACE  
 Route: IOWA 57 Length: 0.00 miles  
 Location: IN THE CITY OF ACKLEY OVER CC R.R.

Project No: BRF-057-1(21)--38-42  
 County: HARDIN  
 Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER  
 Route: IOWA 57 Length: 0.00 miles  
 Location: IN THE CITY OF ACKLEY OVER CC R.R.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - BRF-057-1(15)--38-42		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	12,459 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	1,929 SY
SECTION NO. 0004		
DESIGN NO. 0112; A 366'-0 X 30'-0 CWPG BRIDGE & REINFORCED CONCRETE RETAINING WALLS - BRF-057-1(21)--38-42		
2403-0100010	STRUCT CONC (BRIDGE)	1,353 CY
2404-7775000	REINFORC STEEL	72,504 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	190,077 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 58-0929-124

Proposed Contract Period: Late Start Date of 08/26/13 with 35 WORK DAYS

Project(s):

Project No: BRFN-092-9(124)--39-58

County: LOUISA

Type of Work: BRIDGE DECK OVERLAY

Route: IOWA 92 Length: 0.00 miles

Location: OVER D.D. #25 5.5 MILES WEST OF SOUTH JCT. US 61

Item No.	Item Description	Quantity/Unit
	SECTION NO. 0001	
	DESIGN NO. 0113; REPAIRS TO A 70'-0 X 44'-0 CONTINUOUS CONCRETE SLAB BRIDGE	
2413-0698074	DECK REPAIR, CL A	36 SY
	SECTION NO. 0002	
	ALTERNATE 'AA' OPTION 1: DECK OVERLAY CL O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	587 SY
	SECTION NO. 0003	
	ALTERNATE 'AA' OPTION 2: DECK OVERLAY CL HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	587 SY
	SECTION NO. 0005	
	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	240 CY
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	33 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 68-C068-066

Proposed Contract Period: Late Start Date of 07/29/13 with 65 WORK DAYS

Project(s):

Project No: BROS-C068(66)--8J-68

County: MONROE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 500TH AVE Length: 0.10 miles

Location: H16 N 0.5 MI

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR 110'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,470 CY
2403-0100010	STRUCT CONC (BRIDGE)	210 CY
2404-7775000	REINFORC STEEL	54,260 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 79-C079-043

Proposed Contract Period: Late Start Date of 06/24/13 with 75 WORK DAYS

Project(s):

Project No: BROS-C079(43)--5F-79

County: POWESHIEK

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: 202ND STREET Length: 0.00 miles

Location: OVER THE DEEP RIVER  
SECTION 5, T78N, R13W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,275 CY
2403-0100010	STRUCT CONC (BRIDGE)	185 CY
2404-7775000	REINFORC STEEL	47,543 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 83-C083-051

Proposed Contract Period: Late Start Date of 07/08/13 with 75 WORK DAYS

Project(s):

Project No: BROS-C083(51)--5F-83

County: SHELBY

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: 1500TH ST Length: 0.00 miles

Location: REDLINE HIGH TRUSS BRIDGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR 151'-4 X 24' PRECAST PRESTRESSED CONCRETE BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	400 CY
2403-0100010	STRUCT CONC (BRIDGE)	190 CY
2404-7775000	REINFORC STEEL	57,940 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 86-C086-080

Proposed Contract Period: Late Start Date of 07/08/13 with 75 WORK DAYS

Project(s):

Project No: BROS-C086(80)--8J-86

County: TAMA

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 270TH STREET Length: 0.01 miles

Location: B AVE. TO C AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 90' X 30' CCS BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	318 CY
2403-0100010	STRUCT CONC (BRIDGE)	200 CY
2404-7775000	REINFORC STEEL	51,262 LB



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 52-3715-654

Proposed Contract Period: Late Start Date of 04/01/13 with 175 WORK DAYS  
Site 01: SEE PROPOSAL NOTE  
Late Start Date of 04/01/13 with 75 WORK DAYS  
Site 02: SEE PROPOSAL NOTE  
Late Start Date of 04/01/13 with 130 WORK DAYS  
Site 03: SEE PROPOSAL NOTE  
Late Start Date of 04/01/13 with 150 WORK DAYS

Proposal Note:

\*\*\*SITE 01\*\*\*

TO COMPLETE THE FOLLOWING CONSTRUCTION ACTIVITIES BY AUGUST 1, 2013:  
PHASE 2 STAGE 2A THRU 3B (LOWER MUSCATINE ROAD STA. 20+13 TO 27+25)  
PHASE 2 STAGE 2A (SYCAMORE STREET FROM LOWER MUSCATINE ROAD TO DEFOREST AVE)  
PHASE 2 STAGE 2A (DEFOREST AVENUE FROM LOWER MUSCATINE ROAD TO SYCAMORE STREET)  
PHASE 3 STAGE 1 (MIDAMERICAN ENTRANCE/KIRKWOOD ENTRANCE & KIRKWOOD PARKING LOT)

\*\*\*SITE 02\*\*\*

TO COMPLETE THE FOLLOWING CONSTRUCTION ACTIVITIES BY NOVEMBER 1, 2013:  
PHASE 2 STAGE 1A THRU 3B (LOWER MUSCATINE ROAD STA. 33+34 TO 46+31, EXCLUDING SIDEWALK AND FINAL SURFACE RESTORATION (SEEDING/SODDING))

\*\*\*SITE 03\*\*\*

TO COMPLETE THE FOLLOWING CONSTRUCTION ACTIVITIES BY DECEMBER 20, 2013:  
PHASE 1, PHASE 2, PHASE 3 (ALL STAGES EXCLUDING SIDEWALK STA. 27+25 TO EOP , PARCEL # 34 CORE SYCAMORE TOWN CENTER LLC PARKING LOT AND FINAL SURFACE RESTORATION (SEEDING/SODDING))

\*\*\*WINTER RESTRICTIONS\*\*\*

Project(s):

Project No: STP-U-3715(654)--70-52  
County: JOHNSON  
Type of Work: PCC PAVEMENT - GRADE & REPLACE  
Route: LOWER MUSCATINE ROAD Length: 0.84 miles  
Location: IN THE CITY OF IOWA CITY  
KIRKWOOD AVENUE TO FIRST AVENUE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,924 CY
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	4,072 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	5,144 SY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	22,760 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 85-0305-239

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS  
 Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.  
 No Start Date Specified with 20 WORK DAYS  
 Site 02: SEE SITE NUMBER 02 DESCRIPTION BELOW.  
 No Start Date Specified with 60 WORK DAYS

Proposal Note:

\*\*\* SITE NUMBER 01 \*\*\*  
 TO COMPLETE STAGE 2A CONSTRUCTION AND OPEN TO NORMAL FOUR  
 LANE TRAFFIC (REFER TO SHEET J.1)

\*\*\* SITE NUMBER 02 \*\*\*  
 TO COMPLETE PROJECT NUMBER BRFN-030-5(238)--39-85 AND ALSO  
 TO COMPLETE STAGE 3A AND 3B CONSTRUCTION AND OPEN TO NORMAL  
 FOUR LANE TRAFFIC (REFER TO SHEET J.1).

Project(s):

Project No: BRFN-030-5(238)--39-85  
 County: STORY  
 Type of Work: RECONSTRUCTION - BRIDGE WIDENING  
 Route: U.S. 30 Length: 0.00 miles  
 Location: EB US 30 OVER GRANT CREEK  
 2.8 MILES E. OF I-35

Project No: NHSX-030-5(239)--3H-85  
 County: STORY  
 Type of Work: PCC PAVEMENT - GRADE & REPLACE  
 Route: U.S. 30 Length: 4.10 miles  
 Location: FROM W. OF CO. RD. R-70 E. TO NEVADA(EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 213; WIDENING AN 80'-0 X 30' TO AN 80'-0 X 37'	
	CONTINUOUS CONCRETE SLAB BRIDGE BRFN-030-5(238)--39-85	
2403-0100010	STRUCT CONC (BRIDGE)	36 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	11,164 LB
2413-0698074	DECK REPAIR, CL A	76 SY
SECTION NO. 0002		
	DESIGN NO. 213; ALTERNATE 'AA' OPTION 1: CLASS O PCC	
	BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (238)	
2413-0698066	DECK OVERLAY (CL O PCC)	337 SY
SECTION NO. 0003		
	DESIGN NO. 213; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC	
	BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (238)	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	337 SY
SECTION NO. 0004		
	ROADWAY ITEMS	
	NHSX-030-5(239)--3H-85	

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

SECTION NO. 0004

ROADWAY ITEMS

NHSX-030-5(239)--3H-85

2102-2625000	EMBANKMENT-IN-PLACE	4,325 CY
2301-1003100	STD/S-F PCC PAV'T, QM-C CL 3, 10"	69,425 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	170 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	584 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	15 EACH

SECTION NO. 0007

ALTERNATE 'CC' OPTION 1: PCC SHOULDERS

BID THIS SECTION IF ALTERNATE 'CC' OPTION 1 IS CHOSEN (239)

2122-5190006	PAVED SHLD, PCC, 6"	16,392 SY
--------------	---------------------	-----------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 07-0636-089

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS  
Site 01: TO COMPLETE STAGE 3 AS SHOWN ON SHEET J.1 OF THE (89) PLANS.  
No Start Date Specified with 20 WORK DAYS

Project(s):

Project No: NHSX-063-6(89)--3H-07  
County: BLACK HAWK  
Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING  
Route: U.S. 63 Length: 5.60 miles  
Location: FROM S. OF HUDSON N. TO US 20 IN  
WATERLOO

Project No: CS-3577(605)--84-07  
County: BLACK HAWK  
Type of Work: PCC PAVEMENT - GRADE & REPLACE  
Route: E. ELDORA RD. Length: 0.11 miles  
Location: IN THE CITY OF HUDSON  
FROM U.S. 63 TO APPROX. 600 FT. EAST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
NHSX-063-6(89)--3H-07		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	8,474 CY
2303-0041750	HMA (3M ESAL) BASE, 3/4"	38,449 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	19,534 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	13,318 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	80 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0003		
ROADWAY ITEMS		
CS-3577(605)--84-07		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,430 CY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	2,373 SY
2511-0302400	RECREATIONAL TRAIL, PCC, 4"	484 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 42-C042-068

Proposed Contract Period: Late Start Date of 07/15/13 with 65 WORK DAYS

Site 01: A + B BIDDING FOR RAILROAD FLAGGERS

Cost Plus Time Site (A + B). Road User Cost per Day: \$ 700.00

Project(s):

Project No: STP-S-C042(68)--5E-42

County: HARDIN

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: D41 Length: 10.50 miles

Location: HAMILTON CO. LINE EAST TO U.S. 65

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	17,166 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	12,531 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 09-0931-021

Proposed Contract Period: Late Start Date of 09/30/13 with 15 WORK DAYS

Project(s):

Project No: STPN-093-1(21)--2J-09

County: BREMER

Type of Work: PIPE CULVERTS

Route: IOWA 93 Length: 0.00 miles

Location: IN THE CITY OF SUMNER 250' E. OF WALNUT ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	100 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	310 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 25-0802-223

Proposed Contract Period: Late Start Date of 09/23/13 with 25 WORK DAYS

Project(s):

Project No: IMN-080-2(223)109--0E-25

County: DALLAS

Type of Work: SLIDE REPAIR

Route: I-80 Length: 0.00 miles

Location: SLIDE AREAS W. AND E. OF U.S. 169

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	15,772 CY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 31-C031-065

Proposed Contract Period: Late Start Date of 09/02/13 with 30 WORK DAYS

Project(s):

Project No: ER-C031(65)--58-31  
 County: DUBUQUE  
 Type of Work: EMERGENCY REPAIR - EROSION  
 Route: CLAY HILL ROAD Length: 0.00 miles  
 Location: AT AND NEAR BRIDGE FHWA # 362916

Project No: ER-C031(66)--58-31  
 County: DUBUQUE  
 Type of Work: EMERGENCY REPAIR - EROSION  
 Route: CLAY HILL ROAD Length: 0.00 miles  
 Location: AT AND NEAR BRIDGE FHWA # 147201

Project No: ER-C031(67)--58-31  
 County: DUBUQUE  
 Type of Work: EMERGENCY REPAIR - EROSION  
 Route: SWISS VALLEY ROAD Length: 0.00 miles  
 Location: AT AND NEAR BRIDGE FHWA # 146490

Project No: ER-C031(68)--58-31  
 County: DUBUQUE  
 Type of Work: EMERGENCY REPAIR - EROSION  
 Route: CUROE ROAD Length: 0.00 miles  
 Location: N. JUNCTION OF HIGGINSPO RT AND CUROE RD  
 AT AND NEAR FHWA # 145651

Project No: ER-C031(69)--58-31  
 County: DUBUQUE  
 Type of Work: EMERGENCY REPAIR - EROSION  
 Route: WASINGTON MILLS ROAD Length: 0.00 miles  
 Location: AT AND NEAR FHWA # 145671

Item No.	Item Description	Quantity/Unit
-----		
	SECTION NO. 0001	
	ITEMS FOR BRIDGE SITE S-503	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	ER-C031(65)--58-31 350 CY
	SECTION NO. 0003	
	ITEMS FOR BRIDGE SITE S-1210	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	ER-C031(67)--58-31 870 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 304                      Proposal ID: 44-2182-136

Proposed Contract Period: Late Start Date of 09/16/13 with 25 WORK DAYS

Project(s):

Project No: ER-218-2(136)--28-44

County: HENRY

Type of Work: SLIDE REPAIR

Route: U.S. 218                      Length: 0.00 miles

Location: APPROX. 2 MILES N. OF LEE CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 306 Proposal ID: 78-0293-136

Proposed Contract Period: Late Start Date of 11/19/12 with 60 WORK DAYS

Project(s):

Project No: IMN-029-3(136)48--0E-78

County: POTTAWATTAMIE

Type of Work: GRADING

Route: I-29 Length: 0.00 miles

Location: IN THE CITY OF COUNCIL BLUFFS SE OF THE US 275  
INTERCHANGE(RIGID INCLUSION TEST SITE)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5,598 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 307 Proposal ID: 78-0801-423

Proposed Contract Period: Late Start Date of 11/19/12 with 30 WORK DAYS

Project(s):

Project No: IM-080-1(423)2--13-78

County: POTTAWATTAMIE

Type of Work: SANITARY SEWER

Route: I-80 Length: 0.00 miles

Location: IN THE CITY OF COUNCIL BLUFFS, AT SOUTH 24TH STREET  
INTERCHANGE NORTH OF I-80/I-29 WESTBOUND EXIT RAMP

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,530 CY





IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 33-0037-041

Proposed Contract Period: Late Start Date of 09/09/13 with 10 WORK DAYS

Project(s):

Project No: TSF-003-7(41)--92-33

County: FAYETTE

Type of Work: PAVEMENT MARKINGS

Route: IOWA 3 Length: 0.50 miles

Location: IN THE CITY OF OELWEIN FROM IA. 150 E. TO 9TH AVE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 35-0571-026-A

Proposed Contract Period: Approx Start Date of 12/31/12 with 15 WORK DAYS

Project(s):

Project No: STPN-57-1(26)--2J-35

County: FRANKLIN

Type of Work: SALVAGE AND REMOVAL

Route: IOWA 57 Length: 0.00 miles

Location: IN THE CITY OF ACKLEY AT 919 SHERMAN  
PARCEL # 2

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 402 Proposal ID: 78-0801-424

Proposed Contract Period: Approx Start Date of 12/31/12 with 10 WORK DAYS

Project(s):

Project No: IMN-080-1(424)3--0E-78

County: POTTAWATTAMIE

Type of Work: SALVAGE AND REMOVAL

Route: I-80 Length: 0.00 miles

Location: IN THE CITY OF COUNCIL BLUFFS AT 2803 S. 7TH ST.  
PARCEL #328

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 403 Proposal ID: 82-0741-232

Proposed Contract Period: Approx Start Date of 12/31/12 with 50 WORK DAYS

Project(s):

Project No: IMN-074-1(232)5--0E-82

County: SCOTT

Type of Work: SALVAGE AND REMOVAL

Route: I-74 Length: 0.00 miles

Location: IN THE CITY OF BETTENDORF AT 6 LOCATIONS  
PARCEL NO. 320/359/327/361/335/368

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 42-0205-081

Proposed Contract Period: Late Start Date of 03/04/13 with 40 WORK DAYS

Project(s):

Project No: NHSN-020-5(81)--2R-42

County: HARDIN

Type of Work: LANDSCAPING

Route: U.S. 20 Length: 0.00 miles

Location: FROM US 65 E. TO CO. RD. S-56

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: October 16, 2012 10:00 A.M.

Proposed Bid Order: 502 Proposal ID: 91-0352-399

Proposed Contract Period: Late Start Date of 04/01/13 with 30 WORK DAYS

Project(s):

Project No: IMN-035-2(399)63--0E-91

County: WARREN

Type of Work: WETLAND MITIGATION

Route: I-35 Length: 0.00 miles

Location: WATTS INDIANA BAT MITIGATION SITE OUTSIDE OF  
DES MOINES ADJACEMENT TO I-35

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

