

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: October 16, 2012  
Date of Addendum: September 28, 2012

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
151	07-0636-089	HMA Pavement Widening/ HMA Resurfacing	Black Hawk	NHSX-063-6(89)--3H-07 CS-3577(605)--84-07	16oct151.a02

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Attached is a SCHEDULE OF PRICES for the following items:

Line No. 0741 2105-8425005 TOPSOIL, FURNISH AND SPREAD

Bid this item as instructed and submit the bid for this item with the Bid Proposal.

Make the following change to the Plan Sheet C.2 for Project No. NHSX-063-6(89)--3H-07:

Add the following note to the reference notes for the item 2105-8425005 TOPSOIL, FURNISH AND SPREAD:

Refer to Tabulation 103-4 for additional information. Item is provided to spread additional topsoil to disturbed areas within tabulation 103-4 and areas not covered by the contract documents to provide a minimum 4" thick uniform depth. All disturbed areas not covered by concrete, asphalt or gravel shall have a minimum of 4 inches of topsoil. The Contractor shall provide all the required topsoil.

**METHOD OF MEASUREMENT:** The quantity of topsoil furnished and spread will be measured in cubic yards and will be computed on the depth of topsoil specified in the contract documents over the area involved. Estimated project quantity includes 40% to account for compaction and shrinkage. Sufficient field measurements will be taken to assure reasonable conformity with the required final thickness of topsoil in place. Topsoil from stripping, ditch cleaning and approved by the Engineer for placement, may also be used. Stripping of topsoil for placement of fill is considered incidental to this bid item.

**BASIS OF PAYMENT:** The Contractor will be paid the contract unit price for topsoil spread per cubic yard of topsoil placed, measured as provided above.

Overhaul will not be paid on this item.

Make the following change to the Plan Sheet J.1 for Project No. NHSX-063-6(89)--3H-07:

Replace Staging Note 4D with the following note:

From Station 818+40 to EOP: Place northbound traffic in the inside lane and shoulder. Place southbound traffic in the outside lane and shoulder. Mill, rubblize and resurface through the intermediate lift of HMA the northbound outside lane. Refer to Typical MC-2, MC-3 and PH-2 and Sheets J.4 and J.9.

Add the following note:

The Contractor will be allowed to work at night during Stages 4 C-F and Stages 5 and 6. Refer to the Staging Notes on Sheet J.1 for additional information.

