

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 01-0802-220

Proposed Contract Period: By individual sites.

Site 02: PROJECT CLEAN UP AND EROSION CONTROL

Late Start Date of 09/16/13 with 20 WORK DAYS

Proposal Note:

WORK RESTRICTIONS

NO LANE CLOSURES DURING THE MONTH OF AUGUST

SITE 01

TO COMPLETE BRIDGE, APPROACHES & GUARDRAIL INCLUDING TRAFFIC CONTROL SET-UP AND REMOVAL OF TC-61.

*** SITE 01 A+B BIDDING ***

ARTICLE 1112 A+B BIDDING SHALL APPLY TO SITE 01 WITH THE FOLLOWING CONDITIONS:

DAILY ROAD USER COST: \$3000.00/DAY.

MAXIMUM NUMBER OF CALENDAR DAYS ALLOWED: 105

THE ROAD USER COST PER CALENDAR DAY (DAILY ROAD USER COST) SHOWN IN THE PROPOSAL INCLUDES COSTS TO THE TRAVELING PUBLIC AND DAMAGES TO THE CONTRACTING AUTHORITY WHEN TRAFFIC ON I-80 IS TWO-WAY, TWO-LANE.

THE DOLLAR AMOUNT 'LIQUIDATED DAMAGES' FOR THE TIME BID SITE IS EQUAL TO THE DAILY ROAD USER COST. THE DISINCENTIVE ASSESSMENT/INCENTIVE PAYMENT IS EQUAL TO THE DAILY ROAD USER COST.

SITE 02

FOR FINAL PROJECT CLEAN-UP, PERMANENT SEEDING AND EROSION CONTROL.

*** CRITICAL CLOSURE ACTIVITY ***

THE CRITICAL CLOSURE ACTIVITY IS WHEN I-80 TRAFFIC IS TWO-WAY, TWO-LANE AND REDUCED TO ONE LANE FOR TRAFFIC CONTROL SET-UP AND REMOVAL OF TC-61.

Project(s):

Project No: IMX-080-2(220)85--02-01

County: ADAIR

Type of Work: BRIDGE NEW - STEEL GIRDER

Route: I-80 Length: 0.00 miles

Location: I-80 OVER MIDDLE RIVER 1.4 MILES W. OF IA. 25(EBL)

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	DESIGN 0310; A 220'-0 X 40'-0 ROLLED STEEL BEAM BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	541 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001

DESIGN 0310; A 220'-0 X 40'-0 ROLLED STEEL BEAM BRIDGE

2404-7775000 REINFORC STEEL 27,088 LB

2404-7775005 REINFORC STEEL, EPOXY COATED 102,400 LB

SECTION NO. 0002

4R FUNDING - ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 983 CY

SECTION NO. 0003

ALTERNATE AA - OPTION 1

2122-5190007 PAVED SHLD, PCC, 7" 607 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 04-C004-094

Proposed Contract Period: Late Start Date of 07/29/13 with 65 WORK DAYS

Project(s):

Project No: FM-C004(94)--55-04

County: APPANOOSE

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 610TH STREET Length: 0.10 miles

Location: OVER SPRING CREEK, 4 MILES SE OF EXLINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 8' X 10' X 72'-0 RCB CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,010 CY
2403-0100020	STRUCT CONC (RCB CULV)	255 CY
2404-7775000	REINFORC STEEL	37,629 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 16-1302-014

Proposed Contract Period: Late Start Date of 06/03/13 with 100 WORK DAYS

Project(s):

Project No: STP-130-2(14)--2C-16

County: CEDAR

Type of Work: BRIDGE REPLACEMENT - CCS

Route: IOWA 130 Length: 0.00 miles

Location: OVER SUGAR CREEK 1.9 MILES E. OF TIPTON

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0112; 150'-0 X 44' CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	744 CY
2404-7775000	REINFORC STEEL	7,430 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	131,494 LB
SECTION NO. 0002		
ROADWAY ITEMS - DIVISION 2		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,798 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	519 SY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	120 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	62 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 20-0352-300-A

Proposed Contract Period: By individual sites.

Site 02: PROJECT CLEAN UP

Approx Start Date of 09/16/13 with 20 WORK DAYS

Proposal Note:

SITE 01

TO COMPLETE SB BRIDGES, APPROACHES & GUARDRAIL INCLUDING TRAFFIC CONTROL SET-UP AND REMOVAL OF TC-61.

*** SITE 01 A+B BIDDING ***

ARTICLE 1112 A+B BIDDING SHALL APPLY TO SITE 01 WITH THE FOLLOWING CONDITIONS:

DAILY ROAD USER COST: \$3000.00/DAY.

MAXIMUM NUMBER OF CALENDAR DAYS ALLOWED: 150

THE ROAD USER COST PER CALENDAR DAY (DAILY ROAD USER COST) SHOWN IN THE PROPOSAL INCLUDES COSTS TO THE TRAVELING PUBLIC AND DAMAGES TO THE CONTRACTING AUTHORITY WHEN TRAFFIC ON I-35 IS TWO-WAY, TWO-LANE.

THE DOLLAR AMOUNT 'LIQUIDATED DAMAGES' FOR THE TIME BID SITE IS EQUAL TO THE DAILY ROAD USER COST. THE DISINCENTIVE ASSESSMENT/INCENTIVE PAYMENT IS EQUAL TO THE DAILY ROAD USER COST.

*** CRITICAL CLOSURE ACTIVITY ***

THE CRITICAL CLOSURE ACTIVITY IS WHEN I-35 TRAFFIC IS TWO-WAY, TWO-LANE AND REDUCED TO ONE LANE FOR TRAFFIC CONTROL SET-UP AND REMOVAL OF TC-61.

Project(s):

Project No: BRFIMX-035-2(296)37--14-20

County: CLARKE

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: I-35 Length: 0.00 miles

Location: OVER SOUTH SQUAW CREEK 0.7 MILES NORTH OF IA 152 (SBL)

Project No: BRFIMX-035-2(300)39--14-20

County: CLARKE

Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER

Route: I-35 Length: 0.00 miles

Location: OVER SQUAW CREEK 2.5 MILES N. OF IA. 152(SBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0411; A 201'-4 X 40'-0 PRETENSIONED PRESTRESSED		
CONCRETE BEAM BRIDGE - BRFIMX-035-2(296)37--14-20		
2403-0100010	STRUCT CONC (BRIDGE)	580 CY
2404-7775000	REINFORC STEEL	31,776 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001
 DESIGN NO. 0411; A 201'-4 X 40'-0 PRETENSIONED PRESTRESSED
 CONCRETE BEAM BRIDGE - BRFIMX-035-2(296)37--14-20
 2404-7775005 REINFORC STEEL, EPOXY COATED 96,452 LB

SECTION NO. 0002
 ROADWAY ITEMS - BRFIMX-035-2(296)37--14-20
 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 445 CY
 2303-0062500 HMA (30M ESAL) INTERMEDIATE, 1/2" 749 TON
 2303-0063502 HMA (30M ESAL) SURF, 1/2", FRIC L-2 266 TON

SECTION NO. 0003
 ALTERNATE 'AA' OPTION 1: PAVED PCC SHOULDERS - (296)
 BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN
 2122-5190007 PAVED SHLD, PCC, 7" 327 SY

SECTION NO. 0006
 DESIGN NO. 0211; A 260'-0 X 40'-0 ROLLED STEEL BEAM BRIDGE
 BRFIMX-035-2(300)39--14-20
 2403-0100010 STRUCT CONC (BRIDGE) 662 CY
 2404-7775000 REINFORC STEEL 37,418 LB
 2404-7775005 REINFORC STEEL, EPOXY COATED 121,702 LB

SECTION NO. 0007
 ROADWAY ITEMS - BRFIMX-035-2(300)39--14-20
 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,865 CY
 2303-0062500 HMA (30M ESAL) INTERMEDIATE, 1/2" 804 TON
 2303-0063502 HMA (30M ESAL) SURF, 1/2", FRIC L-2 274 TON

SECTION NO. 0008
 ALTERNATE 'BB' OPTION 1: PAVED PCC SHOULDERS (300)
 BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN
 2122-5190007 PAVED SHLD, PCC, 7" 388 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 36-3331-026

Proposed Contract Period: Late Start Date of 10/22/12 with 10 WORK DAYS

Project(s):

Project No: BRFN-333-1(26)--39-36

County: FREMONT

Type of Work: PERMANENT SCOUR COUNTERMEASURES

Route: IOWA 333 Length: 0.00 miles

Location: OVER DD NO. 6, 0.3 MILE E. OF I-29

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 50-C050-076

Proposed Contract Period: Late Start Date of 07/15/13 with 70 WORK DAYS

Project(s):

Project No: BROS-C050(76)--8J-50

County: JASPER

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 52ND AVE Length: 0.02 miles

Location: OVER SUGAR CREEK
SECTION 24, T79N, R17W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	ITEMS FOR A 100'-0" X 24'-0" CONTINUOUS CONCRETE SLAB BRIDGE	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	225 CY
2403-0100010	STRUCT CONC (BRIDGE)	171 CY
2404-7775000	REINFORC STEEL	46,711 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 54-C054-085

Proposed Contract Period: Late Start Date of 04/01/13 with 125 WORK DAYS

Project(s):

Project No: BRS-C054(85)--60-54

County: KEOKUK

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: V67 Length: 0.15 miles

Location: OVER NORTH SKUNK RIVER 6 MILES NORTHEAST OF OLLIE

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR A 468'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	8,650 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	462 SY
2403-0100010	STRUCT CONC (BRIDGE)	954 CY
2404-7775000	REINFORC STEEL	64,056 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	151,844 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 62-C062-079

Proposed Contract Period: Late Start Date of 09/09/13 with 35 WORK DAYS

Project(s):

Project No: BROS-C062(79)--8J-62

County: MAHASKA

Type of Work: RCB CULVERT NEW - SINGLE BOX

Route: RUTLEDGE AVE Length: 0.20 miles

Location: ABOUT 1 MILE NORTH OF 215TH ST. ON RUTLE
DGE AVE.

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR A SINGLE 10' X 10' X 60'-0 REINFORCED CONCRETE BOX CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	168 CY
2404-7775000	REINFORC STEEL	24,173 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 62-C062-080

Proposed Contract Period: Late Start Date of 09/03/13 with 40 WORK DAYS

Project(s):

Project No: BROS-C062(80)--8J-62

County: MAHASKA

Type of Work: RCB CULVERT NEW - TWIN BOX

Route: MERINO AVE Length: 0.20 miles

Location: JUST NORTH OF 300TH ST. ON MERINO AVE.

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	ITEMS FOR TWIN 10' X 10' X 68'-0 REINFORCED CONCRETE BOX	
	CULVERT	
2403-0100020	STRUCT CONC (RCB CULV)	276 CY
2404-7775000	REINFORC STEEL	36,813 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 67-1832-042

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Project(s):

Project No: BRFN-183-2(42)--39-67

County: MONONA

Type of Work: RCB CULVERT NEW - TWIN BOX

Route: IOWA 183 Length: 0.00 miles

Location: OVER SMALL STREAM 1.1 MILES SOUTH
OF IA. 37

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0212; TWIN 12' X 12' X 126'-0 REINFORCED CONCRETE BOX CULVERT W/ FLUME & BASIN		
2403-0100020	STRUCT CONC (RCB CULV)	742 CY
2404-7775000	REINFORC STEEL	125,025 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,978 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	47 CY
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	120 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 77-0805-297

Proposed Contract Period: Specified Start Date of 03/11/13 with 120 WORK DAYS
Site 01: TO REMOVE THE EXISTING 34TH AVE. NW BRIDGE OVER I80.
Specified Start Date of 03/11/13 with 15 WORK DAYS

Proposal Note:

Project(s):

Project No: BRFIM-080-5(297)142--05-77
County: POLK
Type of Work: BRIDGE REPLACEMENT - PPCB
Route: I-80 Length: 1.00 miles
Location: NW 34TH AVENUE OVER I-80
0.4 MILE W. OF US 65

Project No: IM-080-5(312)142--13-77
County: POLK
Type of Work: PCC PAVEMENT - GRADE AND NEW
Route: I-80 Length: 0.62 miles
Location: 34TH AVE. NW IN ALTOONA OVER I-80, 0.4 MILE
W. OF US 65

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
DESIGN NO. 2113; A 306'-0 X 40'-0 PRETENSIONED PRESTRESSED		
CONCRETE BEAM BRIDGE WITH A 14' WALKWAY BRFIM-080-5(297)142-		
2403-0100010	STRUCT CONC (BRIDGE)	256 CY
2404-7775000	REINFORC STEEL	41,252 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	206,774 LB
SECTION NO. 0002		
ROADWAY ITEMS		
IM-080-5(312)142--13-77		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	29,431 CY
2301-1032090	STD/S-F PCC PAV'T, CL C CL 2, 9"	8,613 SY
2303-0041500	HMA (3M ESAL) BASE, 1/2"	590 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	264 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	262 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 89-C089-077

Proposed Contract Period: Late Start Date of 09/23/13 with 25 WORK DAYS

Project(s):

Project No: BHS-C089(77)--63-89

County: VAN BUREN

Type of Work: PIER REPAIR

Route: J40 Length: 0.00 miles

Location: OVER THE DES MOINES RIVER APPROX. 1 MILE WEST OF KEOSAUQUA.

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR MASONARY PIER REPAIRS TO A 750' X 26' WELDED STEEL		
GIRDER BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	45 CY
2404-7775000	REINFORC STEEL	2,428 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 96-0242-014

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE BRFN-024-2(14)--39-96

Late Start Date of 04/01/13 with 100 WORK DAYS

Site 02: TO COMPLETE BRFN-024-1(22)--39-19

Specified Start Date of 06/03/13 with 65 WORK DAYS

Project(s):

Project No: BRFN-024-1(22)--39-19

County: CHICKASAW

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: IOWA 24 Length: 0.00 miles

Location: OVER DRY RUN CREEK 2.3 MILES EAST OF CO. RD. V-56

Project No: BRFN-024-2(14)--39-96

County: WINNESHIEK

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: IOWA 24 Length: 0.00 miles

Location: OVER LITTLE TURKEY RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0112; A TWIN 12'-0 X 8'-0 X 84'-0 REINFORCED CONCRETE BOX CULVERT - BRFN-024-1(22)--39-19		
2403-0100020	STRUCT CONC (RCB CULV)	267 CY
2404-7775000	REINFORC STEEL	42,451 LB
SECTION NO. 0002		
ROADWAY ITEMS - BRFN-024-1(22)--39-19		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	620 CY
2301-1033095	STD/S-F PCC PAV'T, CL C CL 3, 9.5"	419 SY
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	162 TON
SECTION NO. 0003		
DESIGN NO. 0112; A 174'-0 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE - BRFN-024-2(14)--39-96		
2403-0100010	STRUCT CONC (BRIDGE)	507 CY
2404-7775000	REINFORC STEEL	25,034 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	85,385 LB
SECTION NO. 0004		
ROADWAY ITEMS - BRFN-024-2(14)--39-96		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5,164 CY
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	347 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 97-C097-100

Proposed Contract Period: Late Start Date of 06/10/13 with 95 WORK DAYS

Project(s):

Project No: BROS-C097(100)--8J-97

County: WOODBURY

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: 290TH STREET Length: 0.28 miles

Location: NEAR THE NORTHEAST CORNER SECTION 11-86-45 APPROXIMATELY
3 MILES NORTHEAST OF HOLLY SPRINGS

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR A 243'-0 X 30'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,964 CY
2403-0100010	STRUCT CONC (BRIDGE)	391 CY
2404-7775000	REINFORC STEEL	5,828 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	88,315 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 07-3807-117

Proposed Contract Period: Late Start Date of 04/22/13 with 20 WORK DAYS

Proposal Note:

*** WORKING DAYS ***

THE WORKING DAYS ARE INTENDED FOR COMPLETION OF CONTRACT ITEMS OUTSIDE THE INCENTIVE/DISINCENTIVE PERIOD BELOW. THIS IS FOR WORK THAT DOES NOT REQUIRE A LANE CLOSURE, AND FOR EROSION CONTROL WORK REQUIRING A LANE CLOSURE OR SHOULDER CLOSURE PROVIDED THE LANE CLOSURE OR SHOULDER CLOSURE IS BETWEEN THE HOURS OF 7:00 PM AND 6:00 AM FROM 7:00 PM MONDAY TO 6:00 AM FRIDAY OR FROM 10:00 PM SUNDAY TO 6:00 AM MONDAY.

*** SITE NUMBER 01 ***

IN STAGE 2B TO CONSTRUCT THE PORTION OF RAMP D TAPER OF THE I-380/U.S. 20/IA. 27 INTERCHANGE AS SHOWN ON SHEET J.24.

*** INCENTIVE/DISINCENTIVE ***

SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:
CLOSURE DAYS: 150
MAXIMUM INCENTIVE: NONE
INCENTIVE RATE PER DAY: \$10,000.00
DISINCENTIVE RATE PER DAY: \$10,000.00
THE CRITICAL CLOSURE ACTIVITY INCLUDES COMPLETION OF ALL CONTRACT ITEMS DESCRIBED AS STAGES 1 THROUGH 5 ON SHEET J.1 OF THE PLANS. THE INCENTIVE/DISINCENTIVE AMOUNT WILL BE PAID/COLLECTED BY THE CONTRACTING AUTHORITY UPON COMPLETION OF THE CRITICAL CLOSURE ACTIVITY.

*** NO EXCUSE ROAD OPENING BONUS ***

THE CONTRACTOR WILL BE PAID THE PREDETERMINED LUMP SUM AMOUNT SHOWN IN THE PROPOSAL SCHEDULE OF PRICES FOR THE BID ITEM 'NO EXCUSE ROAD OPENING BONUS' FOR COMPLETING CONSTRUCTION SO THAT I-380 IS OPEN TO TRAFFIC ON OR BEFORE THE CALENDAR DATE SHOWN. COMPLIANCE REQUIRES THAT THE CONTRACTOR MUST HAVE ALL I-380 OPEN TO TRAFFIC WITH NO FURTHER LANE CLOSURES. ANY OTHER DELAYS DUE TO WEATHER, CHANGE ORDERS, OVERRUNS OF QUANTITIES, UTILITY DELAYS, OR ANY OTHER DELAYS WILL NOT BE CONSIDERED AS JUSTIFICATION TO MODIFY THE CALENDAR DATE.

Project(s):

Project No: IMX-380-7(117)64--02-07
County: BLACK HAWK
Type of Work: PCC PAVEMENT - GRADE & REPLACE
Route: I-380 Length: 6.60 miles
Location: IN THE CITY OF EVANS DALE FROM THE US 20/I-380
INTERCHANGE TO W. OF RIVER FOREST RD.(NBL)

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,866 CY
2122-5190007	PAVED SHLD, PCC, 7"	2,331 SY
2301-1004115	STD/S-F PCC PAV'T, QM-C CL 3I, 11.5"	164,933 SY
SECTION NO. 0007		
DESIGN NO. 1912; REPAIRS TO A 1521'-4 X VARIABLE WIDTH CONTINUOUS WELDED PLATE GIRDER BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	3 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,683 LB
SECTION NO. 0010		
CRITICAL CLOSURE ACTIVITY I/D		
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	30 CDAY
SECTION NO. 0011		
NO EXCUSE ROAD OPENING BONUS		
2528-5160000	NO EXCUSE ROAD OPENING BONUS, _____	Lump Sum LUMP

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 38-0146-031

Proposed Contract Period: Late Start Date of 06/03/13 with 90 WORK DAYS
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.
No Start Date Specified with 45 WORK DAYS

Proposal Note:

*** SITE NUMBER 01 ***

FOR COMPLETION OF ALL CONSTRUCTION WORK THAT REQUIRES IOWA
14 TO BE DETOURED, REFER TO STAGE 2 WORK SHOWN ON PLAN SHEET
J.1.

Project(s):

Project No: STP-014-6(31)--2C-38

County: GRUNDY

Type of Work: PCC OVERLAY - UNBONDED

Route: IOWA 14 Length: 6.91 miles

Location: FROM 0.5 MILE S. OF US 20 N. TO S. JCT. IA. 57

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ROADWAY ITEMS		
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	97 SY
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	853 TON
2310-5151600	PCC OVERLAY, QM-C, FURN ONLY	21,479 CY
2310-5151620	PCC OVERLAY, QM-C, PLACE ONLY (UNBONDED)	119,469 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001

ROADWAY ITEMS

IM-080-5(275)142--13-77

2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	102 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	1,284 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	623 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

SECTION NO. 0004

ALTERNATE 'BB' OPTION 1: PCC PAVED SHOULDER

BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN (275)

2122-5190007	PAVED SHLD, PCC, 7"	7,924 SY
--------------	---------------------	----------

SECTION NO. 0008

TRAFFIC SIGNS

IM-080-5(296)142--13-77

2403-0100000	STRUCT CONC (MISCELLANEOUS)	465 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	56,210 LB

SECTION NO. 0009

DESIGN NO. 2213; A 312'-0 X 79'-4 PRETENSIONED PRESTRESSED

CONCRETE BEAM BRIDGE BRFIM-080-5(299)142--05-77

2403-0100010	STRUCT CONC (BRIDGE)	169 CY
2404-7775000	REINFORC STEEL	45,579 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	258,861 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 81-0203-704-A

Proposed Contract Period: Late Start Date of 09/16/13 with 20 WORK DAYS

Project(s):

Project No: MP-020-3(704)80--76-81

County: SAC

Type of Work: BRIDGE APPROACH REPAIR

Route: U.S. 20 Length: 0.50 miles

Location: APPROACHES TO BIG CEDAR CREEK BRIDGE EAST OF SAC CITY.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 85-0155-678

Proposed Contract Period: Late Start Date of 10/22/12 with 30 WORK DAYS

Project(s):

Project No: STP-E-0155(678)--8V-85

County: STORY

Type of Work: PCC SIDEWALK/TRAIL

Route: SKUNK RIVER TRAIL Length: 0.40 miles

Location: IN THE CITY OF AMES

HUNZIKER SPORTS COMPLEX TO SE 16TH

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,500 CY
2511-0302700	RECREATIONAL TRAIL, PCC, 7"	2,650 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 11-0717-053

Proposed Contract Period: Late Start Date of 05/13/13 with 100 WORK DAYS

Project(s):

Project No: HSIPX-071-7(53)--3L-11

County: BUENA VISTA

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 71 Length: 15.81 miles

Location: FROM SIOUX RAPIDS N. TO SCL OF SPENCER

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	900 CY
	SECTION NO. 0002	
	DESIGN NO. 0112;	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	3 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	696 LB
	SECTION NO. 0003	
	DESIGN NO. 0212;	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	3 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	928 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 12-0572-705

Proposed Contract Period: Late Start Date of 09/23/13 with 10 WORK DAYS

Project(s):

Project No: MP-057-2(705)26--76-12

County: BUTLER

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 57 Length: 0.62 miles

Location: APPROX. 1.6 MI. EAST OF PARKERSBURG

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	36 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	937 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	905 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 15-0831-024-A

Proposed Contract Period: Late Start Date of 07/22/13 with 60 WORK DAYS

Project(s):

Project No: STP-083-1(24)--2C-15

County: CASS

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: IOWA 83 Length: 5.98 miles

Location: FROM CO. RD. N-28 E. TO WCL OF ANITA

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	200 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	10,158 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	9,945 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 31-0618-135-A

Proposed Contract Period: Late Start Date of 05/13/13 with 110 WORK DAYS

Project(s):

Project No: HSIPX-061-8(135)--3L-31

County: DUBUQUE

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 61 Length: 8.46 miles

Location: FROM JACKSON CO. LINE N. TO US 151 INTERCHANGE

Project No: HSIPX-061-7(80)--3L-49

County: JACKSON

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 61 Length: 16.05 miles

Location: FROM IA. 64 IN MAQUOKETA N. TO DUBUQUE CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 48-0066-048

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Project(s):

Project No: STP-006-6(48)--2C-48

County: IOWA

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: U.S. 6 Length: 20.65 miles

Location: FROM POWESHIEK CO. LINE E. TO W. JCT. US 151

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	905 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	41,049 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	33,149 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	53 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 50-3301-030

Proposed Contract Period: Late Start Date of 05/27/13 with 100 WORK DAYS

Project(s):

Project No: HSIPX-330-1(30)--3L-50
 County: JASPER
 Type of Work: HMA PAVED SHOULDER - NEW
 Route: IOWA 330 Length: 0.00 miles
 Location: FROM U.S. 65 NE TO U.S. 30

Project No: MP-330-1(709)11--76-64
 County: MARSHALL
 Type of Work: PCC PATCHING
 Route: IOWA 330 Length: 0.50 miles
 Location: FROM U.S. 65/IOWA 117 JCT. TO U.S. 30.

Project No: TSF-330-2(88)--92-64
 County: MARSHALL
 Type of Work: HMA PAVED SHOULDER - NEW
 Route: IOWA 330 Length: 0.00 miles
 Location: N. OF U.S. 30 AND W. OF CO. RD. S-75

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
PAVED SHOULDER ITEMS		
JASPER COUNTY HSIPX-330-1(30)--3L-50		
2102-2625000	EMBANKMENT-IN-PLACE	36 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	30,493 TON
SECTION NO. 0003		
ROADWAY ITEMS		
MARSHALL COUNTY MP-330-1(709)11--76-64		
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	433 TON
2303-0053502	HMA (10M ESAL) SURF, 1/2", FRIC L-2	433 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,993 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	46 EACH
SECTION NO. 0004		
ROADWAY ITEMS		
MARSHALL COUNTY TSF-330-2(88)--92-64		
2303-0031500	HMA (1M ESAL) BASE, 1/2"	218 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 52-0015-101

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Project(s):

Project No: STP-001-5(101)--2C-52
 County: JOHNSON
 Type of Work: HMA RESURFACING
 Route: IOWA 1 Length: 2.45 miles
 Location: IN THE CITY OF IOWA CITY FROM KITTY LEE RD. NEAR
 US 218 NE TO S. JCT. US 6

Project No: STP-006-6(74)--2C-52
 County: JOHNSON
 Type of Work: HMA RESURFACING
 Route: U.S. 6 Length: 2.41 miles
 Location: IN THE CITY OF IOWA CITY FROM 500' N. OF S. JCT. IA. 1
 E. TO LAKESIDE DR.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
STP-001-5(101)--2C-52		
2102-2625000	EMBANKMENT-IN-PLACE	300 CY
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	10,199 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	10,539 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	140 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	13 EACH
SECTION NO. 0003		
ROADWAY ITEMS		
STP-006-6(74)--2C-52		
2102-2625000	EMBANKMENT-IN-PLACE	90 CY
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	9,569 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	9,888 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	164 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	28 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 55-0094-047

Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS

Project(s):

Project No: STP-009-4(47)--2C-55

County: KOSSUTH

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: IOWA 9 Length: 10.82 miles

Location: FROM EMMET CO. LINE E. TO W. JCT. US 169

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	3,700 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	497 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	21,126 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	16,273 TON
2303-0141750	HMA (3M ESAL) BASE, 3/4"	9,526 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 57-0307-161-A

Proposed Contract Period: Late Start Date of 08/26/13 with 35 WORK DAYS

Project(s):

Project No: HSIPX-030-7(161)--3L-57

County: LINN

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 30 Length: 5.54 miles

Location: FROM KIRKWOOD BLVD. IN CEDAR RAPIDS E. TO
E. JCT. US 151

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 57-1513-140-A

Proposed Contract Period: Late Start Date of 05/20/13 with 100 WORK DAYS

Project(s):

Project No: HSIPX-151-3(140)--3L-57

County: LINN

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 151 Length: 19.49 miles

Location: US 151 FROM SPRINGVILLE NE TO MONTICELLO

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	3,440 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 67-0371-050

Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.
Completion Date of 05/31/13

Proposal Note:

*** SITE NUMBER 01 ***

THIS SITE REQUIRES THE RESURFACING CONTRACTOR TO WIDEN AND RESURFACE THE PAVEMENT WITHIN THE AREA ENCOMPASSED IN THE TRAFFIC CONTROL REQUIRED FOR THE BRIDGE PROJECT. THE INTENT IS TO COMPLETE ALL RESURFACING ACTIVITIES PRIOR TO THE BRIDGE CONTRACTOR BEGINNING HIS PROJECT. THIS INVOLVES APPROXIMATELY 4,900 FEET OF HMA WIDENING, 4" HMA RESURFACING, HMA SHOULDER CONSTRUCTION AND PAVEMENT MILLING FOR TRANSITIONS. THE BRIDGE DECK OVERLAY PROJECT WILL HAVE A JUNE 3, 2013 START DATE. THIS START DATE WILL ALLOW SUFFICIENT TIME TO COMPLETE THE BRIDGE DECK OVERLAY PROJECT IN THE REMAINING CONSTRUCTION SEASON. REFER TO PLAN SHEET NUMBER J.1 FOR FURTHER DETAILS.

Project(s):

Project No: STP-037-1(50)--2C-67
County: MONONA
Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
Route: IOWA 37 Length: 13.09 miles
Location: FROM IA. 183 IN SOLDIER SE TO US 30 IN DUNLAP.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	2,870 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	22,768 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	23,292 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 73-0021-097

Proposed Contract Period: Late Start Date of 07/08/13 with 70 WORK DAYS

Project(s):

Project No: STP-002-1(97)--2C-73

County: PAGE

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: IOWA 2 Length: 9.48 miles

Location: FROM SHENANDOAH EAST TO MIDDLE TARKIO RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	72 CY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	43 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	13,569 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	13,437 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	143 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	8 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 163 Proposal ID: 78-0593-032

Proposed Contract Period: Late Start Date of 09/03/13 with 40 WORK DAYS

Project(s):

Project No: STP-059-3(32)--2C-78

County: POTTAWATTAMIE

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: U.S. 59 Length: 4.70 miles

Location: FROM IOWA 92 NORTH TO OAKLAND

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	420 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	7,161 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	7,328 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 164 Proposal ID: 84-0181-079

Proposed Contract Period: Late Start Date of 04/29/13 with 110 WORK DAYS

Project(s):

Project No: HSIPX-018-1(79)--3L-84

County: SIOUX

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 18 Length: 16.91 miles

Location: FROM N. JCT. US 75 E. TO SHELDON

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	1,000 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 165 Proposal ID: 90-0347-139

Proposed Contract Period: Late Start Date of 04/15/13 with 120 WORK DAYS

Project(s):

Project No: NHSN-034-6(77)--2R-68

County: MONROE

Type of Work: SLIDE REPAIR

Route: U.S. 34 Length: 0.00 miles

Location: US 34 FROM ALBIA E. TO OTTUMWA(VARIOUS LOCATIONS)

Project No: NHSX-034-7(139)--3H-90

County: WAPELLO

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: U.S. 34 Length: 10.55 miles

Location: FROM MONROE CO. LINE E. TO OTTUMWA

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
NHSN-034-6(77)--2R-68		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	15,482 CY
SECTION NO. 0003		
ROADWAY ITEMS		
NHSX-034-7(139)--3H-90		
2102-2625000	EMBANKMENT-IN-PLACE	895 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	24,025 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	17,837 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	212 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	16 EACH
SECTION NO. 0004		
DESIGN NO. 0113; 150'-0 X 30'-0 CONTINUOUS I-BEAM BRIDGE		
NHSX-034-7(139)--3H-90		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	6 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,068 LB
SECTION NO. 0005		
DESIGN NO. 0213; 150'-0 X 30'-0 CONTINUOUS I-BEAM BRIDGE		
NHSX-034-7(139)--3H-90		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	6 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,042 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 00-0002-738

Proposed Contract Period: Late Start Date of 10/15/12 with 20 WORK DAYS

Project(s):

Project No: MP-000-2(738)0--76-00

County: STATEWIDE

Type of Work: PCC PATCHING

Route: VARIOUS ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 2

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,173 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	60 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 33-C033-063

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Proposal Note:

*** WINTER WORK/WORK RESTRICTION ***

THE CONTRACTING AUTHORITY WOULD LIKE THE CONTRACTOR TO DO AS MUCH WORK THIS FALL AS POSSIBLE WITHOUT REQUIRING IT. THEREFORE, SELECT WINTER WORK AS DESCRIBED BELOW WILL BE ALLOWED DURING THE WINTER OF 2012/2013. NO WORKING DAYS WILL BE CHARGED BETWEEN NOVEMBER 15, 2012 AND APRIL 1, 2013 FOR THE WORK DESCRIBED BELOW:

THERE IS A VERY LARGE FILL NEAR THE BOP, THE CUT NEXT TO IT INCLUDES ROCK; IT WOULD BE ADVANTAGEOUS TO GET AN EXTRA FREEZE THAW CYCLE ON THIS LARGE FILL, THEREFORE, THE CONTRACTOR IS ALLOWED TO COME IN AS SOON AS THEIR SCHEDULE PERMITS AND WORK INTO THE WINTER SEASON AS LONG AS THEY CAN. THE ROAD FROM BOP TO STA. 70+00 WILL BE ALLOWED TO BE CLOSED OVER THE WINTER. IF WORK PROGRESSES FASTER AND WEATHER PERMITS, FURTHER WORK ON THE PROJECT MAY BE DONE IF ACCESS TO THE RESIDENCES AT STA. 72+00 AND STA. 86+00 HAVE SUITABLE ALL WEATHER ACCESS FOR LIVESTOCK TRAILERS OUT THE OTHER (SE) WAY.

Project(s):

Project No: FM-C033(63)--55-33

County: FAYETTE

Type of Work: GRADING

Route: EAGLE RD. Length: 1.42 miles

Location: FROM US 18 IN CLERMONT

N ON STONE ST. TO EAGLE RD & DEERFIELD

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	33,970 CY
2108-5025000	OVERHAUL	670,920 ST-Y
2403-0100020	STRUCT CONC (RCB CULV)	2 CY
2404-7775000	REINFORC STEEL	102 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 36-0021-099

Proposed Contract Period: Late Start Date of 10/22/12 with 20 WORK DAYS

Project(s):

Project No: ER-002-1(99)--28-36

County: FREMONT

Type of Work: SLIDE REPAIR

Route: IOWA 2 Length: 0.00 miles

Location: 2.5 MILES & 6.1 MILES E. OF MISSOURI RIVER

Project No: ER-029-1(107)1--06-36

County: FREMONT

Type of Work: SLIDE REPAIR

Route: I-29 Length: 0.00 miles

Location: 1.4 MILES N. OF MISSOURI STATE LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		ER-002-1(99)--28-36
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,000 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	110 CY
SECTION NO. 0002		
ROADWAY ITEMS		
		ER-029-1(107)1--06-36
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	420 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 51-0348-158

Proposed Contract Period: Late Start Date of 10/22/12 with 15 WORK DAYS

Project(s):

Project No: NHSN-034-8(158)--2R-51

County: JEFFERSON

Type of Work: GRADING

Route: U.S. 34 Length: 0.15 miles

Location: MINT BLVD. OVER CROW CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	705 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 54-0781-017

Proposed Contract Period: Late Start Date of 09/23/13 with 25 WORK DAYS

Project(s):

Project No: ER-078-1(17)--28-54

County: KEOKUK

Type of Work: SLIDE REPAIR

Route: IOWA 78

Length: 0.00 miles

Location: 3.5 MILES W. OF RICHLAND

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,341 CY
	SECTION NO. 0002	
	DESIGN NO. 0112; AN 8'-0 X 8'-0 RCB EXTENSION	
2403-0100020	STRUCT CONC (RCB CULV)	66 CY
2404-7775000	REINFORC STEEL	10,546 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 82-0671-125

Proposed Contract Period: Late Start Date of 09/09/13 with 35 WORK DAYS

Project(s):

Project No: NHSN-067-1(125)--2R-82

County: SCOTT

Type of Work: SLIDE REPAIR

Route: U.S. 67 Length: 0.00 miles

Location: APPROX. 1.5 MILES S. OF I-80

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	228 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	329 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH
SECTION NO. 0002		
EMERGENCY REPAIR OF EARTH SLIDE ITEMS		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	622 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: September 18, 2012 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 31-2100-663

Proposed Contract Period: Late Start Date of 10/22/12 with 20 WORK DAYS

Project(s):

Project No: SRTS-U-2100(663)--8U-31

County: DUBUQUE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE Length: 1.24 miles

Location: IN THE CITY OF DUBUQUE
AT ASBURY, JFK, RHOMBERG & RADFORD

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	60 SY

