MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 001 Proposal ID: 06-C006-088 Proposed Contract Period: Late Start Date of 07/29/13 with 65 WORK DAYS Project(s): Project No: BROS-C006(88)--8J-06 County: BENTON Type of Work: BRIDGE REPLACEMENT - CCS Route: 25TH AVE. Length: 0.00 miles Location: OVER MUD CREEK \_\_\_\_\_ Quantity/Unit Item No. Item Description \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 150'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 416 CY 91,952 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 002 Proposal ID: 12-C012-072 Proposed Contract Period: Late Start Date of 05/06/13 with 105 WORK DAYS Project(s): Project No: BRS-C012(72)--60-12 County: BUTLER Type of Work: BRIDGE AND APPROACHES - PPCB Route: T16 Length: 0.00 miles Location: HWY 3 TO 220TH ST. \_\_\_\_\_ Quantity/Unit Item No. Item Description \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 294'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 510 CY 2404-7775000 REINFORC STEEL 24,846 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 94,737 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 7,968 CY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 1,610 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 003 Proposal ID: 26-C026-071-A Proposed Contract Period: Late Start Date of 08/05/13 with 60 WORK DAYS Project(s): Project No: BROS-C026(71)--8J-26 County: DAVIS Type of Work: BRIDGE REPLACEMENT - PPCB Route: JADE AVE Length: 0.10 miles Location: OVER SOUTH WYACONDAH RIVER APPROXIMATELY 4 MILES SOUTHWEST OF BLOOMFIELD \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 80'-0 X 24'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,119 CY 2403-0100010 STRUCT CONC (BRIDGE) 132 CY 2404-7775000 REINFORC STEEL 32,506 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 004 Proposal ID: 40-C040-078 Proposed Contract Period: Late Start Date of 06/10/13 with 90 WORK DAYS Project(s): Project No: BROS-C040(78)--8J-40 County: HAMILTON Type of Work: BRIDGE REPLACEMENT - CCS Route: 360TH STREET Length: 0.10 miles Location: OVER THE SOUTH SKUNK RIVER SECTION 14, T86N, R24W \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 120'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 294 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 73,008 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 6,441 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 005 Proposal ID: 41-C041-104 Proposed Contract Period: Late Start Date of 07/01/13 with 70 WORK DAYS Project(s): Project No: BROS-C041(104)--8J-41 County: HANCOCK Type of Work: BRIDGE REPLACEMENT - CCS Route: 130TH STREET Length: 0.00 miles Location: NASH AVENUE TO PALM AVENUE \_\_\_\_\_ Quantity/Unit Item No. Item Description \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 130'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 1,145 CY 356 CY 69,085 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 006 Proposal ID: 41-2837-602 Proposed Contract Period: Late Start Date of 04/15/13 with 40 WORK DAYS Project(s): Project No: SBRFM-2837(602)--5D-41 County: HANCOCK Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX Route: 225TH STREET Length: 0.00 miles Location: IN THE CITY OF GARNER OVER DRAINAGE DITCH #5 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 12' X 12' X 85'-0 TWIN PRECAST CONCRETE BOX CULVERT 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 340 CY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 227 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 007 Proposal ID: 42-0571-021 Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS Project(s): Project No: BRF-057-1(15)--38-42 County: HARDIN Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: IOWA 57 Length: 0.00 miles Location: IN THE CITY OF ACKLEY OVER CC R.R. Project No: BRF-057-1(21)--38-42 County: HARDIN Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER Route: IOWA 57 Length: 0.0 Location: IN THE CITY OF ACKLEY OVER CC R.R. Length: 0.00 miles \_\_\_\_\_ Item Description Item No. Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS - BRF-057-1(15)--38-42 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 12,459 CY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 1,929 SY SECTION NO. 0004 DESIGN NO. 0112; A 366'-0 X 30'-0 CWPG BRIDGE & REINFORCED CONCRETE RETAINING WALLS - BRF-057-1(21)--38-42 2403-0100010 STRUCT CONC (BRIDGE) 1,359 CY 2404-7775000 REINFORC STEEL 72,504 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 190,091 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 008 Proposal ID: 48-C048-062 Proposed Contract Period: Late Start Date of 07/08/13 with 80 WORK DAYS Project(s): Project No: BRS-C048(62)--60-48 County: IOWA Type of Work: BRIDGE REPLACEMENT - PPCB Route: 108TH ST Length: 0.10 miles Location: OVER UNNAMED STREAM -SEC 8-81-11 \_\_\_\_\_ Quantity/Unit Item No. Item Description \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 90' -0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 480 CY 177 CY 2404-7775000 REINFORC STEEL 42,129 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 009 Proposal ID: 52-3715-650 Proposed Contract Period: Late Start Date of 05/27/13 with 105 WORK DAYS Project(s): Project No: BRM-3715(650)--8N-52 County: JOHNSON Type of Work: BRIDGE REPLACEMENT - PPCB Route: ROCHESTER AVE. Length: 0.00 miles Location: IN THE CITY OF IOWA CITY OVER RALSTON CREEK \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 55'-0 X 36'-0 PRETENSIONED PRESTESSED CONCRETE BEAM BRIDGE W/ 9'-0 SIDEWALKS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 402 CY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 381 SY 2403-0100010 STRUCT CONC (BRIDGE) 216 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 44,571 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 010 Proposal ID: 68-C068-064-A Proposed Contract Period: Late Start Date of 06/10/13 with 100 WORK DAYS Project(s): Project No: BROS-C068(64)--5F-68 County: MONROE Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX Route: H35 Length: 0.20 miles Location: 695TH AVE W 0.3 MI \_\_\_\_\_ Quantity/Unit Item No. Item Description \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR TWIN 12' X 12' X 118'-0 REINFORCED CONCRETE BOX CULVERT 697 CY 2403-0100020 STRUCT CONC (RCB CULV) 2404-7775000 REINFORC STEEL 87,211 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 4,378 CY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 2,323 SY

### IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 011 Proposal ID: 69-C069-043 Proposed Contract Period: Late Start Date of 04/15/13 with 120 WORK DAYS Project(s): Project No: BRS-C069(43)--60-69 County: MONTGOMERY Type of Work: BRIDGE REPLACEMENT - PPCB Route: 150TH ST Length: 0.25 miles Location: OVER EAST NISHNABOTNA RIVER APPROX 5 MILES NORTH OF RED OAK \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 309' -0 X 30' -0 PRETENSIONED PRESTRESSED CONCRETE BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 552 CY 2404-7775000 REINFORC STEEL 32,000 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 101,837 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 5,826 CY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 384 SY SECTION NO. 0003 BOAT RAMP ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 954 CY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 012 Proposal ID: 78-0804-513 Proposed Contract Period: Late Start Date of 09/03/13 with 50 WORK DAYS Proposal Note: \*\*\*WORK RESTRICTION\*\*\* NO LANE CLOSURES DURING THE MONTH OF AUGUST. Project(s): Project No: MBIN-080-4(513)35--0M-78 County: POTTAWATTAMIE Type of Work: BRIDGE REHABILITATION Route: I-80 L Length: 0.00 miles Location: OVER SILVER CREEK 5.1 MILES W. OF US 59(WBL) \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 DESIGN NO. 1812; DUAL 175'-10 X 39' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100000 STRUCT CONC (MISCELLANEOUS) 47 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 4,543 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 653 CY

### IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 013 Proposal ID: 84-0123-006 Proposed Contract Period: Late Start Date of 04/15/13 with 120 WORK DAYS Project(s): Project No: BRF-012-3(6)--38-84 County: SIOUX Type of Work: BRIDGE REPLACEMENT - CCS Route: IOWA 12 Length: 0.00 miles Location: OVER SIX MILE CREEK 2 MILES N. OF CO. RD. C-12 \_\_\_\_\_ Item No. Quantity/Unit Item Description \_\_\_\_\_ SECTION NO. 0001 DESIGN NO. 0213; 256'-0 X 40'-0 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 1,079 CY 2404-7775000 REINFORC STEEL 17,240 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 200,999 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 3,422 CY 2301-1033095 STD/S-F PCC PAV'T, CL C CL 3, 9.5" 230 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 014 Proposal ID: 85-C085-111 Proposed Contract Period: Late Start Date of 06/24/13 with 85 WORK DAYS Project(s): Project No: BROS-C085(111)--5F-85 County: STORY Type of Work: BRIDGE REPLACEMENT - CCS Route: E23 (170TH STREET) Length: 0.15 miles Location: OVER KEIGLEY BRANCH, A BRANCH OF THE SKUNK RIVER, APPROX. 3 MILES EAST OF GILBERT. \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A 120'-0 X 30'-0 CCS BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,514 CY 2403-0100010 STRUCT CONC (BRIDGE) 293 CY 2404-7775000 REINFORC STEEL 3,162 LB

69,358 LB

2404-7775005 REINFORC STEEL, EPOXY COATED

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 015 Proposal ID: 93-C093-070 Proposed Contract Period: Late Start Date of 09/23/13 with 30 WORK DAYS Project(s): Project No: BHOS-C093(70)--89-93 County: WAYNE Type of Work: BRIDGE REHABILITATION Route: RACOON ROAD Length: 0.01 miles Location: OVER TO NINE MILE CREEK \_\_\_\_\_ Item No. Quantity/Unit Item Description \_\_\_\_\_

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 016 Proposal ID: 96-C096-110 Proposed Contract Period: Late Start Date of 06/03/13 with 85 WORK DAYS Project(s): Project No: BROS-C096(110)--8J-96 County: WINNESHIEK Type of Work: RCB CULVERT NEW - TRIPLE BOX Route: TROUT RUN ROAD Length: 0.00 miles Location: OVER UNNAMED CREEK \_\_\_\_\_ Quantity/Unit Item No. Item Description \_\_\_\_\_ SECTION NO. 0001 ITEMS FOR A TRIPLE 12' X 12' X 58'-0" RCB CULVERT 2102-2625000 EMBANKMENT-IN-PLACE 2303-0131500 HMA (1M ESAL) BASE, 1/2" 63 CY 1,913 SY 2303-0132500 HMA (1M ESAL) INTERMEDIATE, 1/2" 1,913 SY 2303-0133500 HMA (1M ESAL) SURF, 1/2", NO FRIC 1,913 SY 2403-0100020 STRUCT CONC (RCB CULV) 546 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 64,463 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 101 Proposal ID: 44-5292-619 Proposed Contract Period: Late Start Date of 04/08/13 with 95 WORK DAYS Project(s): Project No: STP-U-5292(619)--70-44 County: HENRY Type of Work: PCC PAVEMENT - GRADE AND NEW Route: GRAND AVENUE Length: 0.59 miles Location: IN THE CITY OF MOUNT PLEASANT JAMES AVENUE TO BNSF RAIL BRIDGE \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033070 STD/S-F PCC PAV'T, CL C CL 3, 7" 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 12,467 CY 27,898 SY 1,536 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 102 Proposal ID: 78-1642-663 Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS Project(s): Project No: STP-A-1642(663)--86-78 County: POTTAWATTAMIE Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: 24TH ST. Length: 0.20 miles Location: IN THE CITY OF COUNCIL BLUFFS S. 24TH ST - MARKETPLACE DR. TO 25TH AV \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 5,600 CY 2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10" 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 10,785 SY 688 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 103 Proposal ID: 79-C079-047 Proposed Contract Period: Late Start Date of 07/22/13 with 65 WORK DAYS Project(s): Project No: STP-S-C079(47)--5E-79 County: POWESHIEK Type of Work: PCC PAVEMENT WIDENING / PCC RESURFACING Route: F29 Length: 5.50 miles Location: FROM US63 EAST TO BROOKLYN \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 

 2301-1033080
 STD/S-F PCC PAV'T, CL C CL 3, 8"
 7,438 SY

 2310-5151040
 PCC OVERLAY, FURN ONLY
 15,076 CY

 2310-5151551
 PCC OVERLAY PLACE ONLY (WHITE TOPPING)
 70,489 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 104 Proposal ID: 97-0296-222 Proposed Contract Period: Late Start Date of 04/01/13 with 20 WORK DAYS Proposal Note: REFER TO 656.0183 FOR THE FOLLOWING INFORMATION: \*\*\* WORK PRIOR TO THE SPECIFIED START DATE (SITE 01) \*\*\* \*\*\* WORKING DAYS \*\*\* \*\*\* INCENTIVE/DISINCENTIVE \*\*\* \*\*\* NO EXCUSE ROAD OPENING BONUS \*\*\* Project(s): Project No: MB-020-3(502)1--77-97 County: WOODBURY Type of Work: DECK JOINT REPAIR Route: U.S. 20 Length: 0.0 Location: IN THE CITY OF SIOUX CITY ON-RAMP Length: 0.00 miles OVER IA. 376(S. HILLS DR.) & UP R.R. Project No: IM-NHS-029-6(176)142--03-97 County: WOODBURY Type of Work: TRAFFIC SIGNS Route: I-29 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY FROM HARBOR DR. OUTFALL N. TO 0.25 MILE S. OF BN/SF R.R. Project No: IM-NHS-029-6(222)143--03-97 County: WOODBURY Type of Work: PCC PAVEMENT - GRADE AND NEW Route: I-29 Length: 4.21 miles Location: IN THE CITY OF SIOUX CITY FROM HARBOR DR. OUTFALL N. TO 0.25 MILE S. OF BN/SF R.R. (NBL/RAMPS) Project No: IM-NHS-029-6(231)142--03-97 County: WOODBURY Type of Work: RCB CULVERT NEW - TWIN BOX Route: I-29 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY OVER THE AIRPORT OUTFALL (NBL) \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 DESIGN NO. 0613; REPAIRS TO A 339'-6 X VARIES CWPG BRIDGE MB-020-3(502)1--77-97 2403-0100000 STRUCT CONC (MISCELLANEOUS) 14 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 1,358 LB SECTION NO. 0002 ROADWAY ITEMS MB-020-3(502)1--77-97 2122-5190008 PAVED SHLD, PCC, 8" 924 SY SECTION NO. 0004

| MAJOR ITEMS<br>ROADWAY ITEMS          | - PRELIMINARY QUANTI<br>(for information only) | ITY REPORT |      |
|---------------------------------------|--|------------|------|
| IM-NHS-029-6(222)14303-97             |  |            |      |
|                                       | L 10, RDWY+BORROW                              | 187,058    | СҮ   |
| 2301-1004110 STD/S-F PCC P            | AV'T, QM-C CL 3I, 11"                          | 184,327    | SY   |
| 2301-1033100 STD/S-F PCC P            | AV'T, CL C CL 3, 10"                           | 15,915     | SY   |
| 2303-0101000 HMA WEDGE/LEVEL/STRENGTH |  | 594        | SY   |
| 2403-0100000 STRUCT CONC (            | MISCELLANEOUS)                                 | 157        | СҮ   |
| 2404-7775005 REINFORC STEE            | L, EPOXY COATED                                | 19,807     | LB   |
| 2511-0302500 RECREATIONAL             | TRAIL, PCC, 5"                                 | 1,227      | SY   |
| 2511-0302600 RECREATIONAL             | TRAIL, PCC, 6"                                 | 102        | SY   |
| SECTION NO. 0006                      |  |            |      |
| CONTRACT ITEMS                        |  |            |      |
| 2528-5160000 NO EXCUSE ROA            | D OPENING BONUS,                               | Lump Sum   | LUMP |
| 2528-5160100 CRITICAL CLOS            | URE ACTIVITY I/D                               | 50         | CDAY |
| 2528-5160100 CRITICAL CLOS            | URE ACTIVITY I/D                               | 10         | CDAY |
| 2528-5160100 CRITICAL CLOS            | URE ACTIVITY I/D                               | 10         | CDAY |
| 2528-5160100 CRITICAL CLOS            | URE ACTIVITY I/D                               | 20         | CDAY |

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 151 Proposal ID: 06-C006-076 Proposed Contract Period: Late Start Date of 08/19/13 with 40 WORK DAYS Project(s): Project No: HRRR-C006(76)--5R-06 County: BENTON Type of Work: HMA PAVEMENT - GRADE AND REPLACE Route: W28 Length: 1.75 miles Location: FROM HWY 30 TO ATKINS \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2303-0021500 HMA (300K ESAL) BASE, 1/2" 11,025 CY 1,039 TON 2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 1,072 TON 2403-0100000 STRUCT CONC (MISCELLANEOUS) 1 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 152 Proposal ID: 12-1881-018 Proposed Contract Period: Late Start Date of 05/27/13 with 100 WORK DAYS Project(s): Project No: STP-188-1(18)--2C-12 County: BUTLER Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: IOWA 188 Length: 10.20 miles Location: FROM THE NORTH LIMITS OF CLARKSVILLE TO 0.25 MILE EAST OF THE BREMER/BUTLER COUNTY LINE \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 5,040 CY 2303-0031750 HMA (1M ESAL) BASE, 3/4" 10,025 TON 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 14,553 TON 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 15,016 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 93 SY 2529-5070111 PATCH,FULL-DEPTH FINISH,BY AREA(=>50 FT) 1,866 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 10 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 153 Proposal ID: 13-0043-031 Proposed Contract Period: Late Start Date of 06/17/13 with 90 WORK DAYS Project(s): Project No: STP-004-3(31)--2C-13 County: CALHOUN Type of Work: HMA RESURFACING WITH MILLING Route: IOWA 4 Length: 10.10 miles Location: FROM THE WEST JCT. OF D36 TO SCL OF POMEROY \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 513 CY 17,002 TON 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 16,882 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 80 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 2 EACH

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 154 Proposal ID: 42-0656-054 Proposed Contract Period: Late Start Date of 06/24/13 with 75 WORK DAYS Project(s): Project No: STP-065-6(54)--2C-42 County: HARDIN Type of Work: HMA RESURFACING WITH MILLING Route: U.S. 65 Length: 5.74 miles Location: FROM S. JCT. IA. 175 IN HUBBARD N. TO JUST E. OF N. JCT. IA. 175 Project No: MP-065-1(700)123--76-85 County: STORY Type of Work: HMA RESURFACING WITH MILLING Route: U.S. 65 Length: 0.42 miles Location: FROM 0.2 MILE S. OF CO. RD. E-18 NEAR ZEARING N. 0.4 MILE \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS STP-65-6(54)--2C-42 2102-2625000 EMBANKMENT-IN-PLACE 2,030 CY 2303-0031500 HMA (1M ESAL) BASE, 1/2" 5,071 TON 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 14,478 TON 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 10,720 TON SECTION NO. 0003 ROADWAY ITEMS MP-65-1(700)123--76-85 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 479 TON 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 479 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 155 Proposal ID: 47-0596-036 Proposed Contract Period: Late Start Date of 05/20/13 with 100 WORK DAYS Project(s): Project No: STP-059-6(36)--2C-47 County: IDA Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: U.S. 59 Length: 10.35 miles Location: FROM OAK GROVE RD. IN IDA GROVE N. TO E. JCT. US 20 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 638 CY 14,424 TON 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 14,257 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 222 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 14 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 156 Proposal ID: 77-C077-197 Proposed Contract Period: Late Start Date of 09/23/13 with 15 WORK DAYS Project(s): Project No: STP-S-C077(197)--5E-77 County: POLK Type of Work: HMA RESURFACING Route: NW 54TH AVE. Length: 2.23 miles Location: FROM NW 2 ST TO I-35 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 4,750 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 157 Proposal ID: 77-4151-050 Proposed Contract Period: Late Start Date of 05/28/13 with 100 WORK DAYS Project(s): Project No: HSIPX-044-5(25)--3L-25 County: DALLAS Type of Work: HMA PAVED SHOULDER - NEW Route: IOWA 44 Length: 7.56 miles Location: FROM DALLAS CENTER E. TO GRIMES Project No: TSF-415-1(49)--92-77 County: POLK Type of Work: HMA PAVED SHOULDER - NEW Route: IOWA 415 Length Location: N. OF ANKENY NEAR 44TH ST. Length: 0.00 miles Project No: HSIPX-415-1(50)--3L-77 County: POLK Type of Work: HMA PAVED SHOULDER - NEW Route: IOWA 415 Length: 0.00 miles Location: FROM NW 26TH STREET IN ANKENY TO IOWA 141 IN POLK COUNTY Project No: MP-415-1(712)6--76-77 County: POLK Type of Work: HMA RESURFACING Route: IOWA 415 Length: 0.90 miles Location: IN ANKENY FROM NW 26TH ST. TO IA. 141 IN POLK CO. \_\_\_\_\_ Item No. Item Description Ouantity/Unit SECTION NO. 0001 ROADWAY ITEMS HSIPX-44-5(25)--3L-25 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 4,148 TON 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 3,084 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 617 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 61 EACH SECTION NO. 0004 ROADWAY ITEMS HSIPX-415-1(50)--3L-77 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 1,000 CY SECTION NO. 0005 ROADWAY ITEMS MP-415-1(712)6--76-77 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 1,394 TON 1,033 TON 2303-0033504 HMA (1M ESAL) SURF, 1/2", FRIC L-4 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 248 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 29 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 201 Proposal ID: 26-0025-705 Proposed Contract Period: Late Start Date of 09/09/13 with 40 WORK DAYS Project(s): Project No: MP-002-5(705)205--76-26 County: DAVIS Type of Work: PCC PATCHING Route: IOWA 2 Length: 0.50 miles Location: IN THE CITY OF PULASKI. \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 3,266 SY 5 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 202 Proposal ID: 55-0182-708 Proposed Contract Period: Late Start Date of 04/01/13 with 60 WORK DAYS Project(s): Project No: MP-065-2(710)195--76-17 County: CERRO GORDO Type of Work: HMA CRACK FILLING Route: U.S. 65 Length: 11.21 miles Location: FROM 0.1 MILE SOUTH OF 27TH STREET SW IN MASON CITY TO IA 9 IN MANLY. Project No: MP-122-2(709)7--76-17 County: CERRO GORDO Type of Work: HMA CRACK FILLING Route: IOWA 122 Length: 2.67 miles Location: IN THE CITY OF MASON CITY FROM PIERCE AVE. E. TO ILLINOIS AVE. Project No: MP-018-2(708)141--76-55 County: KOSSUTH Type of Work: HMA CRACK FILLING Route: U.S. 18 Length: 21.48 miles Location: FROM W. OF WESLEY E. TO SEYMOUR AVE. IN GARNER. Project No: MP-169-2(720)197--76-55 County: KOSSUTH Type of Work: HMA CRACK FILLING Route: U.S. 169 Length: 0.66 miles Location: IN THE CITY OF ALGONA FROM IRVINGTON ROAD N. TO STATE ST. Item No. Item Description Quantity/Unit \_\_\_\_\_

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 301 Proposal ID: 82-0671-125-A Proposed Contract Period: Late Start Date of 07/22/13 with 70 WORK DAYS Project(s): Project No: NHSN-067-1(125)--2R-82 County: SCOTT Type of Work: SLIDE REPAIR Route: U.S. 67 Length: 0.00 miles Location: SLIDE AREA APPROX. 1.5 MILES S. OF I-80 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070EXCAVATION, CL 10, RDWY+BORROW2529-5070110PATCH, FULL-DEPTH FINISH, BY AREA2529-5070120PATCH, FULL-DEPTH FINISH, BY COUNT 228 CY 313 SY 4 EACH SECTION NO. 0002 ITEMS FOR PIPE PILES 2403-0100000 STRUCT CONC (MISCELLANEOUS) 622 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 351 Proposal ID: 77-C077-194 Proposed Contract Period: Late Start Date of 08/12/13 with 45 WORK DAYS Project(s): Project No: FM-TSF-C077(194)--5B-77 County: POLK Type of Work: TRAFFIC SIGNALS Route: NW 26TH ST. Length: 0.00 miles Location: AT HWY 415 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 2,703 CY 745 TON 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 539 TON 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 150 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 352 Proposal ID: 77-3827-613 Proposed Contract Period: Late Start Date of 09/03/13 with 35 WORK DAYS Project(s): Project No: STP-A-3827(613)--86-77 County: POLK

Type of Work: TRAFFIC SIGNALS Route: MERLE HAY ROAD Length: 2.43 miles Location: IN THE CITY OF JOHNSTON NW 70TH AVE TO I-35/80 N RAMP

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 401 Proposal ID: 78-0293-137 Proposed Contract Period: Approx Start Date of 02/25/13 with 5 WORK DAYS Project(s): Project No: IMN-029-3(137)48--0E-78 County: POTTAWATTAMIE Type of Work: SALVAGE AND REMOVAL Length: 0.00 miles Route: I-29 Location: IN THE CITY OF COUNCIL BLUFFS AT 2822 S. 8TH ST. PARCEL NO. 319A \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 501 Proposal ID: 07-0206-066-A Proposed Contract Period: Late Start Date of 03/04/13 with 45 WORK DAYS Project(s): Project No: NHSN-020-6(66)--2R-07 County: BLACK HAWK Type of Work: LANDSCAPING Route: U.S. 20 Length: 5.02 miles Location: IN THE CITY OF WATERLOO FROM US 63 E. TO US 218 \_\_\_\_\_ Item No. Quantity/Unit Item Description \_\_\_\_\_

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 502 Proposal ID: 13-0203-100 Proposed Contract Period: Late Start Date of 03/04/13 with 60 WORK DAYS Project(s): Project No: NHSN-020-3(100)--2R-13 County: CALHOUN Type of Work: EROSION CONTROL Route: U.S. 20 Length: 11.25 kilometers Location: FROM CO. RD. N-33 E. TO IA. 4 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 EROSION CONTROL ITEMS 2102--100100 CL 10 EXCAVATION RDWY+BORROW 500 M3

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 503 Proposal ID: 81-0202-072 Proposed Contract Period: Late Start Date of 03/04/13 with 65 WORK DAYS Project(s): Project No: NHSN-020-2(72)--2R-81 County: SAC Type of Work: EROSION CONTROL Route: U.S. 20 Length: 27.20 kilometers Location: FROM US 71 N. OF EARLY E. TO UNION AVE./CO. RD. N-14 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 EROSION CONTROL ITEMS 750 M3 2102--100100 CL 10 EXCAVATION RDWY+BORROW

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 504 Proposal ID: 81-0202-093 Proposed Contract Period: Late Start Date of 03/04/13 with 60 WORK DAYS Project(s): Project No: NHSN-020-2(93)--2R-81 County: SAC Type of Work: EROSION CONTROL Route: U.S. 20 Length: 27.20 kilometers Location: FROM UNION AVE./CO. RD. N-14 E. TO CO. RD. N-33 IN CALHOUN CO. \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 EROSION CONTROL ITEMS 750 M3 2102--100100 CL 10 EXCAVATION RDWY+BORROW

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 505 Proposal ID: 81-1961-023 Proposed Contract Period: Late Start Date of 03/18/13 with 30 WORK DAYS Project(s): Project No: STPN-196-1(23)--2J-81 County: SAC Type of Work: EROSION CONTROL Route: IOWA 196 Length: 0.00 miles Location: FROM JUST N. OF EXIST. US 20 N. TO RELOC. US 20 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_ SECTION NO. 0001 EROSION CONTROL ITEMS 100 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 506 Proposal ID: 82-0615-140 Proposed Contract Period: Late Start Date of 03/04/13 with 15 WORK DAYS Project(s):

Project No: NHSN-061-5(140)--2R-82 County: SCOTT Type of Work: LANDSCAPING Route: U.S. 61 Location: CO. RD. Y-48 E. TO JUST W. OF I-280

Item No. Item Description Quantity/Unit

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 601 Proposal ID: 07-9342-500 Proposed Contract Period: Late Start Date of 07/15/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 0704.75934 Project(s): Project No: MB-934-2(500)5--77-07 County: BLACK HAWK Type of Work: BRIDGE PAINTING Route: IOWA 934 Length: 0.00 miles Location: OVER ABAND. R.R. 0.2 MILE W. OF US 63 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 602 Proposal ID: 09-0032-505 Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 0939.1S003 Project(s): Project No: MB-003-2(505)239--77-09 County: BREMER Type of Work: BRIDGE PAINTING Route: IOWA 3 Length: 0.00 miles Location: OVER BUCK CREEK 2.4 MILES W. OF FAYETTE CO. LINE \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 603 Proposal ID: 12-0572-503 Proposed Contract Period: Late Start Date of 06/10/13 with 50 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 1224.9S057 1220.3S057 Project(s): Project No: MB-057-2(503)25--77-12 County: BUTLER Type of Work: BRIDGE PAINTING Route: IOWA 57 Length: 0.00 miles Location: OVER PHELPS CREEK 0.3 MILE EAST OF THE EAST JCT. IOWA 14 Project No: MB-057-2(504)20--77-12 County: BUTLER Type of Work: BRIDGE PAINTING Length: 0.00 miles Route: IOWA 57 Location: OVER D.D. 0.1 MILE EAST OF THE EAST JCT. T25 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 604 Proposal ID: 13-0073-500 Proposed Contract Period: Late Start Date of 06/10/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 1361.9S007 Project(s): Project No: MB-007-3(500)62--77-13 County: CALHOUN Type of Work: BRIDGE PAINTING Route: IOWA 7 Length: 0.00 miles Location: OVER CCP R.R. 0.9 MILE EAST OF SR P-19 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 605 Proposal ID: 18-0313-500 Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 1838.2S031 Project(s): Project No: MB-031-3(500)38--77-18 County: CHEROKEE Type of Work: BRIDGE PAINTING Route: IOWA 31 Length: 0.00 miles Location: OVER SILVER CREEK, 0.5 MILE WEST OF U.S. 59. \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 606 Proposal ID: 27-0355-510 Proposed Contract Period: Late Start Date of 07/08/13 with 50 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 2019.1S034 2717.30035 Project(s): Project No: MB-034-5(500)119--77-20 County: CLARKE Type of Work: BRIDGE PAINTING Route: U.S. 34 Length: 0.00 miles Location: OVER BN/SF R.R. 2.4 MILES EAST OF U.S. 69 Project No: MBIN-035-5(510)17--0M-27 County: DECATUR Type of Work: BRIDGE PAINTING Length: 0.00 miles Route: I-35 Location: 4.5 MILES NORTH OF IOWA 2. \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 607 Proposal ID: 37-0301-500 Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 3716.7S030 Project(s): Project No: MB-030-1(500)117--77-37 County: GREENE Type of Work: BRIDGE PAINTING Route: U.S. 30 Length: 0.00 miles Location: OVER W. BEAVER CREEK 0.9 MILE EAST OF GRAND JCT. \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 608 Proposal ID: 39-0444-500 Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 3961.8S044 Project(s): Project No: MB-044-4(500)62--77-39 County: GUTHRIE Type of Work: BRIDGE PAINTING Route: IOWA 44 Length: 0.00 miles Location: OVER SEELEY CREEK 1.3 MILES WEST OF SR N-70 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 609 Proposal ID: 67-1413-500 Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 6731.9S141 Project(s): Project No: MB-141-3(500)32--77-67 County: MONONA Type of Work: BRIDGE PAINTING Route: IOWA 141 Length: 0.00 miles Location: OVER SOLDIER RIVER, 3.8 MILES WEST OF IOWA 183. \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: December 18, 2012 10:00 A.M. Proposed Bid Order: 610 Proposal ID: 76-0033-501 Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS Proposal Note: . \*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\* THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED  $\{ \ \}$  PORTIONS OF THE NUMBER ARE DEFINED BELOW.) .  $\{52\}10.90380$  County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: 7601.2S003 Project(s): Project No: MB-003-3(501)101--77-76 County: POCAHONTAS Type of Work: BRIDGE PAINTING Route: IOWA 3 Length: 0.00 miles Location: OVER DITCH 5.1 MILES WEST OF IOWA 4 \_\_\_\_\_ Item No. Item Description Quantity/Unit \_\_\_\_\_