

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 03-C003-049

Proposed Contract Period: Late Start Date of 07/15/13 with 70 WORK DAYS

Project(s):

Project No: BROS-C003(49)--8J-03

County: ALLAMAKEE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: IRISH HOLLOW ROAD Length: 0.01 miles

Location: OVER BRANCH OF UPPER IOWA RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR 70' X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	8,519 CY
2403-0100010	STRUCT CONC (BRIDGE)	131 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	34,776 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 09-3792-601

Proposed Contract Period: Late Start Date of 07/15/13 with 70 WORK DAYS

Project(s):

Project No: SRTS-U-3792(601)--8U-09

County: BREMER

Type of Work: BRIDGE NEW - PPCB

Route: BARRICK ROAD Length: 0.11 miles

Location: IN THE CITY OF JANESVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 546'-0 X 10'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,504 CY
2403-0100010	STRUCT CONC (BRIDGE)	331 CY
2404-7775000	REINFORC STEEL	32,212 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	42,554 LB
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	558 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 10-C010-082

Proposed Contract Period: Late Start Date of 04/01/13 with 90 WORK DAYS
Site 01: TO OPEN BRIDGE TO CONSTRUCTION TRAFFIC
Late Start Date of 04/15/13 with 60 WORK DAYS

Project(s):

Project No: BRS-C010(82)--60-10
County: BUCHANAN
Type of Work: BRIDGE REPLACEMENT - PPCB
Route: D22 Length: 0.00 miles
Location: OVER PINE CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,579 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	15 TON
2403-0100010	STRUCT CONC (BRIDGE)	272 CY
2404-7775000	REINFORC STEEL	21,414 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	76,697 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 18-0597-045

Proposed Contract Period: Late Start Date of 05/13/13 with 90 WORK DAYS

Project(s):

Project No: BRFN-059-7(43)--39-18
County: CHEROKEE
Type of Work: BRIDGE DECK OVERLAY
Route: U.S. 59 Length: 0.00 miles
Location: OVER WESTCOTT PARK LOOP
0.4 MILES S. OF S.R. C-38

Project No: BRFN-059-7(45)--39-18
County: CHEROKEE
Type of Work: BRIDGE DECK OVERLAY
Route: U.S. 59 Length: 0.00 miles
Location: OVER LITTLE SIOUX RIVER
0.2 MILES S. OF S.R. C-38

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0113; REPAIRS TO A 75'-0 X 56'-0 CCS BRIDGE BRFN-059-7(43)--39-18		
2413-0698074	DECK REPAIR, CL A	109 SY
SECTION NO. 0002		
DESIGN NO. 0113; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (43)		
2413-0698066	DECK OVERLAY (CL O PCC)	485 SY
SECTION NO. 0003		
DESIGN NO. 0113; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (43)		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	485 SY
SECTION NO. 0005		
DESIGN NO. 0213; REPAIRS TO A 391'-0 X 56'-0 CONT. I-BEAM & WELDED GIRDER BRIDGE BRFN-059-7(45)--39-18		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	21 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	3,429 LB
2413-0698074	DECK REPAIR, CL A	89 SY
SECTION NO. 0006		
DESIGN NO. 0213; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (45)		
2413-0698066	DECK OVERLAY (CL O PCC)	2,421 SY
SECTION NO. 0007		
DESIGN NO. 0213; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (45)		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	2,421 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 23-C023-088

Proposed Contract Period: Late Start Date of 07/29/13 with 60 WORK DAYS

Project(s):

Project No: BRS-C023(88)--60-23

County: CLINTON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: Y54

Length: 0.10 miles

Location: OVER SMALL CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 80' X 30' CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	174 CY
2404-7775000	REINFORC STEEL	3,116 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	43,488 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	240 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	195 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 25-8177-614

Proposed Contract Period: Late Start Date of 04/15/13 with 60 WORK DAYS

Project(s):

Project No: SBRM-8177(614)--8F-25

County: DALLAS

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: UTE AVENUE Length: 0.10 miles

Location: IN THE CITY OF WAUKEE, OVER JOHNSON CREEK APPROXIMATELY
1 MILE SOUTH OF WAUKEE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 14'-0 X 10'-0 X 84'-0 REINFORCED CONCRETE BOX CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	280 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	570 SY
2403-0100020	STRUCT CONC (RCB CULV)	493 CY
2404-7775000	REINFORC STEEL	75,347 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 31-0522-090

Proposed Contract Period: Late Start Date of 04/01/13 with 240 WORK DAYS

Project(s):

Project No: NHSX-052-2(83)--3H-31
County: DUBUQUE
Type of Work: PCC PAVEMENT - GRADE & REPLACE
Route: U.S. 52 Length: 1.37 miles
Location: IN THE CITY OF DUBUQUE FROM US 61/151 N. TO
GRANDVIEW AVE.(CATFISH CREEK)

Project No: BRF-052-2(90)--38-31
County: DUBUQUE
Type of Work: BRIDGE REPLACEMENT - PPCB
Route: U.S. 52 Length: 0.00 miles
Location: IN THE CITY OF DUBUQUE OVER
CATFISH CREEK/CC R.R.

Project No: NHSN-052-2(91)--2R-31
County: DUBUQUE
Type of Work: LIGHTING
Route: U.S. 52 Length: 0.00 miles
Location: IN THE CITY OF DUBUQUE AT US 61/151/
GRANDVIEW AVE. INTERSECTION

Project No: NHSN-052-2(112)--2R-31
County: DUBUQUE
Type of Work: TRAFFIC SIGNS
Route: U.S. 52 Length: 1.23 miles
Location: IN THE CITY OF DUBUQUE JUST S. OF GRANDVIEW AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
	NHSX-052-2(83)--3H-31	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	88,679 CY
2122-5190010	PAVED SHLD, PCC, 10"	18,945 SY
2301-1003100	STD/S-F PCC PAV'T, QM-C CL 3, 10"	48,329 SY
SECTION NO. 0004		
	DESIGN NO. 211; FOR A 623'-8 X VARIOUS HEIGHT SOLDIER PILE	
	RETAINING WALL	NHSX-052-2(83)--3H-31
2403-0100000	STRUCT CONC (MISCELLANEOUS)	498 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	32,086 LB
SECTION NO. 0005		
	DESIGN NO. 311; FOR A 658'-10 X VARIOUS HEIGHT REINFORCED	
	CONCRETE RETAINING WALL	NHSX-052-2(83)--3H-31
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1,220 CY
2404-7775000	REINFORC STEEL	48,666 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	81,320 LB
SECTION NO. 0007		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

DESIGN NO. 111; FOR A 518'-0 X 40' DUAL PRETENSIONED

PRESTRESSED CONCRETE BEAM BRIDGE BRF-052-2(90)--38-31

2403-0100010	STRUCT CONC (BRIDGE)	3,607 CY
2404-7775000	REINFORC STEEL	191,057 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	524,637 LB

SECTION NO. 0009

ROADWAY ITEMS - SIGNING

NHSN-052-2(112)--2R-31

2403-0100000	STRUCT CONC (MISCELLANEOUS)	11 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,120 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 31-1515-062

Proposed Contract Period: Late Start Date of 07/08/13 with 50 WORK DAYS

Project(s):

Project No: BRFN-151-5(62)--39-31

County: DUBUQUE

Type of Work: BRIDGE DECK OVERLAY

Route: U.S. 151 Length: 0.00 miles

Location: OVER BRANCH PRAIRIE CREEK 1.9 MILES N. OF
SR Y-21

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0113; A 168'-0 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	267 LB
2413-0698074	DECK REPAIR, CL A	38 SY
SECTION NO. 0002		
	DESIGN NO. 0113; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	836 SY
SECTION NO. 0003		
	DESIGN NO. 0113; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	836 SY
SECTION NO. 0004		
	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	280 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 32-C032-043

Proposed Contract Period: Late Start Date of 08/19/13 with 50 WORK DAYS

Project(s):

Project No: FM-C032(43)--55-32
County: EMMET
Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX
Route: N24 Length: 0.01 miles
Location: 180TH ST. TO A-22

Project No: FM-C032(44)--55-32
County: EMMET
Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX
Route: 520TH AVE. Length: 0.00 miles
Location: APPROX. 1250' S OF N 1/4 CORNER S6 T
99N R31W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 10'-0 X 8'-0 REINFORCED CONCRETE BOX CULVERT		
SINGLE		FM-C032(43)--55-32
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	315 CY
2301-1032090	STD/S-F PCC PAV'T, CL C CL 2, 9"	231 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 36-0294-501

Proposed Contract Period: Late Start Date of 08/05/13 with 60 WORK DAYS

Project(s):

Project No: MBIN-029-4(501)10--0M-36
County: FREMONT
Type of Work: BRIDGE REPAIR
Route: I-29 Length: 0.00 miles
Location: OVER IA. 2 AT JUNCTION OF IA. 2

Project No: MBIN-029-4(502)9--0M-36
County: FREMONT
Type of Work: BRIDGE REPAIR
Route: I-29 Length: 0.00 miles
Location: OVER DIKE ROAD & ABAND. R.R. 1.6 MILES S. OF IA. 2

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0311; 212'-0 X 40'-0 CONTINUOUS WELDED GIRDER	
	BRIDGE MBIN-029-4(501)10--0M-36	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	43 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	7,144 LB
SECTION NO. 0002		
	DESIGN NO. 0511; 212'-0 X 40'-0 CONTINUOUS WELDED GIRDER	
	BRIDGE MBIN-029-4(501)10--0M-36	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	43 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	7,144 LB
SECTION NO. 0003		
	ROADWAY ITEMS	
	MBIN-029-4(501)10--0M-36	
2102-2625000	EMBANKMENT-IN-PLACE	400 CY
SECTION NO. 0004		
	DESIGN NO. 0411; 296'-0 X 40'-0 CONTINUOUS WELDED GIRDER	
	BRIDGE MBIN-029-4(502)9--0M-36	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	27 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	4,690 LB
SECTION NO. 0005		
	ROADWAY ITEMS	
	MBIN-029-4(502)9--0M-36	
2102-2625000	EMBANKMENT-IN-PLACE	200 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 43-0301-145

Proposed Contract Period: Late Start Date of 06/24/13 with 80 WORK DAYS

Project(s):

Project No: BRFN-030-1(145)--39-43

County: HARRISON

Type of Work: BRIDGE DECK OVERLAY

Route: U.S. 30 Length: 0.00 miles

Location: OVER BOYER RIVER/CC R.R./UP R.R/ROAD
0.3 MILE E. OF IA 127

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0413; REPAIRS TO A 777'-0 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	84 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	7,635 LB
2413-0698074	DECK REPAIR, CL A	42 SY
SECTION NO. 0002		
	DESIGN NO. 0413; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	3,733 SY
SECTION NO. 0003		
	DESIGN NO. 0413; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	3,733 SY
SECTION NO. 0004		
	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	95 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 45-C045-061

Proposed Contract Period: Late Start Date of 08/05/13 with 55 WORK DAYS

Project(s):

Project No: BROS-C045(61)--5F-45

County: HOWARD

Type of Work: BRIDGE REPLACEMENT - CCS

Route: V-46 Length: 0.00 miles

Location: 13-97-12 TO 13-97-12, 0.33 MI. S. OF
200TH ST. OVER THE LITTLE TURKEY RIVER.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 80'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	174 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	46,943 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 47-C047-049

Proposed Contract Period: Late Start Date of 07/22/13 with 65 WORK DAYS

Project(s):

Project No: BRS-C047(49)--60-47

County: IDA

Type of Work: BRIDGE AND APPROACHES - CCS

Route: D15 Length: 0.00 miles

Location: CARRIAGE W 0.2 MI

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 80'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,712 CY
2403-0100010	STRUCT CONC (BRIDGE)	175 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	46,973 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 50-0064-156

Proposed Contract Period: Late Start Date of 09/03/13 with 30 WORK DAYS
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.
No Start Date Specified with 15 WORK DAYS

Proposal Note:

*** SITE NUMBER 01 ***

TO CONSTRUCT THE RCB AND COMPLETE ALL NECESSARY GRADING AND
PAVING WHILE U.S. 6 IS CLOSED TO THROUGH TRAFFIC. ONCE U.S.
6 IS OPENED TO NORMAL TRAFFIC NO ADDITIONAL LANE CLOSURES
WILL BE ALLOWED.

Project(s):

Project No: STPN-006-4(156)--2J-50
County: JASPER
Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX
Route: U.S. 6 Length: 0.00 miles
Location: 3.3 MILES W. OF IA. 224

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0113; ALT 'AA' OPT 1: 10' X 6' X 116' C-I-P RCB		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2403-0100020	STRUCT CONC (RCB CULV)	161 CY
2404-7775000	REINFORC STEEL	28,212 LB
SECTION NO. 0003		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,200 CY
2122-5190006	PAVED SHLD, PCC, 6"	83 SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	248 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 50-0801-506

Proposed Contract Period: Late Start Date of 05/20/13 with 95 WORK DAYS

Project(s):

Project No: MB-065-1(501)98--77-50
County: JASPER
Type of Work: DECK JOINT REPAIR
Route: U.S. 65 Length: 0.00 miles
Location: OVER INDIAN CREEK 0.2 MILE S. OF IA. 117(NBL)

Project No: MBIN-080-1(506)158--0M-50
County: JASPER
Type of Work: DECK JOINT REPAIR
Route: I-80 Length: 0.00 miles
Location: OVER INDIAN CREEK 2.6 MILES E. OF IA. 117(EBL/WBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0413; 212' X 36' CONTINUOUS I-BEAM BRIDGE		
MB-065-1(501)98--77-50		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	16 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,306 LB
SECTION NO. 0003		
DESIGN NO. 0513; TWIN 317'-6 X 39'-0 PPCB BRIDGE WB		
MBIN-080-1(506)158--0M-50		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	3 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	434 LB
SECTION NO. 0004		
DESIGN NO. 0613; TWIN 317'-6 X 39'-0 PPCB BRIDGE EB		
MBIN-080-1(506)158--0M-50		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	8 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,036 LB
SECTION NO. 0005		
ROADWAY ITEMS		
MBIN-080-1(506)158--0M-50		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	176 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	402 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 56-2697-621

Proposed Contract Period: Late Start Date of 07/15/13 with 75 WORK DAYS

Project(s):

Project No: BROS-2697(621)--8J-56
County: LEE
Type of Work: BRIDGE REPLACEMENT - CCS
Route: D STREET Length: 0.00 miles
Location: IN THE CITY OF FORT MADISON
OVER FRENCH CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 90'-0 X 42'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	224 CY
2403-0100010	STRUCT CONC (BRIDGE)	263 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	70,029 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 57-0307-163

Proposed Contract Period: Late Start Date of 07/01/13 with 80 WORK DAYS

Project(s):

Project No: BRFN-030-7(163)--39-57

County: LINN

Type of Work: BRIDGE DECK OVERLAY

Route: U.S. 30 Length: 0.00 miles

Location: OVER R.R./CREEK/ST.

1.6 MILES W. OF I-380 (EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0613; REPAIRS TO A 988'-0 X 40'-0 CONTINUOUS WELDED GIRDER BRIDGE	
2413-0698074	DECK REPAIR, CL A	233 SY
SECTION NO. 0002		
	DESIGN NO. 0613; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	4,396 SY
SECTION NO. 0003		
	DESIGN NO. 0613; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	4,396 SY
SECTION NO. 0004		
	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	70 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 018 Proposal ID: 57-0307-164

Proposed Contract Period: Late Start Date of 07/29/13 with 60 WORK DAYS

Project(s):

Project No: BRFN-030-7(164)--39-57

County: LINN

Type of Work: DECK JOINT REPAIR

Route: U.S. 30 Length: 0.00 miles

Location: AT EDGEWOOD RD. 2.6 MILES W. OF I-380

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0312; REPAIRS TO A 289'-6 X 68'-0 PRETENSIONED		
PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	66 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,420 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 019 Proposal ID: 64-1464-026

Proposed Contract Period: Late Start Date of 06/17/13 with 90 WORK DAYS

Project(s):

Project No: BRF-146-4(26)--38-64

County: MARSHALL

Type of Work: RCB CULVERT NEW - TWIN BOX

Route: IOWA 146 Length: 0.00 miles

Location: IA. 146 OVER STREAM 0.2 MILE N. OF CO. RD. E-63

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0113; TWIN 10' X 12' X 124'-0 REINFORCED		
CONCRETE BOX CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	510 CY
2404-7775000	REINFORC STEEL	68,020 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	8,439 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	82 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	106 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 020 Proposal ID: 77-2352-628

Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.
No Start Date Specified with 60 WORK DAYS

Proposal Note:

*** SITE NUMBER 01 ***

TO COMPLETE THE (628) PROJECT, THE WEST BRIDGE APPROACH WORK
FOR THE (628) PROJECT AND ALL WORK ON 73RD STREET.

*** SITE NUMBER 02 ***

TO COMPLETE THE GRADING AND PAVING FROM STATION 1515+00 TO
1522+25. REFER TO THE J SHEETS FOR MORE INFORMATION.

Project(s):

Project No: IM-235-2(627)4--13-77
County: POLK
Type of Work: HMA PAVEMENT - GRADE AND NEW
Route: I-235 Length: 0.00 miles
Location: IN THE CITY OF WINDSOR HEIGHTS FROM 73RD /8TH ST. E. TO
63RD ST.(WB AUXILIARY LANE)

Project No: IM-235-2(628)4--13-77
County: POLK
Type of Work: RECONSTRUCTION - BRIDGE WIDENING
Route: I-235 Length: 0.00 miles
Location: IN THE CITY OF WINDSOR HEIGHTS OVER 73RD ST./8TH ST.
AND IAIS R.R.

Project No: IM-235-2(629)4--13-77
County: POLK
Type of Work: RECONSTRUCTION - BRIDGE WIDENING
Route: I-235 Length: 0.00 miles
Location: IN THE CITY OF WINDSOR HEIGHTS OVER WALNUT CREEK

Project No: IM-235-2(630)4--13-77
County: POLK
Type of Work: TRAFFIC SIGNS
Route: I-235 Length: 0.00 miles
Location: IN THE CITY OF WINDSOR HEIGHTS FROM 73RD /8TH ST. E. TO
63RD ST.(WB AUXILIARY LANE)

Project No: IM-235-2(631)4--13-77
County: POLK
Type of Work: LIGHTING
Route: I-235 Length: 0.00 miles
Location: IN THE CITY OF WINDSOR HEIGHTS FROM 73RD /8TH ST. E. TO
63RD ST.(WB AUXILIARY LANE)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001

ROADWAY ITEMS- IM-235-2(627)4--13-77

2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	25,071 CY
2301-1034120	STD/S-F PCC PAV'T, CL C CL 3I, 12"	12 SY
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	27 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	27 TON
2303-0061500	HMA (30M ESAL) BASE, 1/2"	763 TON
2303-0062500	HMA (30M ESAL) INTERMEDIATE, 1/2"	152 TON
2303-0063502	HMA (30M ESAL) SURF, 1/2", FRIC L-2	152 TON

SECTION NO. 0002

DESIGN NO. 0312; A 332'-0 X 69'-6 CONTINUOUS WELDED GIRDER

BRIDGE - IM-235-2(628)4--13-77

2403-0100010	STRUCT CONC (BRIDGE)	388 CY
2404-7775000	REINFORC STEEL	17,517 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	105,835 LB

SECTION NO. 0004

DESIGN NO. 0412; A 331'-0 X 69'-6 CONTINUOUS WELDED GIRDER

BRIDGE - IM-235-2(629)4--13-77

2403-0100010	STRUCT CONC (BRIDGE)	181 CY
2404-7775000	REINFORC STEEL	17,200 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	63,016 LB

SECTION NO. 0005

TRAFFIC SIGN ITEMS - IM-235-2(630)4--13-77

2403-0100000	STRUCT CONC (MISCELLANEOUS)	68 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	8,152 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 021 Proposal ID: 84-0181-080

Proposed Contract Period: Late Start Date of 09/30/13 with 20 WORK DAYS

Project(s):

Project No: NHSN-018-1(80)--2R-84

County: SIOUX

Type of Work: RCB CULVERT - REPAIR

Route: U.S. 18 Length: 9.83 miles

Location: FROM LYON CO. LINE E. TO WCL OF ROCK VALLEY

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR AN RCB CULVERT - REPAIR		
2102-2625000	EMBANKMENT-IN-PLACE	180 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 022 Proposal ID: 91-0352-294

Proposed Contract Period: Late Start Date of 04/15/13 with 130 WORK DAYS

Project(s):

Project No: IM-035-2(294)61--13-91
County: WARREN
Type of Work: BRIDGE REPLACEMENT - PPCB
Route: I-35 Length: 0.00 miles
Location: S.B. I-35 OVER NORTH RIVER 3.8 MILES N. OF IA 92

Project No: IM-035-2(355)61--13-91
County: WARREN
Type of Work: GRADING
Route: I-35 Length: 0.36 miles
Location: OVER NORTH RIVER 3.8 MILES. N. OF IA. 92(SBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0312; A 334'-0 X 60' PRETENSIONED PRESTRESSED		
CONCRETE BEAM BRIDGE - IM-035-2(294)61--13-91		
2403-0100010	STRUCT CONC (BRIDGE)	559 CY
2404-7775000	REINFORC STEEL	72,886 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	202,201 LB
SECTION NO. 0003		
ROADWAY ITEMS - IM-035-2(355)61--13-91		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	83,963 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 023 Proposal ID: 96-C096-110

Proposed Contract Period: Late Start Date of 06/03/13 with 85 WORK DAYS

Project(s):

Project No: BROS-C096(110)--8J-96

County: WINNESHIEK

Type of Work: RCB CULVERT NEW - TRIPLE BOX

Route: TROUT RUN ROAD Length: 0.00 miles

Location: OVER UNNAMED CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TRIPLE 12' X 12' X 58'-0 RCB CULVERT		
2102-2625000	EMBANKMENT-IN-PLACE	63 CY
2303-0131500	HMA (1M ESAL) BASE, 1/2"	1,913 SY
2303-0132500	HMA (1M ESAL) INTERMEDIATE, 1/2"	1,913 SY
2303-0133500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,913 SY
2403-0100020	STRUCT CONC (RCB CULV)	546 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	64,463 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 024 Proposal ID: 99-C099-070

Proposed Contract Period: Late Start Date of 07/08/13 with 75 WORK DAYS

Project(s):

Project No: BRS-C099(70)--60-99

County: WRIGHT

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: R-33 Length: 0.00 miles

Location: APPROXIMATELY 0.39 MILES SOUTH OF THE
JUNCTION WITH 150TH ST. OVER OTTER CRK.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 90' X 30' PRETENSIONED PRESTRESSED CONCRETE BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	238 CY
2403-0100010	STRUCT CONC (BRIDGE)	173 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	42,041 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 07-0636-088

Proposed Contract Period: By individual sites.

Proposal Note:

REFER TO 656.0184 FOR THE FOLLOWING INFORMATION:

*** INCENTIVE/DISINCENTIVE - SITE INFORMATION ***

*** NO EXCUSE ROAD OPENING BONUSES ***

Project(s):

Project No: NHSX-063-6(88)--3H-07

County: BLACK HAWK

Type of Work: PCC PAVEMENT - GRADE AND NEW

Route: U.S. 63 Length: 1.00 miles

Location: IN THE CITY OF WATERLOO FROM S. OF NEWELL/CONGER ST.
TO DONALD ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		DIVISION 1
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	28,690 CY
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	1,623 SY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	1,560 SY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	282 SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	38,014 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	3,913 SY
SECTION NO. 0002		
I/D ITEMS		
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	30 CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	10 CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	30 CDAY
SECTION NO. 0003		
BONUS ITEMS		
2528-5160000	NO EXCUSE ROAD OPENING BONUS, _____	Lump Sum LUMP
2528-5160000	NO EXCUSE ROAD OPENING BONUS, _____	Lump Sum LUMP

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 29-C029-071

Proposed Contract Period: Late Start Date of 06/03/13 with 30 WORK DAYS

Project(s):

Project No: STP-S-C029(71)--5E-29

County: DES MOINES

Type of Work: PCC PAVEMENT - GRADE AND NEW

Route: 210TH Length: 1.50 miles

Location: FROM IOWA CITY ROAD 1.53 MILES EAST TO US 61

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	7,378 CY
2122-5190009	PAVED SHLD, PCC, 9"	789 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	1,055 SY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	22,780 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 30-0861-010

Proposed Contract Period: Specified Start Date of 04/01/13 with 5 WORK DAYS

Proposal Note:

*** WORKING DAYS ***

THE WORKING DAYS ARE INTENDED FOR COMPLETION OF CONTRACT
ITEMS/CLEAN UP THAT DOES NOT REQUIRE THE DETOUR.

*** INCENTIVE/DISINCENTIVE - SITE 01 ***

SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR
INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL
APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:
CALENDAR/CLOSURE DAYS: 235
MAXIMUM INCENTIVE: \$450,000.00
INCENTIVE RATE PER DAY: \$15,000.00
DISINCENTIVE/LIQUIDATED DAMAGES RATE PER DAY: \$15,000.00
THE CRITICAL CLOSURE ACTIVITY INCLUDES COMPLETION OF ALL
CONTRACT ITEMS THAT REQUIRE THE DETOUR. THE
INCENTIVE/DISINCENTIVE/LIQUIDATED DAMAGES AMOUNT WILL BE
PAID/COLLECTED BY THE CONTRACTING AUTHORITY UPON COMPLETION
OF THE CRITICAL CLOSURE ACTIVITY.

Project(s):

Project No: HSIPX-086-1(8)--3L-30

County: DICKINSON

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: IOWA 86 Length: 1.24 miles

Location: FROM 1 MILE S. TO JUST N. OF MINNESOTA STATE LINE

Project No: STP-086-1(10)--2C-30

County: DICKINSON

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: IOWA 86 Length: 3.88 miles

Location: IA 86 FROM IA. 9 N. TO THE RELOC. CURVES JUST S. OF
MINNESOTA STATE LINE

Project No: HSIPX-086-1(14)--3L-30

County: DICKINSON

Type of Work: TRAFFIC SIGNS

Route: IOWA 86 Length: 0.00 miles

Location: FROM 1 MILE S. TO JUST N. OF MINNESOTA STATE LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	86,785 CY
2108-5025000	OVERHAUL	4,083,521 ST-Y
2301-1003095	STD/S-F PCC PAV'T, QM-C CL 3, 9.5"	29,368 SY
SECTION NO. 0004		
ALTERNATE 'BB' OPTION 1: PCC PAVED SHOULDER		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN-(008)

2122-5190006 PAVED SHLD, PCC, 6" 4,766 SY

SECTION NO. 0007

ROADWAY ITEMS - STP-086-1(010)--2C-30

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 267,731 CY

2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 10 CY

2108-5025000 OVERHAUL 4,271,962 ST-Y

2122-5190007 PAVED SHLD, PCC, 7" 1,645 SY

2301-1003095 STD/S-F PCC PAV'T, QM-C CL 3, 9.5" 64,493 SY

SECTION NO. 0010

ALTERNATE 'DD' OPTION 1: PCC PAVED SHOULDER

BID THIS SECTION IF ALTERNATE 'DD' OPTION 1 IS CHOSEN-(010)

2122-5190006 PAVED SHLD, PCC, 6" 17,389 SY

SECTION NO. 0013

INCENTIVE/DISINCENTIVE ITEM FOR CONTRACT

2528-5160100 CRITICAL CLOSURE ACTIVITY I/D 30 CDAY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 49-C049-056

Proposed Contract Period: Late Start Date of 08/26/13 with 35 WORK DAYS

Project(s):

Project No: FM-C049(56)--55-49

County: JACKSON

Type of Work: PCC PAVEMENT - NEW

Route: D53 Length: 3.70 miles

Location: ST. DONATUS CITY LIMITS TO 253RD AVENUE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	49,803 SY
2303-0013500	HMA (100K ESAL) B-I-S, 1/2", NO FRIC	596 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 53-C053-068

Proposed Contract Period: Late Start Date of 07/22/13 with 60 WORK DAYS

Project(s):

Project No: FM-C053(68)--55-53

County: JONES

Type of Work: PCC OVERLAY - UNBONDED

Route: X28 Length: 0.68 miles

Location: FROM THE WAPSIPINICON RIVER BRIDGE NORTHEASTERLY TO THE
PCC TIE-IN ON E28

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	2,454 CY
2122-5190008	PAVED SHLD, PCC, 8"	6,918 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	1,754 SY
2310-5151040	PCC OVERLAY, FURN ONLY	1,372 CY
2310-5151251	PCC OVERLAY PLACE ONLY (UNBONDED)	7,160 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,596 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	54 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 69-6360-616

Proposed Contract Period: Late Start Date of 10/07/13 with 20 WORK DAYS

Project(s):

Project No: STP-E-6360(616)--8V-69

County: MONTGOMERY

Type of Work: PCC SIDEWALK/TRAIL

Route: TRAIL Length: 0.34 miles

Location: IN THE CITY OF RED OAK, FROM 4TH ST TO 8TH ST ALONG US HWY
34 ROW & SE CORNER EVERGREEN CONN. TO INMAN DR & MILLER AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	1,900 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	12 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 75-0752-080

Proposed Contract Period: Specified Start Date of 04/01/13 with 5 WORK DAYS

Proposal Note:

*** WORKING DAYS ***

THE WORKING DAYS ARE INTENDED FOR COMPLETION OF CONTRACT
ITEMS/CLEAN UP THAT DOES NOT REQUIRE TRAFFIC TO BE IMPACTED.

*** WORK RESTRICTION ***

THE CONTRACTOR WILL NOT HAVE ACCESS TO THE BUILDINGS ON
PARCELS 7 AND 11 FOR DEMOLITION UNTIL MAY 1, 2013.

*** INCENTIVE/DISINCENTIVE, SITE NUMBER 01 AND 02***

SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR
INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL
APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:

SITE NUMBER 01:

CALENDAR/CLOSURE DAYS: 235

MAXIMUM INCENTIVE: NONE

INCENTIVE RATE PER DAY: \$2,500.00

DISINCENTIVE/LIQUIDATED DAMAGES RATE PER DAY: \$2,500.00

THE CRITICAL CLOSURE ACTIVITY INCLUDES COMPLETION OF ALL
CONTRACT ITEMS THAT REQUIRE TRAFFIC CONTROL STAGES 1 THROUGH
5 AS SHOWN ON PLAN SHEET J.1. THE

INCENTIVE/DISINCENTIVE/LIQUIDATED DAMAGES AMOUNT WILL BE
PAID/COLLECTED BY THE CONTRACTING AUTHORITY UPON COMPLETION
OF THE CRITICAL CLOSURE ACTIVITY.

SITE NUMBER 02:

CALENDAR/CLOSURE DAYS: 28

MAXIMUM INCENTIVE: NONE

INCENTIVE RATE PER DAY: \$2,000.00

DISINCENTIVE/LIQUIDATED DAMAGES RATE PER DAY: \$2,000.00

THE CRITICAL CLOSURE ACTIVITY INCLUDES COMPLETION OF ALL
CONTRACT ITEMS THAT REQUIRE TRAFFIC CONTROL STAGES 3B
THROUGH 4A AS SHOWN ON PLAN SHEET J.1. THE

INCENTIVE/DISINCENTIVE/LIQUIDATED DAMAGES AMOUNT WILL BE
PAID/COLLECTED BY THE CONTRACTING AUTHORITY UPON COMPLETION
OF THE CRITICAL CLOSURE ACTIVITY.

Project(s):

Project No: NHSN-075-2(80)--2R-75

County: PLYMOUTH

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: U.S. 75 Length: 0.70 miles

Location: IN MERRILL FROM BN/SF R.R. N. TO W. BRANCH FLOYD RIVER
BRIDGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	31,304 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001

ROADWAY ITEMS

2301-1034105	STD/S-F PCC PAV'T, CL C CL 3I, 10.5"	30,587 SY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	88 TON

SECTION NO. 0002

ALTERNATE 'AA' OPTION 1: PCC PAVED SHOULDERS

BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN

2122-5190007	PAVED SHLD, PCC, 7"	2,020 SY
--------------	---------------------	----------

SECTION NO. 0005

INCENTIVE/DISINCENTIVE ITEMS FOR CONTRACT

2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	30 CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	7 CDAY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 77-0354-167

Proposed Contract Period: Late Start Date of 04/01/13 with 160 WORK DAYS
Site 01: TO COMPLETE STAGE 1 GRADING WORK SHOWN ON SHEET J.2.
Late Start Date of 04/01/13 with 40 WORK DAYS
Site 02: TO COMPLETE STAGE 3A PAVING WORK SHOWN ON SHEET J.2.
No Start Date Specified with 40 WORK DAYS

Project(s):

Project No: IMX-035-4(154)100--02-77
County: POLK
Type of Work: TRAFFIC SIGNS
Route: I-35 Length: 0.00 miles
Location: REST AREA RELOCATION 3 MILES S. OF IA. 210 (NBL/SBL)

Project No: IMX-035-4(155)100--02-77
County: POLK
Type of Work: LIGHTING
Route: I-35 Length: 0.00 miles
Location: REST AREA RELOCATION 3 MILES S. OF IA. 210 (NBL/SBL)

Project No: IMX-035-4(167)100--02-77
County: POLK
Type of Work: PCC PAVEMENT - GRADE AND NEW
Route: I-35 Length: 3.73 miles
Location: REST AREA RELOCATION 3 MILES S. OF IA. 210 (NBL/SBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0003		
ROADWAY ITEMS		
IMX-035-4(167)100--02-77		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	221,475 CY
2301-1034085	STD/S-F PCC PAV'T, CL C CL 3I, 8.5"	6,772 SY
2301-1034105	STD/S-F PCC PAV'T, CL C CL 3I, 10.5"	57,460 SY
SECTION NO. 0004		
ALTERNATE 'AA' OPTION 1: PCC SHOULDERS		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (167)		
2122-5190007	PAVED SHLD, PCC, 7"	12,558 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 77-8500-025

Proposed Contract Period: Late Start Date of 08/19/13 with 40 WORK DAYS

Project(s):

Project No: NG-850-0(25)--7D-77

County: POLK

Type of Work: PCC PAVEMENT - NEW

Route: DES MOINES AVENUE Length: 0.00 miles

Location: CAMP DODGE IN JOHNSTON ON DES MOINES AVE. FROM
13TH ST. TO NW 90TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	7,292 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	18,767 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 110 Proposal ID: 91-0352-336

Proposed Contract Period: Late Start Date of 04/01/13 with 260 WORK DAYS

Site 01: TO COMPLETE STAGE 2B AS SHOWN ON SHEET J.02
No Start Date Specified with 10 WORK DAYS

Site 02: TO COMPLETE STAGE 2C AS SHOWN ON SHEET J.02
No Start Date Specified with 10 WORK DAYS

Proposal Note:

SITE 02

STAGE 2C SHALL BEGIN SOON AFTER COMPLETION OF STAGE 2B AS
SHOWN OF SHEET J.02 OF IM-035-2(336)65--13-91.

Project(s):

Project No: BRFIM-035-2(276)65--05-91
County: WARREN
Type of Work: BRIDGE REPLACEMENT - PPCB
Route: I-35 Length: 0.00 miles
Location: CO. RD. G-14 (CUMMINGS) INTERCHANGE
2 MILES S. OF POLK CO. LINE

Project No: IMN-035-2(332)65--0E-91
County: WARREN
Type of Work: TRAFFIC SIGNS
Route: I-35 Length: 0.00 miles
Location: I-35 FROM 0.5 MILE S. OF CO. RD. G-14(CUMMING) N. TO
IA. 5

Project No: IMN-035-2(333)65--0E-91
County: WARREN
Type of Work: LIGHTING
Route: I-35 Length: 0.00 miles
Location: CO. RD. G-14 (CUMMING) INTERCHANGE

Project No: IM-035-2(336)65--13-91
County: WARREN
Type of Work: PCC PAVEMENT - GRADE AND NEW
Route: I-35 Length: 5.95 miles
Location: FROM 1.6 MILE S. OF CO. RD. G-14(CUMMING) N. TO
IA. 5 (SBL)

Project No: BRFIM-035-2(356)63--05-91
County: WARREN
Type of Work: BRIDGE REPLACEMENT - PPCB
Route: I-35 Length: 0.00 miles
Location: OVER BADGER CREEK 3.8 MILES S. OF POLK CO. LINE(SBL)

Project No: IM-035-2(357)63--13-91
County: WARREN
Type of Work: GRADING
Route: I-35 Length: 0.00 miles
Location: OVER BADGER CREEK 3.8 MILES S. OF POLK CO. LINE (SBL)

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0112; A 341'-0 X 60'-0 PRETENSIONED PRESTRESSED		
CONCRETE BEAM BRIDGE - BRFIM-035-2(276)65--05-91		
2403-0100010	STRUCT CONC (BRIDGE)	1,073 CY
2404-7775000	REINFORC STEEL	95,197 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	206,917 LB
SECTION NO. 0003		
TRAFFIC SIGNS AND DELINEATORS - IMN-035-2(332)65--0E-91		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	73 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	11,612 LB
SECTION NO. 0005		
ROADWAY ITEMS - IM-035-2(336)65--13-91		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,169,834 CY
2122-5190007	PAVED SHLD, PCC, 7"	7,765 SY
2301-1003090	STD/S-F PCC PAV'T, QM-C CL 3, 9"	15,703 SY
2301-1003115	STD/S-F PCC PAV'T, QM-C CL 3, 11.5"	225,385 SY
SECTION NO. 0009		
DESIGN NO. 0412; A 299'-0 X 60'-0 PRETENSIONED PRESTRESSED		
CONCRETE BEAM BRIDGE - BRFIM-035-2(356)63--05-91		
2403-0100010	STRUCT CONC (BRIDGE)	471 CY
2404-7775000	REINFORC STEEL	67,294 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	185,181 LB
SECTION NO. 0011		
ROADWAY ITEMS - IM-035-2(357)63--13-91		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	276,242 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 111 Proposal ID: 97-C097-117

Proposed Contract Period: Late Start Date of 08/26/13 with 30 WORK DAYS

Project(s):

Project No: STP-S-C097(117)--5E-97

County: WOODBURY

Type of Work: PCC OVERLAY - UNBONDED

Route: D54 Length: 4.57 miles

Location: COUNTY ROAD L27 TO DANBURY

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2301-1032090	STD/S-F PCC PAV'T, CL C CL 2, 9"	293 SY
2301-1082090	STD/S-F PCC PAV'T, CL M CL 2, 9"	113 SY
2310-5151040	PCC OVERLAY, FURN ONLY	9,881 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	59,286 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 112 Proposal ID: 97-C097-118

Proposed Contract Period: Late Start Date of 08/12/13 with 45 WORK DAYS

Project(s):

Project No: FM-C097(118)--55-97

County: WOODBURY

Type of Work: PCC PAVEMENT - REPLACE

Route: D51

Length: 3.50 miles

Location: K45 TO K42

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	11,366 CY
2301-1033000	STD/S-F PCC PAV'T, CL C CL 3, VAR THICK	52,867 SY
2301-1083090	STD/S-F PCC PAV'T, CL M CL 3, 9"	672 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 03-C003-052

Proposed Contract Period: Late Start Date of 05/13/13 with 85 WORK DAYS

Project(s):

Project No: STP-S-C003(52)--5E-03

County: ALLAMAKEE

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: X52 Length: 6.20 miles

Location: B-25 INTERSECTION TO IA 76 SOUTH

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	25,545 CY
2122-5190008	PAVED SHLD, PCC, 8"	482 SY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	15,800 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	13,300 TON
2403-0100000	STRUCT CONC (MISCELLANEOUS)	61 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	115 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 06-C006-076-A

Proposed Contract Period: Late Start Date of 08/19/13 with 40 WORK DAYS

Project(s):

Project No: HRRR-C006(76)--5R-06

County: BENTON

Type of Work: HMA PAVEMENT - GRADE AND REPLACE

Route: W28 Length: 1.75 miles

Location: FROM HWY 30 TO ATKINS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	11,025 CY
2303-0021500	HMA (300K ESAL) BASE, 1/2"	1,039 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	1,072 TON
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 08-C008-060

Proposed Contract Period: Late Start Date of 09/09/13 with 25 WORK DAYS

Project(s):

Project No: L-61--73-08
County: BOONE
Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
Route: 330TH STREET Length: 0.50 miles
Location: P-54 E 0.5 MI TO PERRY GOLF CLUB

Project No: FM-C008(60)--55-08
County: BOONE
Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
Route: P54 Length: 4.49 miles
Location: FROM E-57 SOUTH 4.5 MILES TO HWY 144

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
L-61--73-08		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	1,201 TON
SECTION NO. 0002		
ROADWAY ITEMS		
FM-C008(60)--55-08		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	10,479 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 12-C012-082

Proposed Contract Period: Late Start Date of 09/09/13 with 35 WORK DAYS

Project(s):

Project No: STP-S-C012(82)--5E-12

County: BUTLER

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: C33 Length: 7.32 miles

Location: HWY 14 TO CLARKSVILLE WCL

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	18,250 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 23-C023-093

Proposed Contract Period: Late Start Date of 08/26/13 with 20 WORK DAYS

Project(s):

Project No: STP-S-C023(93)--5E-23

County: CLINTON

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: Y44 Length: 4.92 miles

Location: FROM E-63 TO U.S.30

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0021500	HMA (300K ESAL) BASE, 1/2"	5,736 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	6,507 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 23-1040-604

Proposed Contract Period: Late Start Date of 09/30/13 with 15 WORK DAYS

Project(s):

Project No: STP-U-1040(604)--70-23
County: CLINTON
Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING
Route: 3RD STREET Length: 0.61 miles
Location: IN THE CITY OF CAMANCHE
FROM 4TH AVENUE TO 13TH AVENUE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	511 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 24-0302-156

Proposed Contract Period: Late Start Date of 10/07/13 with 10 WORK DAYS

Project(s):

Project No: NHSN-030-2(156)--2R-24
County: CRAWFORD
Type of Work: HMA PAVED SHOULDER - NEW
Route: U.S. 30 Length: 1.39 miles
Location: FROM DENISON TO GLIDDEN(VARIOUS LOCATIONS)

Project No: STPN-039-1(25)--2J-24
County: CRAWFORD
Type of Work: HMA PAVED SHOULDER - NEW
Route: IOWA 39 Length: 0.32 miles
Location: FROM BUFFALO AVE. TO N. OF VERNON VOSS RD.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 28-0208-049

Proposed Contract Period: Late Start Date of 05/13/13 with 115 WORK DAYS

Project(s):

Project No: NHSX-020-8(49)--3H-28

County: DELAWARE

Type of Work: HMA RESURFACING

Route: U.S. 20

Length: 16.61 miles

Location: FROM DELAWARE E. TO FARLEY(WBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	27,385 TON
2303-0053502	HMA (10M ESAL) SURF, 1/2", FRIC L-2	28,333 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 49-4742-617

Proposed Contract Period: Late Start Date of 07/29/13 with 55 WORK DAYS

Project(s):

Project No: STP-U-4742(617)--70-49

County: JACKSON

Type of Work: HMA RESURFACING WITH MILLING

Route: S. MATTESON ST. Length: 0.29 miles

Location: IN THE CITY OF MAQUOKETA
FROM E MAPLE ST TO E SUMMIT ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	796 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	168 TON
2303-0021500	HMA (300K ESAL) BASE, 1/2"	225 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	544 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 57-0131-056

Proposed Contract Period: Late Start Date of 09/30/13 with 10 WORK DAYS

Project(s):

Project No: NHSN-013-1(56)--2R-57

County: LINN

Type of Work: HMA PAVED SHOULDER - NEW

Route: IOWA 13 Length: 2.80 miles

Location: FROM COGGON TO NEAR THE DELAWARE CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 61-C061-093

Proposed Contract Period: Late Start Date of 06/03/13 with 75 WORK DAYS

Project(s):

Project No: FM-C061(93)--55-61

County: MADISON

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: G68 Length: 11.69 miles

Location: SW COR 31-75-27 TO E1/2 COR 16-74-26

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0031750	HMA (1M ESAL) BASE, 3/4"	13,755 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	12,609 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 84-0181-072

Proposed Contract Period: Late Start Date of 07/08/13 with 60 WORK DAYS

Project(s):

Project No: NHSX-018-1(72)--3H-84

County: SIOUX

Type of Work: PCC PAVEMENT WIDENING / HMA RESURFACING

Route: U.S. 18 Length: 0.52 miles

Location: FROM 0.3 MILE E. OF CO. RD. K-24 E. TO 0.6 MILE W. OF
CO. RD. K-30 IN ROCK VALLEY

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	30,529 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	1,476 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	1,466 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 163 Proposal ID: 89-C089-078

Proposed Contract Period: Late Start Date of 07/22/13 with 40 WORK DAYS

Project(s):

Project No: FM-C089(78)--55-89
County: VAN BUREN
Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
Route: J40 Length: 3.50 miles
Location: J 40 FROM LEE COUNTY LINE TO W 40

Project No: FM-C089(80)--55-89
County: VAN BUREN
Type of Work: HMA RESURFACING
Route: J40 Length: 1.00 miles
Location: FROM NEAR W 1/4 CORNER SEC 8 TO
BONAPARTE CITY LIMITS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		FM-C089(78)--55-89
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	3,856 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	3,722 TON
SECTION NO. 0002		
ROADWAY ITEMS		
		FM-C089(80)--55-89
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	1,260 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 164 Proposal ID: 89-0025-703

Proposed Contract Period: Late Start Date of 10/07/13 with 15 WORK DAYS

Project(s):

Project No: MP-002-5(703)219--76-89

County: VAN BUREN

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 2 Length: 6.64 miles

Location: FROM CANTRIL TO THE JCT. OF IOWA 1.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	1,293 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	1,280 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 13-0043-707

Proposed Contract Period: Late Start Date of 04/01/13 with 60 WORK DAYS

Project(s):

Project No: MP-004-3(707)49--76-13

County: CALHOUN

Type of Work: TRANSVERSE JOINT REPAIR

Route: IOWA 4 Length: 15.10 miles

Location: FROM LOHRVILLE TO THE W. JCT. OF D-36.

Project No: MP-007-3(703)50--76-13

County: CALHOUN

Type of Work: HMA CRACK FILLING

Route: IOWA 7 Length: 12.73 miles

Location: FROM S. JCT. OF IOWA 4 TO JUST EAST OF WEBSTER COUNTY LINE.

Project No: MP-175-3(702)87--76-81

County: SAC

Type of Work: TRANSVERSE JOINT REPAIR

Route: IOWA 175 Length: 12.11 miles

Location: FROM THE E. JCT. OF U.S. 71 TO THE W. JCT. OF IOWA 4.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 17-0352-719

Proposed Contract Period: Late Start Date of 05/13/13 with 30 WORK DAYS

Project(s):

Project No: MPIN-035-2(719)185--0N-17

County: CERRO GORDO

Type of Work: MICROSURFACING

Route: I-35 Length: 7.51 miles

Location: FROM 3 MILES NORTH OF B-60 NORTH TO 1.1 MILES NORTH OF
B-35.

Project No: MPIN-035-2(716)175--0N-35

County: FRANKLIN

Type of Work: MICROSURFACING

Route: I-35 Length: 2.80 miles

Location: FROM 0.3 MILES NORTH OF C-23 TO THE CERRO GORDO
COUNTY LINE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 17-0352-720

Proposed Contract Period: Late Start Date of 04/01/13 with 45 WORK DAYS

Project(s):

Project No: MPIN-035-2(720)197--0N-17

County: CERRO GORDO

Type of Work: HMA CRACK FILLING

Route: I-35 Length: 9.19 miles

Location: FROM 0.67 MI. S. OF B-20 NORTH TO 1.8 MILES NORTH OF
ROAD105. VARIOUS LOCATIONS.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 20-0345-704

Proposed Contract Period: Late Start Date of 09/30/13 with 30 WORK DAYS

Project(s):

Project No: MP-034-5(704)118--76-20

County: CLARKE

Type of Work: HMA CRACK FILLING

Route: U.S. 34 Length: 10.08 miles

Location: FROM THE ECL OF OSCEOLA TO THE LUCAS COUNTY LINE.

Project No: MP-063-5(707)64--76-62

County: MAHASKA

Type of Work: HMA CRACK FILLING

Route: U.S. 63 Length: 2.57 miles

Location: FROM 2ND AVENUE IN OSKALOOSA TO JUST SOUTH OF THE
UNION PACIFIC RAILROAD BRIDGE.

Project No: MP-092-5(705)179--76-62

County: MAHASKA

Type of Work: HMA CRACK FILLING

Route: IOWA 92 Length: 3.23 miles

Location: IN THE CITY OF OSKALOOSA, FROM WCL TO ECL.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 22-1803

Proposed Contract Period: Late Start Date of 08/26/13 with 10 WORK DAYS

Project(s):

Project No: L-1803--73-22

County: CLAYTON

Type of Work: SEAL COAT

Route: JOLLY RIDGE ROAD Length: 2.52 miles

Location: FROM OSTERDOCK ROAD TO US HWY 52

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 27-0351-127

Proposed Contract Period: Late Start Date of 10/07/13 with 20 WORK DAYS

Project(s):

Project No: IMN-035-1(127)0--0E-27

County: DECATUR

Type of Work: PCC PATCHING

Route: I-35 Length: 0.00 miles

Location: I-35 FROM MISSOURI STATE LINE N. TO W. I-35/80/235
INTERCHANGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,942 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	202 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 34-C034-088

Proposed Contract Period: Late Start Date of 07/01/13 with 70 WORK DAYS

Project(s):

Project No: FM-C034(88)--55-34

County: FLOYD

Type of Work: PCC PATCHING

Route: T66

Length: 5.60 miles

Location: 155TH STREET(B33) TO 210TH STREET(B57)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	3,817 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	459 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 43-0295-216

Proposed Contract Period: Late Start Date of 09/09/13 with 25 WORK DAYS

Project(s):

Project No: IMN-029-5(216)72--0E-43

County: HARRISON

Type of Work: PCC PATCHING

Route: I-29 Length: 0.00 miles

Location: I-29 FROM POTTAWATTAMIE CO. LINE N. TO SOUTH DAKOTA
STATE LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,778 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	137 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 209 Proposal ID: 48-0806-713

Proposed Contract Period: Late Start Date of 06/10/13 with 50 WORK DAYS

Project(s):

Project No: MPIN-080-6(713)205--0N-48
County: IOWA
Type of Work: HMA PAVED SHOULDER - FOG SEAL
Route: I-80 Length: 21.13 miles
Location: FROM POWESHIEK COUNTY LINE TO 1 MI. EAST OF U.S. 151.

Project No: MPIN-080-6(706)248--0N-52
County: JOHNSON
Type of Work: HMA PAVED SHOULDER - FOG SEAL
Route: I-80 Length: 9.76 miles
Location: FROM JUST E. OF IOWA CITY EAST TO 3 MI. E. OF WEST BRANCH.

Project No: MPIN-074-6(707)0--0N-82
County: SCOTT
Type of Work: HMA PAVED SHOULDER - FOG SEAL
Route: I-74 Length: 5.36 miles
Location: FROM I-80 SOUTHEASTERLY TO ILLINOIS STATE LINE.

Project No: MPIN-080-6(708)278--0N-82
County: SCOTT
Type of Work: HMA PAVED SHOULDER - FOG SEAL
Route: I-80 Length: 28.63 miles
Location: FROM CEDAR COUNTY LINE EASTERLY TO ILLINOIS STATE LINE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 210 Proposal ID: 49-0526-708

Proposed Contract Period: Late Start Date of 04/01/13 with 65 WORK DAYS

Project(s):

Project No: MP-030-6(705)234--76-06

County: BENTON

Type of Work: HMA CRACK FILLING

Route: U.S. 30 Length: 11.64 miles

Location: FROM U.S. 218 E. TO MORGAN CREEK.

Project No: MP-032-6(703)0--76-31

County: DUBUQUE

Type of Work: HMA CRACK FILLING

Route: IOWA 32 Length: 3.13 miles

Location: IN THE CITY OF DUBUQUE FROM U.S. 20 TO JFK ROAD(SBL).

Project No: MP-052-6(708)23--76-49

County: JACKSON

Type of Work: HMA CRACK FILLING

Route: U.S. 52 Length: 12.65 miles

Location: FROM JEFFERSON STREET IN BELLEVUE TO THE DUBUQUE COUNTY LINE

Project No: MP-062-6(702)19--76-49

County: JACKSON

Type of Work: HMA CRACK FILLING

Route: IOWA 62 Length: 0.87 miles

Location: IN THE CITY OF BELLEVUE, FROM THE WCL TO U.S. 52.

Project No: MP-006-6(725)247--76-52

County: JOHNSON

Type of Work: HMA CRACK FILLING

Route: U.S. 6 Length: 2.92 miles

Location: FROM 0.5 MILE EAST OF IOWA 965, EASTERLY TO EAST OF HAWKINS DRIVE.

Project No: MP-038-6(715)65--76-53

County: JONES

Type of Work: HMA CRACK FILLING

Route: IOWA 38 Length: 21.29 miles

Location: FROM MONTICELLO NORTHERLY TO 0.5 MILE N. OF DELAWARE
(VARIOUS LOCATIONS)

Project No: MP-064-6(707)0--76-53

County: JONES

Type of Work: HMA CRACK FILLING

Route: IOWA 64 Length: 10.07 miles

Location: FROM U.S. 151 EASTERLY TO THE EAST JCT. OF IOWA 38.

Project No: MP-151-6(714)38--76-57

County: LINN

Type of Work: HMA CRACK FILLING

Route: U.S. 151 Length: 11.41 miles

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Location: FROM IOWA 13 NORTHEASTERLY TO IOWA 1. (VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 211 Proposal ID: 60-0093-705

Proposed Contract Period: Late Start Date of 04/01/13 with 65 WORK DAYS

Project(s):

Project No: MP-009-3(705)18--76-60
County: LYON
Type of Work: HMA CRACK FILLING
Route: IOWA 9 Length: 22.97 miles
Location: FROM 0.6 MI. W. OF U.S. 75 TO U.S. 75 & FROM 0.37 MI. W. OF
THE ECL OF ROCK RAPIDS TO THE JCT. OF IOWA 60.

Project No: MP-075-3(700)163--76-60
County: LYON
Type of Work: HMA CRACK FILLING
Route: U.S. 75 Length: 5.67 miles
Location: FROM BUNCOMBE DR. IN ROCK RAPIDS, WEST AND NORTH TO THE
MINNESOTA STATE LINE.

Project No: MP-003-3(708)28--76-75
County: PLYMOUTH
Type of Work: HMA CRACK FILLING
Route: IOWA 3 Length: 16.44 miles
Location: FROM THE JCT. OF IA 404 IN LE MARS, EAST TO THE CHEROKEE
COUNTY LINE.

Project No: MP-010-3(704)20--76-84
County: SIOUX
Type of Work: HMA CRACK FILLING
Route: IOWA 10 Length: 9.00 miles
Location: FROM THE JCT. OF U.S. 75, EAST TO THE JCT. OF IOWA 60.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 212 Proposal ID: 74-0043-706

Proposed Contract Period: Late Start Date of 04/01/13 with 60 WORK DAYS

Project(s):

Project No: MP-018-3(711)78--76-21
County: CLAY
Type of Work: HMA CRACK FILLING
Route: U.S. 18 Length: 4.02 miles
Location: FROM THE N. JCT. OF US 71 TO NEAR 2ND AVE. SE IN THE CITY
OF SPENCER.

Project No: MP-004-3(706)138--76-32
County: EMMET
Type of Work: HMA CRACK FILLING
Route: IOWA 4 Length: 1.67 miles
Location: FROM THE JCT. OF IOWA 9 TO NCL OF ESTHERVILLE.

Project No: MP-009-3(707)87--76-32
County: EMMET
Type of Work: HMA CRACK FILLING
Route: IOWA 9 Length: 3.19 miles
Location: IN THE CITY OF ESTHERVILLE, FROM THE WCL TO ECL.

Project No: MP-015-3(703)21--76-55
County: KOSSUTH
Type of Work: HMA CRACK FILLING
Route: IOWA 15 Length: 8.78 miles
Location: FROM UP RAILROAD IN WEST BEND TO THE WEST JCT. OF U.S. 18.

Project No: MP-004-3(706)118--76-74
County: PALO ALTO
Type of Work: HMA CRACK FILLING
Route: IOWA 4 Length: 18.66 miles
Location: FROM THE JCT. OF U.S. 18 TO ESTHERVILLE.

Project No: MP-018-3(704)96--76-74
County: PALO ALTO
Type of Work: HMA CRACK FILLING
Route: U.S. 18 Length: 9.60 miles
Location: FROM EAST OF RUTHVEN TO EMMETSBURG.

Project No: MP-004-3(704)93--76-76
County: POCAHONTAS
Type of Work: HMA CRACK FILLING
Route: IOWA 4 Length: 5.74 miles
Location: FROM THE JCT. OF IOWA 10 NORTH TO PALO ALTO COUNTY LINE.

Project No: MP-015-3(709)7--76-76
County: POCAHONTAS
Type of Work: HMA CRACK FILLING
Route: IOWA 15 Length: 10.10 miles
Location: FROM ROLFE NORTH & EAST TO THE JCT. OF C-20/P-19.

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 213 Proposal ID: 77-0691-710

Proposed Contract Period: Late Start Date of 10/07/13 with 10 WORK DAYS

Project(s):

Project No: MP-069-1(710)95--76-77

County: POLK

Type of Work: PAVEMENT PLANING/GROOVING

Route: U.S. 69 Length: 1.00 miles

Location: IN THE CITY OF ANKENY, FROM 1ST STREET TO 18TH STREET.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	144 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	18 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 214 Proposal ID: 79-0061-707

Proposed Contract Period: Late Start Date of 08/26/13 with 40 WORK DAYS

Project(s):

Project No: MP-006-1(707)186--76-79

County: POWESHIEK

Type of Work: HMA PATCHING

Route: U.S. 6 Length: 1.50 miles

Location: IN THE CITY OF GRINNELL FROM THE WCL TO THE BEGINNING OF THE
4-LANE SECTION.

Project No: MP-146-1(707)18--76-79

County: POWESHIEK

Type of Work: HMA PATCHING

Route: IOWA 146 Length: 5.00 miles

Location: IN GRINNELL FROM NEAR I-80 TO 1.3 MI. NORTH OF GRINNELL.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
MP-6-1(707)186--76-79		
2303-0143504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	3,505 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	340 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	29 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
MP-146-1(707)18--76-79		
2303-0143504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	1,757 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	941 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	91 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 215 Proposal ID: 82-0741-176

Proposed Contract Period: Late Start Date of 07/29/13 with 50 WORK DAYS

Project(s):

Project No: IMN-080-7(93)254--0E-16
County: CEDAR
Type of Work: PCC PATCHING
Route: I-80 Length: 24.52 miles
Location: FROM JOHNSON CO. LINE E. TO SCOTT CO. LINE

Project No: IMN-074-1(176)0--0E-82
County: SCOTT
Type of Work: PCC PATCHING
Route: I-74 Length: 5.36 miles
Location: FROM I-80 SOUTH TO MISSISSIPPI RIVER

Project No: IMN-080-8(255)278--0E-82
County: SCOTT
Type of Work: PCC PATCHING
Route: I-80 Length: 28.63 miles
Location: FROM CEDAR COUNTY LINE EAST TO MISSISSIPPI RIVER

Project No: IMN-280-8(145)0--0E-82
County: SCOTT
Type of Work: PCC PATCHING
Route: I-280 Length: 9.70 miles
Location: FROM I-80 SOUTH TO MISSISSIPPI RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
IMN-80-7(93)254--0E-16		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	491 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	35 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
IMN-74-1(176)0--0E-82		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	967 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(>=50 FT)	153 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	81 EACH
SECTION NO. 0003		
ROADWAY ITEMS		
IMN-80-8(255)278--0E-82		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	901 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(>=50 FT)	395 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	93 EACH
SECTION NO. 0004		
ROADWAY ITEMS		
IMN-280-8(145)0--0E-82		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0004

ROADWAY ITEMS

IMN-280-8(145)0--0E-82

2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	734 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	73 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	59 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 07-0582-500

Proposed Contract Period: Late Start Date of 05/13/13 with 30 WORK DAYS

Project(s):

Project No: MB-058-2(500)5--77-07

County: BLACK HAWK

Type of Work: SLOPE PROTECTION

Route: IOWA 58

Length: 0.00 miles

Location: OVER U.S. 20

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 17-0352-505

Proposed Contract Period: Late Start Date of 05/13/13 with 30 WORK DAYS

Project(s):

Project No: MBIN-035-2(505)183--0M-17

County: CERRO GORDO

Type of Work: SLOPE PROTECTION

Route: I-35 Length: 0.00 miles

Location: 5.1 MILES NORTH OF FRANKLIN CO. LINE

Project No: MBIN-035-2(507)174--0M-35

County: FRANKLIN

Type of Work: SLOPE PROTECTION

Route: I-35 Length: 0.00 miles

Location: 2 MILES S. OF C-13

Project No: MBIN-035-2(505)209--0M-98

County: WORTH

Type of Work: SLOPE PROTECTION

Route: I-35 Length: 0.00 miles

Location: 4.8 MILES NORTH OF IOWA 9

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 24-C024-100

Proposed Contract Period: Late Start Date of 06/17/13 with 25 WORK DAYS

Project(s):

Project No: FM-C024(100)--55-24

County: CRAWFORD

Type of Work: PIPE CULVERTS

Route: E46 Length: 0.00 miles

Location: OVER UNNAMED TRIBUTARY TO PARADISE CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,069 CY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	17 CY
2404-7775000	REINFORC STEEL	1,237 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 40-0351-502

Proposed Contract Period: Late Start Date of 05/13/13 with 30 WORK DAYS

Project(s):

Project No: MBIN-035-1(502)144--0M-40

County: HAMILTON

Type of Work: SLOPE PROTECTION

Route: I-35

Length: 0.00 miles

Location: OVER D-25

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 63-0053-065

Proposed Contract Period: Late Start Date of 10/21/13 with 10 WORK DAYS

Project(s):

Project No: NHSN-005-3(65)--2R-63

County: MARION

Type of Work: PIPE CULVERTS

Route: IOWA 5 Length: 0.00 miles

Location: APPROX. 3 MILES W. OF KNOXVILLE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 306 Proposal ID: 73-C073-117

Proposed Contract Period: Late Start Date of 04/15/13 with 15 WORK DAYS

Project(s):

Project No: FM-C073(117)--55-73

County: PAGE

Type of Work: GRANULAR SURFACING OF ROADWAY

Route: VARIOUS LOCATIONS Length: 60.00 miles

Location: ROCK HAUL ON FARM-TO-MARKET ROADS

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-547

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE DIVISION 1- STANDARD TIME FRAME
Late Start Date of 07/31/13 with 20 WORK DAYS

Site 02: TO COMPLETE DIVISION 2 - ACCELERATED TIME FRAME
Late Start Date of 03/29/13 with 20 WORK DAYS

Project(s):

Project No: NHSN-000-S(547)--2R-00

County: STATEWIDE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 19-C019-081

Proposed Contract Period: Late Start Date of 09/09/13 with 40 WORK DAYS

Project(s):

Project No: FM-C019(81)--55-19

County: CHICKASAW

Type of Work: PAVEMENT MARKINGS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS HARD SURFACED ROADS

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 52-0806-281

Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS

Project(s):

Project No: IM-080-6(281)244--13-52

County: JOHNSON

Type of Work: BARRIER RAIL

Route: I-80 Length: 7.90 miles

Location: FROM JUST E. OF I-380 E. TO 1.5 MILES E. OF IA.1

Item No.	Item Description	Quantity/Unit
SECTION NO. 0002		
DESIGN NO. 0213; 570'-0 X 56'-0 CONTINUOUS WELDED PLATE		
GIRDER BRIDGE (EASTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	5,208 LB
SECTION NO. 0003		
DESIGN NO. 0313; 562'-0 X 66'-0 CONTINUOUS WELDED PLATE		
GIRDER BRIDGE (WESTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	6,788 LB
SECTION NO. 0004		
DESIGN NO. 0413; DUAL 223'-9 X VARIABLE PRETENSIONED		
PRESTRESSED CONCRETE BEAM BRIDGE (EASTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	7,011 LB
SECTION NO. 0005		
DESIGN NO. 0513; DUAL 223'-9 X VARIABLE PRETENSIONED		
PRESTRESSED CONCRETE BEAM BRIDGE (WESTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	7,011 LB
SECTION NO. 0006		
DESIGN NO. 0613; DUAL 169'-0 X 57'-3 CONTINUOUS I-BEAM		
BRIDGES (EASTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	5,641 LB
SECTION NO. 0007		
DESIGN NO. 0713; DUAL 169'-0 X 57'-3 CONTINUOUS I-BEAM		
BRIDGE (WESTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	5,641 LB
SECTION NO. 0008		
DESIGN NO. 0813; DUAL 427'-0 X 66'-0 3/4 CONTINUOUS WELDED		
GIRDER BRIDGE (EASTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	13,650 LB
SECTION NO. 0009		
DESIGN NO. 0913; DUAL 427'-0 X 66'-0 3/4 CONTINUOUS WELDED		
GIRDER BRIDGE (WESTBOUND)		
2404-7775005	REINFORC STEEL, EPOXY COATED	13,650 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 354 Proposal ID: 77-C077-165

Proposed Contract Period: Late Start Date of 09/30/13 with 20 WORK DAYS

Project(s):

Project No: HRRR-C077(165)--5R-77

County: POLK

Type of Work: TRAFFIC SIGNS

Route: SE 6TH AVE. Length: 0.15 miles

Location: IN POLK COUNTY AT INTERSECTION
OF SE 80TH ST.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 06-0306-202

Proposed Contract Period: Late Start Date of 03/25/13 with 20 WORK DAYS

Project(s):

Project No: NHSN-030-6(202)--2R-06

County: BENTON

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 30 Length: 0.00 miles

Location: 2132 73RD ST.(US 30), VAN HORNE
PARCEL NO. 64

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 402 Proposal ID: 78-0801-427

Proposed Contract Period: Approx Start Date of 03/25/13 with 50 WORK DAYS

Project(s):

Project No: IMN-080-1(427)3--0E-78

County: POTTAWATTAMIE

Type of Work: SALVAGE AND REMOVAL

Route: I-80 Length: 0.00 miles

Location: IN THE CITY OF COUNCIL BLUFFS AT 6 LOCATIONS
PARCEL # 308/315B/327A/327B/440/459

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 403 Proposal ID: 82-0741-236

Proposed Contract Period: Approx Start Date of 03/25/13 with 10 WORK DAYS

Project(s):

Project No: IMN-074-1(236)5--0E-82

County: SCOTT

Type of Work: SALVAGE AND REMOVAL

Route: I-74 Length: 0.00 miles

Location: IN THE CITY OF BETTENDORF AT 1430 GRANT ST.
PARCEL # 357

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 404 Proposal ID: 91-0054-074

Proposed Contract Period: Approx Start Date of 03/25/13 with 20 WORK DAYS

Project(s):

Project No: NHSN-005-4(74)--2R-91

County: WARREN

Type of Work: SALVAGE AND REMOVAL

Route: IOWA 5 Length: 1.91 miles

Location: 2463 SWAN IOWA PARCEL # 24S

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 30-0861-012

Proposed Contract Period: Late Start Date of 04/01/13 with 20 WORK DAYS

Project(s):

Project No: STPN-086-1(12)--2J-30

County: DICKINSON

Type of Work: WETLAND MITIGATION

Route: IOWA 86 Length: 0.00 miles

Location: LAGO-GUNDERSON SITE (LAGO #2 SITE)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,352 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 502 Proposal ID: 57-0307-169

Proposed Contract Period: Late Start Date of 10/14/13 with 15 WORK DAYS

Project(s):

Project No: NHSN-030-7(169)--2R-57

County: LINN

Type of Work: CLEARING AND GRUBBING

Route: U.S. 30 Length: 8.36 miles

Location: IN THE CITY OF CEDAR RAPIDS FROM 16TH AVE. INTERCHANGE E. TO
"C" ST. INTERCHANGE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 503 Proposal ID: NOTUSED; 13/02

Project(s):

Item No.	Item Description	Quantity/Unit

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 504 Proposal ID: NOTUSED; 13/02

Project(s):

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 505 Proposal ID: 77-0805-319

Proposed Contract Period: Late Start Date of 09/23/13 with 30 WORK DAYS

Project(s):

Project No: IMN-080-5(319)138--0E-77

County: POLK

Type of Work: CLEARING AND GRUBBING

Route: I-80 Length: 0.00 miles

Location: FROM I-35 E. TO THE CO. RD. V-38(VICTOR) INTERCHANGE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 506 Proposal ID: 78-6802-156

Proposed Contract Period: Late Start Date of 10/07/13 with 25 WORK DAYS

Project(s):

Project No: IMN-680-2(156)29--0E-78

County: POTTAWATTAMIE

Type of Work: CLEARING AND GRUBBING

Route: I-680 Length: 0.00 miles

Location: IA. 191 AND I-80 INTERCHANGES

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 507 Proposal ID: 84-0181-076

Proposed Contract Period: Late Start Date of 07/22/13 with 20 WORK DAYS

Project(s):

Project No: NHSN-018-1(76)--2R-84

County: SIOUX

Type of Work: WETLAND MITIGATION

Route: U.S. 18 Length: 0.00 miles

Location: ABMA II WETLAND MITIGATION SITE 1 MILE NE OF ROCK VALLEY

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 07-9342-500-A

Proposed Contract Period: Late Start Date of 07/15/13 with 40 WORK DAYS

Proposal Note:

. *** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***
THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS
AS SHOWN FOR THE FOLLOWING EXAMPLE:
. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.90{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE
FOLLOWING BRIDGES:

0704.7S934

Project(s):

Project No: MB-934-2(500)5--77-07
County: BLACK HAWK
Type of Work: BRIDGE PAINTING
Route: IOWA 934 Length: 0.00 miles
Location: OVER ABAND. R.R. 0.2 MILE W. OF U.S. 63

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 602 Proposal ID: 27-0355-509

Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS
AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.90{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE
FOLLOWING BRIDGES:

. 2708.80035

Project(s):

Project No: MBIN-035-5(509)9--0M-27

County: DECATUR

Type of Work: BRIDGE PAINTING

Route: I-35

Length: 0.00 miles

Location: J-48 OVER I-35

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 603 Proposal ID: 29-0349-198

Proposed Contract Period: Late Start Date of 05/13/13 with 15 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS
AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.90{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE
FOLLOWING BRIDGES:

. 2708.80035

Project(s):

Project No: BRFN-034-9(198)--39-29

County: DES MOINES

Type of Work: BRIDGE CLEANING

Route: U.S. 34 Length: 0.00 miles

Location: BURLINGTON INTERCHANGE AND THE MISSISSIPPI RIVER BRIDGE
BETWEEN BURLINGTON AND GULFPORT.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 981 Proposal ID: 63-1635-700

Proposed Contract Period: Late Start Date of 10/14/13 with 15 WORK DAYS

Project(s):

Project No: MP-063-5(708)55--76-62

County: MAHASKA

Type of Work: CLEARING AND GRUBBING

Route: U.S. 63 Length: 6.20 miles

Location: FROM JUST N. OF EDDYVILLE NORTH TO IOWA 163 S. OF OSKALOOSA

Project No: MP-163-5(700)38--76-63

County: MARION

Type of Work: CLEARING AND GRUBBING

Route: IOWA 163 Length: 5.30 miles

Location: FROM 2 MILES W. OF PELLA EAST TO U.S. 63 S. OF OSKALOOSA

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 19, 2013 10:00 A.M.

Proposed Bid Order: 982 Proposal ID: 68-0345-703

Proposed Contract Period: Late Start Date of 10/14/13 with 15 WORK DAYS

Project(s):

Project No: MP-034-5(703)169--76-68

County: MONROE

Type of Work: CLEARING AND GRUBBING

Route: U.S. 34 Length: 0.00 miles

Location: FROM JUST EAST OF ALBIA EAST TO THE WAPELLO CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

