

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 19, 2013
Date of Addendum: February 15, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
019	64-1464-026	RCB CULVERT NEW - TWIN BOX	MARSHALL	BRF-146-4(26)--38-64	19FEB019.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0051 2418-0000010 TEMPORARY STREAM DIVERSION; EACH 1.0

Change Proposal Line No. 0070 2102-2710070 EXCAVATION, CLASS 10 ROADWAY AND BORROW:

From: 8,439.000 CY
To: 6,258.000CY

Change Proposal Line No. 0110 2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD:

From: 5,345.000 CY
To: 5,637.000CY

If the above changes are not made, they will be made as shown here.

Make the following change to the Plans:

Make the following change to the Plan Sheet 3 STANDARD TAB:

ADD: STANDARD ROAD PLAN RL-20 Dated 10-16-12

ADD the following STANDARD NOTE to the Plan Sheet 3

281-1 10-18-11
SECTION 404 PERMIT AND CONDITIONS
Construct this project according to the requirements of U.S. Army Corps of Engineers NWP14, Permit No. 2013-1022. A copy of this permit is available from the Iowa DOT Office of Contracts upon request. The U.S. Army Corps of Engineers reserves the right to visit the site without prior notice.

Correction on plan sheet C.1

2102-2710070 Excavation, Class 10, Roadway and Borrow;

Change quantities in Estimate Reference Note:

Includes 5082 Cu. Yds. Of cut from ditching borrow. See sheets D.3 and D.4

Includes 786 Cu. Yds. from class 20 waste. See bridge sheets.

Correction on plan sheet C.5

Tab 103-4 (04-19-11) Topsoil Tab:

Amount reserved from Sta. 295+00 to 299+37 changed to 1631 CY;

Remarks: 291 CY surplus topsoil to be uniformly wasted on FS

Correction to Sheet D.2; balance should read:

Cut = 390 CY	
Ditch Borrow = 5082 CY	Fill +30% = 6258 CY
Excavation for culvert = 786 CY	

Correction to Sheet D.3; balances should read (left to right):

Cut = 720 CY	Fill + 30% = 23 CY	Cut = 893 CY	Fill + 30% = 86 CY
To Sta 298 = 697 CY		To Sta 298 = 807 CY	
= 697 CY		= 893 CY	
Cut = 399 CY	Fill + 30% = 97 CY	Cut = 1670 CY	Fill + 30% = 109 CY
To Sta 298 = 302 CY		To Sta 298 = 1561 CY	
= 399 CY		= 1670 CY	

Correction to Sheet D.4; balances should read (left to right):

Cut = 588 CY	Fill + 30% = 39 CY	Cut = 1218 CY	Fill + 30% = 52 CY
To Sta 298 = 549 CY		To Sta 298 = 1166 CY	
= 588 CY		= 1218 CY	

Replace Sheet T.1 with attached sheet.

TABULATION OF TEMPLATE QUANTITIES AND ADJUSTMENTS

Refer to Standard Plan EW-101 and RL-1B.

[illegible]

ENGLISH	IOWA DOT	Design Team	Schoenrock\Thede	MARSHALL COUNTY	Project Number	BRF-146-4(26) -- 38-64	Sheet Number	T.1
---------	----------	-------------	------------------	-----------------	----------------	------------------------	--------------	-----