

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 19, 2013
Date of Addendum: February 19, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
502	77-0354-139	EROSION CONTROL	POLK	IMN-035-4(139)94--0E-77	19MAR502.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to Plan Sheet C.3:

Add the following note to the reference notes for the item 2602-0000120, DITCH CHECK (SYNTHETIC - HDPE):

Installation shall be as per the manufacture's recommendations.

The Ditch Check (Synthetic-HDPE) shall be made of UV resistant high density polyethylene. Each sections height shall be a minimum nine inches and length minimum three feet. A complete section without stakes shall weigh a minimum two pounds. Percent open area shall be a minimum 30%.

Approved Products Georidge or Enviroberm.

Method of Measurement: The Engineer shall measure in feet the length of the Ditch Check (Synthetic-HDPE) to the nearest tenth of a foot.

Basis of Payment: The contractor shall be paid the contract unit price per foot for the number of feet of properly installed Ditch Check (Synthetic-HDPE).

Make the following change to the Plan Sheet C.4:

Add the attached Tabulation 111-25 INDEX OF TABULATIONS.

<div> <div>111-25</div> <div>10-18-11</div> </div> <div>INDEX OF TABULATIONS</div>			Sheet No.
Tabulation	Tabulation Title		
105-4	Standard Road Plans		C-4
100-22	Special Ditch Control		C-4
100-23	Rock Ditch Checks/Ditches/Flumes/Splash Basins/Slope Protection		C-4
281-1	Section 404 Permit and Conditions		C-4
108-26A	Staging Notes		C-4
231-2	Herbicide		C-5
108-23A	Traffic Control Plan		C-5
104-9	Longitudinal Subdrain Shoulder and Backslope		C-5
110-12A	Pollution Prevention Plan		C-6