

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: March 19, 2013  
Date of Addendum: February 26, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
014	77-0651-504	DECK JOINT REPAIR	POLK	MB-005-1(500)104--77-77 MBIN-035-1(501)68--0M-77 MB-065-1(504)83--77-77	19MAR014.A01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to Sheet 1 for Project No. MB-065-1(504)83--77-77:

Change the location of Design Numbers 2513 and 2913 on the Location Map:  
From: 34<sup>th</sup> Ave. SW  
To: NE 46<sup>th</sup> Ave.

Make the following change to Plan Sheet C.1 for Project No. MB-065-1(504)83--77-77:

Tab. 100-1D PROJECT DESCRIPTION:

Replace the Project Description with the following Project Description:

The following repairs will be made on NB and SB US 65 bridges over NW 46th Ave in Des Moines (Design 2513) and (Design 2913).

- Removal and installation of new neoprene glands at abutments.
- Replace the concrete around the extrusion turn up at gutter lines and replace glands on the dual bridges.
- Seal abutment seats under the expansion joints and the face of the barrier rails.

The following repairs will be made on the NB US 65 Ramp bridge over EB & WB I-80 (Design 2613).

- Removal and installation of new neoprene glands at abutments.
- Replace the concrete around the extrusion turn up at gutter lines.
- Seal abutment seats under the expansion joints and the face of the barrier rails.

The following repairs will be made on NB US 65 bridge over Four Mile Creek and Iowa Interstate Railroad NB (Design 2713).

- Removal and installation of new neoprene glands at abutments.
- Replace the concrete around the extrusion turn up at gutter lines.
- Seal abutment seats under the expansion joints and the face of the barrier rails.

Make the following change to Plan Sheet J.1 for Project No. MB-065-1(504)83--77-77:

Tab. 108-23A TRAFFIC CONTROL PLAN:

Delete the following: Traffic will be maintained on 34th Ave SW at all times.  
Replace with the following: Traffic will be maintained on NE 46<sup>th</sup> Ave at all times.

Delete the following:  
34th St SW  
One lane of traffic may be closed during the day using Standard Road Plan TC-213.

Tab. 108-26A STAGING NOTES:

Add the following note to the Staging Notes:

Design 2613

Stage 1:

Traffic Control:

Close outside lane and shoulder.

Construction: Median lane and shoulder.

Remove and replace leaking neoprene glands, replace concrete around extrusion turn up, etc.

Stage 2:

Traffic Control:

Close median lane and shoulder.

Construction: Outside lane and shoulder.

Remove and replace leaking neoprene glands, replace concrete around extrusion turn up, etc.

Make the following change to Plan Sheet J.1 for Project No. MB-005-1(500)104--77-77:

Tab. 111-01 COORDINATED OPERATIONS:

Add the following Projects and Types of Work:

BRFIM-035-2(276)65—05-91	Bridge Replacement – PPCB
IMN-035-2(232)65—0E-91	Traffic Signs
IMN-035-2(233)65—0E-91	Lighting
IMN-035-2(336)65—13-91	PCC Pavement – Grade and New
BRFIM-035-2(356)63—05-91	Bridge Replacement – PPCB
IM-035-2(357)63—13-91	Grading

Make the following change to Plan Sheet J.1 for Project No. MBIN-035-1(501)68--0M-77:

Tab. 111-01 COORDINATED OPERATIONS:

Add the following Projects and Types of Work:

BRFIM-035-2(276)65—05-91	Bridge Replacement – PPCB
IMN-035-2(232)65—0E-91	Traffic Signs
IMN-035-2(233)65—0E-91	Lighting
IMN-035-2(336)65—13-91	PCC Pavement – Grade and New
BRFIM-035-2(356)63—05-91	Bridge Replacement – PPCB
IM-035-2(357)63—13-91	Grading