

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 19, 2013
Date of Addendum: February 27, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
102	07-0636-089-A	HMA Pavement Widening/ HMA Resurfacing	BLACK HAWK	NHSX-063-6(89)--3H-07 CS-3577(605)--84-07	19MAR102.A02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 1170 2511-0302400 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 4 IN.:

From: 484.000 SY

To: 421.000 SY.

Change Proposal Line No. 1180 2511-7526004 SIDEWALK, P.C. CONCRETE, 4 IN.:

From: 291.000 SY

To: 266.000 SY.

Add Proposal Line No. 1341 2511-0302600 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 6 IN.; 63.000 SY

Add Proposal Line No. 1342 2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.; 25.000 SY

If the above changes are not made, they will be made as shown here.

Make the following change to the Proposal Special Provisions Text and the Proposal Special Provisions List.:

Add the following proposal note:

005.2120

*** FUEL ADJUSTMENT ***

A fuel adjustment factor will be applied to payments on this contract in accordance with section 2120 of the standard specifications.

Make the following change to the Drawing C.01 for Project No. CS-3577(605)--84-07:

Add the following note to the reference notes for the item 2511-0302600 RECREATIONAL TRAIL, PORTLAND CEMENT CONCRETE, 6 IN.:

Unit price includes all labor, equipment and materials for placement of PCC Recreational Trail a six inch depth, compacting and smoothing, testing and cleanup. This item includes areas of 10 foot width recreational trail where the trail is required to be six inches in depth on areas that are designated as "Ramps" within Sidewalk Compliance Table on Drawing S.01 (sheet 13); and where said ramps are shown with Detectable Warnings and shaded pink in color on Drawing

S.02 (sheet 14). Where these apply, the entire area shaded pink shall meet the requirements associated with this item.

Add the following note to the reference notes for the item 2511-7526006 SIDEWALK, P.C. CONCRETE, 6 IN.:

Unit price includes all labor, equipment and materials for surface preparation, finish grading and placement of PCC Sidewalk a six inch depth, compacting and smoothing, testing and cleanup. This item includes areas of 5 foot width sidewalk where the sidewalk is required to be six inches in depth on areas that are designated as "Ramps" within Sidewalk Compliance Table on Drawing S.01 (sheet 13); and where said ramps are shown with Detectable Warnings and shaded pink in color on Drawing S.02 (sheet 14). Where these apply, the entire area shaded pink shall meet the requirements