

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 19, 2013
Date of Addendum: January 29, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
102	29-C029-071	PCC PAVMENT - GRADE AND NEW	DES MOINES	STP-S-C029(71)--5E-29	19FEB102.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to plan sheet B.02:

For Item Codes 2301-1033080 and 2301-1033090, add the following note to the Estimate Reference Information:

Skewed 'CD' joints stop and 'CT' joints begin either side of the 'EF' joint assemblies as tabulated on Sheet C.04. See joint detail at Sta.1+92 for the Iowa City Road approach at center of Sheet L.01. Due to drawing scale factor a similar detail does not appear on Sheet L.01 at Sta.77+50 for the Highway #61 approach.

Make the following change to plan sheet L.02:

Add the following note:

Disregard 'CT-2' joints erroneously labeled on Sheet L.02 for joints typically placed as 'CT' joints (they shall be placed as 'CT' joints). Depending on the contractor's preference longitudinal joints detailed at logical spacing labeled 'CT-2' for commercial entrances Sta.20+32.40 and Sta.23+00.09 may be placed as 'KT-2' or 'L-2' joints.