

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: May 21, 2013  
Date of Addendum: April 22, 2013

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
102	00-000S-516	PCC SIDEWALKS	DISTRICT 5	NHSN-000-S(516)--2R-00	21MAY102.A01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following changes to the plan:

Add the following note to sheet C.1

#### SMALL QUANTITY CONCRETE TESTING

- Test air and Slump once per 30 CY poured, or minimum of once per day.
- Verification gradations are not required.
- In lieu of flexural strength testing, time for opening for use may be 48 hours for pedestrian traffic and 72 hours for curb & gutter or patching.