

A d d e n d u m

Iowa Department of Transportation

Date of Letting: June 18, 2013

Office of Contracts

Date of Addendum: May 31, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
601	97-0772-015	Bridge Cleaning	Woodbury	BRFN-077-2(15)--39-97	18jun601.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Replace page 2 of 3 with the attached page 2 of 3.

Bridge No.: 9700.0S077 – VETERAN’S MEMORIAL BRIDGE

Estimate reference information for 2427-0686010 Bridge Cleaning:

"Clean the Nebraska and Iowa approach spans and the main arch span; that is, between Nebraska and Iowa abutments. Bridge cleaning consists of the removal of accumulated foreign material from the following areas: It also includes washing these elements with water under pressure."

- a. Sidewalks.
- b. Pier tops and abutments seats.
- c. Beams, stringers, girders, diaphragms, floor beams, lateral bracing, and gusset plates.
- d. Exterior surfaces (no enclosed interiors) of:
Tie girders, end floor beams, and arch ribs below a plane located 15 feet above the deck surface.
- e. Expansion joints including top surfaces (care shall be taken to not dislodge neoprene box seals or glands).
- f. Deck drain inlets and drain pipes.
- g. Bird nests (Except Cliff Swallow Nests) & adjacent droppings throughout the entire structure below a plane located 15 feet above the deck surface.

"The accumulated foreign material shall be removed prior to washing with water under pressure."

Cliff Swallow nests shall not be disturbed on this structure.