

# **A d d e n d u m**

Iowa Department of Transportation  
Office of Contracts

Date of Letting: October 15, 2013  
Date of Addendum: October 7, 2013

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
104	65-C065-077	PCC OVERLAY - UNBONDED	MILLS	STP-S-C065(77)--5E-65	15OCT104.A01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the PROPOSAL DETAILS, Page 2:

CHANGE the CONTRACT PERIOD as follows:

Late Start Date from 08/25/14 to 07/28/14

Working Days from 45 DAYS to 60 DAYS

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0010 2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW:

From: 1,508.000 CY

To: 1,119.000 CY

Change Proposal Line No. 0140 2310-5151251 PORTLAND CEMENT CONCRETE OVERLAY, PLACEMENT ONLY (UNBONDED):

From: 32,733.000 SY

To: 33,345.000 SY

Add Proposal Line No. 0321 2105-8425005 TOPSOIL, FURNISH AND SPREAD; 389.000 CY

If the above changes are not made, they will be made as shown here.

Make the following changes to the plan set:

Plan Sheet C.01:

Replace the existing Estimate Reference Information for Item Code 2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW with:

Roadway construction requires 1508 CY of excavation. See tabulation on Sheet C.05. Adj. Cut refers to offsite material required. 708 CY of cut is available from on-site cuts and 389 CY is to be provided, and will be paid, as Topsoil. The remaining 411 CY is to be furnished as borrow. The contractor is to provide his own borrow. No payment for overhaul will be made on this project.

Add the following Estimate Reference Information for Item Code 2105-8425005  
TOPSOIL, FURNISH AND SPREAD:

Quantity of topsoil required has been calculated based on an average 6" thickness over foreslopes between Sta 184+00 and Sta 189+00. See notes on Sheet C.02 for material requirements. Sufficient field measurements will be made to insure reasonable conformity with the specified depth of coverage. Cross-sections show finished groundline. Pay quantity will be based on calculations of measured area covered multiplied by average depth of coverage. Contractor will be paid contract unit price per cubic yard for measured quantity. This payment will be full compensation for acquiring, stripping, transporting and placing topsoil as described above.

Plan Sheet C.02:

Add the following to STAGING NOTES:

In the event that one-half width paving is required as part of the staging plan, the profile gradeline will be adjusted to provide a minimum thickness of 6" at centerline for the length of the affected stage. A KT-1 joint will be required between the two pours.