

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: February 18, 2014  
Date of Addendum: February 11, 2014

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
104	57-C057-119	PCC OVERLAY - UNBONDED	LINN	STP-S-C057(119)--5E-57	18FEB104.A02

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the PROPOSAL DETAILS, Page 2:

Change the CONTRACT PERIOD as follows:

From: LATE START DATE: 06/16/14  
To: APPROXIMATE START DATE: 06/16/14

Make the following change to Plan Sheet C.01:

Add the following to the Estimate Reference Information for Item No.7 & 8:

L-2 joint shall be placed at centerline and at 12' left and right of centerline. Joint at centerline shall be sawed at 1/8" (PV-101, D-1) using an early concrete saw. Joints at 12' from centerline shall be sawed at 1/4" (PV-101, D-2) and sealed.

Payment for safety edge placement shall be considered incidental to Item 8, PCC Overlay, Place Only (White Topping).