

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: February 18, 2014  
Date of Addendum: February 13, 2014

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
101	17-1372-619	PCC PAVEMENT - GRADE & REPLACE	CERRO GORDO	STP-U-1372(619)--70-11	18FEB101.A01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the plan:

For Plan Sheet A.02:

Replace Plan Sheet A.02 with Plan Sheet A.02

For Plan Sheet C.05:

Delete Note 3 in its entirety and replace with the following:

Field Verify existing sanitary sewer service elevation. The sanitary sewer service is to be installed with a minimum depth of 8' to at least a distance 6' behind the proposed back of curb. If the sanitary sewer main depth does not allow this, the sanitary sewer service shall be installed so as to maximize the depth of the sanitary sewer service to at least a distance 6' behind the curb. It is anticipated that risers will be required for some services at the connection where connecting to the existing sewer service. All sanitary sewer services to be replaced to the right-of-way line.

ADDENDUM NO. 1

GAS MAIN RELOCATION

ALLIANT ENERGY WILL BE REBUILDING THEIR EXISTING GAS MAIN ALONG NORTH SHORE DRIVE AND MANY OF THE SIDE STREETS WITHIN THIS CORRIDOR. THE FOLLOWING IS THE INFORMATION FROM ALLIANT REGARDING THEIR PROPOSED WORK:

- ERODGED GAS MAIN RELOCATION FROM 409 TO 5TH AVENUE NORTH NEW GAS MAIN WILL BE APPROXIMATELY 5' NORTH OF NORTH SHORE DRIVE... 3' EAST OF WEST RIGHT OF WAY LINE (UNDER THE SIDEWALK)... APPROXIMATELY 2' SOUTH OF NORTH CURB LINE (UNDER THE STREET PAVING)...

GAS SERVICES GAS SERVICES WILL BE REPLACED WITH PLASTIC GAS SERVICES. THE EXISTING PLASTIC GAS SERVICES WILL BE REUSED UNLESS IN CONFLICT WITH NEW STORM SEWER WORK.

ALLIANT ENERGY GAS WORK TIMELINE GAS MAIN AND SERVICE WORK WILL BEGIN IN WEEK 024 AND THE WORK IS TO BE COMPLETED PRIOR TO THE BEGINNING OF THE PROJECT PRIOR TO CONSTRUCTION STARTING IN THE EVENT THEY ARE NOT COMPLETE BY JULY.

GENERAL LEGEND table with columns for SYMBOL, CL, and DESCRIPTION. Includes symbols for station indicators, surfaces, manholes, and various utility lines.

UTILITIES CONTACT LIST table with columns for UTILITY, CONTACT INFORMATION, and phone numbers for various providers like MEDIACOM, CLEAR LAKE, and ALLIANT ENERGY.

PROTECTION OF VEGETATION TREES AND OTHER VEGETATION WHICH MAY BE REMOVED ARE MARKED WITH AN 'X' OVER THE APPROPRIATE SYMBOLS... CONTRACTOR TO BE RESPONSIBLE FOR RECONNECTING DAMAGED SUMP PUMP DISCHARGE LINES TO SUBDRAN OR STORM SEWER.