IOWA DEVELOPMENT OF RUBBLIZED CONCRETE PAVEMENT BASE MILLS COUNTY

Final Report for Iowa Highway Research Board Project HR-315

January 1995

Project Development Division



Iowa Department of Transportation

Final Report Iowa Highway Research Board Project HR-315

Iowa Development of Rubblized Concrete Pavement Base Mills County

By

Shane Tymkowicz Secondary Road Research Coordinator 515-239-1382 Office of Materials Project Development Division Iowa Department of Transportation Ames, Iowa 50010

and

Steve DeVries, P.E. Mills County Engineer 712-527-4873

January 1995

TECHNICAL REPORT TITLE PAGE

1.	REPORT NO.	2.	REPORT DATE
	HR-315		January 1995
3.	TITLE AND SUBTITLE	4.	TYPE OF REPORT & PERIOD COVERED
	Iowa Development of Rubblized Pavement Base - Mills County		Final Report, 9-89 to 12-94
5.	AUTHOR(S)	6.	PERFORMING ORGANIZATION ADDRESS
	Shane Tymkowicz Secondary Road Research Coordinator		Iowa Department of Transportation Materials Department 800 Lincoln Way Ames, Iowa 50010
	Steve DeVries Mills County Engineer		418 Sharp Street Glenwood, Iowa 51534

7. ACKNOWLEDGEMENT OF COOPERATING ORGANIZATIONS

Mills County Board of Supervisors

8. ABSTRACT

Iowa counties have tried to rehabilitate deteriorating portland cement concrete (PCC) pavements with standard overlays, placement of engineering fabric, rock, open graded bituminous mixes and cracking and seating. While these methods prolong the life of the road, the cracks in the old pavement have eventually reflected to the surface. One possible alternative for rehabilitating severely deteriorated roads and preventing reflective cracking is the rubblization process.

The objective of this research project was to rehabilitate and evaluate a severely deteriorated PCC roadway using a rubblization process. A 3.0 km (1.9 mi.) section of L63 in Mills County was selected for this research. The road was divided into 16 sections. A resonate frequency vibration pavement breaker was used to rubblize the existing pavement. The variables of rubblization, drainage, and ACC overlay depths of 75 mm (3 in.), 100 mm (4 in.), and 125 mm (5 in.) were evaluated.

The research on rubblized concrete pavement bases support the following conclusions:

- 1. The rubblization process prevents reflective cracking.
- 2. Edge drains improved the structural rating of the rubblized roadway.
- 3. An ACC overlay of 125 mm (5 in.) on a rubblized base provided an excellent roadway regardless of soil and drainage conditions.
- 4. An ACC overlay of 75 mm (3 in.) on a rubblized base can provide a good roadway if the soil structure below the rubblized base is stable and well drained.
- 5. The Road Rater structural ratings of the rubblized test sections for this project are comparable to the nonrubblized test sections.

9.	KEY WORDS	10.	NO. OF PAGES
	Asphalt concrete paving		
	Asphalt overlay		62
	Break and seat		
	Crack and seat		
	Portland cement concrete		
	Rehabilitation		
	Rubblize		

TABLE OF CONTENTS

.

Introduction	1
Objective	2
Project Location and Description	2
Preconstruction	4
Construction	5
 Daily Construction Record. Tuesday, September 5, 1989. Wednesday, September 6, 1989. Thursday, September 7, 1989. Friday, September 8, 1989. Monday, September 11, 1989. Tuesday, September 12, 1989. Wednesday, September 13, 1989. Friday, September 15, 1989. Monday, September 18, 1989 through Wednesday, September 20,1989. Saturday, September 23, 1989 through Monday, September 25, 1989. Friday, September 27, 1989 through Friday, October 6, 1989. Wednesday, October 11, 1989 through Tuesday, October 24, 1989. 	6 7 8 9 9 10 10 10 11 11 11 11 12
Testing Sample Cores Road Rater Summary Roughness Testing Crack Survey	12 13 13 17 17
Discussion	18
Conclusion	20
Acknowledgements	21
Appendices Appendix A - Maps. Appendix B - Construction Documents. Appendix C - Testing. Appendix D - Material Testing. Appendix E - Photos.	22 25 31 40 58

DISCLAIMER

The contents of this report reflect the views of the author and do not necessarily reflect the official views of the Iowa Department of Transportation. This report does not constitute any standard, specification or regulation.

:

And the second s

INTRODUCTION

Iowa counties have constructed several thousand miles of portland cement concrete (PCC) pavement over the past thirty years. Many of these pavements have deteriorated to a condition that requires rehabilitation or reconstruction. Because of the cost of total reconstruction, several alternatives are being reviewed to rehabilitate these deteriorated pavements including standard overlays, placement of engineering fabric, rock, open-graded bituminous mixes and cracking and seating. While these methods have prolonged the life of the roads, the cracks in the old pavement have eventually reflected to the surface. The most successful method to date appears to be the cracking and seating operation.

Due to budget constraints, these deteriorating PCC pavements are typically not being repaired at the most opportune time. Instead, they are rehabilitated later when a more substantial repair is required. Since this work is not being done, many of the existing pavements have deteriorated beyond the point where standard methods, including cracking and seating, would be successful. If the pavement has become severely deteriorated before the cracking and seating operation can take place, full and partial depth patching of joints, "D" cracked areas and areas of load related pavement failures is necessary. The patching process can increase the cost of the cracking and seating procedure to a point where other alternatives, including complete replacement, should be investigated.

One possible alternative for rehabilitating severely deteriorated roads is the rubblization process. With the rubblization process the existing PCC is broken into nominal

50 mm (2 in.) pieces. An asphaltic cement concrete (ACC) overlay is placed on the rubblized road. The purpose of this process is to create a dense drainable base. The base will ideally give structure to the roadway and prevent the reflective cracking from the original PCC overlay.

OBJECTIVE

The objective of this research project was to rehabilitate and evaluate a severely deteriorated PCC roadway using a rubblization process. Specific topics to be investigated include:

- 1. The thickness of the overlay to produce an effective roadway.
- 2. Any cracking pattern that may develop in the ACC overlay.
- 3. The structural integrity of the rubblized roadway.
- 4. The cost effectiveness of rubblizing.

PROJECT LOCATION AND DESCRIPTION

The project is located on Mills County road L63 (FAS route 6058) from its intersection with county road H40 to the south corporate limits of Malvern (see map, page 23).

The project is 3.0 km (1.9 mi.) in length. The original road was a 6.7 m (22 ft.) wide, 150 mm (6 in.) thick, Class B, PCC pavement with 12.2 m (40 ft.) joint spacings. The pavement was constructed with a Class 1 coarse aggregate. The pavement was severely deteriorated. Joints exhibited pop-outs and "D" cracking. The pavement structure had failed to such an extent that the pavement had shifted toward the foreslopes in some areas. Load related failure in the "Y" pattern was very apparent at the outside edges of the pavement. See photographs on page 59, Appendix E.

Average daily traffic in 1989 varied from 580 vehicles per day (vpd) near the south end of the project to 1190 vpd at the north end. Average daily traffic in 1992 varied from 410 vpd near the south end of the project to 970 vpd at the north end.

The project consisted of sixteen test sections. The test sections had nominal asphalt overlay depths of 75, 100 and 125 mm (3, 4, and 5 in.). Three of the test sections were not rubblized for use as control sections. Test sections were both drained and undrained. Table 1 on page 4 lists the test sections, their location and the variables used in each test section.

The rubblization process consists of breaking an existing PCC pavement with a resonate frequency vibration pavement breaker. Existing pavement is ideally broken into particles with a nominal size of 50 mm (2 in.). Particle size generally increases with depth since the energy for breaking the pavement is dissipated with depth. The rubblized roadway is compacted with a vibratory steel drum roller. A layer of chokestone may be placed on the compacted rubblized base. The chokestone serves as a leveling coarse to establish a final grade and to fill depressions created by the rubblization process. A vibratory steel drum roller is used to compact the chokestone. The result is a flexible interlocked stone like base that contributes to the structure of the roadway and prevents reflective cracking. An ACC overlay is placed over the rubblized base.

TABLE 1TEST SECTIONS

TEST SECTION	STATION		N	ACC OVERLAY DEPTH	RUBBLIZED	SUBDRAIN
1	1+00	ТО	3+50	75 mm	YES	NO
2	3+50	ТО	6+00	75 mm	YES	YES
3	7+00	ТО	9+50	100 mm	YES	YES
4	9+50	то	12+00	100 mm	YES	NO
5	13+00	ТО	15+50	125 mm	YES	NO
6	15+50	то	19+00	125 mm	YES	YES
7	19+00	то	24+00	125 mm	NO	YES
8	36+00	ТО	64+70	125 mm	YES	YES
9	64+70	то	69+00	125 mm	YES	NO
10	69+00	то	83+00	125 mm	YES	YES
11	84+00	ТО	86+50	100 mm	YES	YES
12	86+50	то	89+00	100 mm	YES	NO
13	90+00	ТО	92+50	75 mm	YES	NÖ
14	92+50	то	95+00	75 mm	YES	YES
15	95+00	то	97+50	75 mm	NO	YES
16	97+50	то	101+01	75 mm	NO	NO

PRECONSTRUCTION

A detailed crack survey was conducted prior to construction. The crack survey was used to record distress and cracks in the ACC overlay. The crack survey was also used to identify pre-existing conditions that may have caused deterioration of the roadway after the rubblization and ACC overlay. Preconstruction average structural ratings were determined using the Iowa DOT Road Rater (Appendix C, page 32).

The project was let on May 16, 1989 with the award being made to Cessford Construction Company from LeGrand, Iowa. The total contract amount was \$286,990.30. A bid of \$26,471.90 was made for the rubblization portion of the contract. The remainder of the contract included application of the chokestone, ACC pavement, full depth granular shoulders, guardrail and other associated items. A copy of the contract can be found in Appendix B on page 26-28.

CONSTRUCTION

Construction of the project was done in accordance to the Standard Specifications Series of 1984 of the Iowa Department of Transportation plus the special provisions and supplemental specifications that were in effect at the time. Rubblizing of the PCC roadway was done in accordance with Special Provision 812 (Appendix B, page 29).

Rubblization of the existing PCC pavement was done with a PB4 pavement breaker manufactured by Gurries Industries (Appendix E, Photos, page 60 and 61). The PB4 is a resonant pavement breaker that transmits power through a 163 mm by 450 mm by 3.81 m (6.5 in. x 18.0 in. x 12.5 ft.) forged steel beam. The PB4 operates at a frequency of 44 impacts per second. Each impact transmits a force to the pavement of approximately 8900 N (2000 lbs.). The operating speed of the PB4 is approximately 4.0 km per hour (2.5 mph).

After rubblizing, a 50 mm to 100 mm (2 in. to 4 in.) layer of 19 mm (3/4 in.) chokestone was spread over the broken concrete (Appendix E, Photos, page 62). The chokestone acted

as a base leveling course to establish a final grade, and it filled depressions in the rubblized base. An ACC overlay was placed on the project. The overlay varied from 75 mm to 125 mm (3 in. to 5 in.) in depth. Subdrains were installed along the edge in such a manner that the drain would be in a portion of two different thicknesses of the ACC pavement. A layout of the project with the location of subdrains, ACC pavement thicknesses and rubblized and nonrubblized areas is in Appendix A, page 24.

The original asphalt mix design for the project is in Appendix D, page 41. The coarse stone was out of specification by approximately 3.5% for the minus 200 sieve. New rock was brought to the project from the same source. The Southwest Iowa Transportation Center Materials office approved a combined gradation that consisted of: 15% initial gradation stone, 45% new gradation stone and 40% sand. Proportions and production limits for the aggregates can be found in Appendix D, page 42. The design asphalt content was also lowered from 6.6% to 6.4%.

The drainage system used on the project was AdvanEDGE by Advanced Drainage Systems, Inc. A Typar geotextile wrap was placed around the panel edge drain. Typical design sections are shown in Appendix B on page 30.

DAILY CONSTRUCTION RECORD

The daily construction record is taken from the HR-315, "Iowa Development of Rubblized Concrete Pavement Base - Mills County," construction report. The construction report was written by Vaughn Bennet in March 1990.

Tuesday, September 5, 1989

The rubblizing procedure began at Station 95+00 on Tuesday, September 5, 1989 and proceeded south toward the beginning of the project (B.O.P). The entire width of the pavement was rubblized rather than just one lane at a time. The contractor began with a 225 mm (9 in.) shoe on the PB4, but was not achieving a small enough particle size. The contractor converted to a 175 mm (7 in.) shoe which provided better results. The project plan called for the PB4 to break the pavement into pieces with a nominal particle size of 50 mm (2 in.); however, the existing subbase condition made breaking the pavement into nominal 50 mm (2 in.) pieces impossible. To operate effectively the PB4 must impact against a solid surface. The soft subgrade at the project site caused the concrete to break into pieces ranging from 300 to 450 mm (12 to 18 in.). The pavement was broken into pieces ranging from 150 to 200 mm (6 to 8 in.) where the subgrade was reasonably solid. Particle sizes of 25 to 50 mm (1 to 2 in.) were obtained in areas where there was severe "D" cracking. Approximately 1692 m² (2022 sq. yds.) of pavement were rubblized.

Wednesday, September 6, 1989

Rubblizing continued approaching the B.O.P. Near Station 81+00 a subgrade seep area was encountered which would not allow complete rubblizing of the pavement. The subgrade was so soft that the PB4 pavement breaker fell through the broken pavement and became stuck. Additionally, while continuing to break up the old pavement in that area, the PB4 occasionally had to be pushed to prevent it from getting stuck again. An additional 5202 m^2 (6222 sq. yds.) of pavement were rubblized.

The contractor began applying the chokestone in the afternoon with a "Jersey" spreader attached to a bulldozer. The spreader was set to place stone at a depth of 50 mm (2 in.). Some of the rubblized pavement was still exposed after the application of the chokestone, but it did not appear to present any problems during the compaction procedure. However, the decision was made to remove the exposed rubblized pavement before the placement of ACC pavement. The contractor found that a better grade could be achieved by lightly blading the chokestone after it had been rolled.

Thursday, September 7, 1989

The project received approximately 38 mm (1.5 in.) of rain overnight. The rain continued intermittently until approximately 11:00 A.M. Outlets were dug in the shoulder of the road to allow the water to get out of the base. All other activities ceased until the open house demonstration at 12:30 P.M. The rubblizing continued for the remainder of the day. Approximately 7379 m² (8825 sq. yds.) of pavement were rubblized.

An open house was held at 10:30 A.M. with an informational meeting on rubblizing and alternate techniques of pavement repair with asphalt cement concrete pavement. At 12:30 P.M. the people in attendance were bused to the project site to observe the choking and rubblizing operations.

Friday, September 8, 1989

An extreme amount of rain was received overnight, and all operations on the project were suspended.

Discussions during the day concerning the drainage problem resulted in a decision to attempt to install the drainage structures before the placement of the ACC. It was felt that this would help to stabilize the subgrade as well as prevent any damage to the ACC pavement surface.

Monday, September 11, 1989

Approximately 3026 m² (3619 sq. yds.) of pavement were rubblized. This completed the rubblizing operation with a total of 17,309 m² (20,701 sq. yds.) of pavement being rubblized.

In the morning, the contractor began applying chokestone again in preparation for the placement of ACC pavement at a later date.

A second layer of chokestone was applied over the area near Station 81+00 to serve as a strengthening course. The chokestone that had been applied prior to the rain had developed a crust on the surface much like that on a granular surfaced road.

Tuesday, September 12, 1989

The placement of the ACC pavement was to begin, but rain overnight prevented paving operations. The remainder of the chokestone was placed. Discussions on the subdrain installation brought to light a scheduling problem so it was decided to begin ACC pavement placement on Wednesday, September 13 without the installation of the drains. The placement of the ACC pavement would begin near Station 64+00 and proceed toward the

B.O.P. The contractor would then complete the project by starting at 64+00 and proceed to the end of the project (E.O.P). This procedure would prevent loaded ACC trucks from driving over the 75 and 100 mm (3 and 4 in.) portions of the fresh pavement.

Wednesday, September 13, 1989

The ACC pavement placement was to begin, but a check of the material gradation showed that the minus 200 sieve of the coarse stone was out of specification by approximately 3.5%. Replacement material needed to be crushed in order for the project to continue.

Friday, September 15, 1989

After conferring with the Iowa DOT Southwest Iowa Transportation Center Materials Office, it was determined that an approved combined gradation could be achieved using three aggregates in the following percentages:

initial gradation rock		15%
new gradation rock	=	45%
sand	==	40%

The placement of the ACC pavement began as described earlier at approximately 1:15 P.M. Approximately 910 Mg (1000 tons) of mix were placed.

Monday, September 18, 1989 through Wednesday, September 20, 1989 The placement of ACC pavement was completed on Wednesday. No problems out of the ordinary were encountered. The intended ACC pavement thickness was 88 mm (3.5 in.), but the actual thickness of the ACC pavement ranged from 79.5 to 127 mm (3.13 to 5.00 in.) with an average of 91.7 mm (3.61 in.). This may have been caused by the rough subgrade that resulted from the rubblizing. The densities ranged from 96.64% to 101.05% with an average density of 98.27%.

Saturday, September 23, 1989 through Monday, September 25, 1989

The placement of full depth shoulders was begun and completed on the entire length of the project.

Friday, September 27, 1989 through Friday, October 6, 1989

The required pavement markings and construction of guardrails on the bridge at Station 30+00 were completed.

Wednesday, October 11, 1989 through Tuesday, October 24, 1989

Work was done on the installation of shoulder drains. A problem developed when the trench was cut to place the drain tile. The saw would occasionally get caught on a piece of the rubblized concrete and pull it upward. This caused the ACC pavement to break at the edge of the roadway. After looking at the soil that came out of the trench and seeing that it would allow water to percolate through it, a decision was made to move the drain away from the edge of the ACC pavement approximately 150 mm (6 in.) to avoid damaging the pavement. Two different trenching methods were used. Initially, a large concrete wheel saw was used,

but it was this method that was causing the fraying of the ACC pavement edges as well as allowing a considerable amount of material to remain in the trench. A "Ditch Witch" type trencher was then brought to the site to complete the operation. Using this machine the contractor was able to have more control on the depth of the trench, and the contractor was able to eliminate the fraying of the ACC pavement edge. The "Ditch Witch" type trencher achieved a much cleaner trench.

Tuesday, October 24, 1989

A final inspection was conducted and project approval given.

TESTING

Testing for the project was conducted by Iowa DOT Materials personnel. Tests were conducted for both the construction and post construction stages. During the construction stages of the project, standard Iowa DOT tests were conducted for aggregate durability, aggregate gradation, density and asphalt mix design. The results of the durability tests can be found in Appendix D, page 44. Aggregate gradation test results can be found in Appendix D, pages 45 and 48-49. Asphalt concrete sample test results are in Appendix D, pages 50-52. A summary table in Appendix D on pages 46-47 lists all the known data about the asphalt samples from the plant report, cores and box samples. Copies of the daily plant reports are in Appendix D, pages 54-57. These reports have the gradation, density, voids and percent AC as measured at the ACC plant. Standard Iowa DOT testing was also conducted on the asphalt cement, but the results of the testing are not included in this report. The results of the Iowa DOT standard tests were within allowable limits. Post construction testing included coring samples, Road Rater testing, B.P.R. Roughness testing and crack surveys.

Sample Cores

Cores samples were cut as soon as possible the morning following any ACC paving. Seven samples were taken each time at random locations. The results of the coring are listed on the daily plant reports in Appendix D, pages 54-57. The seven cores from September 19, 1989 were sent to the Southwest Iowa Transportation Center as assurance samples. A copy of the assurance sample results is in Appendix D, page 53. The information obtained from the cores is listed as part of the table on pages 46-47. No correlation was found between the information obtained from the cores and the performance of the roadway.

Road Rater Summary

The Road Rater is a dynamic deflection measuring device that determines the structural rating of pavements. The Road Rater can also determine the soil K value (Westergaard's modulus of subgrade reaction) of the subbase.

Road Rater testing was conducted prior to the start of the project on August 23, 1989 (Appendix C, page 32). Road Rater testing was also conducted each year after construction during the month of March or April. A summary of the Road Rater information is in Table 2 on page 16.

A regression analysis was performed with the dependent variable being the Road Rater structural value. The independent variables were the nominal thickness of the asphalt overlay, the soil K value of the subbase from the Road Rater, rubblized or nonrubblized payement, drained or undrained base and the time in years since construction. A list of the input variables is given in Appendix C on pages 33-35. First, a simple one variable linear regression test was performed to determine if any of the independent variables had a significant correlation with the structural value obtained from the Road Rater. The variables of ACC depth, drainage, rubblized, and soil K value were found to be statistically significant (Appendix C, page 36). A multiple linear regression analysis was performed with these four variables with the complete data set. The result was an r^2 (sample correlation coefficient squared) value of 0.39. However, the coefficient for the depth of ACC overlay in mm was -0.0039. A negative coefficient is not logical since the structural rating is known to increase linearly with depth. Therefore, a linear regression analysis was performed without ACC depth as a variable. Linear regression analysis was also performed on only the rubblized test sections with ACC depth, drainage and soil K value as independent variables. The coefficient for ACC depth was again found to be negative, so a second linear regression was performed without ACC depth as a variable. A summary of the linear regression analysis is given in Appendix C on page 37.

The analysis is skewed because all test sections were not equally represented, and a complete matrix of possible test combinations was not built at the project site. The analysis is still capable of providing information about the significance of input variables. Drainage always provided a positive coefficient for structural rating of approximately 0.3 to 0.7. The higher end of the range represents the analysis of only rubblized test sections. Rubblizing also had positive coefficients for structural rating of approximately 0.4 to 0.5. This result was

unexpected, but might be partially explained if the existing PCC pavement panels are able to move due to the poor subgrade while Road Rater testing is being performed. The positive coefficient of soil K value was expected and supports the importance of a good base for roadway construction.

The Road Rater tests were used to back calculate the structural rating of the existing roadway and rubblized roadway. The AASHTO design coefficient of 0.44 structural numbers per 25 mm (1 in.) of asphaltic concrete were used. The structural value of the overlay was determined for each test site, and it was subtracted from the Road Rater structural rating. The resulting structural number was then divided by 150 mm (6 in.) for nonrubblized test sections and 200 mm (8 in.) for rubblized test sections. The extra 50 mm (2 in.) for the rubblized test sections is for the chokestone. The results were then divided into four subgroups based on drained or undrained and rubblized or nonrubblized. The average was calculated for each subgroup. The results are given in Appendix C on page 39. Note the rubblized and drained group is the only group to have a positive structural rating, but the structural rating for the rubblized material and chokestone is not large enough to consider in the designing of the pavement thickness.

TABLE 2

ANNUAL AVERAGE ROAD RATER VALUES

TEST SECTION	ACC OVERLAY DEPTH	RUBBLIZED	SUBDRAIN	S.R. 1990	S.R. 1991	S.R. 1992	S.R. 1993	S.R. 1994	S.R. AVG.
1	75 mm	YES	NO	*	*	*	*	*	*
2	75 mm	YES	YES	3.18	2.88	2.98	3.29	3.34	3.13
3	100 mm	YES	YES	1.64	1.66	2.07	1.65	1.63	1.73
4	100 mm	YES	NO	1.64	1.51	1.80	1.49	1.46	1.58
5	125 mm	YES	NO	*	*	*	*	*	*
6	125 mm	YES	YES	1.39	1.22	1.46	1.54	1.42	1.41
7	125 mm	NO	YES	1.65	1.60	1.90	1.83	1.75	1.75
8	125 mm	YES	YES	1.55	1.68	3.00	1.93	2.01	2.03
9	125 mm	YES	NO	1.28	1.22	1.46	1.30	1.51	1.35
10	125 mm	YES	YES	3.18	3.21	3.80	4.30	3.93	3.68
11	100 mm	YES	YES	*	*	*	*	*	*
12	100 mm	YES	NO	1.27	1.41	1.46	1.43	1.75	1.46
13	75 mm	YES	NO	0.94	1.00	0.83	0.94	0.95	0.93
14	75 mm	YES	YES	*	*	*	*	*	*
15	75 mm	NO	YES	0.92	1.15	1.06	*	*	1.04
16	75 mm	NO	NO	0.83	0.83	2.75	0.77	0.97	1.23
AVG. S.R.				1.66	1.69	2.17	1.99	1.92	1.89

Roughness Testing

B.P.R. Roughness testing was conducted on September 8, 1994. The results of the testing are in Appendix C on page 38. Road roughness indicated by this method is a comparative index expressed as inches of roughness per mile of driving lane tested. The B.P.R. Roughness value was converted into a Longitudinal Profile Value (LPV). This was accomplished by using an Iowa DOT conversion table that correlated the B.P.R. Roughness with the CHLOE Profilometer. The LPV was converted to a Present Serviceability Index (PSI). Table 3 on page 19 shows the final PSI for each test section.

The nonrubblized test sections still have high PSI values even though reflective cracking has occurred. The rubblized test sections have good ratings except for sections 1 and 2 where load failure has occurred. A reason why the rubblized sections have a lower PSI than the nonrubblized sections is that the grade of the rubblized roadway visible undulates in many areas.

Crack Survey

A detailed crack survey was conducted prior to construction in 1989. The crack survey documented cracks, joint and areas of pavement failure that might lead to reflective cracking after the rubblization process. Additional crack surveys were conducted in 1990, 1992, 1993 and 1994. The crack surveys document the occurrence of new or reflective cracks. A summary of the crack survey is presented in Table 4 on page 20.

The rubblization process prevented reflective cracking. Test section 1 and 2 (rubblized, 75 mm (3 in.) of ACC) show a large amount of cracking, but the cracking is mostly alligator cracking in the outside wheelpath. The failure is load related and not reflective. Test section 4 (rubblized, 100 mm (4 in.) of ACC) is starting to show signs of distress in year 5 of the project. The rubblized test sections on the north end of the project have fewer cracks than those in the south end. This may be due to the poor soil conditions at the south end of the project. Note that the south end of the project is where the soil was the softest during the rubblization process. Rubblized test sections with 125 mm (5 in.) of ACC have all performed well. The nonrubblized sections all have reflective cracking. The reflective cracking the first winter and has increased each year.

DISCUSSION

The rubblization process was an effective alternative for this project. Many of the test sections are crack free after 5 years. Because of the good performance, a cost effectiveness in terms of life cycle cost can not yet be determined. However, the process has shown itself to be a viable alternative when an existing pavement has severe failure and low structural rating numbers. The use of edge drains is encouraged in a rubblization project. If soil conditions are wet, the drains should be installed prior to rubblization. The drained soil will allow the pavement to be more effectively rubblized.

ACC PRESENT TEST STATION **OVERLAY** RUBBLIZED **SUBDRAIN** SERVICEABILITY DEPTH INDEX SECTION YES 1+00 TO 75 mm NO 2.12 1 3 + 50YES YES 2.29 2 3+50 TO 6+00 75 mm YES 3 7+00 TO 9+50 100 mm YES 2.65 4 9+50 TO 12+00 100 mm YES NO 2.64 YES 2.66 5 13+00 TO 15+50 125 mmNO YES YES 6 15+50 TO 19+00 125 mm 2.63 7 19+00 TO 24+00 125 mm NO YES 3.64 36+00 TO 64+70 8 125 mm YES YES 2.84 9 64+70 TO 69+00 125 mm YES NO 3.17 YES 10 69+00 TO 83+00 125 mm YES 2.80 YES 84+00 TO 86+50 100 mm YES 2.82 11 12 86+50 TO 89+00 100 mm YES NO 3.17 90+00 TO 92+50 YES 13 75 mm NO 2.84 14 92+50 TO 95+00 75 mm YES YES 2.82 15 95+00 TO 97+50 NO 75 mm YES 4.69 16 97+50 TO 101+01 75 mm NO NO 3.83

TABLE 3PRESENT SERVICEABILITY INDEX FOR HR-315

DATE TESTED 9/8/94

TABLE 4CRACK SURVEY SUMMARY FOR HR-315LINEAR FEET OF CRACKS PER 100 LINEAR FEET OF ROADWAY

TEST	YEAR							
SECTION	1990	1992	1993	1994				
1	8.8	8.8	8.8	209.2				
2	0.0	48.0	194.0	200.0				
3	0.0	0.0	0.0	5.6				
4	0.0	0.0	0.0	44.8				
5	0.0	0.0	0.0	0.0				
6	0.0	0.0	0.0	0.0				
7	11.2	20.4	24.4	30.2				
8	0.0	0.1	0.1	0.8				
9	0.0	0.0	1.4	2.6				
10	0.0	0.0	0.0	1.6				
11	0.0	0.0	0.0	0.0				
12	0.0	0.0	0.0	0.0				
13	0.0	0.0	0.0	0.0				
14	0.0	0.0	0.0	0.8				
15	58.4	64.8	68.0	68.0				
16	36.8	41.9	50.4	85.8				

1.0 ft = 0.3048 m

CONCLUSIONS

This research on rubblized concrete pavement bases support the following conclusions:

- 1. The rubblization process prevents reflective cracking.
- 2. Edge drains improved the structural rating of the rubblized roadway.

- 3. An ACC overlay of 125 mm (5 in.) on a rubblized base provided an excellent roadway regardless of soil and drainage conditions.
- 4. An ACC overlay of 75 mm (3 in.) on a rubblized base can provide a good roadway if the soil structure below the rubblized base is stable and well drained.
- 5. The Road Rater structural ratings of the rubblized test sections for this project are comparable to the nonrubblized test sections.

ACKNOWLEDGEMENTS

Research project HR-315 was sponsored by the Iowa Highway Research Board and Mills County. Funding for this project was from the Secondary Road Research Fund in the amount of \$62,984.00. An additional \$35,545.00 was placed in a contingency fund. The fund is for additional costs due to research. Mills County received approval for the reimbursement of funds from the Iowa Highway Research Board on December 8, 1994.

The authors wish to extend their appreciation to the Mills County Board of Supervisors, the Iowa Department of Transportation and the Asphalt Paving Association of Iowa for their support in developing and conducting this project. Additionally, the employees of Cessford Construction Company deserve credit and thanks for the extra effort and cooperation that was put forth in the completion of this research project.

Appreciation is expressed to the Special Investigations Section of the Office of Materials for their work in obtaining test data. Appreciation is also expressed to the Research Section of the Office of Materials for their help and guidance in writing this report. Appendix A Maps



PROJECT LAYOUT



Appendix B Construction Documents

CONTRACT

ND. 30059

County MILLS Project No. SN=6058(1)=-51=65
Type of Work ASPH CEMENT CUNC PAVEMENT Miles 1.9140
ON SECONDARY ROAD L63 FROM THE JUNCTION SECONDARY ROAD HAD
NEAR THE NW CORNER OF SECTION 8-71-41, NORTH TO THE MALVERN
CITY LIMITS.
This agreement made and entered by and between the <u>BOARD OF SUPERVISORS OF MILLS</u> COUNTY, IOWA
Contracting Authority, and
CESSFORD CONSTRUCTION CO. OF LE GRAND, IOWA
00007350 Contractor.
It is agreed that the notice and instructions to bidders, the proposal filed herein, the general specifications of the lowa Department of Transportation for 1984 , together with supplemental specifications and special provisions, together with the general and detailed plans, if any, for said project
10/20/89 40
Time is the essence of this contract. To accomplish the purpose herein expressed, Contracting Authority and Contractor have signed this and four other identical instruments as of the <u>155</u> day of <u>June</u> , <u>1989</u> .
BOARD OF SUPERVISORS OF MILLS COUNTY, IOWA
By Philand & Jammon II sim
CESSFORD CONSTRUCTION CO. DE LE GRAND. IOWA
By Stephene Chable

prm 650031 8-67 H-688

.

CONTRACT PRICES

CONTRACT NO. 30059

Bid Order No. 65

ontractor's No. 0, 7, 3, 5, 0

Proposal I.D. No. 890791

Project No. SN-6058(1)--51-65

.

County MILLS

Page No. 1

Type of Work ASPH CEMENT CONC PAVEMENT

				antity	Unk Price		Amount	
•	³ Line No.	ltem	and U	Inita	Dollars X,XXX,XXX	Cents XXXX	Dollars XX,XXX,XXX	Centr XX
1->	0010	RUBBLIZING PAVEMENT	20363 \$	SQ. YDS.	1.	3000	26,471	•90
1000 - 1000	0020	ASPHALT CEMENT CONCRETE, TYPE B SURFACE COURSE, MIXT, SIZE 1/2 IN.	5765	TONS	17.	2800	99,619	.20
	0030	ASPHALT CEMENT	339	TONS	124.	8000	42,307	•20
,	0040	SUBDRAIN, (LÓNGITUDINAL) AS PER PLAN	7353	LINEAR F	-T 2.	6000	19,117	.80
	0050	SHOULDERS, GRANULAR, TYPE B	2087	TONS	10.	1600	21,203	•92
	0060	SURFACING, DRIVEWAY	405	TONS	11.	.0500	4,475	•25
	0070	PAVEMENT MARKINGS, TRAFFIC STRIPE REFLECTORIZED, BROKEN LINE YELLOW	1.67	MILES	280.	.0000	467	• 60
	0080	PAVEMENT MARKINGS, TRAFFIC STRIPE REFLECTORIZED, SOLID LINE YELLOW	1.65	MILES	280	.0000	462	.00
•	0090	PAVEMENT MARKINGS, TRAFFIC STRIPE REFLECTORIZED, SOLID LINE WHITE	3.83	MILES	280	.0000	1,072	.40
	0100	GUARDRAIL, END ANCHORAGES, BEAM, RE-52	4	ONLY	360	.0000	1,440) .0 0
-	0110	GUARDRAIL, END ANCHORAGES, BEAM, RE-53	1	ONLY	450	.0000) 450).00
	0120	GUARDRAIL, FORMED STEEL BEAM	181.25	LINEAR	FT 7	.6000	1,377	1.50
, (0130	GUARDRAIL, FORMED STEEL THRIE BEAM	637.5	LINEAR	FT 12	.5000	7,968	3.75
2	0140	GUARDRAIL, POSTS, BEAM	53	ONLY	41	8000	2,21	5.40
;	0150	MOBILIZATION		LUMP SU	IM		14,123	3.00
	0160	BRIDGE CONNECTIONS	86	ONLY	43	.0000	3 ,690	8.00
	0170	PRIMER OR TACK-COAT BITUMEN	1216	GALLONS	s c	.6800	0 820	5.8 8
:	0180	EXCAVATION, CLASS 10, ROADWAY & BORROW	1145	CUBIC	rds 3	8.5000	0 4,00	7.50
-	0190	PAVEMENT SCARIFICATION	255	SQ. YD	5. 1(0.250	0 2,61	3.75
	0200	SEEDING, FERTILIZING & Mulching	1.7	ACRES	2200	000.000	0 3,74	0.00
-	0210	SAMPLES		LUMP SI	MM		25	0.00

Form 650031 8-87 H-666

CONTRACT PRICES

CONTRACT NO. 30059

County MILLS

Bid Order No. 65

Contractor's No. 0, 7, 3, 5, 0

Proposal I.D. No. 890791 *

Project No. SN-6058(1)--51-65

Page No. 2

Type of Work ASPH CEMENT CONC. PAVEMENT

		14 Que	Unit Price	Amount	
Line No.	Item	and Units	Dollars Cents X,XXX,XXX XXXX	Dollars C ta	
0220	(CONTINUED) TRAFFIC CONTROL	LUMP SUM	1	2,500.00	
0230	BASE, CHOKE STONE	2645 TONS	10.0500	26,582. 5	

TOTAL \$286,990.70

LAST PAGE





lowa Department of Transportation

SPECIAL PROVISIONS for RUBBLIZING EXISTING PORTLAND CEMENT CONCRETE PAVEMENT

Project SN-6058(1)--51-65, Wills County

May 16, 1989

812.01 DESCRIPTION. Under this item, the contractor shall rubblize and compact the existing non-reinforced portland cement concrete pavement as shown on the plans or as directed by the Engineer.

812.02 HATERIALS. All choke stone material shall meet the requirements of Article 4120.04 of the 1984 Standard Specifications with a maximum particle size of 3/4".

812.03 EQUIPMENT. The equipment required for the rubblizing process shall be a self contained, self propelled, resonant frequency pavement breaking unit capable of producing low amplitude, 2000 pound force blows at a rate of not less than 44 per second. The unit shall be equipped with a water system to suppress dust generated by the operation. A standard steel drum vibratory roller having a gross weight of not less than 10 tons operated in the vibration mode shall be used to compact the rubblized pavement.

812.04 CONSTRUCTION METHODS. A transverse joint shall be sawed full depth and load transfer devices severed on the mainline where the rubblizing abuts concrete pavement which is to remain in place. The operating speed of the rubblizing unit shall be such that the existing pavement is reduced into particles with a nominal size of 2" continuous coverage with the breaking shoe shall be required. Additional passes of the resonator may be required if larger sizes remain after the initial rubblizing pass. Unless otherwise directed by the Engineer, the rubblizing procedure shall begin at a free shoulder edge and work to the longitudinal centerline joint.

Prior to placing the initial bituminous course, the rubblized pavement shall be compacted with 4 passes of a vibratory steel drum roller. The roller shall be operated at a speed not to exceed 6 feet per second. Any depressions in the compacted rubblized base of 1" or greater in depth from that of the surrounding area, shall be leveled using a 3/4", Class "A" crushed choke stone as specified on the plans. Additionally, the crushed choke stone will be used as needed to establish the final gradeline before the initial bituminous course is applied. The crushed choke stone shall then be compacted with the same roller and compactive effort previously described.

Reinforcement in the rubblized pavement shall be left in place. However, any reinforcement exposed at the surface as a result of rubblizing and/or compaction operations shall be cut off below the surface and removed from the site.

Except at restricted crossovers, traffic will not be allowed on the rubblized pavement before the initial bituminous base is in place. No more than 48 hours shall elapse between rubblizing pavement segments and placement of the initial bituminous course. In the event of rain, however, this time limitation may be extended to allow sufficient time for the rubblized pavement to dry to the satisfaction of the engineer.

812.05 METHOD OF MEASUREMENT.

- A. Rubblizing Pavement. The total area of rubblized pavement shall be measured in square yards by the Engineer.
- B. Choke Stone Base. The quantity of choke stone base placed shall be measured as provided in Article 2210.11 of the 1984 Iowa Department of Transportation Standard Specifications.

812.06 BASIS OF PAYMENT.

- A. Rubblizing Pavement. For the number of square yards of pavement rubblized, the Contractor will be paid the contract price per square yard. This payment shall be full compensation for furnishing all equipment and materials, including water, and labor to rubblize the pavement, suppress dust, remove exposed reinforcement, and compact the rubblized pavement until the initial bituminous course is in place.
- B. Choke Stone Base. For the number of tons of choke stone base placed, the Contractor will be paid as provided in Article 2210.12 of the 1984 Iowa Department of Transportation Standard Specifications.

SUBDRAIN TYPICAL SECTIONS





Appendix C Testing

and the second s

.

ARRONAUTER MAIL AND AND AND A

PRECONSTRUCTION ROAD RATER RESULTS HR-315 MILLS COUNTY TESTED ON 08-23-89

MILE	TEST	ACC			NORTH	BOUND	SOUTH	BOUND
POST	SECTION	OVERLAY	DRAINAGE	RUBBLIZED	S.R.	SOIL K	S.R.	SOIL K
		(mm)						
0.075	2	75	YES	YES	2.42	50		
0.150	3	100	YES	YES			2.34	153
0.225	4	100	NO	YES	2.77	50		
0.300	6	125	YES	YES			2.34	50
0.375	7	125	YES	NO	2.50	50		
0.450	7	125	YES	NO			3.13	1.09
0.750	8	125	YES	YES			2.34	60
0.825	8	125	YES	YES	2.04	50		
0.900	8	125	YES	YES			2.77	112
0.975	8	125	YES	YES	2.67	50		
1.050	8	125	YES	YES			2.28	50
1.125	8	125	YES	YES	2.58	50		
1.200	8	125	YES	YES			2.58	50
1.275	9	125	NO	YES	2.42	50		
1.375	10	125	YES	YES			2.58	69
1.425	10	125	YES	YES	2.58	50		
1.500	10	125	YES	YES			2.67	92
1.650	12	100	NO	YES			2.28	50
1.725	13	75	NO	YES	2.42	50		
1.800	15	75	YES	NO			2.77	50
1.850	16	75	NO	NO	3.00	50		
1.900	16	75	NO	NO			2.50	50

VARIABLES FOR REGRESSION ANALYSIS

POINT	TEST	MILE			DEPTH OF	SOIL	DRAINAGE	RUBBLIZED	
NUMBER	SECTION	POST	DIR.	S.R.	ACC (mm)	K VALUE	(0=N, 1=Y)	(0=N, 1=Y)	YEAR*
1	2	0.075	N	3.42	75	127	1	1	1
2	3	0.150	S	1.69	100	191	1	1	1
3	4	0.225	N	1.75	100	187	0	1	1
4	6	0.300	S	1.56	125	155	1	1	1
5	7	0.375	N	1.56	125	50	1	0	1
6	7	0.450	S	1.78	125	184	1	0	1
7	8	0.750	S	1.36	125	50	1	1	1
8	8	0.825	N	1.47	125	121	1	1	1
9	8	0.900	S	1.47	125	69	1	1	1
10	8	0.975	N	1.81	125	115	1	1	1
11	8	1.050	S	1.56	125	53	1	1	1
12	8	1.125	N	1.56	125	53	1	1	1
13	8	1.200	S	1.22	125	50	1	1	1
14	9	1.275	N	1.36	125	50	0	1	1
15	10	1.375	S	2.96	125	120	1	1	1
16	10	1.425	N	3.61	125	147	1	1	1
17	10	1.500	S	2.90	125	164	1	1	1
18	12	1.650	S	1.22	100	50	0	1	1
19	13	1.725	N	0,99	75	50	0	1	1
20	15	1.800	S	0.64	75	50	1	0	1
21	16	1.850	N	0.69	75	50	0	0	1
22	16	1.900	S	1.25	75	50	0	0	1
23	2	0.075	N	2.94	75	50	1	1	1
24	3	0.150	S	1.59	100	62	1	1	1
25	4	0.225	N	1.52	100	52	0	1	1
26	6	0.300	S	1.22	125	50	1	1	1
27	7	0.375	N	1.52	125	93	1	0	1
28	7	0.450	S	1.72	125	94	1	0	1
29	8	0.750	S	1.41	125	50	1	1	1
30	8	0.825	N	1.52	125	93	1	1	1
31	8	0.900	S	1.88	125	73	1	1	1
32	8	0.975	N	1.35	125	50	1	1	1
33	8	1.050	S	2.26	125	139	1	1	1
34	8	1.125	N	1.22	125	50	1	1	1
35	8	1.200	S	1.59	125	50	1	1	1
36	9	1.275	N	1.20	125	50	0	1	1
37	10	1.375	S	2.66	125	50	1	1	1
38	10	1.425	N	3.39	125	50	1	1	1
39	10	1.500	S	3.54	125	170	1	1	1
40	12	1.650	S	1.32	100	50	0	1	1
41	13	1.725	N	0.88	75	50	0	1	1
42	15	1.800	S	1.20	75	50	1	0	1
43	16	1.850	N	0.51	75	50	0	0	1
44	16	1.900	S	0.86	75	50	0	0	1
45	2	0.075	N	2.88	75	180	1	1	2
46	3	0.150	S	1.66	100	. 223	1	1	2
47	4	0.225	N	1.51	100	145	0	1	2
48	6	0.300	S	1.22	125	154	1	1	2
49	7	0.375	N	1.63	125	184	1	0	2
50	7	0.450	S	1.57	125	210	1	0	2
51	8	0.750	S	1.51	125	121	1	1	2
52	8	0.825	N	1.44	125	170	1	1	2

POINT	TEST	MILE			DEPTH OF	SOIL	DRAINAGE	RUBBLIZED	
NUMBER	SECTION	POST	DIR.	S.R.	ACC (mm)	K VALUE	(0=N, 1=Y)	(0=N, 1=Y)	YEAR*
53	8	0.900	S	1.99	125	225	1	1	2
54	8	0.975	N	1.49	125	166	1	1	2
55	8	1.050	S	2.22	125	223	1	1	2
56	8	1.125	N	1.41	125	113	1	1	2
57	8	1.200	S	1.73	125	225	1	1	2
58	9	1.275	N	1.22	125	50	0	1	2
59	10	1.375	S	3.02	125	225	1	1	2
60	10	1.425	N	3.16	125	198	1	1	2
61	10	1.500	S	3.46	125	197	1	1	2
62	12	1.650	S	1.41	100	53	0	1	2
63	13	1.725	N	1.00	75	50	0	1	2
64	15	1.800	S	1.15	75	50	1	0	2
65	16	1.850	N	0.64	75	50	0	0	2
66	16	1.900	S	1.02	75	50	0	0	2
67	2	0.075	Ν	2.98	75	50	1	1	. 3
68	3	0.150	S	2.07	100	180	1	1	3
69	4	0.225	N	1.80	100	50	0	1	3
70	6	0.300	S	1.46	125	67	1	1	3
71	7	0.375	N	1.84	125	73	1	0	3
72	7	0.450	S	1.95	125	177	1	0	3
73	8	0.750	S	2.01	125	97	1	1	3
74	8	0.825	N	1.67	125	50	1	1	3
75	8	0.900	S	2.74	125	173	1	1	3
76	8	0.975	Ν	2.01	125	97	1	1	3
77	8	1.050	S	2.74	125	173	1	1	3
78	8	1.125	Ν	1.71	125	50	1	1	3
79	8	1.200	S	2.20	125	115	1	1	3
80	9	1.275	Ν	1.46	125	50	0	1	3
81	10	1.375	S	3.65	125	107	1	1	3
82	10	1.425	N	3.88	125	125	1	1	3
83	10	1.500	S	3.88	125	185	1	1	3
84	12	1.650	S	1.46	100	50	0	1	3
85	13	1.725	N	0.83	75	50	0	1	3
86	15	1.800	S	1.06	75	50	1	0	3
87	16	1.850	N	4.42	75	225	0	0	3
88	16	1.900	S	1.07	75	50	0	0	3
89	2	0.075	S	3.29	75	132	1	1	4
90	3	0.150	N	1.65	100	130	1	1	4
91	4	0.225	S	1.49	100	50	0	1	4
92	6	0.300	Ν	1.54	125	110	1	1	4
93	7	0.375	S	2.06	125	71	1	0	4
94	7	0.450	N	1.59	125	117	1	0	4
95	8	0.750	N	1.98	125	139	1	1	4
96	8	0.825	S	2.13	125	195	1	1	4
97	8	0.900	N	2.27	125	216	1	1	4
98	8	0.975	S	1.62	125	110	1	1	4
99	8	1.050	N	1.74	125	163	1	1	4
100	8	1.125	S	1.65	125	83	1	1	4
101	8	1.200	N	2.11	125	174	1	1	4
102	9	1.275	S	1.30	125	50	0	1	4
103	10	1.375	N	4.43	125	186	<u> </u>	1	4
104	10	1.425	S	3.93	125	168	1		4
105	10	1.500	Ň	4.53	125	199	1	1	Δ

POINT	TEST	MILE		·	DEPTH OF	SOIL	DRAINAGE	RUBBLIZED	[]
NUMBER	SECTION	POST	DIR.	S.R.	ACC (mm)	K VALUE	(0=N, 1=Y)	(0=N, 1=Y)	YEAR*
106	12	1.650	N	1.43	100	50	0	1	4
107	13	1.725	S	0.94	75	50	0	1	4
108	16	1.850	S	0.58	75	50	0	0	4
109	16	1.900	N	0.95	75	50	0	0	4
110	2	0.750	N	3.34	75	171	1	1	5
111	3	0.150	N	1.14	100	105	1	1	5
112	3	0.150	S	2.11	100	190	1	1	5
113	4	0.225	N	1.46	100	123	0	1	5
114	6	0.300	N	1.30	125	110	1	1	5
115	6	0.300	S	1.54	125	225	1	1	5
116	7	0.375	N	1.80	125	225	1	0	5
117	7	0.450	S	1.70	125	225	1	0	5
118	8	0.750	S	1.90	125	209	1	1	5
119	8	0.825	N	2.48	125	225	1	1	5
120	8	0.900	S	2.46	125	225	1	1	5
121	8	0.975	N	2.01	125	163	1	1	5
122	8	1.050	S	1.60	125	198	1	1	5
123	8	1.125	N	1.63	125	167	1	1	5
124	8	1.200	S	1.98	125	181	1	1	5
125	9	1.275	N	1.51	125	153	0	1	5
126	10	1.375	S	4.13	125	225	1	1	5
127	10	1.425	N	4.07	125	225	1	1	5
128	10	1.500	S	3.59	125	225	1	1	5
129	12	1.650	S	1.57	100	69	0	1	5
130	13	1.725	Ν	0.95	75	50	0	1	5
131	15	1.800	S	0.37	75	50	1	0	5
132	16	1.850	N	0.86	75	50	0	0	5
133	16	1.900	S	1.07	75	60	0	0	5

* 1='90, 2='91, 3='92, 4='93, 5='94

,, ...,

1

1999 - 19

And a second second

:

ONE VARRIABLE LINEAR REGRESSION FOR HR-315 ALL REGRESSION USES THE STRUCTURAL RATING AS THE DEPENDENT VARIABLE

			<u> </u>			
DEPT	TH OF ACC		SOIL K VALUE			
Regressi	on Output:		Regressi	on Output:		
Constant	-	0.401303	Constant	·	0.980689	
Std Err of Y Est		0.873996	Std Err of Y Est	0.761029		
R Squared 0.09359			R Squared		0.312761	
No. of Observations 133			No. of Observations	133		
Degrees of Freedom 131			Degrees of Freedom	I	131	
X Coefficient(s)	0.013521		X Coefficient(s)	0.007872		
Std Err of Coef.	0.003676		Std Err of Coef.	0.001019		
DF	AINAGE		RU	BBLIZED		
Regressio	on Output:		Regressi	on Output:		
Constant	·	1.263888	Constant	·	1.346896	
Std Err of Y Est		0.832038	Std Err of Y Est		0.870315	
R Squared		0.178530	R Squared		0.101210	
No. of Observations 133			No. of Observations		133	
Degrees of Freedom		131	Degrees of Freedom		131	

X Coefficient(s) 0.701949 Std Err of Coef. 0.182762

	YEAR	
Regressio	on Output:	
Constant		1.668980
Std Err of Y Est		0.909041
R Squared		0.019445
No. of Observations		133
Degrees of Freedom		131
X Coefficient(s)	0.084261	
Std Err of Coef.	0.052278	

0.866420

0.162379

IF THE COMPUTED R EXCEEDS THE CRITICAL VALUE 0.222, IT IS REJECTED THAT AT A 1% LEVEL OF SIGNIFICANCE THE NULL HYPOTHESIS THAT THE POPULATION HAS ZERO CORRELATION WITH THE STRUCTURAL RATING.

0.222 SQUARED = 0.049284

THUS ANY R SQUARED VALUE GREATER THAN 0.049284 REJECTS THE NULL HYPOTHESIS AND IS CONSIDERED STATISTICALLY SIGNIFICANT.

DEPTH OF ACC, SOIL K, DRAINAGE, AND RUBBLIZING ALL ARE STATISTICALLY SIGNIFICANT.

REFERENCE

X Coefficient(s)

Std Err of Coef.

STATISTICS MANUAL; EDWIN L CROW, FRANCES A. DAVIS, MARGARET W. MAXIFIELD

MULTIVARIABLE LINEAR REGRESSION ANALYSIS

ALL TEST SECTIONS

Regressior	n Output:				
Constant		0.853684			
Std Err of Y Est		0.723311			
R Squared	0.393412				
No. of Observations	133				
Degrees of Freedom		128			
-	Depth ACC	Soil K	Drainage	Rubblized	
X Coefficient(s)	-0.00390	0.006327	0.460010	0.515267	
Std Err of Coef.	0.003966	0.001115	0.179447	0.164661	
L	·····t·····			han	

RUBBLIZED TEST SECTIONS ONLY

Regression	Output:		
Constant		1.498318	
Std Err of Y Est		0.749286	
R Squared		0.323803	
No. of Observations		104	
Degrees of Freedom		100	
-	Depth ACC	Soil K	Drainage
X Coefficient(s)	-0.00554	0.005468	0.672401
Std Err of Coef.	0.004841	0.001315	0.215458
R Squared No. of Observations Degrees of Freedom X Coefficient(s) Std Err of Coef.	Depth ACC -0.00554 0.004841	0.323803 104 100 Soil K 0.005468 0.001315	Drainage 0.67240 0.21545

ALL TEST SECTIONS

Output:			
	0.544151		
	0.723227		
	0.388814		
133			
	129		
Soil K	Drainage	Rubblized	
0.006143	0.379964	0.460929	
0.001099	0.159975	0.155128	
	Output: Soil K 0.006143 0.001099	Output: 0.544151 0.723227 0.388814 133 129 Soil K Drainage 0.006143 0.379964 0.001099 0.159975	

RUBBLIZED TEST SECTIONS ONLY

Regression	Output:	
Constant	-	0.950829
Std Err of Y Est		0.750437
R Squared		0.314941
No. of Observations		104
Degrees of Freedom		101
-	Soil K	Drainage
X Coefficient(s)	0.005367	0.573822
Std Err of Coef.	0.001314	0.197808

HR 315 MILLS COUNTY ROUGHOMETER

Test	North Bound		South	Bound	Section	Longitudinal	Alligator	Present
Section	Revolutions	Roughness	Revolutions	Roughness	Roughness	Profile	Cracking	Serviceability
		(in)		(in)	(in/mile)	Value*	(ft^2)	Index#
1	36	8	38	9	<u></u>		<u></u>	
1	38	8	36	7	160	2.21	500	2.12
1	36	7	36	8				
2	35	7	35	7				
2	35	6	35	7	142	2.39	600	2.29
2	34	6	37	7				
3	36	5	36	6				
3	37	5	35	6	119	2.65	0	2.65
3	36	5	35	7				
4	36	5	36	7				
4	36	5	35	6	118	2.64	0	2.64
4	36	5	37	6				
5	36	6	36	5				· · · · · · · · · · · · · · · · · · ·
5	35	6	36	5	120	2.66	0	2.66
5	34	6	35	6				
6	48	7	49	8				
6	50	7	47	8	117	2.63	0	2.63
6	51	8	49	8				
7	71	9	74	4				
7	77	10	72	7	79	3.64	0	3.64
7	71	9	74	7				
8	368	62	371	48				
8	369	56	376	50	109	2.84	0	2.84
8	370	57	372	50				
9	55	5	57	8				
9	56	6	56	9	93	3.17	0	3.17
9	58	6	55	8				
10	197	31	198	27				
10	199	32	200	27	111	2.80	0	2.80
10	200	33	199	27				
11	36	6	37	5				
11	33	5	35	5	110	2.82	0	2.82
11	36	6	35	4				
12	36	5	35	4				
12	37	4	36	5	98	3.17	0	3.17
12	35	4	36	6				
13	37	6	35	5				
13	37	6	36	5	109	2.84	0	2.84
13	37	5	38	5				
14	35	6	36	5				
14	34	5	34	5	110	2.82	0	2.82
14	37	5	36	5				
15	38	3	35	3				
15	35	3	37	4	65	4.69	0	4.69
15	38	3	36	3				
16	35	3	35	4				
16	36	3	35	4	75	3.83	0	3.83
16	35	3	34	4				

1 in./mile = 15.8 mm/km

Date Tested 9/8/94

* From BPR Roughness and LPV Correlation Table Dated 06/27/91 # Calculated by Test Method No. Iowa 1004-D, September 1991

BACK CALCULATION OF STRUCTURAL RATING VALUES FOR ORIGINAL PAVEMENT

	RUBBLIZED	
DRAINED	0.022 SR	per inch
UNDRAINED	-0.055 SR	per inch

NONRUBBLIZED				
DRAINED	-0.077 SR per inch			
UNDRAINED	-0.027 SR per inch			

ASSUMPTIONS: BASED ON NOMINAL ACC PAVEMENT THICKNESSES ACC SR VALUE OF 0.44 PER INCH RUBBLIZED HAD 6 INCH PAVEMENT AND 2 INCHES OF CHOKESTONE NONRUBBLIZED HAD 6 INCH PAVEMENT Appendix D Material Testing

<

. .

:

() }

Anna Anna A

A8D9-4001 IOWA DEPARTMENT OF TRANSPORTATION BD OFFICE OF MATERIALS TEST REPORT - ASPHALT MIX DESIGN LAB LOCATION - AMES LAB NO....:A8D9-4001 MATERIAL..... TYPE B INTENDED USE.... SURFACE PROJECT NO.....:SN-6058(1)--51-65 COUNTY MILLS CONTRACTOR: CESSFORD SPEC NO.....:1070.00 SIZE....:1/2 SAMPLED BY..... SENDER NO.: DATE RECEIVED: DATE SAMPLED: DATE REPORTED: 08/16/89 PROJ. LOCATION: ON L63 FROM L40 NORTH TO MALVERN AGG SOURCES: 1/2 CR. LSTONE-SCHILDBERG, SILVER CITY; POTTAWATTAMIE CO; SAND- HALLETT, DAKLAND, PUTTAWATTAMIE CO. P.I.: NOT TESTED JOB MIX FORMULA-COMB. GRADATION 1 1/2" 1" 3/4" 1/2" 3/8" NO.4 NO.8 NO.16 NO.30 NO.50 NO.100 NO.200 100.0 99.0 90.0 70.0 52.0 36.0 22.0 11.0 6.8 5.7 TOLERANCE /100 : 92 7 7 6 5 3 A78004 A78504 MATERIAL MIX 60.00 % AGGR. PROP. 40.00 0.00 0.00 0.00 ASPHALT SOURCE AND косн APPROXIMATE VISCOSITY POISES 1094 % ASPHALT IN MIX 6.00 5.00 7.00 0.00 NUMBER OF MARSHALL BLOWS 50 50 50 0 MARSHALL STABILITY - LBS. 2577 2377 2373 0 FLOW - 0.01 IN. 11 13 0 8 SP GR BY DISPLACEMENT (LAB DENS) 2.238 2.315 0.000 2.276 BULK SP. GR. COMB. DRY AGG. 2.613 2.613 2.613 0.000 SP. GR. ASPH. @ 77 F. 1.031 1.031 1.031 0.000 CALC. SOLID SP. GR. 2.438 2.370 0.000 2.404 % VOIDS - CALC. 8.21 5.31 2.33 0.00 RICE SP.GR. 2.362 2.422 2.395 0.000 % VOIDS - RICE 7.60 4.97 1.99 0.00 % WATER ABSORPTION - AGGREGATE 0.42 0.42 0,42 0.00 % VOIDS IN MINERAL AGGREGATE 18.63 % V.M.A. FILLED WITH ASPHALT 55.92 18.63 13.12 17.61 0.00 70.68 86.78 0.00 CALC. ASPH. FILM THICK. MICRONS 8.37 11.86 0.00 10.11 FILLER/BITUMEN RATIO 0.00 0.86 0.00 0.00 TEMP= 210 WT≍ 7100 SLOPE= 4.96 INTER= -5.40 A CONTENT OF 6.6% ASPHALT IS RECOMMENDED TO START THE JOB.

TOLERANCE ON #200 ALSO CONTROLLED BY FILLER/BITUMEN RATIO. COPIES TO: CENTRAL LAB CESSFORD D. HEINS W. OPPEDAL R. MONROE MILLS

DIST. 4

CO.

IOWA DEPARTMENT OF TRANSPORTATION HIGHWAY DIVISION OFFICE OF MATERIALS PROPORTIONS & PRODUCTION LIMITS FOR AGGREGATES FORM 955 PROJECT NO.: SN-6058(1)--51-65 COUNTY: MILLS DATE: 08/09/89 PROJECT LOCATION: ON L63 FROM L40 NORTH TO MALVERN TYPE OF MIX: 8 CLASS OF MIX: COURSE: SURFACE MIX SIZE: 1/2" CONTRACTOR: CESSFORD CONSTR. CO. TRAFFIC: N/A A.D.T. IDENT # % IN MIX MATERIAL PRODUCER & LOCATION SCHILDBERG SILVER CITY A78004 HALLETT MATLS. OAKLAND A78504 1/2" STONE 60 41409-50 ; CONC. SAND 4MD9-51 40 TYPE AND SOURCE OF ASPHALT CEMENT: KOCH AC-10 GRADATION OF INDIVIDUAL AGGREGATE SAMPLES (Typical, Target, or Average) SIEVE ANALYSIS -% PASSING 1-1/2 3/4 1/23/8 8 30 50 100 200 MATERIAL 1 4 16 ----29 56 1/2" STONE 33 81 18 29 |100 |100 100 98 83 52 000 100 14 11 Ģ 1100 coñc. ł Ιτŏŏ ł i i ł 1 6.3 0.6! SAND ŝĒ 100 PRELIMINARY JOB MIX FORMULA TARGET GRADATION TOLERANCE 5 22 3 6 100! 100! 100! ١, ۰, 70 5.7 30 52 36 COMB GRADING 99 11 6.8 $\begin{vmatrix} 0.02 & 0.04 & 0.08 & 0.14 & 0.30 & 0.60 & 1.60 \\ 1.4 & 2.1 & 2.9 & 3.1 & 3.3 & 4.1 & 9.1 \end{vmatrix}$ TOTAL 28.02 SURFACE AREA C. S.A. SQ. FT./LB. +2.09.1 PRODUCTION LIMITS FOR AGGREGATES APPROVED BY THE CONTRACTOR/PRODUCER 40.0% 60.0% SIEVE | SIZE | 1/2" STONE CONC. SAND МАХ MIN MAX ! MIN MIN MAX MIN MAX MIN MAY 100.0 100.0 1 100.0 100.0 3/4 1/2 3/8 100.0 100.0 100.0 100.0 96.0 76.0 100.0 100.0 000000 866539 9 100.0 100.0 90.0 #4 46.0 100.0 25.0 84.0 24.0 #8 96.0 #30 Τŏ.ō 34.0 #200 1.5 6.0 0.0 COMMENTS: AMES, SAMSON, MILLS CO., CESSFORD, GEARHART, WARM, JOHNSON, SCHILDBERG, HALLETT, ATL. LAB., FILE The above data is furnished for informational purposes only. The Contracting Authority makes no representations as to accuracy, either express or implied, which are to be construed to relieve the Contractor from the responsibility to comply with the specifications. Klin Signed Therafore Huisman Contractor/Producer Engr . 4 789 Signed



Iowa Department of Transportation

Materials Department Ames, Iowa

REPORT OF FIELD CHANGES IN ASPHALTIC CONTRETE MIX PROPORTIONS

CountyMills	Project No
Project Engineer	Mix Number ABD9-4001
Date 9-19-89 Contractor Cess	ford Const.
Type Mix Class	Mix Size <u>1/2"</u>
Basic A.C. %	Lab. Recommend A.C. %
For reasons listed below the field intended asphalt of	content was changed from% to%
Lab. Voids % before change	Lab. Voids % after change
Stability before change	Stability after change
For reasons listed below the (aggregate proportions	- target gradation) were adjusted as follows:
Sand was finer than original sample	Job Mix Formula
	SIEVE TOL. ORIG. REV. SIZE *%* % P. % P.
	<u>34" ± 100 100</u>
	$\frac{12''}{2} \pm \frac{92}{100} 99 - \frac{99}{2}$
	$\frac{36''}{14}$ \pm $\frac{107}{90}$ 90 90
· · · · · · · · · · · · · · · · · · ·	
	$\frac{*0}{430}$ \pm 52 52
	+200 + 357 57

<u>Men E. Miller</u> District Materials Engineer

AAT9-0977

ASSURANCE

IOWA DEPARTMENT OF TRANSPORTATION OFFICE OF MATERIALS TEST REPORT - BITUMINOUS AGGREGATES LAB LOCATION - AMES

LAB NO....: AAT9-0977 INTENDED USE....:SURFACE PRODUCER.....SCHILDBERG CONST CO INC PROJECT NO.....:SN-6058(1)--51-65 CONTRACT #:30059 COUNTY.....:MILLS QUARRY NO.: A78004 SPEC NO.....:4126.90 CONTRACTOR: CESSFORD CONSTR. SOURCE......SILVER CITY SE-31-074N-41W, POTTAWATTAMIE UNIT OF MATERIAL:1 - BAG FROM STOCKPILE AT PLANT SAMPLED BY..... JOHNSON SENDER NO.:4FJ90095 DATE SAMPLED: 09/18/89 DATE RECEIVED: 09/20/89 DATE REPORTED: 09/27/89

LAB NUMBERAAT9-0977TYPE OF AGGREGATESTONESPEC NUMBER CLASS1AFTER 16 CYCLES, F&T METHOD A % LOSS23AFTER 25 CYCLES, F&T METHOD C % LOSS6LA ABRASION % LOSS, GRADING B28

COPIES TO: CENTRAL LAB

GEOLOGYF

DIST.1

DISPOSITION: COMPLIES WITH CURRENT SPECS.

ADVISORY GRADATION TEST REPORT Project SW-60.582 Contract No. 3005 Monitor Sample Design	<u>1)51-65</u> -9 -9
Contract No. 3005 Material Combined Mag. Besign Material Combined Mag. Source Location Sec. TWP Range Country Material Combined Mag. Material Producer Contractor Cess ford Constructor Destination A. C. Plant Contractor Cess ford Constructor Destination A. C. Plant Itab No. Identification Identification Sieve Analysis Percent Passing Percentage Objectionat No. Identification Iab No. Identification Viant No. 4 No. No. 100 No. Identification Image Image Viant No. 4 No. No. 100 No. No. 100 No. No. 100 Image Image No. No. 4 No. No. 4 No. No. 100 No. No. 100 No. No. 20 No. No. 1	-9 :9
Assuance Sample Design	<u>></u> 9
Image: Internal location Source Location SecTWPRangeCounty Material Combined Mag. Material Producer	<u>}9</u>
Plant Location Malerial Source Location Sec. TWP Range County Material Material Combined Agg. Material Producer Beds	Nutrissi,
Material Combined Hgg. Material Producer Beds Contractor Cess ford Constr. Destination A. C. Plant Tested By Wahlert at Lab. 9-19.19.89 Sampled By Johnson at Plant 9-19.19.89 Lab No. Identification of Samples -in. 1 in. % in. % in. No.4 No.8 No.16 No.30 No.50 No.100 No.200 1 Shale 2 Coal 3 Shale 4 Cl Waterial Production Limits Max. 100 97 77 58 30 8.7 1 1 1 1 1 92 83 63 46 20 2.7 1	
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	
Tested By Wahlert at Lab. 9–19.1989 Sampled By Johnson at Plant 9 - Lab No. Identification of Samples Identification Sieve Analysis Percent Passing Percentage Objectionat * Production Limits Max. Image: Max and the second	
$ \begin{array}{c c c c c c c c c c c c c c c c c c c $	<u>LB_, 19_89</u>
Grad. No. of Samples in. 1 in. ¼ in. ¼ in. № in.	e Substances
*Production Limits Max. 100 97 77 58 30 8.7 Min. 92 83 63 46 20 2.7 100	y 5 No. ps Sticks Tons
Limits Min. 92 83 63 46 20 2.7	
4FJ9-97 100 88 70 53 90 26 12 7.2 6.3	
100 98 89 70 54 42 28 13 7.7 6.7	
*Production Max.	
Limits Min.	
Note to County and Resident Engineers—If County or Project Number is incorrect, please notify inspector and Ames Office Promptly. Corrected Reports will be issued. Copies to: contractor, producer, Distr. Engr., Proj. Engr., Ames, As Listed. (Check On	
ESTIMATED QUANTITY	Y0. IS
TOTAL PREVIOUSLY REPORTED	Yd.
Comments F;/e TOTAL REPORTED TO DATE Io Total Reported to Date Total Reported t	∵s Yd. is
*APPROVED by the contractor/producer Signed	

Sample	Date	% AC By	% AC By	% AC By	Marshall	Specific	Lab	Specific	% Voids
Type	Sampled	Extraction	Nuclear	Tank	Stability	Gravity	Density	Gravity High	,
				Measure	(lbs)		<i>w</i> 011011	Pressure Meter	
Assurance	9/18/89	6.16	6.86		2188		2 295	110000.0 110101	
Box	9/15/94	6.38	6.82			2.39	2,290	3.362	3.00
Box	9/18/89		6.86			2.39	2,289	2,365	3.10
Box	9/19/89		6.51			2.39	2.295	2.375	3.30
Box	9/20/89		6.96			2.39	2.291	3.372	3.50
Core	9/19/89						2.216		
Core	9/19/89						2.291		
Core	9/19/89						2.232		
Core	9/19/89						2.249		
Core	9/19/89						2.245		
Core	9/19/89						2.267		
Core	9/19/89						2.229		
Plant Report	9/15/89			6,48			2.236		5.33
Plant Report	9/15/89			6.48			2.262		4.23
Plant Report	9/15/89			6.48			2.242		5.08
Plant Report	9/15/89			6.48			2.255		4.53
Plant Report	9/15/89			6.48			2.272		3.81
Plant Report	9/15/89			6.48			2.262		4.23
Plant Report	9/15/89			6.48			2.314		2.03
Plant Report	9/18/89			6.25			2.235		5.50
Plant Report	9/18/89	;		6.25	······································		2.212		6.47
Plant Report	9/18/89			6.25			2.251		4.82
Plant Report	9/18/89			6.25			2.231		5.66
Plant Report	9/18/89			6.25			2.268		4.10
Plant Report	9/18/89	}		6.25			2.269		4.06
Plant Report	9/18/89			6.25			2.223		6.00
Plant Report	9/19/89			6.33			2.219		6.57
Plant Report	9/19/89			6.33			2.291		3.54
Plant Report	9/19/89			6.33			2.231		6.06
Plant Report	9/19/89			6.33			2.256		5.01

ACC TEST RESULTS

ACC TEST RESULTS

Sample	Date	% AC By	% AC By	% AC By	Marshall	Specific	Lab	Specific	% Voids
Туре	Sampled	Extraction	Nuclear	Tank	Stability	Gravity	Density	Gravity High	
				Measure	(lbs)			Pressure Meter	
Plant Report	9/19/89			6.33			2.250		5.26
Plant Report	9/19/89			6.33			2.270		4.42
Plant Report	9/19/89			6.33			2.230		6.11
Plant Report	9/20/89			6.52			2.249		5.14
Plant Report	9/20/89			6.52			2.173		8.43
Plant Report	9/20/89			6.52			2.218		6.49
Plant Report	9/20/89			6.52			2.194		7.50
Plant Report	9/20/89			6.52			2.230		5.99
Plant Report	9/20/89			6.52			2.215		6.62
Plant Report	9/20/89			6.52			2.202		7.17

Form 820237 6-83 FORM 257 20M 4-71 <u>ASSUI</u>	RANCE S	SAMPLE	10	WA D	PEPAI Mi A/ REPORT	tme aterials MES LAB — BITU	PITO Departn ORATOI	f Tra ^{ment} RY S MATER	nspo	ortati	ion	ASPH. CONC. DISTRICT NO. CO. NO. 65
Material	Unc	compact	ted Mix	6.4	1% A.C.		ц	L	iborator	ry No.	ABC9	-309
Intended U	seSur	face					Contr	ract No	. 300)59	er v til ber v Velerberenner i derense	
Project No	sn-	6058(2	1)51-	·65			Count	y Mi	11s		-	1444 - 4
Contractor	Ces	sford	Constr	ructior)			-				
Producer												
Plant											,	
Unit of Ma	terial	1-bo	ox from	ı proje	ect		sa e e e		,,			
Sampled by	, Joh	inson							Sender	's No	4FJ9	-96
Date Sampl	ed <u>9/1</u>	.8/89		Date	Rec'd _	9/2	5/89	te tare attactioners a	Date B	Reported .	10/3,	/89
<u> </u>				SIEV	E ANAL	YSIS —	PER CE	NT PASS	ING	an an suite an		
	1%''	1''	3 /4''	1/2''	3 /8''	No. 4	No.8	No. 16	No. 30	No. 50	No. 100	No.200
			100	99	89	70	54	40	2.7	12	7.6	6.6
	COLD F	EED GF	RAD.	100	88	70	53	40	26	12	7.2	6.3
	% Ag	gregate	- By Extr	action .							93.84	4
	% Bit % Wi % Vo	umen -) iter latile	By Extra	ction	•	· · · · · · · · · · · · · · · · · · ·						
					770 5							
	Mars	mens mo hall Stat	olded & t	ested @	//° F.						218	8
	Flow, Speci After Mars	, 0.01 Ind fic Gravi 8 cycles	ches ity of F&T	Specime	ns molde	ed @ 40°	F. & tes	sted @ 77	°F.		2.29	5
	Flow, Specie Perc	, 0.01 Inc fic Gravi cent AC	ches ity Inten	Ided		. <u> </u>					6.4	
	<u>Perc</u> Perc	ent AC ent AC	: <u>Centr</u> : Distr	<u>al Lab</u> ict 4	<u> (Nucl</u> Lab (N	<u>ear)</u> uclear)				<u>6.90</u> 6.80	5 5

DIS	PO	ST	тт	n	N
D TO	rυ	υı		U	111

• •

48 By Chi Lane .

PROJECT INFO

48C9-0219 BC

IOWA DEPARTMENT OF TRANSPORTATION OFFICE OF MATERIALS TEST REPORT - ASPHALT CONCRETE LAB LOCATION - DISTRICT 4

LAB NO....:48C9-0219

MATERIAL				
INTENDED USE:SURFACE				1
PROJECT NO: SN-6058(1)-	51-65			1000 militaria (h. 1990). 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 -
COUNTYMILLS		CONTRACTOR:	CESSFORD	I.
SAMPLED BY:		SENDER NO.:	HM1A	4
DATE SAMPLED: 09/15/89	DATE RECEIVED:	09/15/89	DATE REPORTED:	09/20/8
			· · · · · · · · · · · · · · · · · · ·	.

	SIEVE ANALYS	SIS PERCENT	PASSING				
SIEVE	GRAM	PERCENT	PERCENT	TARGET	SPEC LOW	SPEC HIGH	
	RETAINED	RETAINED	PASSING	GRADATION	LIMIT	LIMIT	
3/4		10.00		1.001	0.0		
1/2	0.1	0.00		92.100			
3/8	8.8		0.08	309.700			
4	680.0		6.30	770.000		0.5	
8	1000.0	0.00	460.58			38.0	
16					0.2	500.0	
30		17.02	700.00		11.0		
50				0.000	610.0		
100				0.051		0.0	
200	2708.7						
ASPHALT	CONCRETE RESU	JLTS					
% AC IN	MIX BY NUCLEA	AR GAUGE		6-820			

AC IN MIX DI NUCLEAR GAUGE	0.040
% AC INTENDED	6.400
% AGGREGATE BY EXTRACTION	6.380
% BITUMEN BY EXTRACTION	93.620
SPECIFIC GRAVITY	2.390
LAB DENSITY (50 BLOW-MARSHALL)	2.290
SPECIFIC GRAVITY RICE METHOD	2.361
SPECIFIC GRAVITY HIGH PRESSURE METER	2.362
% VOIDS (50 BLOW-MARSHALL-RICE)	3.00

4BC9-0224					. PRO	DJECT	INFO
E :		IOWA DE	EPARTMENT O	F TRANSPORTA	TION		
			OFFICE OF I	MATERIALS			
		TEST RE	EPORT - ASI	PHALT CONCRE	TE		
		LA	AB LOCATION	- DISTRICT	4		
					• 4809-0224		
MATERIAL	+ 1 / 2 #	TYDE 9 CH	1 22V	LAO NU	+4007-0224		
TENDED I		ACC	435 L				
T DISCT NO	JSESUKF	AUC ACC (1) (1)					
T LUJECI HU	0	2 2020/11-21-	-05	CONTRACTOR	·		
	,	. 3		CONTRACTOR	+UESSEUKU +UMSA		
TTT CANDI	(******* (= = = = = = = = = = = = = = = = = = =			SENDER NU.	• MM2A • DATC 0 COL	10	00/10/00
L TE SAMPI	TED: DAVIEVS	SY DATE	E RECEIVED:	04/18/84	DATE REPL	JKIEU:	04/18/84
						'	
· .	STEVE ANALYS	TS PERCENT	PASSING				
. FVE	GRAM	PERCENT	PERCENT	TARGET	SPEC LOW	SPEC	нтсн
04040	RETAINED	RETAINED	PASSING	GRADATION	ITMIT	I TMT	т
21.1		ne manao				344 A. I.I.A.	,
PHALT CI	INCRETE RESU						
Z AC TN M	TX BY NUCLEA	R GAUGE		6.860			
2 AC INTER	VDED			6.400			
DECTETC (1020 18AVITY			2 390			
AR DENST	TY (50 RINW-	-MARSHALL)		2 289			
CRECIETC /	COAVITY WICH	ARCHALLY	4CTC0	2 2 4 5			
SPECIFIC (50 310W-MADS	1 KLJJUKC /		2.00			
AGTOS (3	JO BEOM-MAKI	INALL-NIUE/		0.10			

PROJECT INFO

IOWA DEPARTMENT OF TRANSPORTATION OFFICE OF MATERIALS TEST REPORT - ASPHALT CONCRETE LAB LOCATION - DISTRICT 4

LAB NO....:43C9-0226

INTENDED USE....: SURFACE PROJECT NO.....: SN-6058(1)--51-65 CONTRACTOR: CESSFORD SAMPLED BY: SENDER NO.:HM3A DATE SAMPLED: 09/19/89 DATE RECEIVED: 09/19/89 DATE REPORTED: 09/19/89

SIEVE ANALYSIS PERC	ENT PASSING				1
SIEVE GRAM PERCEN	T PERCENT	TARGET	SPEC LOW	SPEC HIGH	l
RETAINED RETAIN	ED PASSING	GRADATION	LIMIT	LIMIT	
ASPHALT CONCRETE RESULTS					
% AC IN MIX BY NUCLEAR GAUGE		6.510			(
% AC INTENDED		6.400			(
SPECIFIC GRAVITY		2.390			
LAB DENSITY (50 BLOW-MARSHAL	L)	2.295			Į.
SPECIFIC GRAVITY HIGH PRESSU	RE METER	2.375			
% VOIDS (50 BLOW-MARSHALL-RI	CE)	3.30			(

CC: MILLS COUNTY ENGINEER COPIES TO: CENTRAL LAB DIST. 4

4BC9-0226

BC

PROJECT INFO

IOWA DEPARTMENT OF TRANSPORTATION RC OFFICE OF MATERIALS TEST REPORT - ASPHALT CONCRETE LAB LOCATION - DISTRICT 4 LAB NO....:48C9-0230 MATERIAL.....:1/2 TYPE B NTENDED USE....SURFACE ROJECT NO.....:SN-6058(1)--51-65 CONTRACTOR: CESSFORD SAMPLED BY SENDER NO.: HM4A ATE SAMPLED: 09/20/89 DATE RECEIVED: 09/20/89 DATE REPORTED: 09/21/89 SIEVE ANALYSIS PERCENT PASSING IEVE PERCENT PERCENT GRAM TARGET SPEC LOW SPEC HIGH RETAINED RETAINED PASSING GRADATION LIMIT LIMIT SPHALT CONCRETE RESULTS & AC IN MIX BY NUCLEAR GAUGE 6.960 % AC INTENDED 6.400 2.390 PECIFIC GRAVITY 2.291 AB DENSITY (50 BLOW-MARSHALL) 2.372 SPECIFIC GRAVITY HIGH PRESSURE METER

3.50

COPIES TO: CENTRAL LAB

VOIDS (50 BLOW-MARSHALL-RICE)

4809-0230

DIST. 4

		IOW	A DEPARTMEN	NT OF TRAN	SPORTATION		
ASS	URANCE SAME	PLE	OFFICE	OF MATERI	ALS		ł
		Test	Report - Mi Atlanti	iscellaneo ic Laborat	us Materia ory	ls	
Materia	Asphalt	Cores	11111111111111111111111111111111111111	County	Mills	<u> </u>	
Intende	d Use Dons	ity Verif	icotion	_ Project	NO. SN -6	5058(1)	51-65
Laborato	ory No			Design	No		
Date Re	ported	1-8-89		Contrac	t No.		
Produces	~			Contrac	tor Cas	6Ford	
e la constante de la constante							
Source .	1-	-1.0					
Unit of	Material(1) Asphalt C	ores	_ Subcont	ractor		
Sampled	Ву			_ Senders	No	Ďa	te <u>9-19-89</u>
Station				•		<u></u>	
Dist. CL							
Thickness		······					· · · · · · · · · · · · · · · · · · ·
Technicia	n Results						
W 1	1947,0	1022.0	1295.0	1262.0	2171.0	2520,0	2020,0
₩ 3	1949.0	1024,0	1296.6	1263.0	2172.5	2523.0	2022,0
W 2	1071.5	<u>\$78,6</u>	.715,5	703.5	1207,5	1413.0	1116,0
Diff.	877,5	446,0	<u>580.5</u>	<u></u>	96510	1110.0	906.0
Density	2.219	2.291	2,231	2,256	2-250	2.270	2,230
Air Void	. <u></u>		<u></u>		- (• • • • • • • • • • • • • • • • • • •	
Lab Densi	ty		Rice S	S.P.G			
District	Lab. Results						
₩ 1	1944.5	1022.0	1294,5	1261,5	2169.5	2519,0	2017.5
₩ 3	1946.0	1023.6	1295.0	1262,0	2170,5	2520.0	2018.5
₩ 2	1068,5	577,0	715.0	701,0	1204.0	1409,0	1113,5
Diff.	877,5	446.0	580,0	561.0:	966.5	1111.0	905,0
Density	2,216	2,291	2,232	2-249	2.245	2,267	2.229
REMARKS:	Sulface						

Signed <u>S. 00 Osless</u>

								DAI	LY PLANT	REPOR	r					F	roject 之	N-60	253	1-5
	0	1		BI	TUMIN	ous t	REATE	D BASE, A	SPHALT	REATED	BASE,	ASPHA	LT CO	CRETE		c	ontract No	~		
	orto		$\langle \rangle$	net	•				4.1	1000		21	-7			C)ate	7-1	5-2	57
ontractor	62270	<u>iq (</u>	ĿĬ	27		Plant	Locatio	n/	7/4	lux	4	2°	<i>t</i>				eport No.,	· ····································		<u>`</u>
ant Type	darapi	ids,	Make		VIN	<u>n</u>		Pollutio	n Equipmen	1 <i>//</i>				E Resid	ent Enginee	er	mi	bm	<u>21 </u>	<u> </u>
іх Туре 🗕 🕰		Sart	acesiz	• <u> </u>	2	Crush	ed Agg	r. Sources	$\Sigma h q$	ker;	₽ <i>7</i> 4	WC	YLI	Recyc	e Source _		-A/4	+ .	200	
sphalt Source & I	Grade KOC	<u>h Or</u>	nop	CHC	<u>-10</u>	Sand Se	ources	Halle	2H C	<u>IK (</u>	and	Pl	ant Opera	ted Z:	OFH to	6:45	P.M. Mix I	NO. H.	<u>507</u>	7-400
	, -	SIE	E ANAL	YSIS OF C	OMBIN	ED AGO	REGAT	res	•		_		SA	MPLES S	JBMITTED	•	<u> </u>	AMPLES S	UBMITT	ED
SAMPLE		-			ŞIE	VE NQ.	- % PAS	SING				14	Materi	als	Sender	s No	Mate	erials	Sen	ders No.
JOB MIX FORMULA	- LIMITS		100	92/00	2/7)	41	446	x ·	1/27		27	18 1	D QH	1: •	AC.I	H.				
Spl. ID Time	Compl. 1½	1	3/4	1/4	₩	4/	18	16	30	50 10	o ko	io. 7	Ot M	ix_	HMI	4				
1A 1:00	yes		100	99	88	<u>67</u>	51	38	25 1	36	05	Z				•				
•••	/		•																	
																			L	
												1	ntended A	dded	~ 1 6	~ % A.C				7 7
												ł	ntended 1	otal	2140	<u>2 % A.C</u>	. Tank Me	as. 6.	EFIS	5 % A
LAB. DEN.	2,290		DENSITY	RECORD		S		<u>en. 2</u>	1360	<u> </u>		TEMP	ERATUR	E RECOR	D		M	ATERIALS	DELIVE	RIES
Course Laid	Station	¢ Refer	0	Date Laid	• (1) De	ensity	% Density	% Voids	Time	7	9	1.	1	3	5	Туре	Ticket N	lo.	Quantity
Binder	74400	51	. 9	-15-8	<u> 937</u>	220	236	97.647	15.3	Air Air				60	167	20	AC-10	25	26	6180
	37+20	816	9	15-8	r 41	22	262	98-111	4.2	5 A.C.				_ 29	2 290	285	AC-10	382	2 6	05
<u>ä</u>	42+40	34	- 9.	15-8	233	A-7:	242	97,904	50	Aggr.							AC10	389	E	5017
	17+00	712	9.	15-8	15	7:	255	98:472	4-5	3 Mix	_			_ 29	<u> 290</u>	290	AC-10	406	2	5486
11	51+20	4%	9.	15-8	94	- 2	272	99.214	3.8	Mat							AC-10	Z9:	2 4	<u>6207</u>
	57+35	71	. 9-	15-8	235	82	262	98.)17	4.2.	3		REC	YCLED	AIX ONLY			AGIO	410) 6	<u>5203</u>
<i>I</i> l	63+09	34	9-	15-8	74	2	214	107.04.8	120	J Total	AP Used	d Tons								-
			/	~ ,			- ,,			Total	Aggr. Use	ed Tons								
										RAPL	sed %									
										Aggr.	Jsed %									
Avg. Field Density	Lot #1 98	183:	3-2	263	}						PRODUC	TION A	ND PLA	CEMENT	RECORD					
Avg. Field Density	Lot #2				* (2	2) 5	Side	C	ourse Laid			From	Station I	o Station		Тс	ns Today		Tons T	o Date
Fines/Bitumen Ra	tio = (). 80				3	41	_	Bir	der		64	1+1	24.6	62	460	7.6	26:5-			<u>_</u>
Ave. % Field Void:	4.18				7			•								110	32.9	21	,03	<u>37.9</u>
Lab % Voids =	3.0										ļ					/			·	
Q.1. (Density) = '	2.60							Sprinkle			L	·, ·····			l		,			
(Show Calculati										e.	1	3/4	1/2	3/8	4	8	16	30 50	10	0 200

98.833-95.000

COMMENTS: Delays, Breakdowns, Corrective Action, etc. *Thickness: (1) Actual, (2) Intended Bituminous Treated Base: Enter % Moisture in % Voids Column

.

Signed Inspector Cert. No. MATERIALS OFFICE -- PERIODOR GENERAL CONT

Form 820007 11/87 H-1789					·	lowa Department of Transportation													BET	3 198 9 C	e ountv	Mi	115		BJ		
									DAILY PLANT REPORT												P	roject 🛓	SN	605	8().	5-65	
				_	1		E	BITUMIN	INOUS TREATED BASE, ASPHALT TREATED BASE, ASPHALT CONCRETE												с	ontract	No. 0	10	00		
			n Dee	·La	1		n-t	-	Halung, 2d												Date 7-18-87						
Contractor Cassific ONST								a. 1.11	Plant	Locatio	n	_//	1900	wu	7	<u> </u>					R	eport No		\leq			
Plant Type DV CLYN Make CCC									Pollution Equipment											Jent Engineer <u>II F b MEIEV</u>							
	Mix Type		(IN	Crushed Aggr. Sources Line (a) Crushed Aggr. Sources										tecycie 73/11	revele source												
	Aspirat	bource a	Graue			EVE AN	LYSIS OF		OMBINED AGGREGATES										ES SUB	SUBMITTED SAMPLES 5						<u> </u>	
		SAMPLE						S	EVE NO	% PA	SSING				Mat			laterials ,	,	Sender	rs No. Materials			Sende		No.	
	JOB MI	K FORMUL	A - LIMITS			100 92/10 2			Jar 63/17 44/			58 11/27			2-787		HotMix		XA	HM7 A							
	Spl. ID	Time	Compl.	1½	1	1 3/4 1/2			4	8	16		30 50	0 10	0	200	11 11		H	HHIB		<u> </u>					
4	FZH	7:30	YES			100	2/00	89	69	5	3 4	<u> Z</u>	713	3 7	5	66	AC IU		Ľ	ACIB							
							_	+									/	7	-F	CZ	H	<u> </u>					
	•																					1		l	· · · · ·		
			1	+							_{						Inten	ded Adde		.41	<u>, % A.C.</u>	Toolu		512	15	N A C	
	Cou	Course Laid Station			¢ Refe	ar locitos	Date Laid		1) D	ensity	% Dens	sitv	% Voids	Time	T	7	9	11	1	3	5	Туре	Tic	ket No.	Qua	ntity	
	Ri	der	16-1	00	74	5	7-18-	89 7.	135 -	36	97.6	41	5.50	Air		56	12	20	78	84	79	AI	01	47	5.5	71	
	11		21+	40	715	र 7	r)	7:	423	518	96.6	36 6	6.47	A.C.	-	305	302	295	300	300	300	ALI	04	48	67	63	
			391	ť 10	31	2	<i>!'</i>	Z	251 -	3-78	98.3	40	4.82	Aggr.								Plat	04	4 1	62	30	
	11		5/+	. 30	81	<u> </u>	н	2	231 2	14	77.4	6	5.6K	> Mix		320	305	280	290	285	2.90	HO	04	53_	36	02	
5	<i>µ</i>	" 65+80		611	<u>61R "</u>		2	268 :	3	79.08	52	<u>4.10</u>	Mat	<u> </u>							He	04	57	62	76		
01		" 74+35		135	51	516 11		_ 2	<i>16</i>	13 74 9		91. ZE 406				I	RECYCL	ED MIX	ONLY			RL!	0 Z	335	6408		
			901	180	<u>8'/("</u>		Z	237	76	8 97117 6			Total F	RAP	Used To	'ns				/2.st		t 5	5357		1000		
														Total /	٩ggr	. Used T	ons						R.C. 754		10 140.		
						 								RAPU	ised	%						Дw	12	<u>5 H4</u>	920	245	
		2201								ł	······		Aggr. Used %									<u> </u>					
	Avg. Fi	eld Density	y Lot #1		271				* (2) Side Course Laid Erom Station									FLACEM	ation	CORD		ns Today To			ons To Date		
		Sid Densit	y 201 #2	Ð6				3	4	14	13	ina	PV	·····	77+70 - 6+00					Tons roday							
	FINES/E	Situmen Ra Field Void		72				3	4	Ŕ+	R	w	e.V		–	6+00 - 99+9			+4/	>	218	37.	4.0	10 37.7		32	
	Ave. % Field Voids =							-		~	 +++++++++++++++++++++++++++++++++				1		~~~~~						1				
										Sprin	kle		***************************************	1	*****												
(Show Calculation)														1	¾	1/2	⅔	4	8	16	30	50	100	200			
	(00							C	OMMEN	ITS					l										· · · · · · · · · · · · · · · · · · ·		
670, E.95 1000 ·										· · · · · · · · · · · · · · · · · · ·									-								
×	$\sqrt{2}$	1/1	15-	15			2	00																			
ß	IV =		<u> </u>			-	$= \mathcal{D}_{\ell}$																				
-1		O	.47	\mathcal{O}																							
		-																									

COMMENTS: Delays, Breakdowns, Corrective Action, etc. *Thickness: (1) Actual, (2) Intended Bituminous Treated Base: Enter % Moisture in % Voids Column

~~~

|   |                      |                              |        |              | )   | Λ    |      | Λ    |           |       |
|---|----------------------|------------------------------|--------|--------------|-----|------|------|------|-----------|-------|
|   |                      |                              | Signèd | Anne         |     | hoer | INT  | :k   |           |       |
| 1 | managenerations<br>2 | <br>يىمىتىمى يىلىش<br>:<br>ن |        | IIIspector / | ALS | <br> | 1150 | TERY | Cert. No. | ~~~~~ |

-1188 007 1 ner. Trai BI 3 1989 County ACT DAILY PLANT REPORT Project BITUMINOUS TREATED BASE, ASPHALT TREATED BASE, ASPHALT CONCRETE Contract No Date Contracto Plant Location Report No. a vand SC hmeier Resident Engineer Tim Plant Type Make /d Ver Recycle Source 11 Mix Type Class Crushed Aggr. Sour Plant Operate 6:40 A.M. 106:36P.M. Asphalt Source & Grade Koc Sand Sources H Mix No SIEVE ANALYSIS OF COMBINED AGGREGATES SAMPLES SUBMITTED SAMPLES SUBMITTED SAMPLE SIEVE NO. - % PASSING Materials Senders No. Materials Senders No. s JOB MIX FORMULA - LIMITS oves Spl. ID. Time Compl. 200 1% 1 16 30 100 50 11 UPS 39 7:3/ -3 44 21 11 ssurance ٦ 47 フロ 50 Intended Added % A.C. % A.C. Tank Meas. 3 3 Intended Total % A.C. 295 SOLID DEN. 2.375 LAB. DEN. **DENSITY RECORD TEMPERATURE RECORD MATERIALS DELIVERIES** ¢ Refer % Voids Course Laid Station Date Laid • (1) Density % Density Time 11 Туре Ticket No 3 5 Quantity 4 2 80 78 5 7-9.00 Air 551 300 300 A.C. 3NC 300 Aggr. 310 300 300 295785 300 Mix 56 Mat **RECYCLED MIX ONLY** Total RAP Used Tons Total Aggr. Used Tons RAP Used % Aggr. Used % 2,250 Avg. Field Density Lot #1: 5. 7 6 PRODUCTION AND PLACEMENT RECORD Avg. Field Density Lot #2 Course Laid (2) Side From Station to Station Tons Today Tons To Date 90 Fines/Bitumen Ratio =  $O_2 Q S$ OV Ave. % Field Voids = 5.24 ace 4*0(*) Sar toce Lab % Voids = 3.57 Sprinkle Q.I. (Density) = 3.07 \* % 30 50 100 (Show Calculation) 1 1/2 4 8 16 200 COMMENTS

<u>98.020-95.000</u>-3.02-1.107,

COMMENTS: Delays, Breakdowns, Corrective Action, etc. \*Thickness: (1) Actual, (2) Intended Bituminous Treated Base: Enter % Moisture in % Voids Column

Signed Cert. No. FICE-RECORDS CENTER COPY S

| Form 820007 11/87 H-1188                              |                                 |                                |              |             |                 |          |                         |                 | 4                                                             | low         | a Dep                                 | artm | ento     | fTran              | sport     | ation             | l                          |                                                   |              | c                   | ounty Hills                                   |                          |                   |             |            |  |  |  |
|-------------------------------------------------------|---------------------------------|--------------------------------|--------------|-------------|-----------------|----------|-------------------------|-----------------|---------------------------------------------------------------|-------------|---------------------------------------|------|----------|--------------------|-----------|-------------------|----------------------------|---------------------------------------------------|--------------|---------------------|-----------------------------------------------|--------------------------|-------------------|-------------|------------|--|--|--|
|                                                       |                                 |                                |              |             |                 |          |                         |                 | DAILY PLANT REPORT                                            |             |                                       |      |          |                    |           |                   |                            |                                                   |              |                     |                                               | Project 5/1-60.53()5/-65 |                   |             |            |  |  |  |
| BITUMINOUS TREATED BASE, ASPHALT TREATED BASE, ASPHAL |                                 |                                |              |             |                 |          |                         |                 |                                                               |             |                                       |      |          | LT CONC            | RETE      |                   | С                          | ontract I                                         | <b>~</b> ⊙^∕ | 20                  |                                               |                          |                   |             |            |  |  |  |
| •                                                     |                                 |                                |              | for         | 11              | AV       | n < 1                   | •               |                                                               |             |                                       | Uir  | 1 he     | 1111               | / -       | 21                |                            |                                                   |              | D                   | ate                                           | 7-                       | 20-               | <u>' 87</u> |            |  |  |  |
| 1                                                     | Contractor                      | -CC                            | 22           | m           |                 | ЮП       | 24                      | 3.10            | Plapt location Plant Co                                       |             |                                       |      |          |                    |           |                   |                            |                                                   |              |                     |                                               | Report No. 4 DCT -3      |                   |             |            |  |  |  |
|                                                       | Plant Type                      | T                              | <u>NU I</u>  | <u> </u>    | VING            | Make     | Cepi                    | <u>1 / ()</u>   | Cruched Ager Sources Schild How Silver City Basident Engineer |             |                                       |      |          |                    |           |                   |                            |                                                   |              |                     |                                               | ND                       |                   |             |            |  |  |  |
| 1                                                     | vix type .<br>Senhalt So        | -49-                           | endo         |             | c la            | D        |                         | 8               | Crusi                                                         | ned Aggr.   | Sources                               | 24   | ()       | .IA                | Jud       | Pie               | Y                          | Hecycle                                           | Source _     | Gar                 |                                               | v No Z                   | ORT               | Y-CH        | 201        |  |  |  |
|                                                       | spnan 30                        |                                | srade        | fΣα         |                 |          | VSIS OF                 |                 |                                                               | GREGAT      | 7 <i>1</i> 2.1.11<br>FS               | 211  | <u></u>  | MITTED             |           |                   | SAM                        | PLES SUE                                          |              | ~                   |                                               |                          |                   |             |            |  |  |  |
|                                                       | :                               | SAMPLE                         |              |             | 012,1           | - A.G.A. |                         | SIE             | VE NO.                                                        | - % PAS     | SING                                  |      |          |                    |           | -                 | Materials Senders No       |                                                   |              |                     | Materials                                     |                          |                   | Senders No. |            |  |  |  |
|                                                       | JOB MIX I                       | FORMULA                        | - LIMITS     | 1           | T               | 1117     | 924100                  | 8367            | 19762/17 4/58 ZG                                              |             |                                       |      |          |                    | 27        | k                 | ACIO                       |                                                   | AC3A         |                     |                                               | lix                      | /                 | HU4A        |            |  |  |  |
|                                                       | Spl. ID                         | Time                           | Compl.       | 1½          | 1               | 3/4      | 1/2                     | 3/8             | 4                                                             | 8           | 16                                    | 30   | 50       | 10                 | 20        | 0                 | 1                          |                                                   | 13           | B                   |                                               |                          |                   | UM 3        | B          |  |  |  |
| C                                                     | F4A                             | 7:34                           | ~            |             |                 | 100      | 99                      | 90              | 69                                                            | 5           | 3 40                                  | Z    | 5 12     | 26                 | 86        | 0                 | 11                         | 12                                                | 12.3         | Č.                  |                                               | 11                       | '                 | 443         | <u>C</u> . |  |  |  |
| -                                                     |                                 |                                |              | 1995 g      |                 | 14 a. a. |                         |                 |                                                               |             | e e e e e e e e e e e e e e e e e e e |      |          | er, Brij           |           | र हा              | 11                         |                                                   | 96.4         | <u>A</u>            |                                               |                          |                   |             |            |  |  |  |
|                                                       |                                 |                                |              | gyana.      | र्कुले, उठा     | 김성영동     | 1. 12) <sup>1</sup> . 1 | a Prisi         |                                                               | : Proji     |                                       |      | en faite | co. New            | 29 0.2    |                   | Ċox                        | es                                                |              |                     |                                               |                          |                   |             |            |  |  |  |
|                                                       |                                 |                                |              | ļ           | er d'as         | :<br>    |                         |                 |                                                               | .           |                                       |      |          |                    |           | In                | itended Add                | led                                               | 11           | _ % A.C             |                                               |                          |                   | a P         |            |  |  |  |
|                                                       |                                 |                                |              |             |                 |          |                         |                 |                                                               |             |                                       |      |          |                    |           |                   |                            | Intended Total 6 7 4 March Tank Meas. 2 6 March 4 |              |                     |                                               |                          |                   |             | % A.C.     |  |  |  |
|                                                       | LAB. DEN. Z.1291 DENSITY RECORD |                                |              |             |                 |          | <u>D</u>                |                 |                                                               | <u>en. </u> |                                       | 712  | F        | TEMPERATURE RECORD |           |                   |                            |                                                   | T _          | MATERIALS DELIVERIE |                                               |                          | LIVERIES          | 3           |            |  |  |  |
|                                                       | Course                          | e Laid                         | Stat         | ion         | ¢ Refer         |          | Date Laid               | 754             | 20                                                            | ensity      | % Densil                              | y %  | Voids    | Time               | 5         | 9                 | 7 10                       |                                                   | 1 cm         | 5                   | Type                                          |                          | icket No.         |             | antity     |  |  |  |
|                                                       |                                 | <u>r tace</u>                  | 11           | 20          | 10              | /        | -20-2                   |                 | 04                                                            | 241         | <u>70 % 0</u>                         |      | 214      | Air                | 20        | 1 20              | - 67<br>m 795              | 1200                                              | 205          | 4                   | AC.                                           |                          | $\frac{16C}{172}$ | -03         | 3/1        |  |  |  |
|                                                       |                                 | 1<br>1                         | 123          | HID         | 40              |          | <u> </u>                |                 | 5                                                             | 2.84        | 17.8                                  | 42   | .10      | Anor               |           | <u></u>           | 000                        | CN                                                | 675          |                     | AC                                            | 11 2                     | +42               | 121         | al         |  |  |  |
|                                                       | <br>//                          | -                              | 271          | $+\alpha 0$ | $\frac{62}{74}$ |          | <br>#                   | 13              | 55                                                            |             | 25.90                                 | 417  | .50      | Mix                | 371       | 2 79              | 5 21                       | 300                                               | 300          |                     | AU                                            | 02                       | 229               | -6-         | <u> </u>   |  |  |  |
| 57                                                    |                                 |                                | 31           | 100         | 6R              |          | 11                      | 7               | 11 2                                                          | .730 4      | 17.33                                 | 75   | -99      | Mat                |           |                   |                            |                                                   |              | 1                   | HU                                            | 0 0                      | 184               | 161         | 58         |  |  |  |
|                                                       | 1                               |                                | \$4          | +20         | 76              | •        | 11                      | $ \mathcal{T} $ | 134771566,683 6.62                                            |             |                                       |      |          |                    |           | RECYCLED MIX ONLY |                            |                                                   |              |                     |                                               | n <                      | 1Ŷ4               | 3           | 357        |  |  |  |
|                                                       |                                 |                                | 91           | +40         | 38              | 3R 4     |                         |                 | 1 Z                                                           | 202 5       | 6.11:                                 | 5 7  | 1.17     | Total F            | AP Use    | d Tons            | ons                        |                                                   |              |                     | ×+C                                           | ٩_                       |                   |             | <u> </u>   |  |  |  |
|                                                       |                                 |                                |              |             |                 | <u> </u> |                         |                 |                                                               | _ /         |                                       |      |          | Total A            | lggr. Use | ed Tons           |                            |                                                   |              |                     |                                               |                          |                   |             |            |  |  |  |
|                                                       |                                 |                                | · · · · ·    |             |                 |          |                         |                 |                                                               |             |                                       |      | de ty co | RAP U              | sed %     |                   |                            |                                                   |              |                     |                                               |                          |                   |             |            |  |  |  |
|                                                       |                                 |                                | <u> </u>     | L           | ~ ~ ~           | -        |                         |                 | <u> </u>                                                      | <u> </u>    |                                       |      |          | Aggr.              | Jsed %    |                   |                            |                                                   |              |                     |                                               |                          |                   |             |            |  |  |  |
|                                                       | Avg. Field                      | Avg. Field Density Lot #1 Lill |              |             |                 |          |                         |                 | ( i t PRODI                                                   |             |                                       |      |          |                    |           |                   | CTION AND PLACEMENT RECORD |                                                   |              |                     |                                               |                          |                   |             |            |  |  |  |
| Avg. Field Density Lot #2                             |                                 |                                |              |             |                 |          | - 11                    | $\mathbf{Z}$    | Side                                                          |             | Course                                |      | >        | -7.                |           |                   |                            |                                                   | 10           |                     | ~ <u>~</u> ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ |                          |                   |             |            |  |  |  |
| Fines/Bitumen Ratio = 74                              |                                 |                                |              |             |                 |          | 17                      | 2               | ê 🕂                                                           | Zu,         | 1 10                                  | 200  | ð.       | 2700 - 101101      |           |                   |                            |                                                   | /57          | 83.13 2513.7        |                                               |                          | 7/-               |             |            |  |  |  |
| Ave. % Field Voids = 6 .                              |                                 |                                |              |             |                 |          |                         | 6-6             |                                                               | >+          |                                       |      | 40       |                    | 101       |                   | C                          |                                                   |              |                     |                                               |                          | -                 |             |            |  |  |  |
|                                                       |                                 |                                | 20           | <u>ئ</u> لر | -T 1            |          |                         |                 | Sprinkle                                                      |             |                                       |      |          |                    |           |                   |                            |                                                   |              |                     | •                                             |                          |                   |             |            |  |  |  |
|                                                       | (Show                           | Calculatio                     | 4 <b>6</b> 6 | 2           |                 |          |                         |                 |                                                               |             |                                       |      |          |                    | 1         | 3⁄4               | 1/2                        | 3%                                                | 4            | 8                   | 16                                            | 30                       | 50                | 100         | 200        |  |  |  |
|                                                       |                                 |                                |              |             |                 |          |                         |                 | COMMENTS                                                      |             |                                       |      |          |                    |           | ]                 |                            |                                                   |              |                     |                                               |                          |                   |             |            |  |  |  |

QI=96,558-95,000 = 1,466 +466-1.063

COMMENTS: Delays, Breakdowns, Corrective Action, etc. \*Thickness: (1) Actual, (2) Intended Bituminous Treated Base: Enter % Moisture in % Voids Column

t Signed Cert. No. nspecto OF E-RE DS ER TE



.



Typical Longitudinal Cracking



Load Related Pavement Failure



Complete Joint Failure



PB4 Pavement Breaker



PB4 Pavement Breaker in Operation





Impact Foot of PB4 Pavement Breaker

Rubblizing in Process



Rubblized Section of Pavement



Application of Choke Stone Using "Jersey" Spreader



Compaction of Choke Stone