

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: May 20, 2014  
Date of Addendum: April 29, 2014

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
304	97-0201-116	GRADING	WOODBURY	NHSX-020-1(116)--3H-97 NHSX-020-1(131)--3H-97 NHSX-020-1(140)--3H-97 NHSX-020-1(141)--3H-97 NHSX-020-1(142)--3H-97	20MAY304.A01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the PLAN for Project No. NHSX-020-1(116)--3H-97:

SHEET C.2:

Add the following note to the ESTIMATE REFERENCE INFORMATION for the item 2105-8425020, TOPSOIL, STRIP AND STOCKPILE:

It is anticipated that there will be excess top soil. The excess topsoil must be placed within the three designated storage areas. These storage areas are located on the north side of the ROW between the need line and the new ROW. Each area also has a minimum stockpile requirement.

Topsoil Storage Area	Minimum Stockpile
10380+00 to 10405+00	96,000 CY
10480+00 to 10500+00	42,000 CY
10585+00 to 10620+00	20,000 CY

Drainage ways shall not be blocked by topsoil stockpiles. If temporary culverts are needed this will be incidental to the stockpile bid item.