

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: July 15, 2014
Date of Addendum: July 10, 2014

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
005	10-3385-601	BRIDGE REPLACEMENT - CCS	BUCHANAN	BROS-3385(601)--5F-10	15JUL005.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0200 2501-5478053 CONCRETE ENCASEMENT OF STEEL H PILES, HP 12 X 53 (P10L TYPE 3):

From: 498.000 LF
To: 522.000 LF

If the above change is not made, it will be made as shown here.

Make the following changes to the plan:

Plan sheet C.1:

Add the following Estimate Reference Information to Item 2101-0850001 CLEARING AND GRUBBING:

Tree trimming is allowed as needed to accommodate placement of fishing pier piling.

Add the following Estimate Reference Information to Item 2401-6745625 REMOVAL OF EXISTING BRIDGE:

Existing abutment removal shall be to 1' above the normal water elevation, removal shall be in a uniform manner to allow the existing abutment to retain proposed revetment.

Add the following Estimate Reference Information to Item 2501-5478053 CONCRETE ENCASEMENT OF STEEL H PILES, HP 12 X 53 (P10L TYPE 3):

Encasement shall be to 1' below the existing stream elevation instead of 3' as specified on the P10L detail.

Add the following Estimate Reference Information to Item 2507-6800061 REVETMENT, CLASS E:

Revetment shall be filled in behind the existing structure abutment in the areas of the existing structure abutment and the Toe in detail is not relevant in the area behind the abutment. Outside the areas of the existing abutment the revetment shall be toed into the stream bank as shown on the detail on V.1 placed at the elevation as determined by the engineer. It is not the intent that the revetment shall be placed to three feet below the bottom of the streambed.

Plan Sheet V.1:

Replace plan sheet V.1 with attached plan sheet V.1

