

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: October 21, 2014
Date of Addendum: October 15, 2014

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
302	58-0613-057	GRADING	LOUISA	NHSX-061-3(57)--3H-58 NHSN-061-3(77)--2R-58	21OCT302.A02

Add the following to the PROPOSAL SPECIAL PROVISIONS LIST and the PROPOSAL SPECIAL PROVISIONS TEXT:

720.121 ATTACHMENT OF "POINT 25 UTILITY DATA"

*** POINT 25 Utility Data ***

This Estimating Proposal has an attachment of the "POINT 25 Utility Data". This attachment is a part of the proposal form.

Add the attached Utility Bid Attachment to the Proposal



Iowa Department of Transportation

UTILITY BID ATTACHMENT

County:

Louisa

Project Classification:

Point 25

Project No.:

NHSN-061-3(55)--2R-58 (ROW)

NHS-061-3(48)--19-58 (CONST)

District Utility Coordinator:

Bonnie Clancy

Iowa Department of Transportation

District Utility Coordinator

Highway Route Number or Name:

US 61

307 W. Briggs

Fairfield, IA 52556-0587

Segment or Section:

130th St 2 miles S of IA 92 to Muscatine Co

Utilities:

This project comes under the provisions of IAC 761-Chapter 115.25 Iowa Code.

Some of the utility work described below is dependent on prior work being performed by the Contractor at a specific site. In such situations the Contractor shall provide the Engineer and the affected utility a good faith notice of when the utility is to start work at the site. The notice shall be given 14 calendar days in advance of when the Contractor expects to complete the prior work and the site will be available to the utility. The Contractor shall follow up with a confirmation notice to the Engineer and the utility not less than 3 working days before the site will be ready for the utility to begin its' work.

Additional detailed information regarding the location of relocated utility facilities is available on the permits issued to the utility companies. These permits can be viewed at the District office during normal working hours. Contact the **District Utility Coordinator at 641-469-4013.**

Facilities- Affected:

Alliant Energy (Electric Distribution): Permit has been approved. Utility is scheduled to be moved before October 1, 2014. The lighting will be maintained during the construction of this project at the intersection of Hwy 61 and IA 92.

Alliant Energy (Gas Distribution): Permit has been approved. Relocation is scheduled to be before October 1, 2014. The installation will consist of a 2" steel coated pipe between Sta. 882+82 and Sta. 887+81 in existing ROW. The relocated main to lay in first 5 feet of corridor adjacent to north ROW line of old highway 61. depth of installations is to be 4 foot.

The existing 2" SCH 40 steel natural gas pipe will be abandoned in place between approximately Sta. 885+00 to Sta. 892+00. It is estimated to be buried 2 to 6 feet deep. There is a fibrous coating called mill wrap on this pipe that does NOT contain asbestos or other hazardous substances. The pipe will be blown out and capped at both ends. If this pipe is encountered during construction between by the contractor it can be cut, removed and capped at any areas needed. This is the contact person that is doing the work for Alliant on this pipeline. Gary Brindle (641) 754-5813 office / (319) 551-8488 cell / garybrindle@alliantenergy.com

Eastern Iowa Light and Power Cooperative (Electric): Permits approved. Relocates are scheduled to be done by October 1,2014. The lighting for the intersection of Hwy 61 and 170th Street at the L&M School will be maintained during construction project.

G4S Technology LLC (Local Fiber Optic): Utility is affected near IA 92 intersection. May also be affected along US 61 throughout the project. They are still looking over the plans for further involvement.

MidAmerican Energy Company (Electric Transmission): There is a high voltage line that was designed around and should not be affected. See special note on plan sheet D9.

Windstream (Local Fiber Optic): There is a fiber line (formerly Paetec) that will need to be relocated that crosses Hwy 61 and 160th street between stations 905 and 915. They plan to relocate this line this fall, but it may be next spring as this will not be affected until the new lanes are paved and the detour is ready to be built. It is not in the construction area for part of the grading project.

Windstream Communications of Iowa (Local Fiber Optic): Permits approved. Utility is scheduled to be relocated before October 1, 2014.

-- END --