

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: January 21, 2015
Date of Addendum: January 8, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
107	67-0295-236	PCC PAVEMENT - GRADE AND NEW	MONONA	IMX-029-5(236)101--02-67	21JAN107.A02

Make the following change to the PLAN:

Replace SHEET NUMBER C.2 and C.5: With the attached SHEET NUMBER C.2 and C.5:

The RF-26 was removed from the plan during District review, however it did not get deleted from the ERI reference and the Standard Road Plan.

102-5
10-16-12

EXISTING PAVEMENT

No.	Location		Year	Type	Project Number	Surface		Base		Subbase		Removal		Coarse Aggregate		Durability Class	Reinforcement Type	Remarks
	County	Route				Dir. of Travel	Begin Milepost	End Milepost	Type	Depth IN	Type	Depth IN	Type	Depth IN	Type			
HARRISON	I-29	BOTH	2010		ES1MX-025-5(100)95--15-43	HMA	4											
HARRISON	I-29	SB	1992		IR-29-5(72)95--12-43	HMA	5.5											
HARRISON	I-29	SB	1992		IR-29-5(72)95--12-43	HMA	2											
HARRISON	I-29	SB	1987		IR-29-4(33)72--12-43	HMA	2											
HARRISON	I-29	BOTH	1967		I-1G-29-5(15)103--04-67	PCC	8	GSB	4									
MONROA	I-29	BOTH	2010		ES1MX-025-5(100)95--15-43	HMA	4											
MONROA	I-29	BOTH	1992		IR-29-5(72)95--12-43	HMA	5.5											
MONROA	I-29	BOTH	1967		I-1G-29-5(15)103--04-67	PCC	8	GSB	4									

110-11
04-16-13

REMOVAL OF PAVEMENT

Refer to Tabulation 102-5

Begin Station	End Station	Side	Pavement Type	Area	Saw Cut*	Remarks
STAGE 1						
2398+00.00	2410+42.79	RT	HMA/PCC	499.9	1251.0	REMOVAL OF NB INSIDE SHOULDER SIX INCHES BEHIND TBR.
2412+05.19	2423+00.00	RT	HMA/PCC	440.4	1101.0	REMOVAL OF NB INSIDE SHOULDER SIX INCHES BEHIND TBR.
2394+98.00	2410+47.80	LT	HMA/PCC	6888.0	93.4	SB MAINLINE AND SHOULDERS
2412+10.30	2427+50.00	LT	HMA/PCC	6842.8	93.4	SB MAINLINE AND SHOULDERS
STAGE 2						
2394+98.00	2398+00.00	RT	HMA/PCC	1342.2	40.0	NB MAINLINE AND SHOULDERS
2398+00.00	2410+42.79	RT	HMA/PCC	5023.6	53.4	NB MAINLINE AND SHOULDERS EXCLUDING PAVEMENT BEHIND TBR
2412+05.19	2423+00.00	RT	HMA/PCC	4425.5	53.4	NB MAINLINE AND SHOULDERS EXCLUDING PAVEMENT BEHIND TBR
2423+00.00	2427+50.00	RT	HMA/PCC	2000.0	40.0	NB MAINLINE AND SHOULDERS

100-27
10-20-09

PAVEMENT SMOOTHNESS + PCC TEXTURE

Road Identification	Begin Station	End Station	Proposed Posted Speed	Remarks
I-29 SOUTHBOUND	2394+98.00	2427+50.00		MAINLINE
I-29 NORTHBOUND	2394+98.00	2427+50.00		MAINLINE

110-7
04-16-13

REMOVAL OF EXISTING STRUCTURES

Location	Description	Remarks
STA. 2411+27.73	SB LANES - 159' 8" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	REMOVE
STA. 2411+24.31	NB LANES - 159' 8" PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	REMOVE

105-4
10-18-11

STANDARD ROAD PLANS

The following Standard Road Plans apply to construction work on this project.

BA-401	04-16-13	Temporary Barrier Rail (Precast Concrete)
BA-500	04-20-10	Temporary Crash Cushions Sand Barrel
EC-101	04-20-10	Wood Excelsior Mat for Ditch Protection
EC-103	04-20-10	Wood Excelsior Mat for Slope Protection
EC-204	10-16-13	Perimeter and Slope Sediment Control Devices
EW-103	10-15-13	Embankment Subgrade Treatment, Moisture Density Control and Special Compaction
EW-403	10-15-13	Ditch Blocks and Dikes
LT-130	10-21-14	Temporary Erosion Control Measures
LT-130	10-21-14	Temporary Floodlighting Luminaires
MT-101	10-16-13	Fencing Layout and Field Fence Construction
PM-110	04-16-13	Line Types
PM-111	10-16-12	Symbols and Legends
PV-12	04-17-12	Milled Shoulder Humber Strips
PV-12	10-21-14	Joints
RF-2	04-15-14	Construction of Type "C" Concrete Adaptors for Pipe Culvert Connections
RF-14	04-16-13	Connected Pipe Joints
RF-19C	10-16-12	Subdrains (Longitudinal)
RF-19E	10-21-14	Outlets for Longitudinal, Transverse and Backslope Subdrains
RF-29	10-21-14	Safety Grates for Box Culverts
RF-30A	04-15-14	Pipe Culvert (Bearing and Backfill)
RF-30B	04-15-14	Pipe Culvert (Installation Details)
RF-30C	04-16-13	Pipe Culvert (Installation Details)
RF-31	03-28-95	Depth of Cover Tables for Concrete Pipe
SI-171	10-20-09	Reference Posts
SI-172	04-15-14	DeLineators
SI-181	10-18-11	Permanent Road Closure - Rural
SI-181	10-18-11	Work Area Closing Traffic (Two-Lane or Multi-Lane)
TC-81	04-20-10	Shoulder Closure (Multi-Lane)
TC-402	10-15-13	Lane Closure on Divided Highway
TC-418	10-15-13	Lane Closure on Divided Highway
TC-432	04-16-13	Shoulder Humber Strip Operations
TC-433	10-21-14	Pavement Marking Operations

100-26
10-15-13

INCIDENTAL ITEMS

Special or unique items where method of measurement / basis of payment is not indicated in the specifications or other contract documents.

No.	Incidental Item	Unit	Quantity	Item Code	Incidental To Item	Remarks
1	REMOVAL OF SLEEPER BEAM	EACH	8	2510-6745850	REMOVAL OF PAVEMENT	
2	REMOVAL OF SUBDRAIN	LF	5744	2102-2710090	EXCAVATION, CLASS 10, WASTE	(1)
						(1) QUANTITY FOR REMOVAL OF SUBDRAIN THAT IS INCIDENTAL TO EXCAVATION, CLASS 10, WASTE INCLUDES SUBDRAIN LOCATED ABOVE THE PROJECT GRADING LIMITS.

MONONA COUNTY PROJECT NUMBER **IMX-029-5(236)101--02-67** SHEET NUMBER **C.5**