

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 17, 2015
Date of Addendum: February 6, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
114	65-2955-607	PCC PAVEMENT - GRADE & REPLACE	MILLS	STP-U-2955(607)--70-65	17FEB114.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0010 2101-0850002 CLEARING AND GRUBBING:
From: 627.000 UNIT
To: 27.000 UNIT

If the above changes are not made, they will be made as shown here.

Replace plan sheets C.2 and C.6 with the attached sheets:

105-11 08-01-08	
TABULATION OF SPECIAL EVENTS	
Date	Location
04-15-2015	Vine Street
MidAmerican Energy to complete power pole relocation from Tyson Street to Nuckolls Street to facilitate street widening and storm sewer reconstruction.	
05-21-2015	School District
Last day of classes for 2014/2015 school year.	
08-12-2015	School District
First day of classes for 2015/2016 school year.	
07-19-2015	Downtown Square
07-25-2015	Ragbrai
*Dates are tentative subject to Glenwood Community School District approval.	

105-4 10-18-11		
INDEX OF TABULATIONS		
Tabulation	Tabulation Title	Sheet No.
C-Sheets	ESTIMATED PROJECT QUANTITIES (UP TO A 5 DIVISION PROJECT)	C.1
100-10	PROJECT DESCRIPTION	C.1
100-11	ESTIMATE REFERENCE INFORMATION	C.3 - C.4
100-17	TABULATION OF SILT FENCES	C.4
100-24	PERMETER AND SLOPE SEDIMENT CONTROL DEVICE	C.8
100-25	PCC PAVEMENT	C.5
100-26	HWY PAVEMENT	C.9
102-3	ACCESS POINTS AND SAFETY RAMPS	C.6
102-5	EXISTING PAVEMENT	C.4
102-6C	FULL-DEPTH PATCHES	C.5
102-15	TABULATION OF SPECIAL EVENTS	C.2
102-13A	TABULATION OF UTILITIES	C.4
103-1	EMBANKMENT WITH MOISTURE AND DENSITY CONTROL	C.8
103-2	EMBANKMENT WITH MOISTURE AND DENSITY CONTROL	C.8
105-4	STANDARD ROAD PLANS	C.2
108-13A	SAFETY CLOSURES	C.4
110-1	REMOVAL OF PAVEMENT	C.6
110-4	CURB REMOVAL	C.7
110-5	SIDEWALK REMOVAL	C.6
110-8	REMOVAL OF CONCRETE DRIVES	C.7
110-10	REMOVAL OF CONCRETE DRIVE	C.7
110-14	SANITARY OR STORM SEWER ABANDONMENT OR REMOVAL	C.7
110-15	REMOVAL OF INTAKES AND UTILITY ACCESSES	C.8
110-17	CLEARING AND GRUBBING	C.6
111-25	INDEX OF TABULATIONS	C.2
113-1	SIDEWALKS	C.8
199-61	EXISTING SIGNS TO BE REINSTALLED	C.8
232-28	EROSION CONTROL (URBAN SEEDING)	C.9
232-9	EROSION CONTROL (SELECTIVE CLEARING)	C.9
232-10	THREATENED/ENDANGERED BATS	C.9
232-10	EMERALD ASH BORER	C.9
232-11	EROSION CONTROL (STABILIZING CROP SEEDING)	C.9
262-6	UTILITIES (NOT A POINT 25 PROJECT)	C.9
299-01	SMALL QUANTITY CONCRETE TESTING	C.9
M Sheets	STORM SEWER	M.1
104-5B	STORM SEWER	M.1
J Sheets	TRAFFIC CONTROL PLAN	J.1
108-26A	STAGING NOTES	J.1
108-26A	STAGING NOTES	J.1
S Sheets	SIDEWALK COMPLIANCE	S.1 - S.3
113-10	SIDEWALK COMPLIANCE	S.1 - S.3

105-4 10-18-11	
STANDARD ROAD PLANS	
The following Standard Road Plans apply to construction work on this project.	
Number	Title
EC-103	04-20-10 Wood Exclosure Mat for Slope Protection
EC-201	04-20-10 Silt Fence
EC-204	10-16-12 Perimeter and Slope Sediment Control Devices
EM-103	10-15-13 Embankment Subgrade Treatment, Moisture Density Control and Special Compaction
EM-104	10-15-13 Embankment Subgrade Treatment, Moisture Density Control and Special Compaction
WI-220	10-16-12 Detectable Markings and Pedestrian Ramp
PR-103	10-21-14 Full Depth PCC Patch with Dowels
PV-101	10-21-14 Joints
PV-102	04-15-14 PCC Curb Details
PV-103	04-15-14 Manhole Boxouts in PCC Pavement
RF-30A	04-15-14 Pipe Culvert (Bedding and Backfill)
RF-30C	04-15-14 Pipe Culvert (Bedding and Backfill)
RF-31	03-28-05 Depth of Cover Tables for Concrete Pipe
SI-101	04-21-09 Locations - Type 'A' Signs
SI-171	10-20-09 Reference Posts
SM-101	04-21-09 Trench Bedding and Backfill Zones
SM-102	04-21-09 Rigid Gravity Pipe Trench Bedding
SM-105	10-20-09 Miscellaneous Pipe Bedding
SM-401	04-21-09 Circular Storm Sewer Manhole
SM-402	04-21-09 Single Open-Top Curb Intake with Extended Opening
SM-403	04-15-14 Castings for Storm Sewer Manholes
TC-1	04-16-13 Work Not Affecting Traffic (Two-Lane or Multi-Lane)
TC-211	04-17-12 Lane Closure on Low Volume Roadway
TC-252	04-17-12 Routes Closed to Traffic
TC-601	10-18-11 Pedestrian Detour

105-4 10-18-11				
INCIDENTAL ITEMS				
Special or unique items where method of measurement / basis of payment is not indicated in the specifications or other contract documents.				
No.	Item Code	Quantity	Unit	Remarks
	REMOVE ABANDONED WATER VALVE BOX AND CURB STOP BOX (STA. 84+38 LT)	1	LS	INCIDENTAL TO STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 2 DURABI

113-2 04-16-13				
PEDESTRIAN PATH CLOSURES				
Refer to TC-601.				
No.	Item Code	Quantity	Unit	Remarks
	REMOVE ABANDONED WATER VALVE BOX AND CURB STOP BOX (STA. 84+38 LT)	1	LS	INCIDENTAL TO STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 2 DURABI

105-4 10-18-11	
PROJECT DESCRIPTION	
This project is for paving replacement of a two lane curbed roadway from Nuckolls Street to Sharp Street in the City of Glenwood, Mills County.	
This project involves PCC concrete replacement from Nuckolls Street to Coolidge Street and HMA pavement from Coolidge Street to Sharp Street.	
This project involves sidewalk replacement and accessible curb ramp construction from Nuckolls Street to Sharp Street.	
This project involves storm sewer and intake improvements.	
This project does require a Iowa DMR storm water permit constructed under the General Permit No. 2. See General Note on Title Sheet.	

