

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 17, 2015
Date of Addendum: February 13, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
305	57-9220-028	GRADING (MISCELLANEOUS)	LINN	NHSX-U-922-0(28)--8S-57	17FEB305.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0991 2303-0000100 HOT MIX ASPHALT MIXTURE, COMMERCIAL MIX (INCLUDES ASPHALT BINDER), AS PER PLAN; 250.000 TON

If the above changes are not made, they will be made as shown here.

Make the following change to the PROPOSAL DETAILS, Page 2:

Replace the PROPOSAL DETAILS, Page 2 with the attached PROPOSAL DETAILS, Page 2.

Delete the following to the PROPOSAL SPECIAL PROVISIONS TEXT and the PROPOSAL SPECIAL PROVISIONS LIST:

500.01

*** WINTER WORK ***

The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.

Add the following to the PROPOSAL SPECIAL PROVISIONS TEXT and the PROPOSAL SPECIAL PROVISIONS LIST:

500.07.2015

*** WINTER WORK ***

Winter work will be allowed during the winter of 2015/2016.
No working days will be charged between November 15, 2015 and April 1, 2016.

Make the following change to the PLAN:

SHEET C.03:

Add the following note to the ESTIMATE REFERENCE INFORMATION for the item 2303-0000100 HOT MIX ASPHALT MIXTURE, COMMERCIAL MIX (INCLUDES ASPHALT BINDER), AS PER PLAN:

HMA Commercial mixture for temporary wedge between existing pavement surface and gutter surface of new 2.5' curb and gutters along 1st Avenue adjacent

to through traffic lanes. Quantity based on 2' wide wedge from existing pavement surface, feathered to 0" thickness at 1' from new curb face. Also includes HMA as backfill between new gutter edge and existing pavement. Certified Plant inspection not required for this item. Unit price includes removal of HMA down to proposed milled surface elevation of existing pavement.

PROPOSAL DETAILS

 Proposal ID No.: 57-9220-028 Bid Order No.: 305
 Primary Work Type: GRADING (MISCELLANEOUS) Letting Date: February 17, 2015
 10:00 A.M.

Site Number	Contract Period/ Site Description	Liquidated Damages
CONTRACT	APPROXIMATE START DATE: 07/06/15 130 WORKING DAYS	\$ 1,800.00

PROPOSAL NOTES

*** CONTRACTOR PHASING ***
 THE CONTRACTOR SHALL COMPLETE PHASE 1 AND THE STORM SEWER IMPROVEMENTS ON PHASE 2 IN 2015. FOR WINTER SHUTDOWN, ALL TRAFFIC LANES MUST BE RE-OPENED TO TRAFFIC. ANY WORK THAT DOES NOT IMPACT TRAFFIC OPERATIONS DURING THE WINTER SHUTDOWN MAY BE COMPLETED UNDER FREE WINTER WORK. THE REMAINDER OF THE PROJECT, INCLUDING PAVING WORK FROM PHASE 2 THROUGH ALL WORK IN THE REMAINING PHASES, WOULD BE CONSTRUCTED IN 2016.