

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 17, 2015
Date of Addendum: March 5, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
015	52-3715-636	NEW BRIDGE - STEEL GIRDER	JOHNSON	STP-U-3715(636)--70-52	17MAR015.A03

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0440 2501-577500 PILES, STEEL SHEET:
From: 1,140.000 SF
To: 1,440.000 SF

If the above changes are not made, they will be made as shown here.

Add the following to plan sheet C.3 ESTIMATE REFERENCE INFORMATION

Item 9; Item Code 2123-7450020

Roadway pavement with curb and gutter require shoulder earth finishing. This item will be used for locations along First Avenue, Mall Drive, and Southeast Junior High Entrance.

Add the following to plan sheet C.6 Tabulation 104-10 Adjustment Information

1. Structure is 6'x6' with an offset manhole access.
2. Structure is prefabricated 48"x24" RCP tee.
3. Structure size not known. Based on size of main it is estimated at 96" diameter, field verification recommended.
4. Structure size not known. Based on size of main it is estimated at 60" diameter, field verification recommended.
5. Structure size not known. Based on size of main it is estimated at 48" diameter, field verification recommended.
6. Structure size not known. Based on size of main it is estimated at 48" diameter, field verification recommended.