

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 17, 2015
Date of Addendum: March 9, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
015	52-3715-636	NEW BRIDGE - STEEL GIRDER	JOHNSON	STP-U-3715(636)--70-52	17MAR015.A04

Make the following change to the Proposal Special Provisions Text and the Proposal Special Provisions List:

Replace SP-126041 with attached SP-126041a



SPECIAL PROVISIONS
for
WORK ON RAILROAD RIGHT-OF-WAY
(IOWA INTERSTATE RAILROAD)

Johnson County

Project No.
STP-U-3715(636)--70-52

Effective Date
March 17, 2015

THE STANDARD SPECIFICATIONS, SERIES OF 2012, ARE AMENDED BY THE FOLLOWING ADDITIONS AND MODIFICATIONS. THESE ARE SPECIAL PROVISIONS AND SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

126041a.01 PERMITS

Contractor shall, before entering upon Iowa Interstate Railroad (Railroad) property for performance of work secure permission from Railroad's Vice President of Engineering for occupancy and use of Railroad's property and shall confer with Railroad relative to requirements for railroad clearances, operation, and general safety regulations. (In this specification, references to the Railroad's Vice President of Engineering is intended to mean the following: Railroad's Vice President of Engineering or authorized representative)

Contractor shall conduct work in a manner satisfactory to Railroad's Vice President of Engineering and shall not damage Railroad property or interfere with their operations.

Railroad's Vice President of Engineering will at all times have jurisdiction over the safety of Railroad operations, and the decision of the Railroad's Vice President of Engineering as to procedures which may affect safety of Railroad operations shall be final, and Contractor shall be governed by such decision.

Should damage occur to Railroad property as a result of Contractor's operations, and Railroad deems it necessary to repair such damage or to perform work for protection of its property, the required materials, labor, and equipment shall be furnished by Railroad, and Contractor shall reimburse Railroad for costs so incurred.

Contractor shall contact Railroad at least 72 hours prior to access on Railroad property. Contractor shall contact both Thomas Klemm and Greg Mitchell as noted below:

Thomas Klemm
Assistant Chief Engineer – Engineering Services
Iowa Interstate Railroad, Ltd.
5900 6th St SW
Cedar Rapids, Iowa 52404
Phone: 319-298-5417
trklemm@iaisrr.com

Greg D. Mitchell
Office Engineer
Iowa Interstate Railroad, Ltd.
5900 6th Street SW
Cedar Rapids, Iowa 52404
Phone: 319-298-5424
gdmitchell@iaisrr.com

126041a.02 TEMPORARY GRADE CROSSINGS

If Contractor requires construction of a temporary grade crossing across Railroad's track(s) for use during performance of the contract, Contractor shall make necessary arrangements with Railroad for construction, protection, and later removal of such temporary grade crossing. Costs of such temporary grade crossing construction, protection, maintenance, and later removal shall be reimbursed to Railroad on the basis of Railroad's bills, to be rendered monthly.

Contractor shall not cross Railroad's property or track(s) with vehicles or equipment of any kind or character except at such temporary grade crossing as may be constructed as outlined herein, or at an existing and open public grade crossing.

126041a.03 RAILROAD FLAGGING AND WATCHMAN SERVICES

Flagging protection or watchman services required by Railroad for safety of Railroad operations because of work being performed by Contractor, or in connection therewith, will be provided by the Railroad and the cost shall be paid by the City of Iowa City on the basis of Railroad's bills, to be rendered monthly. Requirements of the Railroad are as follows:

Services of at least one and possibly two watchmen or flagmen will be required during: excavation, placing, and removal of cofferdams or sheeting, driving of foundation piling and placing of concrete footings for piers adjacent to track (s); construction and removal of falsework, bracing or forms over or adjacent to track(s); construction or equipment across the track; setting or placing of beams or birders in span(s) over any track(s); any construction operations involving direct interference with Railroad's track(s) or traffic, fouling of Railroad operating clearances or reasonable probability of accidental hazard to railroad traffic; or whenever workers or equipment will be working within 25 feet of the centerline of any live track. If an existing bridge or other structure is to be removed, services or at least one and possibly two watchmen or flagmen will be required during removal of that portion of existing structure immediately over or adjacent to any track. Flagmen will also be furnished whenever, in the opinion of the Railroad, such protection is needed.

In order that the Railroad may be prepared to furnish protective services, Contractor shall notify Railroad at least 72 hours in advance of when protective services will be needed. Contractor shall contact both Thomas Klemm and Greg Mitchell as noted in Section 126041a.01.

Any time track protection services are not being provided, Contractor must provide and maintain an effective physical barrier at a distance of 25 feet from track centerline to prevent unauthorized trespassing. Physical barrier must be posted with a sign stating "CAUTION, LIVE TRACK, TRACK PROTECTION NEEDED BEYOND THIS POINT". Typical barriers included concrete "J" barriers or safety fencing. Other barriers may be used to accommodate varying construction sites with approval of Railroad.

Railroad will notify the City of Iowa City and Contractor when non-compliance is reported by Railroad train crews or other Railroad employees. Contractor work performed without proper track protection services, when such protection is required, will be subject to a \$5,000.00 per day price adjustment to Contractor, and may result in the removal of Contractor by Railroad or City of Iowa City from the project.

126041a.04 SAFETY OF OPERATIONS

During construction of footings or piers or other supports or structures adjacent to any track of the Railroad, Contractor shall make adequate provision against sliding, shifting, sinking, or in any way disturbing railroad embankment and track(s) adjacent to said piers, supports, or structures due to said construction operations, by driving temporary sheeting in a manner satisfactory to both the Engineer and Railroad.

Before commencing work on any pier or structure adjacent to any track, Contractor shall submit prints of proposed sheeting, bracing details, or temporary structure for protection of Railroad's track(s) to the Engineer and Railroad for review. This submittal shall include the proposed method of installation and be accompanied by supporting data, including design computations, logs of soil borings, and other pertinent information.

The Track Shield Detail shall control the requirements for track protection during bridge demolition.

After review by the Engineer, two sets of prints of proposed sheeting and bracing details bearing the seal of a registered structural or professional engineer, registered in the state of Iowa together with the supporting documents, shall be forwarded to the Railroad's Vice President of Engineering for review and approval.

Contractor shall notify the Railroad's Vice President of Engineering in writing no less than 7 calendar days in advance of the proposed time of the beginning of the construction of the piers, supports, or structures adjacent to the track(s).

126041a.05 TEMPORARY CLEARANCES

The following temporary clearances are the minimum which shall be maintained at all times during construction operations:

- Vertical: 21.5 feet above top of highest rail
- Horizontal: 15.0 feet from centerline of nearest track, measured at right angles thereto

If lesser clearances than the above are required for any part of the work, Contractor shall secure written authorization from Railroad's Vice President of Engineering for such lesser clearances in advance of the start of work of that portion of the project along, on, over, or across the property or track(s) of the Railroad.

Contractor shall not store any materials, supplies or equipment closer than 25.0 feet from centerline of any railroad track, measured at right angles thereto.

126041a.06 FINAL CLEANUP

Contractor shall, upon completion of the work, remove from within the limits of the property of the Railroad, all machinery, equipment, surplus materials, falsework, rubbish, or temporary buildings of said Contractor; remove the approaches to any temporary grade crossing(s) constructed for Contractor's use, restoring same as nearly as practicable to conform to adjoining terrain; remove any accumulated silt in Railroad's side ditches, restoring proper flow thereto, employ erosion control measures as appropriate to prevent further siltation until ground cover is reestablished; and in all other respects leave said property in a neat condition satisfactory to Railroad's Vice President of Engineering.

126041a.07 RESPONSIBILITY OF SUPERVISION.

Nothing in this specification shall be construed to place any responsibility on Railroad for quality or conduct of the work performed by the Contractor hereunder. Any approval given or supervision exercised

by Railroad hereunder, or failure of Railroad to object to any work done, material used, or method of operation shall not be construed to relieve Contractor of any obligations pursuant hereto or under the agreement this specification is appended to.

126041a.08 LIABILITY AND PROPERTY DAMAGE INSURANCE FOR WORK WHOLLY OR PARTLY WITHIN RAILROAD RIGHT-OF-WAY.

In addition to the requirements of Article 1107.02, A, of the Standard Specifications, the Contractor shall carry insurance of the following kinds and amounts.

A. Insurance Required of Contractor:

1. Statutory Workers Compensation and Employer's Liability Insurance.
2. Automobile Liability in an amount not less than \$2,000,000 combined single limit.
3. Comprehensive General Liability Occurrence Form in an amount not less than ~~\$2,000,000~~ \$5,000,000 per occurrence. In the event the policy is Claims Made Policy, coverage shall include an aggregate of ~~\$6,000,000~~ \$10,000,000. The policy shall name the Railroad as additional insured. It also shall have no exclusions regarding doing business on, near, or adjacent to railroad facilities or loss or damage resulting from surface or subsurface pollution contamination, seepage, handling, treatment, disposal, or dumping of waste materials or substances. The Policy shall name Iowa Interstate Railroad as additional insured and shall not contain any exclusions related to:
 - i. Doing business on, near, or adjacent to Railroad facilities.
 - ii. Loss or damage resulting from surface, subsurface pollution contamination or seepage, or handling, treatment, disposal, or dumping of waste materials or substances.

The above policies shall contain a waiver of the right of subrogation

4. An Occurrence Form Railroad Protective Policy with limits of not less than ~~\$2,000,000~~ \$5,000,000 per occurrence for Bodily Injury Liability. Property Damage Liability and Physical Damage to Property, with ~~\$6,000,000~~ \$10,000,000 aggregate for the term of the policy with respect of Bodily Injury, Liability, Property Damage Liability and Physical Damage to Property. The policy shall name: Iowa Interstate Railroad.

Before commencing work, Contractor shall submit to the Railroad and Contracting Authority a certificate of insurance evidencing the foregoing coverage and a certified, true, and complete copy of the policy or policies. The policies shall provide for no less than 30 calendar days prior written notice to the Railroad and Contracting Authority of cancellation of or any material change in, the policies.

It is understood and agreed that the foregoing insurance coverage is not intended to, and shall not relieve the Contractor from or serve to limit Contractor's liability or indemnity obligations under the provisions herein.

It is further understood and agreed that, so long as the Contract remains in force, the Contracting Authority may from time to time revise the amount or form of insurance coverage provided as circumstances or changing economic conditions may require. The Contracting Authority will give the Contractor written notice of any such requested change at least 30 Calendar days prior to the date of expiration of the then existing policy or policies, and the Contractor agrees to, and shall, thereupon provide the Contracting Authority with such revised policy or policies therefore. The cost of additional insurance beyond that required by this specification will be paid for according to Article 1109.03, B, of the Standard Specifications.

B. Insurance required of Subcontractor

If a Subcontractor is used by the Contractor for the performance of the work, before commencing

work, the Subcontractor shall provide and maintain the following insurance, in form and amount and with companies satisfactory to, and as approved by, the Contracting Authority.

1. Statutory Workers' Compensation and Employer's Liability insurance.
2. Automobile Liability in an amount not less than \$2,000,000 combined single limit.

The above policies shall contain a waiver of the right of subrogation

3. An Occurrence Form Railroad Protective Policy with limits of not less than ~~\$2,000,000~~ \$5,000,000 per occurrence for Bodily Injury Liability. Property Damage Liability and Physical Damage to Property, with ~~\$6,000,000~~ \$10,000,000 aggregate for the term of the policy with respect of Bodily Injury, Liability, Property Damage Liability and Physical Damage to Property. The policy shall name: Iowa Interstate Railroad

Before commencing work, Subcontractor shall deliver to the Contracting Authority a certificate of insurance and original copy of the policy evidencing the foregoing coverage and upon request the Subcontractor shall deliver a certified, true, and complete copy of the policy or policies. The policies shall provide for no less than 30 calendar days prior written notice to the Railroad and Contracting Authority of cancellation of or any material change in, the policies.

126041a.09 CONTRACTOR SAFETY ORIENTATION

No employee of the Contractor, its subcontractors, agents or invitees that is working on the project may enter Railroad property without first having successfully passed an annual Railroad approved safety course. Proof of passing said course shall be in the employee's possession at all times when on Railroad property. Cost for the required training will be borne by Contractor. Information on approved safety courses can be obtained from Railroad's authorized representative, Thomas Klemm or Greg Mitchell.

126041a.0910 METHOD OF MEASUREMENT AND BASIS OF PAYMENT.

Railroad Protective Liability Insurance for Iowa Interstate Railroad will be paid for as a Lump Sum bid item. The Contractor will be paid the lump sum bid item once the Engineer has received all necessary certificates of insurance.