MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposal ID: 02-C002-066 Proposed Bid Order: 001 Proposed Contract Period: Late Start Date of 07/27/15 with 65 WORK DAYS Project(s): Project No: BROS-C002(66)--8J-02 County: ADAMS Type of Work: RCB CULVERT NEW - TWIN BOX Route: 145TH ROAD Length: 0.10 miles Location: ON 145TH RD., OVER UNNAMED STREAM, AT WLINE S29 T73N R34W _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A TWIN 10' X 10' X 86'-0 REINFORCED CONCRETE BOX CULVERT 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100020 STRUCT CONC (RCB CULV) 9,056 CY 314 CY 2404-7775000 REINFORC STEEL 49,632 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposal ID: 04-C004-080 Proposed Bid Order: 002 Proposed Contract Period: Late Start Date of 07/20/15 with 75 WORK DAYS Project(s): Project No: BROS-C004(80)--5F-04 County: APPANOOSE Type of Work: BRIDGE AND APPROACHES - CCS Route: 290TH AVE Length: 0.10 miles Location: 290TH AVE: NEA W1/4 COR _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 80'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 144 CY 39,165 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 1,643 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,244 CY

IOWA DEPARTMENT OF TRANSPORTATION	
MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)	
Proposed Letting Date: April 21, 2015 10:00 A.M.	
Proposed Bid Order: 003 Proposal ID: 13-1755-028	
Proposed Contract Period: Late Start Date of 08/17/15 with Site 01: TO COMPLETE ALL WORK THAT REQUIRES IOWA 17 Late Start Date of 08/17/15 with	5 TO BE DETOURED.
Project(s): Project No: STPN-175-5(28)2J-13 County: CALHOUN Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX Route: IOWA 175 Length: 0.00 miles Location: 0.75 MILES E OF CO RD N65	
Item No. Item Description	Quantity/Unit
SECTION NO. 0002 ROADWAY ITEMS	
2102-2625000 EMBANKMENT-IN-PLACE	1,025 CY
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	50 CY
2102-2713070 EXCAVATION, CL 13, RDWY+BORROW	17 CY
2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10"	311 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 004 Proposal ID: 15-C015-055 Proposed Contract Period: Late Start Date of 07/06/15 with 80 WORK DAYS Project(s): Project No: BROS-C015(55)--8J-15 County: CASS Type of Work: BRIDGE REPLACEMENT - PPCB Route: 560TH STREET Length: 0.00 miles Location: 560TH STREET 1/2 MI NORTH OF TUCSON ROAD ,BRIDGE #83 OVER BA UGHMAN CREEK _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 138'-10 X 30'-3 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 3,100 CY 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 50 TON 2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 100 TON 2403-0100010 STRUCT CONC (BRIDGE) 236 CY 2404-7775000 REINFORC STEEL 4,128 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 51,400 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 005 Proposal ID: 28-C028-086 Proposed Contract Period: Late Start Date of 08/10/15 with 40 WORK DAYS Project(s): Project No: BROS-C028(86)--8J-28 County: DELAWARE Type of Work: BRIDGE REPLACEMENT - CCS Route: 197TH AVE Length: 0.11 miles Location: 197TH AVENUE: FROM 275TH STREET TO 295TH STREET _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A 100'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 229 CY 59,703 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 006 Proposal ID: 28-C028-087 Proposed Contract Period: Late Start Date of 08/10/15 with 40 WORK DAYS Project(s): Project No: BROS-C028(87)--8J-28 County: DELAWARE Type of Work: BRIDGE REPLACEMENT - CCS Route: 137TH ST Length: 0.04 miles Location: 137TH ST: 252ND AVE E 0.2 MI _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 80'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 582 CY 181 CY 47,721 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 007 Proposal ID: 42-3720-611 Proposed Contract Period: Late Start Date of 05/26/15 with 110 WORK DAYS Project(s): Project No: BHM-3720(611)--8K-42 County: HARDIN Type of Work: BRIDGE REHABILITATION Route: WASHINGTON AVE. Length: 0.10 miles Location: IN THE CITY OF IOWA FALLS, ON WASHINGTON AVE, OVER IOWA RIVER _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR REPAIRS TO A 379'-4 X 24'-0 WITH 5'-0 SIDEWALKS CONCRETE ARCH BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 140 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 36,239 LB 2413-0698081 DECK REPAIR, CL A, SPECIAL 305 SY SECTION NO. 0002 ITEMS FOR ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN 2413-0698041 DECK O-DEPTH OVERLAY (CL O PCC) 871 SY SECTION NO. 0003 ITEMS FOR ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN 2413-0698051 DECK O-DEPTH OVERLAY (CL HPC-O) 871 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 008 Proposal ID: 47-C047-051 Proposed Contract Period: Late Start Date of 07/20/15 with 75 WORK DAYS Project(s): Project No: BRS-C047(51)--60-47 County: IDA Type of Work: BRIDGE AND APPROACHES - CCS Route: JASPER AVE. (M15) Length: 0.05 miles Location: 310TH ST. S 0.6 MI OVER SOLDIER RIVER _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A 120'-0 X 30' CONTINUOUS CONCRETE SLAB BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 1,103 CY 293 CY 72,520 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 009 Proposal ID: 54-C054-095 Proposed Contract Period: Late Start Date of 04/11/16 with 85 WORK DAYS Project(s): Project No: BRS-C054(95)--60-54 County: KEOKUK Type of Work: BRIDGE AND APPROACHES - CCS Route: W15 Length: 0.20 miles Location: ON W15, OVER SMITH CREEK, AT S23/24 T77 R10 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 110'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 255 CY 66,056 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH 13,488 CY 2102-2625001 EMDANNENTIN IN LINE, 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 3,309 CY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 3,650 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 010 Proposal ID: 57-3806-274 Proposed Contract Period: Late Start Date of 07/20/15 with 60 WORK DAYS Project(s): Project No: IMN-380-6(274)17--0E-57 County: LINN Type of Work: BRIDGE REHABILITATION Route: I-380 Length: 0.00 miles Location: IN THE CITY OF CEDAR RAPIDS OVER THE CIC R.R. & CITY STREET (NBL/SBL) _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0115; 564'-0 X 52'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100000 STRUCT CONC (MISCELLANEOUS) 19 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 1,945 LB SECTION NO. 0002 DESIGN NO. 0215; 564'-0 X 52'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100000 STRUCT CONC (MISCELLANEOUS) 19 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 1,949 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 011 Proposal ID: 63-0055-505 Proposed Contract Period: Late Start Date of 05/18/15 with 15 WORK DAYS Project(s): Project No: MB-005-5(505)65--77-63 County: MARION Type of Work: BRIDGE REPAIR Length: 0.00 miles Route: IOWA 5 Location: WHITE BREAST CREEK 2.7 MI W OF IA 14 (SB) _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 012 Proposal ID: 68-C068-060-A Proposed Contract Period: Late Start Date of 04/11/16 with 80 WORK DAYS Project(s): Project No: BROS-C068(60)--8J-68 County: MONROE Type of Work: BRIDGE REPLACEMENT - CCS Route: 625TH AVE Length: 0.10 miles Location: 625TH AVE: US34 N 1.1 MI _____ Item No. Quantity/Unit Item Description _____ SECTION NO. 0001 ITEMS FOR A 110'-0 X 24'-6 CONTINUIOUS CONCRETE SLAB BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 61 CY 211 CY 54,661 LB

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 013 Proposal ID: 77-C077-164 Proposed Contract Period: Late Start Date of 07/06/15 with 320 WORK DAYS Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW. Completion Date of 12/31/15 Proposal Note: *** SITE NUMBER 01 *** THE INTERMEDIATE COMPLETION DATE SHOWN ABOVE IS TO COMPLETE AND PUT IN SERVICE THE DIVISION 2: WATER MAIN ITEMS, REFER TO PLAN SHEET NUMBERS C.1 AND C.2 FOR INCLUDED ITEMS. THE DES MOINES WATER WORKS NEEDS TO HAVE THE WATER LINE COMPLETED BY DEC. 31, 2015 TO MEET THEIR COMMITMENT FOR WATER SUPPLY TO THE CITY OF JOHNSTON. Project(s): Project No: STP-S-C077(164)--5E-77 County: POLK Type of Work: BRIDGE REPLACEMENT - PPCB Route: NW 66TH AVENUE Length: 0.48 miles Location: FROM NW BEAVER DRIVE TO NW 26TH STREET _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH 21,494 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 21,002 CY

 2102-2713070
 EXCAVATION, CL 13, RDWY+BORROW

 2122-5190008
 PAVED SHLD, PCC, 8"

 2122-5190010
 PAVED SHLD, PCC, 10"

 2122-5190012
 PAVED SHLD, PCC, 12"

 979 CY 330 SY 403 SY 53 SY 2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10" 2,254 SY 2303-0041750 HMA (3M ESAL) BASE, 3/4" 357 TON 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 178 TON 2303-0051750 HMA (10M ESAL) BASE, 3/4" 3,980 TON 2303-0052750 HMA (10M ESAL) INTERMEDIATE, 3/4" 1,816 TON 2303-0053500 HMA (10M ESAL) SURF, 1/2", NO FRIC 1,397 TON 2303-0101000 HMA WEDGE/LEVEL/STRENGTH 46 SY 2403-0100000 STRUCT CONC (MISCELLANEOUS) 4 CY 2404-7775000 REINFORC STEEL 59 LB 2511-0301600 RECREATIONAL TRAIL, HMA, 6" 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 1,248 SY 33 SY SECTION NO. 0002 ITEMS FOR AN 834'-0 X 56'-0 PPC BEAM BRIDGE WITH 10'-0 SIDEWALK 2403-0100010 STRUCT CONC (BRIDGE) 4,605 CY 2404-7775000 REINFORC STEEL 444,253 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 478,516 LB

	MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)
	(for information only)
Proposed Letting	J Date: April 21, 2015 10:00 A.M.
Proposed Bid Or	der: 014 Proposal ID: 80-C080-064
TTOPOSCA DIA OI	
Proposed Contr	act Period: Late Start Date of 12/01/15 with 35 WORK DAYS
	STRICTION *** L BE ALLOWED PRIOR TO NOVEMBER 2, 2015.
Project No:	ER-C080(64)58-80
Project No: County:	RINGGOLD
Project No: County:	RINGGOLD PILING REPAIR
Project No: County: Type of Work: Route:	RINGGOLD PILING REPAIR
County: Type of Work: Route:	RINGGOLD PILING REPAIR P33 Length: 0.00 miles
Project No: County: Type of Work: Route: Location:	RINGGOLD PILING REPAIR P33 Length: 0.00 miles 150 FEET WEST OF COUNTY HIGHWAY P33 BRIDGE OVER W.FK GRAND

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 015 Proposal ID: 83-C083-058 Proposed Contract Period: Late Start Date of 07/20/15 with 75 WORK DAYS Project(s): Project No: BROS-C083(58)--5F-83 County: SHELBY Type of Work: BRIDGE REPLACEMENT - CCS Route: NISHNA AVENUE Length: 0.06 miles Location: INTERSECTION OF NISHNA AVENUE AND REDWOOD ROAD E 0.75 MI _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ITEMS FOR A 120'-0 X 24' CONTINUOUS CONCRETE SLAB BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 220 CY 281 CY 59,848 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 016 Proposal ID: 84-C084-149 Proposed Contract Period: Late Start Date of 07/27/15 with 60 WORK DAYS Project(s): Project No: BROS-C084(149)--8J-84 County: SIOUX Type of Work: BRIDGE REPLACEMENT - CCS Route: 290TH STREET Length: 0.00 miles Location: 290TH STREET: NW OF ROCK VALLEY _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 100'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 2404-7775005 REINFORC STEEL, EPOXY COATED 244 CY 4,818 LB 54,644 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 86-2267-601

Proposed Contract Period: Late Start Date of 07/06/15 with 145 WORK DAYS

Proposal Note:
 *** WORK RESTRICTION/START DATE INFORMATION ***

THE FOLLOWING RESTRICTIONS APPLY TO THIS CONTRACT: 1) NO FREE WINTER WORK, REFER TO PROPOSAL NOTE 500.01. 2) NEITHER BRIDGE MAY BE CLOSED DURING THE WINTER. 3) ONE BRIDGE MUST REMAIN OPEN AT ALL TIMES.

THE COUNTY IS NOT REQUIRING THE CONTRACTOR TO CONSTRUCT BOTH BRIDGES BEFORE WINTER SHUTDOWN 2015/2016, HOWEVER, BOTH BRIDGES SHALL BE OPEN OVER THE WINTER. THEREFORE, THE CONTRACTOR HAS TWO OPTIONS: 1) BOTH BRIDGES CAN BE COMPLETED BEFORE WINTER SHUTDOWN OR 2) THE EAST BRIDGE CAN BE COMPLETED THIS SEASON WHILE THE WEST BRIDGE WAITS UNTIL 2016. IF THE CONTRACTOR HAS COMPLETED THE EAST BRIDGE IN 2015 AND INTENDS TO COMPLETE THE WEST BRIDGE IN 2016, CHARGING OF WORKING DAYS WILL BE SUSPENDED UNTIL APRIL 1, 2016. THE WEST BRIDGE HAS CLEARING AND GRUBBING THAT WILL PREVENT STARTING CONSTRUCTION UNTIL JULY 15, 2015 DUE TO MIGRATORY BIRD RESTRICTIONS, SEE PROPOSAL NOTE 005.0012.

County: Type of Work: Route:	BRS-2267(601)60-86 TAMA BRIDGE REPLACEMENT - CCS 1ST STREET (E44) Length: 0.05 miles IN THE CITY OF ELBERON, OVER TROUBLESOME CREEK	
County: Type of Work: Route:	BRS-2267(602)60-86 TAMA BRIDGE REPLACEMENT - CCS 1ST STREET (E44) Length: 0.08 miles IN THE CITY OF ELBERON, OVER TROUBLESOME CREEK	
Item No.	Item Description	Quantity/Unit
BRS 2102-2710070 F 2301-1033080 S	D. 0001 EMS FOR A 90'-0 X 30'-6 CONTINUOUS CONCRETE SLAB S-2267(601)60-86 EXCAVATION, CL 10, RDWY+BORROW STD/S-F PCC PAV'T, CL C CL 3, 8" STRUCT CONC (BRIDGE)	BRIDGE 129 CY 144 SY 283 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

SECTION NO. 0001 ITEMS FOR A 90'-0 X 30'-6 CONTINUOUS CONCRETE SLA	B BRIDGE
BRS-2267(601)60-86	
2404-7775005 REINFORC STEEL, EPOXY COATED	56,674 LB
SECTION NO. 0002	
ITEMS FOR A 90'-0 X 30'-6 CONTINUOUS CONCRETE SLA	B BRIDGE
BRS-2267(602)60-86	
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	341 CY
2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8"	332 SY
2403-0100010 STRUCT CONC (BRIDGE)	197 CY
2404-7775005 REINFORC STEEL, EPOXY COATED	52,185 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 018 Proposal ID: 91-C091-094 Proposed Contract Period: Late Start Date of 08/24/15 with 55 WORK DAYS Project(s): Project No: BROS-C091(94)--5F-91 County: WARREN Type of Work: BRIDGE REPLACEMENT - CCS Route: MCKINLEY ST. (G48) Length: 0.05 miles Location: 0.1 MILES WEST OF 210TH AVE. OVER COAL CREEK _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 70'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2102-2625000 EMBANKMENT-IN-PLACE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 362 CY 126 CY 33,898 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 019 Proposal ID: 91-0352-341 Proposed Contract Period: Late Start Date of 05/25/15 with 195 WORK DAYS Project(s): Project No: IMN-035-2(341)67--0E-91 County: WARREN Type of Work: BRIDGE REPLACEMENT - PPCB Route: I-35 Length: 0.60 miles Location: COUNTY ROAD R-35 (ADAMS STREET) OVER I-35 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 1116; 376'-0 X 40'-0 PRESTRESSED PRETENSIONED CONCRETE BEAM BRIDGE WITH SHARED USE PATH 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 630 CY 65,397 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 227,863 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH 24,369 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,634 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 020 Proposal ID: 92-C092-082 Proposed Contract Period: Late Start Date of 08/24/15 with 45 WORK DAYS Project(s): Project No: FM-C092(82)--55-92 County: WASHINGTON Type of Work: RCB CULVERT NEW - TWIN BOX Route: W64 Length: 0.00 miles Location: W64 OVER SMALL NATURAL STREAM _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A TWIN 12' X 8' X 64'-3 REINFORCED CONCRETE BOX CULVERT 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1034080 STD/S-F PCC PAV'T, CL C CL 3I, 8" 1,768 CY 789 SY 2403-0100020 STRUCT CONC (RCB CULV) 2404-7775000 REINFORC STEEL 253 CY 39,543 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 021 Proposal ID: 93-C093-068 Proposed Contract Period: Late Start Date of 09/21/15 with 35 WORK DAYS Project(s): Project No: BRS-C093(68)--60-93 County: WAYNE Type of Work: RCB CULVERT NEW - TWIN BOX Route: J54 Length: 0.05 miles Location: OVER STREAM, NEAR THE NW CORNER OF SEC 3 T67N R20W APPROX. 5.5 MI. E. OF HWY S40 _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ITEMS FOR A TWIN 12' X 10' REINFORCED CONCRETE BOX CULVERT 2403-0100020 STRUCT CONC (RCB CULV) 2404-7775000 REINFORC STEEL 263 CY 40,292 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 022 Proposal ID: 96-C096-126 Proposed Contract Period: Late Start Date of 07/20/15 with 65 WORK DAYS Project(s): Project No: BROS-C096(126)--8J-96 County: WINNESHIEK Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX Route: 318TH AVENUE Length: 0.00 miles Location: STATE LINE RD.: OVER CREEK _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEM FOR A TWIN 12' X 10' X 52 REINFORCED CONCRETE BOX CULVERT 2102-2625000 EMBANKMENT-IN-PLACE 2403-0100020 STRUCT CONC (RCB CULV) 2404-7775005 REINFORC STEEL, EPOXY COATED 875 CY 302 CY 42,919 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 023 Proposal ID: 98-0096-063 Proposed Contract Period: Late Start Date of 09/14/15 with 30 WORK DAYS Project(s): Project No: BRFN-009-6(63)--39-98 County: WORTH Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX Route: IOWA 9 Length: 0.06 miles Location: 1.5 MILES W. OF US 65 IN MANLY _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0115; ALTERNATE 'AA' OPTION 1: CAST IN PLACE RCB BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN 2403-0100020 STRUCT CONC (RCB CULV) 2404-7775000 REINFORC STEEL 130 CY 25,150 LB SECTION NO. 0003 ROADWAY ITEMS 496 CY 2102-2625000 EMBANKMENT-IN-PLACE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 861 CY 2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10" 180 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 101 Proposal ID: 07-1185-647 Proposed Contract Period: Late Start Date of 08/31/15 with 30 WORK DAYS Project(s): Project No: TAP-U-1185(647)--8I-07 County: BLACK HAWK Type of Work: PCC SIDEWALK/TRAIL Route: HUDSON ROAD Length: 0.70 miles Location: IN THE CITY OF CEDAR FALLS, HUDSON ROAD TRA: FROM W. 12TH ST REET TO W. 1ST STREET _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 PCC TRAIL ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 983 CY 3,323 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 102 Proposal ID: 07-2140-601-A Proposed Contract Period: Late Start Date of 06/29/15 with 30 WORK DAYS Project(s): Project No: STP-U-2140(601)--70-07 County: BLACK HAWK Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: DUNKERTON ROAD Length: 0.14 miles Location: IN THE CITY OF DUNKERTON FROM D & W RAILROAD LLC TO BLOOMFIELD ST. _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 811 CY 2,112 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 103 Proposal ID: 14-4702-603 Proposed Contract Period: Late Start Date of 08/17/15 with 45 WORK DAYS Project(s): Project No: SRTS-U-4702(603)--8U-14 County: CARROLL Type of Work: PCC SIDEWALK/TRAIL Route: EAST ST Length: 0.43 miles Location: IN THE CITY OF MANNING TRAIL ALONG EAST STREET: FROM 3RD STR EET TO IKM-MANNING _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 2511-0302800 RECREATIONAL TRAIL, PCC, 8" 2,128 CY 1,836 SY 192 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 104 Proposal ID: 21-0718-059 Proposed Contract Period: Late Start Date of 05/26/15 with 90 WORK DAYS Project(s): Project No: NHSX-071-8(59)--3H-21 County: CLAY Type of Work: PCC OVERLAY - UNBONDED Route: U.S. 71 Length: 7.91 miles Location: FROM CO. RD. B53 N. TO 15TH ST. IN SPENCER _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10" 2303-0031500 HMA (1M ESAL) BASE, 1/2" 71 CY 347 SY 161 TON 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 526 TON 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 1,002 TON 2310-5151600 PCC OVERLAY, QM-C, FURN ONLY 25,650 CY 2310-5151620 PCC OVERLAY, QM-C, PLACE ONLY (UNBONDED) 138,911 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 105 Proposal ID: 49-0521-107 Proposed Contract Period: Late Start Date of 09/07/15 with 35 WORK DAYS Project(s): Project No: STPN-052-1(107)--2J-49 County: JACKSON Type of Work: PCC PAVEMENT - REPLACE Route: U.S. 52 Length: 0.63 miles Location: FROM TETE DES MORTS CREEK N. TO NEAR NCL OF ST. DONATUS _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS
 2102-2625000
 EMBANKMENT-IN-PLACE
 80 CY

 2301-1033090
 STD/S-F PCC PAV'T, CL C CL 3, 9"
 7,951 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 106 Proposal ID: 50-5482-617 Proposed Contract Period: Late Start Date of 09/08/15 with 25 WORK DAYS Project(s): Project No: STP-U-5482(617)--70-50 County: JASPER Type of Work: PCC OVERLAY - UNBONDED Route: EAST 31ST Length: 0.00 miles Location: IN THE CITY OF NEWTON, E. 31ST STREET N, FROM 1ST AVE E TO N 19TH AVE E, AT S T R _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS 2301-1034090 STD/S-F PCC PAV'T, CL C CL 3I, 9" 2310-5151040 PCC OVERLAY, FURN ONLY 2310-5151251 PCC OVERLAY PLACE ONLY (UNBONDED) 2,064 SY 3,468 CY 17,823 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 107 Proposal ID: 60-C060-110 Proposed Contract Period: Late Start Date of 06/01/15 with 10 WORK DAYS Project(s): Project No: ER-C060(110)--58-60 County: LYON Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: A52 Length: 0.14 miles Location: ON A52, FROM RR UNDERPASS WEST 500 FEET _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1032090 STD/S-F PCC PAV'T, CL C CL 2, 9" 220 CY 320 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 108 Proposal ID: 70-C070-060 Proposed Contract Period: Late Start Date of 09/28/15 with 20 WORK DAYS Project(s): Project No: HRRR-C070(60)--5R-70 County: MUSCATINE Type of Work: PCC PAVED SHOULDER - NEW Route: ZACHARY AVE. (Y36) Length: 1.04 miles Location: Y36: 171ST STREET TO 500' NORTH OF ZALE AVENUE _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2122-5190009 PAVED SHLD, PCC, 9" 1,832 CY 156 CY 7,134 SY 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT . 117 SY 4 EACH

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 109 Proposal ID: 77-8260-635 Proposed Contract Period: Late Start Date of 05/26/15 with 110 WORK DAYS Site 01: TO COMPLETE STAGE 1 AS SHOWN ON PLAN SHEET NUMBER J.1. Completion Date of 07/19/15 Site 02: TO COMPLETE STAGE 2 AS SHOWN ON PLAN SHEET NUMBER J.1. Completion Date of 08/21/15 Project(s): Project No: STP-U-8260(635)--70-77 County: POLK Type of Work: PCC PAVEMENT WIDENING / PCC RESURFACING Route: GRAND AVENUE Length: 0.67 miles Location: IN THE CITY OF WEST DES MOINES: FROM SOUTH 50TH STREET TO SOUTH 35TH STREET _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS 2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH 48,960 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 43,425 CY 2301-1033060 STD/S-F PCC PAV'T, CL C CL 3, 6" 1,900 SY 24,050 SY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 2403-0100020 STRUCT CONC (RCB CULV) 789 CY 2404-7775000 REINFORC STEEL 124,099 LB 3,923 SY 2511-0302600 RECREATIONAL TRAIL, PCC, 6"

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 110 Proposal ID: 78-0801-385 Proposed Contract Period: Late Start Date of 05/26/15 with 240 WORK DAYS Project(s): Project No: IM-NHS-080-1 (385) 0--03-78 County: POTTAWATTAMIE Type of Work: PCC PAVEMENT - GRADE AND NEW Route: I-80 Length: 0.00 miles Location: I-80 WB FR. JUST E. OF MO. RIVER TO E OF INDIAN CR & I-29 NB FR. W OF 24TH ST. TO S OF NEBRASKA AVE WSI RAMPS A,C,E,&H Project No: IM-NHS-080-1(386)0--03-78 County: POTTAWATTAMIE Type of Work: LIGHTING Route: I-80 Length: 0.00 miles Location: I-80 WB FROM E. OF MO. RIVER TO E. OF INDIAN CR. & I-29 NB FROM W. OF 24TH ST. TO S. OF NEBRASKA AVE WSI RAMP C&E Project No: IM-NHS-080-1(387)0--03-78 County: POTTAWATTAMIE Type of Work: TRAFFIC SIGNS Route: I-80 Length: 0.00 miles Location: I-80 WB FROM E. OF MO. RIVER TO E. OF INDIAN CR. & I-29 NB FROM W. OF 24TH ST. TO S. OF NEBRASKA AVE WSI RAMP C&E Project No: IM-NHS-080-1(388)2--03-78 County: POTTAWATTAMIE Type of Work: BRIDGE REPLACEMENT - PPCB Route: I-80 Length: 0.00 miles Location: I-29/80 IN COUNCIL BLUFFS - I-80 WB OVER INDIAN CREEK _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS IM-NHS-080-1(385)0--03-78 2102-2625000 EMBANKMENT-IN-PLACE 17,546 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1004115 STD/S-F PCC PAV'T, QM-C CL 3I, 11.5" 418,833 CY 138,390 SY SECTION NO. 0004 LIGHTING ITEMS IM-NHS-080-1(386)0--03-78 2404-7775000 REINFORC STEEL 6,708 LB SECTION NO. 0005 TRAFFIC SIGN ITEMS IM-NHS-080-1(387)0--03-78 2403-0100000 STRUCT CONC (MISCELLANEOUS) 449 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 57,535 LB SECTION NO. 0006 DESIGN NO. 0118; A 254'-0 X 60'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE IM-NHS-080-1(388)2--03-78

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

SECTION NO. 0006	
DESIGN NO. 0118; A 254'-0 X 60'-0 PRETENSIONED PREST	TRESSED
CONCRETE BEAM BRIDGE IM-NHS-080-1(388)203-78	
2403-0100010 STRUCT CONC (BRIDGE)	62 CY
2404-7775000 REINFORC STEEL	4,706 LB
2404-7775005 REINFORC STEEL, EPOXY COATED	79,404 LB
SECTION NO. 0007	
DESIGN NO. 0212; A 254'-0 X 60'-0 PRETENSIONED PREST	FRESSED
CONCRETE BEAM BRIDGE IM-NHS-080-1(388)203-78	
2403-0100010 STRUCT CONC (BRIDGE)	116 CY
2404-7775000 REINFORC STEEL	9,422 LB
2404-7775005 REINFORC STEEL, EPOXY COATED	151,785 LB

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 111 Proposal ID: 94-2690-625 Proposed Contract Period: Specified Start Date of 07/27/15 with 135 WORK DAYS Proposal Note: *** SPECIFIED START DATE *** DUE TO THE CITY OF FORT DODGE HOSTING RAGBRAI, WORK ON THIS CONTRACT WILL NOT BE ALLOWED UNTIL THE SPECIFIED START DATE SHOWN ABOVE. ALSO, DUE TO THE AMOUNT OF WORK ON THIS CONTRACT, CONSTRUCTION WILL BE ALLOWED TO CONTINUE INTO THE 2016 CONSTRUCTION SEASON, REFER TO THE STAGING J SHEETS IN THE PLANS FOR MORE INFORMATION. THE CONTRACTOR IS REQUIRED TO HAVE THE PERMANENT TRAFFIC SIGNALS INSTALLED, DRIVEWAYS OPEN, AND THE ROADWAYS OPEN TO TWO-WAY TRAFFIC PRIOR TO THE WINTER SHUTDOWN PERIOD. Project(s): Project No: STP-A-2690(625)--86-94 County: WEBSTER Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: 1ST AVE Length: 0.45 miles Location: IN THE CITY OF FORT DODGE: IMPROVEMENTS AT THE INTERSECTION OF 1ST AVE S AND SOUTH 25TH ST _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 4,662 CY 12,146 SY 72 TON 178 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 4 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 112 Proposal ID: 99-0527-603 Proposed Contract Period: Late Start Date of 09/07/15 with 25 WORK DAYS Project(s): Project No: FM-0527(603)--55-99 County: WRIGHT Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: 150TH ST. (C26) Length: 0.13 miles Location: IN THE CITY OF BELMOND, FROM US HWY 69 WEST 700 FEET TO BEGINNING OF PROJECT _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 3,216 CY 2,033 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 151 Proposal ID: 00-0002-503 Proposed Contract Period: Late Start Date of 09/21/15 with 20 WORK DAYS Project(s): Project No: MB-000-2(503)0--77-00 County: STATEWIDE Type of Work: HMA RESURFACING WITH MILLING Route: VARIOUS DIST 2 Length: 0.00 miles Location: VARIOUS LOCATIONS IN HOWARD AND CHICKASAW COUNTIES Project No: MP-063-2(708)175--76-09 County: BREMER Type of Work: HMA RESURFACING Route: U.S. 63 Lengt Location: DENVER TO 1 MI N OF IA 93 Length: 0.00 miles _____ Item Description Item No. Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS MB-000-2(503)0-77-00 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 365 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 164 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 10 EACH SECTION NO. 0002 ROADWAY ITEMS MP-063-2(708)175--76-09 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 140 TON 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 177 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 152 Proposal ID: 06-0082-005 Proposed Contract Period: Late Start Date of 10/05/15 with 10 WORK DAYS Project(s): Project No: STPN-008-2(5)--2J-06 County: BENTON Type of Work: HMA PAVED SHOULDER - NEW Route: IOWA 8 Length: 3.42 miles Location: 1 MI W OF US 218 EAST TO US 218 Project No: MP-008-1(706)8--76-86 County: TAMA Type of Work: TRANSVERSE JOINT REPAIR Route: IOWA 8 Length: 6.03 miles Location: FROM APPROX. 600' E. OF CO. RD. X AVE. E. TO 120' W. OF US 218 IN BENTON CO. _____ Item No. Item Description Quantity/Unit -----_____ SECTION NO. 0001 ROADWAY ITEMS STPN-8-2(5)--2J-06 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 721 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 153 Proposal ID: 07-2187-228 Proposed Contract Period: Late Start Date of 06/22/15 with 90 WORK DAYS Project(s): Project No: NHSX-218-7(228)--3H-07 County: BLACK HAWK Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: U.S. 218 Length: 1.82 miles Location: IN THE CITY OF WATERLOO FROM MARIGOLD DR. TO US 20 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 458 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 923 CY 2303-0031750 HMA (1M ESAL) BASE, 3/4" 857 TON 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 8,589 TON 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 9,032 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 177 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 16 EACH

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 154 Proposal ID: 11-C011-096 Proposed Contract Period: Late Start Date of 07/13/15 with 50 WORK DAYS Project(s): Project No: FM-C011(96)--55-11 County: BUENA VISTA Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: C-25 Length: 3.00 miles Location: C25 US 71 TO 160TH Project No: LFM-R(82)--7X-11 County: BUENA VISTA Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: C-29 Length: 5.00 mile Location: C-29 M50 TO M54 Length: 5.00 miles _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS FM-C011(96)--55-11 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 4,465 TON 2303-0043502 HMA (3M ESAL) SURF, 1/2", FRIC L-2 4,465 TON SECTION NO. 0002 ROADWAY ITEMS LFM-R(82)--7X-11 2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 12,029 TON 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 2303-0043502 HMA (3M ESAL) SURF, 1/2", FRIC L-2 2,125 TON 2,125 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 155 Proposal ID: 22-0189-104 Proposed Contract Period: Late Start Date of 06/15/15 with 10 WORK DAYS Project(s): Project No: TSF-018-9(104)--92-22 County: CLAYTON Type of Work: HMA PAVEMENT - GRADE AND REPLACE Route: U.S. 18 Length: 0.00 miles Location: IN THE CITY OF MONONA AT THE FALCON AVE./MAIN ST. INTERSECTION _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 11 CY 57 SY 1 EACH

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 156 Proposal ID: 24-0302-158 Proposed Contract Period: Late Start Date of 05/26/15 with 95 WORK DAYS Project(s): Project No: HSIPX-030-2(158)--3L-24 County: CRAWFORD Type of Work: HMA PAVED SHOULDER - NEW Route: U.S. 30 Length: 25.25 miles Location: FROM 20TH ST. IN DENISON E. TO E. JCT. RADIANT ST. IN CARROLL Project No: NHSN-030-2(161)--2R-24 County: CRAWFORD Type of Work: MICROSURFACING Route: U.S. 30 Length: 11.52 miles Location: WCL OF WESTSIDE TO US 71 _____ Item No. Item Description Quantity/Unit _____ _____ SECTION NO. 0001 ROADWAY ITEMS HSIPX-030-2(158)--3L-24 2102-2625000 EMBANKMENT-IN-PLACE 580 CY 9,370 CY 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW SECTION NO. 0002 ROADWAY ITEMS NHSN-030-2(161)--2R-24 2303-0043502 HMA (3M ESAL) SURF, 1/2", FRIC L-2 92 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 157 Proposal ID: 31-0209-231 Proposed Contract Period: Late Start Date of 08/31/15 with 25 WORK DAYS Project(s): Project No: NHSN-020-9(231)--2R-31 County: DUBUQUE Type of Work: HMA RESURFACING WITH MILLING Route: U.S. 20 Length: 2.71 miles Location: MILE HILL LANE TO OLD HIGHWAY RD (EBL / WBL) _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS
 2303-0053503
 HMA (10M ESAL) SURF, 1/2", FRIC L-3
 6,765 TON

 2303-7000510
 HMA MIX INCORPORATED W/ ANTI-STRIP AGENT
 6,765 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 158 Proposal ID: 31-0522-131 Proposed Contract Period: Late Start Date of 05/18/15 with 115 WORK DAYS Project(s): Project No: STPN-052-2(131)--2J-31 County: DUBUQUE Type of Work: HMA RESURFACING Route: U.S. 52 Length: 8.08 miles Location: JACKSON CO TO US 61 Project No: NHSN-061-8(137)--2R-31 County: DUBUQUE Type of Work: HMA RESURFACING Route: U.S. 61 Length: 0.94 miles Location: IN DUBUQUE FROM LAKE ELEANOR RD. TO US 52 Project No: NHSN-151-5(67)--2R-31 County: DUBUQUE Type of Work: HMA RESURFACING Route: U.S. 151 Length: 1.00 miles Location: IN DUBUQUE AT THE S. JCT. OF US 61 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS STPN-052-2(131)--2J-31 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 SECTION NO. 0002 2102-2625000 EMBANKMENT-IN-PLACE 104 CY 18,380 TON 18,993 TON SECTION NO. 0002 ROADWAY ITEMS NHSN-061-8(137)--2R-31 2303-0052500 HMA (10M ESAL) INTERMEDIATE, 1/2" 4,700 TON 2303-0053502 HMA (10M ESAL) SURF, 1/2", FRIC L-2 3.650 TON 2303-7000510 HMA MIX INCORPORTED TO SECTION NO. 0003 ROADWAY ITEMS NHSN-151-5(67)--2R-31 2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH 2,206 CY 2303-0031500 $\,$ HMA (1M ESAL) BASE, 1/2" $\,$ 2,269 TON 2303-0052500 HMA (10M ESAL) INTERMEDIATE, 1/2" 2303-0053502 HMA (10M ESAL) SURF, 1/2", FRIC L-2 2,914 TON 3,011 TON SECTION NO. 0005 DESIGN NO. 0215; REPAIRS TO A 303' X 56' WELDED GIRDER NHSN-151-5(67)--2R-31 BRIDGE 2403-0100000 STRUCT CONC (MISCELLANEOUS) 168 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 61,287 LB

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 159 Proposal ID: 41-C041-115 Proposed Contract Period: Late Start Date of 08/17/15 with 35 WORK DAYS Project(s): Project No: STP-S-C041(115)--5E-41 County: HANCOCK Type of Work: HMA RESURFACING Route: R-20 Length: 11.00 miles Location: R-20: FROM U.S. # 18 NORTH 11.0 MILES TO WINNEBAGO COUNTY LI NE Project No: FM-C041(116)--55-41 County: HANCOCK Type of Work: HMA RESURFACING Route: B-14 Length: 3.00 miles Location: B-14: FROM KOSSUTH COUNTY LINE EAST 3.0 MILES TO JCT. R-20 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS STP-S-C041(115)--5E-41 2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 24,514 TON SECTION NO. 0003 ROADWAY ITEMS 2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 5.727 5,727 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 160 Proposal ID: 50-1171-027 Proposed Contract Period: Late Start Date of 09/14/15 with 20 WORK DAYS Project(s): Project No: STPN-117-1(27)--2J-50 County: JASPER Type of Work: HMA PAVED SHOULDER - NEW Route: IOWA 117 Length: 1.00 miles Location: IA 163 TO E. 2ND ST IN THE CITY OF PRAIRIE CITY Project No: MP-117-1(705)0--76-50 County: JASPER Type of Work: PCC PATCHING Route: IOWA 117 Length: 1.62 miles Location: IN THE CITY OF PRAIRIE CITY FROM IA 163 TO IT'S NCL _____ Item Description Item No. Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS STPN-117-1(27)--2J-50 2102-2625000 EMBANKMENT-IN-PLACE 230 CY SECTION NO. 0002 ROADWAY ITEMS MP-117-1(705)0--76-50 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 568 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 37 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 161 Proposal ID: 73-C073-125 Proposed Contract Period: Late Start Date of 06/22/15 with 60 WORK DAYS Project(s): Project No: STP-S-C073(125)--5E-73 County: PAGE Type of Work: HMA RESURFACING Route: VARIOUS ROUTES Length: 21.20 miles Location: J28 FROM IA 48 TO J AVE., J20 FROM N AVE. TO US 71, M60 FROM J52 TO IA 2. _____ Quantity/Unit Item No. Item Description SECTION NO. 0001 ROADWAY ITEMS J20 2102-2625000 EMBANKMENT-IN-PLACE 1,088 CY 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 22,782 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 320 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 8 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 162 Proposal ID: 99-C099-081 Proposed Contract Period: Late Start Date of 06/22/15 with 75 WORK DAYS Project(s): Project No: FM-C099(81)--55-99 County: WRIGHT Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: R-65 Length: 5.00 miles Location: ON R-65, FROM C-25 TO BELMOND CITY LIMITS _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 5,250 TON 3,151 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 201 Proposal ID: 01-0804-713 Proposed Contract Period: Late Start Date of 10/19/15 with 10 WORK DAYS Project(s): Project No: MPIN-080-4(713)80--0N-01 County: ADAIR Type of Work: PCC PATCHING Route: I-80 Length: 0.00 miles Location: EASTBOUND REST AREA _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070111 PATCH,FULL-DEPTH FINISH,BY AREA(=>50 FT) 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 424 SY 167 SY 37 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 202 Proposal ID: 01-0804-714 Proposed Contract Period: Late Start Date of 08/10/15 with 20 WORK DAYS Project(s): Project No: MPIN-080-4(714)93--0N-01 County: ADAIR Type of Work: HMA CRACK FILLING Route: I-80 Length: 5.96 miles Location: FROM 0.2 MI EAST OF P28 TO 0.7 MI WEST OF P53. _____ _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 203 Proposal ID: 25-0804-712 Proposed Contract Period: Late Start Date of 08/31/15 with 10 WORK DAYS Project(s): Project No: MPIN-080-4(712)107--0N-25 County: DALLAS Type of Work: PCC JOINT & CRACK FILLING Route: I-80 Length: 3.00 miles Location: 0.6 MI E OF CO RD F90 TO 0.1 MI W OF US 6 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 204 Proposal ID: 39-1411-707 Proposed Contract Period: Late Start Date of 05/26/15 with 90 WORK DAYS Project(s): Project No: MP-030-1(708)126--76-08 County: BOONE Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 30 Length: 2.00 miles Location: AT ALL 4 EXIT & ENTRANCE RAMPS & LOOPS ON THE U.S. 30 & U.S. 169 INTERCHANGE AT OGDEN. Project No: MP-030-1(710)89--76-14 County: CARROLL Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 30 Length: 9.80 miles Location: IN THE CITY OF GLIDDEN FROM 960' EAST OF UTAH ST., EAST TO 1000' EAST OF IOWA 25 IN GREENE CO. Project No: MP-044-1(707)96--76-25 County: DALLAS Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 44 Length: 7.40 miles Location: IN THE CITY OF DALLAS CENTER FROM 0.15 MI. EAST OF 10TH ST., EAST TO APPROX. 0.12 MI. INTO POLK CO. Project No: MP-144-1(712)12--76-37 County: GREENE Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 144 Length: 5.80 miles Location: FOUR SITES BETWEEN THE CITIES OF RIPPEY & GRAND JUNCTION (SEE PROPOSAL DOCUMENTS FOR LOCATION DETAILS). Project No: MP-025-1(706)100--76-39 County: GUTHRIE Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 25 Length: 2.06 miles Location: FROM W. JCT. IOWA 141 NORTH TO 350 FT. N. OF E-63. IN GREENE CO. Project No: MP-141-1(707)98--76-39 County: GUTHRIE Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 141 Length: 15.95 miles Location: FROM SCL COON RAPIDS E. TO 500 FT. W. OF N. JCT. WITH IOWA 4 Project No: MP-020-1(710)149--76-40 County: HAMILTON Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 20 Length: 3.64 miles Location: FROM U.S. 69 TO I-35. (WB ONLY) Project No: MP-175-1(705)146--76-40

	MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)	
County	HAMILTON	
-	HAMILION HMA JOINT & CRACK SEALING	
	IOWA 175 Length: 7.91 miles	
	FROM THE N. JCT. OF IOWA 17 IN STANHOPE, EAST	TO U.S. 69.
	MP-017-1(706)776-77	
County:		
Type of Work:	HMA JOINT & CRACK SEALING	
	IOWA 17 Length: 12.37 miles	
Location:	FROM 0.18 MI. NORTH OF NW 158TH ST., NORTH TO OF U.S. 30 IN BOONE CO.	0.25 MI. SOUTH
	MPIN-035-1(709)1210N-85	
County:		
	HMA JOINT & CRACK SEALING	
	I-35 Length: 12.59 miles	
Location:	FROM 1.62 MI. S. OF E-18 TO 1 MI. N. OF IOWA HAMILTON CO. (NB LANES ONLY).	175 IN
	MP-069-1(708)11876-85	
County:		
	HMA JOINT & CRACK SEALING	
	U.S. 69 Length: 19.83 miles	
Location:	IN THE CITY OF AMES FROM 0.11 MI. N. OF 24TH	ST. TO NCL OF
	JEWELL IN HAMILTON CO. (VARIOUS LOCATIONS).	
	tem Description	Quantity/Uni

 	1	~

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 205 Proposal ID: 50-1171-704 Proposed Contract Period: Late Start Date of 06/08/15 with 80 WORK DAYS Project(s): Project No: MP-065-1(708)133--76-42 County: HARDIN Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 65 Length: 6.43 miles Location: IN THE CITY OF HUBBARD FROM THE IOWA 175/U.S. 65 S. JCT. N. & E. TO 0.26 MI. EAST OF THE IOWA 175/U.S. 65 N. JCT. Project No: MP-117-1(704)9--76-50 County: JASPER Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 117 Length: 9.53 miles Location: FROM 0.29 MI. NORTH OF I-80, NORTH TO 0.5 MI. SOUTH OF JCT WITH U.S. 65. Project No: MP-063-1(710)76--76-62 County: MAHASKA Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 63 Length: 6.59 miles Location: IN THE CITY OF NEW SHARON, FROM ECL, EAST & NORTH TO APPROX. 100' INTO POWESHIEK CO. Project No: MP-006-1(709)186--76-79 County: POWESHIEK Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 6 Length: 1.50 miles Location: IN THE CITY OF GRINNELL, FROM 1 MILE WEST OF IOWA 146, EAST 1.5 MILES. Project No: MPIN-080-1(704)184--0N-79 County: POWESHIEK Type of Work: HMA JOINT & CRACK SEALING Route: I-80 Length: 9.20 miles Location: FROM 0.94 MI. E. OF IOWA146 TO 1.1 MI. E. OF U.S. 63 (EB LANES ONLY). Project No: MP-085-1(701)1--76-79 County: POWESHIEK Type of Work: HMA JOINT & CRACK SEALING 8.42 miles Route: IOWA 85 Length: Location: FROM THE ECL OF MONTEZUMA, E. TO JCT. WITH IOWA 21. Project No: MP-030-1(711)164--76-85 County: STORY Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 30 Length: 8.24 miles Location: FROM 0.6 MI. WEST OF U.S. 65 TO 0.2 MI. E. OF. S52 IN MARSHALL CO.

	MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)	
Project No:	MP-008-1 (705) 076-86	
County:	TAMA	
Type of Work:	HMA JOINT & CRACK SEALING	
Route:	IOWA 8 Length: 0.49 miles	
Location:	IN THE CITY OF TRAER FROM U.S. 63, E. TO THE B OVER COON CR.	RIDGE
Project No:	MP-096-1(702)1076-86	
County:	ТАМА	
	HMA JOINT & CRACK SEALING	
Route:	IOWA 96 Length: 6.19 miles	
Location:	IN THE CITY OF GLADBROOK FROM T-47 TO	
	0.33 MI. WEST OF THE JCT. WITH U.S. 63.	
	tem Description	Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 206 Proposal ID: 52-2186-703 Proposed Contract Period: Late Start Date of 05/26/15 with 60 WORK DAYS Project(s): Project No: MP-038-6(706)36--76-16 County: CEDAR Type of Work: HMA CRACK FILLING Route: IOWA 38 Length: 7.22 miles Location: FARMERS ST. IN STANWOOD TO WALNUT CREEK IN OLIN Project No: MP-130-6(711)0--76-16 County: CEDAR Type of Work: HMA CRACK FILLING Route: IOWA 130 Length: 0.64 miles Location: IN TIPTON, FROM 2 BLOCKS E OF IOWA 38 TO ECL Project No: MP-136-6(717)39--76-23 County: CLINTON Type of Work: HMA CRACK FILLING Route: IOWA 136 Let Length: 15.44 miles Location: LOST NATION TO W JCT IOWA 64 Project No: MP-220-6(707)6--76-48 County: IOWA Type of Work: HMA CRACK FILLING Route: IOWA 220 Length: 1.42 miles Location: MIDDLE AMANA TO U.S. 151 Project No: MP-218-6(703)89--76-52 County: JOHNSON Type of Work: HMA CRACK FILLING Route: U.S. 218 Length: 7.95 Location: FROM 1 MI S OF RIVERSIDE DR TO I-80 Length: 7.95 miles Project No: MP-218-6(707)81--76-92 County: WASHINGTON Type of Work: HMA CRACK FILLING Route: U.S. 218 Length: 7.82 miles Location: FROM IOWA 22 TO 1 MI S OF RIVERSIDE DR _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 207 Proposal ID: 77-0651-711 Proposed Contract Period: Late Start Date of 08/31/15 with 10 WORK DAYS Project(s): Project No: MP-028-1(710)21--76-77 County: POLK Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 28 Length: 1.26 miles Location: IN THE CITY OF DES MOINES FROM 600 FT. S. OF MADISON AVE. NORTH TO 445 FT. N. OF SUTTON DR. Project No: MP-065-1(711)89--76-77 County: POLK Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 65 Length: 4.55 miles Location: TWO LOCATIONS (1 NB, 1 SB) BETWEEN NE 88TH ST. & NE 112TH ST ; SEE PROPOSAL DOCUMENTS FOR LOCATION MAP _____ Item Description Quantity/Unit Item No.

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 208 Proposal ID: 78-0804-716 Proposed Contract Period: Late Start Date of 08/24/15 with 15 WORK DAYS Project(s): Project No: MPIN-080-4(716)47--0N-78 County: POTTAWATTAMIE Type of Work: SLURRY SEAL Route: I-80 Length: 7.55 miles Location: WALNUT TO IOWA 173 _____ Quantity/Unit Item No. Item Description _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 301 Proposal ID: 03-0511-016-A Proposed Contract Period: Late Start Date of 10/12/15 with 10 WORK DAYS Project(s): Project No: BRFN-051-1(16)--39-03 County: ALLAMAKEE Type of Work: SLOPE PROTECTION Route: IOWA 51 Length: 0.00 miles Location: 3.4 MI N OF POSTVILLE _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 302 Proposal ID: 57-1513-155 Proposed Contract Period: Late Start Date of 10/05/15 with 10 WORK DAYS Project(s): Project No: ER-151-3(155)--28-57 County: LINN Type of Work: REVETMENT Length: 0.00 miles Route: U.S. 151 Location: DRAINAGE DITCH 0.6 MI S OF US 30 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 303 Proposal ID: 60-C060-111 Proposed Contract Period: Late Start Date of 06/01/15 with 20 WORK DAYS Project(s): Project No: ER-C060(111)--58-60 County: LYON Type of Work: REVETMENT Route: A34 Length: 0.05 miles Location: AT INTERSECTION OF DOVE AVE IN LYON COUNTY _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 300 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 304 Proposal ID: 70-0224-076 Proposed Contract Period: Late Start Date of 05/18/15 with 15 WORK DAYS Project(s): Project No: ER-022-4(76)--28-70 County: MUSCATINE Type of Work: REVETMENT Route: IOWA 22 Length: 0.00 miles Location: WAPSINONOC CREEK 1.6 MI E OF W JCT IA 70 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 305 Proposal ID: 91-C091-098 Proposed Contract Period: Late Start Date of 05/18/15 with 10 WORK DAYS Project(s): Project No: FM-C091(98)--55-91 County: WARREN Type of Work: GRANULAR SURFACING OF ROADWAY Route: VARIOUS ROUTES Length: 0.00 miles Location: VARIOUS FM ROADS THROUGHOUT THE COUNTY _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 306 Proposal ID: 92-C092-087 Proposed Contract Period: Late Start Date of 09/28/15 with 15 WORK DAYS Project(s): Project No: FM-C092(87)--55-92 County: WASHINGTON Type of Work: GRANULAR SHOULDERS - REPAIR Route: W38 Length: 8.51 miles Location: ON W38, FROM HWY 92 NORTH TO WELLMAN CITY LIMITS _____ Item No. Item Description Quantity/Unit _____

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 351 Proposal ID: 00-000S-725 Proposed Contract Period: By individual sites. Site 01: TO COMPLETE DIVISION 1 SIGNS Late Start Date of 09/28/15 with 25 WORK DAYS Site 02: TO COMPLETE DIVISION 2 SIGNS Late Start Date of 05/26/15 with 15 WORK DAYS Project(s): Project No: NHSN-000-S(725)--2R-00 County: STATEWIDE Type of Work: TRAFFIC SIGNS Route: MULTIPLE ROUTES Length: 0.00 miles Location: VARIOUS LOCATIONS STATEWIDE _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 352 Proposal ID: 00-000S-779 Proposed Contract Period: Late Start Date of 08/03/15 with 60 WORK DAYS Project(s): Project No: NHSN-000-S(779)--2R-00 County: STATEWIDE Type of Work: TRAFFIC SIGNS Route: MULTIPLE ROUTES Length: 0.00 miles Location: VARIOUS LOCATIONS IN DISTRICT 1 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 353 Proposal ID: 00-000S-780 Proposed Contract Period: Late Start Date of 05/26/15 with 125 WORK DAYS Project(s): Project No: NHSN-000-S(780)--2R-00 County: STATEWIDE Type of Work: TRAFFIC SIGNS Route: MULTIPLE ROUTES Length: 0.00 miles Location: VARIOUS LOCATIONS IN DISTRICT 2 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 354 Proposal ID: 25-C025-097 Proposed Contract Period: Late Start Date of 08/31/15 with 25 WORK DAYS Project(s): Project No: HSIP-S-C025(97)--6C-25 County: DALLAS Type of Work: PAVEMENT MARKINGS Route: VARIOUS LOCATIONS Length: 59.00 miles Location: ON F90, P46, P58, R16, R22 & 323RD PL. _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 355 Proposal ID: 44-C044-078-A Proposed Contract Period: Late Start Date of 09/14/15 with 15 WORK DAYS Project(s): Project No: HSIP-S-C044(78)--6C-44 County: HENRY Type of Work: PAVEMENT MARKINGS Route: VARIOUS LOCATIONS Length: 30.00 miles Location: PVMT MARKINGS GROOVE & PAINT PCC PAVEMENTS- COUNTY WIDE _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 356 Proposal ID: 55-0183-094-B Proposed Contract Period: Late Start Date of 08/31/15 with 35 WORK DAYS Project(s): Project No: TSF-018-3(94)--92-55 County: KOSSUTH Type of Work: TRAFFIC SIGNALS Route: U.S. 18 Length: 0.00 miles Location: IN THE CITY OF ALGONA AT THE N. MAIN ST. INTERSECTION _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 601 Proposal ID: 17-0352-509 Proposed Contract Period: Late Start Date of 05/26/15 with 110 WORK DAYS Project(s): Project No: MB-018-2(501)178--77-17 County: CERRO GORDO Type of Work: BRIDGE CLEANING Route: U.S. 18 Length: 0.00 miles Location: S I-35 INTERCHANGE Project No: MBIN-035-2(509)192--0M-17 County: CERRO GORDO Type of Work: BRIDGE CLEANING Route: I-35 Len Location: VARIOUS BRIDGES ON I-35 Length: 0.00 miles Project No: MBIN-035-2(513)165--0M-35 County: FRANKLIN Type of Work: BRIDGE CLEANING Route: I-35 Lengt Length: 0.00 miles Location: VARIOUS BRIDGES ON I-35 Project No: MBIN-035-2(502)155--0M-99 County: WRIGHT Type of Work: BRIDGE CLEANING Route: I-35 Length: 0.00 miles Location: VARIOUS BRIDGES ON I-35 Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 602 Proposal ID: 77-2351-512 Proposed Contract Period: Late Start Date of 05/26/15 with 80 WORK DAYS Project(s): Project No: MBIN-235-1(512)10--0M-77 County: POLK Type of Work: BRIDGE PAINTING Length: 0.00 miles Route: I-235 Location: IN DES MOINES FROM UNIVERSITY AVE. TO GUTHRIE AVE. (7 LOCATIONS) _____ Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 603 Proposal ID: 97-0772-018 Proposed Contract Period: Late Start Date of 06/08/15 with 40 WORK DAYS Project(s): Project No: BRFN-077-2(18)--39-97 County: WOODBURY Type of Work: BRIDGE CLEANING Route: U.S. 77 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY OVER THE MISSOURI RIVER _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 604 Proposal ID: 97-1296-037 Proposed Contract Period: Late Start Date of 06/08/15 with 40 WORK DAYS Project(s): Project No: IMN-129-6(37)0--0E-97 County: WOODBURY Type of Work: BRIDGE CLEANING Route: I-129 Length: 0.00 miles Location: MISSOURI RIVER BRIDGE IN SIOUX CITY _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: April 21, 2015 10:00 A.M. Proposed Bid Order: 605 Proposal ID: 97-1296-038 Proposed Contract Period: Late Start Date of 07/13/15 with 80 WORK DAYS Project(s): Project No: IMN-129-6(38)0--0E-97 County: WOODBURY Type of Work: BRIDGE PAINTING Route: I-129 Length: 0.00 miles Location: MISSOURI RIVER BRIDGE IN SIOUX CITY _____ Item No. Item Description Quantity/Unit _____