

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: May 19, 2015
Date of Addendum: May 14, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
109	97-7057-689	PCC PAVEMENT - REPLACE	WOODBURY	STP-U-7057(689)--70-97	19MAY109.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0811 2528-8445113 FLAGGERS; 16.000 EACH

Add Proposal Line No. 0812 2549-0006100 BUILDING SANITARY SEWER SERVICE RECONNECTION; 26.000 EACH

If the above changes are not made, they will be made as shown here.

Make the following changes to the plan:

Plan Sheet B.1 – Chang the label from “12 inch C-Stone subbase over 12” prepared subgrade compacted to 95% of Standard Proctor Density to within -3% to +2% of optimum moisture content” to “18 inch C-Stone subbase over 12” prepared subgrade compacted to 95% of Standard Proctor Density to within -3% to +2% of optimum moisture content”

Plan sheet C.2

- a. Delete the following to Estimate Reference Information number 0050 – Subgrade Stabilization Material, C-Stone – “Only 12” will be placed unless unsuitable soils are found. Unsuitable soils will be marked for replacement by Engineer”.
- b. Add the following to Estimate Reference Information number 0420 - Traffic Control: “Bid item includes necessary traffic control for Site Number 2 (Sanitary Sewer Lining and sodding). Refer to Standard Road Plan TC-212. Bid item shall include extra barricades and traffic control devices as necessary to restrict lane width.”
- c. Add the following to Estimate Reference Information number 0260 - San Sewer G-Main, Trenched, VCP, Standard Strength, 8 IN: “Bid item includes Video Inspection and shall be completed and approved by Engineer prior to paving. Refer to section 2504.”