

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: September 15, 2015
Date of Addendum: September 10, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
451	07-3807-121	NOISE WALL	BLACK HAWK	IMX-380-7(121)65--02-07	15SEP451.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Delete Proposal Line No. 0090 2526-8285000 CONSTRUCTION SURVEY; LUMP

Delete Proposal Line No. 0190 2526-8285000 CONSTRUCTION SURVEY; LUMP

If the above changes are not made, they will be made as shown here.

Make the following change to the plans:

Replace plan SHEET NUMBER 2, SHEET NUMBER 26, SHEET NUMBER J.1

With the attached SHEET NUMBER 2, SHEET NUMBER 26, SHEET NUMBER J.1

108-234
08-01-08

TRAFFIC CONTROL PLAN

I-380 shall remain open to traffic at all times. Nighttime single lane closures will be allowed at the bridge over McCoy Road for removal and installation of the noise wall on the bridge and the short sections where the noise wall tapers into the bridge. Lane closures allowed only between 7:00 PM and 6:00 AM Monday evening through Friday morning, and from 10:00 PM Sunday until 6:00 AM Monday. Short-term shoulder closures on I-380 will be allowed for the delivery of equipment and materials. Shoulder closures will not be allowed between 6:00 AM Friday and 10:00 PM Sunday and from 6:00 AM and 3:00 PM Monday through Thursday. Materials, vehicles, and equipment shall not be stored on the shoulder. The duration of any vehicles or equipment on the shoulder shall be limited to only the amount of time it takes to load or unload materials or equipment.

The Iowa DOT reserves the right to modify the hours specified above as necessary to accommodate unexpected traffic volumes.

Night work will only be allowed during the times it is necessary to close a lane for the removal and installation of the noise wall on the bridge over McCoy Road and the short sections where the noise wall tapers into the bridge, or to load and unload materials and equipment with shoulder closures.

McCoy Road may be closed to traffic during installation of the noise wall on the bridge. No detour route will be established. Notify the Engineer 3 business days in advance of the proposed closure. The sidewalk along McCoy Road will also be closed during the roadway closure.

Lane closures or shoulder closures may not begin prior to April 4, 2016.

Take measures to prevent tracking and spilling of dirt, mud, snow, ice, or other foreign materials onto the I-380 traffic lanes and ramps.

Do not store materials and equipment closer than 15 feet from the edge of the traffic lane. It is the intent to minimize the size, number, and duration of storage areas and to maximize the distance of such storage areas from the edge of the travel lane subject to the approval of the Engineer. During times when loading or unloading is not occurring, sign and channelize storage areas in accordance with TC-402, with the channelizers placed to the outside edge of the shoulder. No more than one production day worth of materials or waste may be stored closer to the roadway than the 11.5 foot wide bench upon which the proposed noise wall is centered.

108-26A
08-01-08

STAGING NOTES

The Contractor may choose the sequence and timing of wall construction; more than one section of wall may be worked on at a time. Noise Wall B shall be included in the construction stage for either Noise Wall A or Noise Wall C at the Contractor's option. Each section of noise wall (A, C, or D) must be replaced within 60 calendar days of beginning removal of that section of wall.

113-2
04-16-13

PEDESTRIAN PATH CLOSURES

Refer to TC-601.

*Assumes 6 foot wide barricade. Closures may need to be removed and re-established.

Location	Slide	Type III Barricades* No.	Remarks
McCoy Road sidewalk under I-380	Both	2	Concurrent with McCoy Road closure

111-01
04-17-12

COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
IMX-380-7(120)71--0E-07	DECK JOINT REPAIR

ENGLISH IOWA DOT DESIGN TEAM Snyder & Associates, Inc.

9/7/2015 9:28:59 AM cspencer J:\0812_PROJECTS\132_05500\cand\msign\kexce\107880121361.x15a

Black Hawk COUNTY

PROJECT NUMBER

IMX-380-7(121)65--02-07

SHEET NUMBER

J.1