

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: October 27, 2015
Date of Addendum: October 6, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
001	78-0801-372	BRIDGE NEW - STEEL GIRDER	POTTAWATTAMIE	IM-NHS-080-1(372)4--03-78 IM-NHS-080-1(373)4--03-78 IM-NHS-080-1(374)4--03-78 IM-NHS-080-1(375)4--03-78 IM-NHS-080-1(376)4--03-78 IM-NHS-080-1(377)4--03-78 IM-NHS-080-1(420)4--03-78 IM-NHS-080-1(462)4--03-78	27OCT001.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 3841 2599-9999099 Temporary RW0100 – Waler, Steel, W14x34 ;
25.000 LF

Change Proposal Line No. 3420 2513-0001020 CONCRETE BARRIER, BA-102:
From: 695.800 LF
To: 796.000 LF

If the above changes are not made, they will be made as shown here.

Make the following change to the Proposal Special Provisions List and the Proposal Special Provisions Text.:

Add the attached SP-150027 - DRILLED-IN SOLDIER PILE AND LAGGING WALL

Replace SP-150008 with attached SP-150008a

REPLACE Railroad Data sheets for BNSF Railroad with the attached sheets:

IM-NHS-80-1(372)--03-78
IM-NHS-80-1(377)--03-78
IM-NHS-80-1(374)--03-78

New data sheets decrease the railroad frequency from 46 trains/day to 2 trains/day.

Make the following changes to Plans:

IM-NHS-080-1(372)4--03-78

Replace sheets J.1 & J.4 with attached plan sheets.

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

J.4 Revised Access Routes for the rail yard area:

IM-NHS-080-1(373)4--03-78

Replace sheets J.1 with attached plan sheet.

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

IM-NHS-080-1(374)4--03-78

Replace sheets C.2, J.1, & J.5 with attached plan sheets.

C.2 - Updated ESTIMATE REFERENCE INFORMATION for Item Code 243-0254902 — Intake Tops shall be Cast-In-Place

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

J.5 Revised Access Routes for the rail yard area:

IM-NHS-080-1(375)4--03-78

Replace sheets J.1 with attached plan sheet.

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

IM-NHS-080-1(376)4--03-78

Replace sheets J.1 with attached plan sheet.

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

IM-NHS-080-1(377)4--03-78

Replace sheets J.1 & J.25 with attached plan sheets.

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

J.25 Revised Access Routes for the rail yard area:

IM-NHS-080-1(420)4--03-78

Replace sheets J.1 with attached plan sheet.

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

IM-NHS-080-1(462)4--03-78

Replace sheets C.1, C.2, J.1, V.4, V.5, & V.6 with attached plan sheets

C.1 - Update Project Quantities for IM-NHS-80-1(462)4—03-78
Item Code 2513-0001020 – Concrete Barrier, BA-102 – 762 LF

C.2 - Update ESTIMATE REFERENCE INFORMATION for
Item Code 2435-0256210 – Intake Tops for SW-549 shall be cast-in-place

J.1 - Update Traffic Control Plan Notes to include Friday lane closure times for I-80 eastbound (east of the I-29 southbound diverge in the east system interchange)

V.4 - Drilled-in Soldier Pile and Lagging Retaining Wall Situation Plan:
Plan revises the retaining wall design to include a waler and increases pile spacing to accommodate an existing sanitary sewer line.

V.5 - Revised locations and elevations for soldier pile. Added Quantities for Temporary RW0100 – Item Code 2599-99990099 – Waler, Steel, W14x34 – 25 LF
Added General Notes for waler installation.

V.6 - Added notes and detail for installation of waler



Iowa Department of Transportation

SPECIAL PROVISIONS FOR DRILLED-IN SOLDIER PILE AND LAGGING WALL

**Pottawattamie County
IM-NHS-080-1(462)4--03-78**

**Effective Date
October 27, 2015**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

150027.01 DESCRIPTION.

- A.** This work shall consist of furnishing and constructing drilled-in soldier pile and lagging walls in accordance with this special provision and with the lines, grades and dimensions shown on the contract drawings and per the shop drawings prepared by the specialty wall Contractor.
- B.** A drilled-in soldier pile and lagging wall is a cut retaining wall system composed of drilled-in steel soldier piles placed in pre-bored holes. The portion of the piles that will be embedded below the excavation are encased in structural concrete while controlled low strength material (CLSM) or approved equivalent encase the portion of the soldier piles above the proposed bottom of excavation. After the soldier piles are installed, timber lagging is placed between the soldier piles to transfer lateral loads from the soil to the soldier piles.
- C.** Sequence of construction for the drilled-in soldier pile and lagging wall is shown on the contract drawings. The soldier piles will be drilled in from the existing grade to the tip elevation, followed by filling of the pre-drilled hole with structural concrete and CLSM around the steel element. Sequential excavation and placement of the timber lagging will follow. As necessary, granular fill or approved equivalent will be used to fill any voids between the timber lagging and retained soil.

150027.02 MATERIALS.

A. Steel Soldier Pile.

- 1.** Conform to Section 4167 of the Standard Specifications.
- 2.** Storing, transporting, and handling shall be performed in a manner to prevent bending stresses or other damage.

B. Concrete for Drilled in Soldier Piles.

1. All materials, proportioning, air entraining, mixing, slump, and transporting of PCC shall be according to Section 2403 of the Standard Specifications, except as modified herein.
2. Water/cement ratio: not to exceed 0.45.
3. Drilled-in soldier pile construction: use Class D PCC mixture with a slump of 8 inches ± 1.5 inches.
4. Portland cement: meet the requirements of ASTM C 150 Type I / II and Section 4101 of the Standard Specifications.
5. Air entrainment: apply Section 2403 of the Standard Specifications.
6. Mid-range water reducer is required according to Materials I.M. 403.
7. Retarder is required according to Materials I.M. 403 to maintain workable concrete.
8. Do not use Ground Granulated Blast Furnace Slag (GGBFS).

C. Timber Lagging.

Graded for extreme fiber stress of at least 1000 psi and with the full dimension thickness shown on the shop drawings.

D. Granular Backfill Material.

Ensure the backfill material meets the requirements of Section 4133 of the Standard Specifications, except that the percent passing the No. 200 sieve is not to exceed 5.0%.

E. Controlled Low Strength Material (CLSM).

Apply Section 2552.02 of the Standard Specifications.

F. Waler.

1. Conform to Section 4167 of the Standard Specifications.
2. Storing, transporting, and handling shall be performed in a manner to prevent bending stresses or other damage.

150027.03 CONSTRUCTION.

A. Contractor Qualifications.

Prior to initiating construction of the drilled-in soldier pile and lagging wall, the Contractor shall submit to the Engineer a report which identifies the Contractor's personnel who will be performing and supervising the work. The report shall include the names of an engineer-in-charge, on-site supervisors, and drill operators. The report shall also contain a list of employer's names and telephone numbers, location and dates of previous projects, and the extent of work performed. This information must be verifiable.

1. An on-site supervisor shall be present at the job site at all times during the performance of the work. The on-site supervisor shall have 1 year of construction experience in the installation of soldier pile and lagging walls and shall have supervised the successful installation of three walls. The work experience time period is computed by the addition of all documented durations of the work time on construction projects.
2. Drill operators shall have successfully installed three soldier pile and lagging walls.

B. Submittals.

The Contractor shall submit their proposed drilled-in soldier pile and lagging wall installation plans to the Engineer for review and approval. The submission shall consist of details required to completely describe the retaining wall system and shall include the following:

1. Shop drawings for the drilled-in soldier pile and lagging wall shown on the contract drawings at least 2 weeks before beginning the work, which indicate at a minimum, the following:
 - a. Grade and strengths of all construction materials used.
 - b. Materials, details, arrangement, and method of construction of the proposed soldier pile and lagging retaining wall system.
 - c. Details for the timber lagging.
 - d. Method for installing soldier piles, including pre-drilling procedures. Driven soldier piles are not permitted.
 - e. Mix designs for structural concrete and procedures for placing and verifying installation elevations of the structural concrete in accordance with the contract documents.
 - f. Mix design for the CLSM and procedures for placing the CLSM in accordance with the contract documents.
 - g. Details outlining additional grading to create a working platform (if needed).
 - h. Details outlining traffic control (if needed) to prevent lane closures of the existing Woodbury Avenue Bridge.
 - i. Sequence of construction.
2. Descriptive data and operating procedure for all equipment to be used. This shall include, at a minimum; machinery required to install soldier piles (including drilling procedures), timber lagging, excavate soil, and remove obstructions. Submit all pertinent equipment data including sizes, weights, capacities, torques, and operating frequencies.
3. Review and approval of the above submittals for the soldier pile and lagging retaining wall by the Engineer will not relieve the Contractor from the responsibility for the adequacy of the construction of drilled-in soldier pile and lagging wall to achieve the required results.

C. General Construction Methods.

1. Install and maintain the drilled-in soldier pile and lagging wall in accordance with the design as shown on the contract drawings and on the accepted shop drawings, and in such a manner as to minimize movement, settlement, loss of ground, removal of fines from adjacent ground, and damage to or movement of adjacent structures or utilities.
2. Ensure no gaps or pockets occur between the retained fill and timber lagging.

D. Drilled-in Soldier Pile and Lagging Construction.

1. Excavate or fill as needed to provide a suitable working pad at the proposed location where each soldier pile is to be installed, as shown on the contract drawings.
2. Predrill holes for soldier pile installation. If needed use steel casing to prevent collapse of the hole. Diameter of the pre-drilled holes shall meet the dimensions shown on the contract drawings. Prior to inserting the soldier pile, the Contractor shall make the necessary provisions to allow the Engineer to sound each hole to assure that loose soil has been removed to the Engineer's satisfaction. Once the design depth has been reached and loose soil removed from the bottom of the hole, the bottom of the hole shall be cleaned such that no more than 1 inch of loose/soft soil remains at the bottom. The soldier pile section shall then be lowered into the hole to the tip elevation specified on the contract drawings and structural concrete shall be immediately tremied to the proposed elevation shown on the contract drawings. CLSM is then to be tremied from the top elevation of the structural concrete to the existing grade. If casing is used for the construction of the soldier pile excavation, remove the

casing as concrete placement progresses and throughout concrete placement. The Contractor shall maintain the bottom of the casing at least 3 feet below the level of structural concrete. Drilling for adjacent soldier piles shall not be permitted until concrete and CLSM in adjacent drilled holes has set for a period of at least 24 hours.

3. After installation of the soldier piles, excavate along the proposed wall face in stages to the elevation shown on the contract drawings.
4. Allow no more than 5 feet of unsupported excavation prior to placing lagging. Install lagging as detailed in the contract drawings.
5. Fill any gap between the soldier pile and lagging wall and the retained fill with granular backfill specified in Section 2.

E. Construction Tolerances.

1. Ensure the drilled-in soldier pile is within 3 inches of plan position.
2. Ensure the vertical alignment of soldier pile excavation does not vary from the plan alignment by more than 1/4 inch per foot.
3. Soldier pile excavations and completed soldier piles not constructed within the required tolerances will be considered unacceptable. Correct all unacceptable excavations and completed soldier piles to the Engineer's satisfaction. Furnish materials and work necessary, including engineering analysis and redesign, to complete corrections for out of tolerance excavations (without either cost to the Contracting Authority or an extension of the completion dates of the project).

150027.04 METHOD OF MEASUREMENT.

- A. The soldier piles will be measured from the finished tip elevation to the top of the soldier pile elevation for payment in units of linear feet, as shown on the contract drawings.
- B. The drilled-in pile will be measured for payment in units of linear feet along the axis of the drilled-in pile from the top of the concrete encasement to the bottom of the drilled-in pile, as shown on the contract drawings.
- C. Installation of timber lagging will be measured by area in units of square yards, as shown on the contract drawings. Includes all costs of furnishing and installing timber lagging, including hardwood shimming, wood spacer plates, nails and clips. No additional payment will be provided to furnish damaged or otherwise unsuitable lagging boards.
- D. Class 20 excavation will be measured by volume in units of cubic yards, as shown on the contract drawings. This includes only the excavation of soil immediately in front (a maximum of 2 feet in front of the finished face of the wall) of the soldier pile wall to install the timber lagging. Excavation does not include the excavation quantity for roadway earthwork that will take place to construct the proposed I-80 west bound lanes. Additional payment will not be provided for furnishing and placing granular backfill specified in Section 2 to fill voids between retained fill and timber lagging due to over-excavation.
- E. The waler will be measured along the horizontal distance across specified piles for payment in units of linear feet, as shown on the contract drawings.

150027.05 BASIS OF PAYMENT.

- A. Payment for Piles, Steel, W21X132 shall be made at the contract unit price per linear foot. The unit price bid per vertical linear foot of pile shall include all labor, material, and equipment for furnishing the pile and the cost of one splice per pile (if required).
- B. Payment for Drilled-in Pile, 30 Inch Diameter shall be made at the contract unit price per linear foot. The unit price bid per vertical linear foot of pile shall include all labor, material and equipment for drilling and installing the drilled-in pile, including structural concrete, and incidental items include CLSM and the cost of centralizers (if necessary). The cost shall include drilled-in pile excavation from ground surface to tip of the pile, including temporary casing (if necessary), disposal of excavated material, water, installing the pile and all other materials, providing equipment for checking the dimensions, and alignment of each hole. No additional payment will be given for site preparation, establishing a working platform, or maintenance of traffic.
- C. Payment for Timber Lagging, 3 Inch Thick will be made at the contract unit price per square yard. The unit price will constitute full compensation for providing all labor, material, and equipment required for installation.
- D. Payment for Excavation, Class 20 will be made at the contract unit price per cubic yard. The unit price will constitute full compensation for providing all labor, material, and equipment. Incidental items are to include furnishing and placing of granular material defined in Section 2 to fill voids between retained fill and timber lagging as a result of over excavation.
- E. Payment for Waler, Steel, W14X34 shall be made at the contract unit price per linear foot. The unit price bid per horizontal linear foot of pile shall include all labor, material, and equipment for furnishing the pile and the cost of welding and shims (if required).



**SPECIAL PROVISION
FOR
MSE WALL WITH LIGHTWEIGHT FOAMED CONCRETE FILL**

**Pottawattamie County
IM-NHS-080-1(374)4--03-78**

**Effective Date
October 27, 2015**

THE STANDARD SPECIFICATIONS, SERIES 2015, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.

150008a.01 DESCRIPTION.

- A.** This work shall consist of providing and placing lightweight foamed concrete fill, hereafter referred to as LFCF, as backfill for mechanically stabilized earth (MSE) walls at locations designated on the plans, and, as specified in these special provisions.
- B.** The LFCF manufacturer shall be recommended in writing by the MSE wall vendor. The LFCF manufacturer and installer shall coordinate its work with the MSE wall designer/supplier and the MSE wall installer.
- C.** Section 2432 of the Standard Specifications shall be used with the exception of what is specified herein.

150008a.02 DESIGN AND MATERIALS.

A. Design.

1. Design Requirements.

- a.** The design by the wall system supplier shall consider the internal stability of the wall mass. Wall design shall be according to the LRFD Bridge Design Specifications AASHTO (2014), with a minimum service life of 75 years.
- b.** All appurtenances behind, in front of, under, mounted upon, or passing through the wall such as drainage structures, utilities, or other appurtenances shown on the plans shall be accounted for in the stability design of the wall.

2. Submittals.

- a.** Submit a LFCF quality control (QC) and placement plan. Placement of the MSE backfill shall be in accordance with the information provided in the QC plan. Submit the plan to the Engineer for review and comment no later than 2 weeks prior to LFCF

placement. LFCF production shall not begin before the plan has been reviewed and accepted by the Engineer. The submitted plan shall provide, as a minimum, the following elements:

- 1) An organizational chart including names, telephone numbers, current certifications / titles, roles, and responsibilities of those involved with the quality control program.
 - 2) The process of communication by which the quality control information will be disseminated to the appropriate persons, including materials suppliers. This shall include a list of recipients, the communication means that will be used, action time frames, and report formats.
 - 3) Materials list of items proposed to be provided under this section.
 - 4) Manufacturer's specifications, catalog cuts, and other engineering data needed to demonstrate compliance with the specified requirements.
 - 5) Mix designs for the LFCF, prepared by the manufacturer, showing compliance with the specified properties.
 - 6) Certification of batch, mixing and placing equipment by the LFCF manufacturer meeting the requirements specified herein.
 - 7) Written evidence of acceptance of the certified producer/supplier by the foam agent manufacturer.
 - 8) Written evidence that LFCF Installer is certified by and approved by the foam agent manufacturer.
 - 9) LFCF curing procedures.
- b. At least 2 weeks prior to placement, a trial batch will be prepared and trial batch testing results submitted showing that the proposed LFCF material properties comply with the requirements of this specification and design requirements of the MSE wall. This shall include certified test results of the LFCF reinforcing pullout resistance and pullout friction factor, f^* , meeting the minimum requirements of the MSE wall design and written certification that the reinforcing material is not susceptible to corrosion when in contact with the proposed LFCF material. The accepted trial batch mix design and tested properties will become the standard of the material furnished under this contract.
 - c. At least two weeks prior to placing, the contractor shall submit ten 3 inch diameter by 6 inch high cylinder samples of the designed and tested LFCF to the Engineer. Specimens shall be covered after casting to prevent loss of moisture and shall not be oven dried. At the department's option, the samples may be tested for strength and density in accordance with the requirements of ASTM C495 and ASTM C796, respectively, to verify the submitted test results and validate the contractor's testing procedures and quality of the furnished product.

B. Materials.

1. The materials used for the LFCF Backfill shall meet the following requirements:
 - a. Portland cement and Portland pozzolan cement type 1 meeting the requirements of Section 4101 of the Standard Specifications.
 - b. Air Entraining, water reducing, set retarding admixtures meeting the requirement of Section 4103 of the Standard Specifications.
 - c. Engineering fabrics meeting the requirements of Materials I.M. 496.01
 - d. Pozzolans and admixtures (for accelerating, water reducing, retaining, improving the bond, etc.) may only be used if specifically designated and approved by the LFCF Manufacturer.
 - e. During placement of the initial batches, the density shall be checked and the mix adjusted as required to obtain the specified cast density at the point of placement. Take four test specimens for each 300 cubic yards of LFCF placed or every 4 hours of placing.
 - f. Testing shall be performed by the LFCF manufacturer in accordance with ASTM C796 (except do not oven dry load test specimens). The specimens shall be 3 inch diameter by 6 inch high cylinders covered after casting to prevent damage and loss of moisture. Moist

cure the specimens at for at least 7 days prior to a 28 day compressive strength test. Specimens may be tested at any age to monitor the compressive strength. The manufacturer shall report test results to its certified applicator for distribution.

- g. The foaming agent from the selected manufacturer should produce a lightweight foamed concrete fill material that complies with the specifications in table below.

PROPERTY	REQUIREMENTS	TEST METHOD
Class B: Maximum/ Minimum Dry Density Minimum Unconfined Compressive Strength 28 days curing Class B	48.0 pcf / 40.0 pcf 50 psi / 120 psi	Unit Weight (ASTM C 796) (No oven drying) ASTM C 796 (No oven drying)
Internal Friction Angle	45 degrees (min.)	AASHTO T236 (ASTM D3080-72)
Frost Heave Sample @ 250 hr exposure, 4.5 inches high x 4 inch dia.	< 0.5 in	British Road Research Laboratory, Lab Report LR 90, 1967, by Croney, Jacobs.
Freeze-Thaw Resistance - minimum cycles @ relative E = N/N ≥ 70% per ASTM C666 modified per Bidwell Report dated April, 1975	Relative Young's Modulus, E ≥ 80% at 300 cycles.	ASTM C 666 Procedure B (Rapid freezing in air and Thawing in water) As modified below
Coefficient of permeability @ 2.0 psi	1 x 10 ⁻⁵ cm/sec	

150008a.03 CONSTRUCTION.

A. Construction Supervision

LFCF suppliers shall provide a qualified and experienced representative on site at the beginning of the wall construction for up to 3 days at no additional cost to the Contracting Authority.

B. Personnel Requirements.

1. The LFCF installer shall be certified by the manufacturer of the foaming agent and regularly engaged in the production and placement of the LFCF. This shall include the completion of lightweight foamed concrete fills having a minimum of 1000 total cubic yards in the past 4 years. Furthermore, the material shall have been successfully applied on at least three LFCF projects, which have performed satisfactorily for at least 3 years.
2. The LFCF installer shall be certified and approved in writing by the foam agent manufacturer of the LFCF material. The Installer's foreman shall have a minimum of 2 years of experience in this type of work and shall have worked on at least one of the three successful LFCF projects presented.
3. The Installer shall use adequate numbers of skilled workers who are thoroughly trained and experienced in the necessary crafts and who are familiar with the specified requirements and the methods needed to assure proper performance of the work noted in this Section.
4. The manufacturer's representative shall be experienced in the placement of LFCF and shall be on site full time during placement.

C. Reinforcement Placement within the LFCF.

1. The reinforcement shall be installed in accordance with the manufacturer's recommendations, unless otherwise modified by this special provision. The reinforcement shall be placed within the layers of the LFCF as shown on the plans.
2. The reinforcement shall be placed in continuous longitudinal strips in the direction of the main reinforcement.

3. Place only that amount of reinforcement required for immediately pending work to prevent undue damage. Suitable arrangement shall be made to hold the reinforcement in place before placing the LFCF. Care should be taken that the reinforcement is not damaged or displaced during the placement of the LFCF.
4. After the specified LFCF layer has been placed, the next reinforcement layer shall be installed. The process shall be repeated for each subsequent layer of reinforcement and LFCF.
5. During construction, the surface of the fill should be kept relatively horizontal.
6. Reinforcements are to be placed within 3 inches of the design elevations and extend the length as shown on the elevation view unless otherwise directed by the Engineer. Correct orientation of the reinforcement shall be verified by the Contractor.

D. Placement of LFCF.

1. LFCF shall be a homogeneous mixture and all materials shall be approved prior to use.
2. The areas to be filled shall not have any standing water prior to placement of the LFCF. The contractor shall ensure the LFCF remains above the water table at all times during construction.
3. Subgrade for LFCF fill will be prepared in accordance with Section 2109 of the Standard Specifications.
4. Material shall be protected before, during, and after installation and the LFCF installer shall protect the work and materials of other trades. In the event of damage, immediately make replacements and repairs to the acceptance of the Engineer at no additional cost to the Department.
5. Precast panels and MSE steel reinforcing strips should be fully or partially encased in the LFCF and properly set and stable prior to the installation of the LFCF. Drainage pipes, or any other items that will be encased in the LFCF shall be set and stable prior to installation of the LFCF.
6. LFCF shall not be placed at a temperature below 32°F, nor when freezing conditions are expected in less than 24 hours unless precautions are taken to maintain temperatures above freezing. Do not place LFCF on frozen ground.
7. Cure LFCF in accordance with the accepted placement plan.
8. LFCF shall only be proportioned, mixed, and placed using equipment approved by the manufacturer as indicated in the accepted LFCF placement plan. Once mixed, the LFCF concrete shall be conveyed promptly to the location of placement without excessive handling.
9. LFCF shall be placed in lifts not exceeding 24 inches in depth. The first lift shall be at least 2 inches below the top of the lowest MSE wall precast panel or wire face.
10. Prior to placing LFCF, vertical and horizontal joints between MSE wall panels and the wire mesh facing shall be covered with geotextile fabric on the back face of the panels or wire face.

11. Scarify each lift before placing the next lift. Each lift shall be scarified to a minimum depth of 1/2 inch using a hand rake or other suitable means. Scarifying shall be done in a manner to not disturb the alignment of the reinforcing strips/mesh. Scarifying shall be done after sufficient curing time such that foot traffic will not excessively damage the lift surface (no greater than 1/4 inch indentation).
12. Allow a minimum of 24 hours between subsequent lifts. Prior to verification of the minimum specified compressive strength by testing, additional lifts may be placed after the one day minimum at the Contractor's risk. Any material that does not meet the minimum specified strength within 28 days shall be removed and replaced by the Contractor at no additional cost.
13. Move the discharge hose(s) sufficiently to ensure leveled filling through the specified fill area. Uneven filling is not permitted.
14. Limit the area of placement to the volume that can be placed within 1 hour, up to the maximum lift height of 2 feet. Stagger placements such that the vertical joints are at least 10 feet apart.
15. The discharge hose length shall not exceed 500 feet in length.
16. The final surface finish of LFCF shall be within + 0.1 foot of the elevations shown on the plans, and shall be sloped to promote drainage as indicated on the plans.
17. Paving machines, heavy construction equipment or other unusual loading of the LFCF shall not be permitted until it has attained the specified 28-day compressive strength.
18. Sawing or ripping of the LFCF for utilities, drains, or other conflicts will be by methods approved by the Engineer.
19. Any material that does not comply with the minimum specified criteria shall be removed and replaced at no additional cost.
20. The LFCF will be applied at locations designated on the plans and in accordance with the manufacturer's recommendation.

150008a.04 METHOD OF MEASUREMENT.

The quantity of Class B Lightweight Foamed Concrete Fill, in cubic yards, required in the reinforced earth zone and the zone behind the MSE wall reinforcement identified in the contract documents will be the quantity shown in the contract documents. LFCF material placed outside the limits shown on the plans will not be measured for payment unless authorized in advance of placement by the Engineer.

150008a.05 BASIS OF PAYMENT.

- A. For Contractor furnished Class B Lightweight Foamed Concrete Fill for the reinforced earth zone; any core-outs or other remedial/ground improvement locations; and placed in the zone behind the reinforced earth zone as shown in the contract documents, the Contractor will be paid for the quantity of material furnished, hauled, and placed at the contract unit price per cubic yard.
- B. Payment is full compensation for preparation of written submittals, material testing, coordination of and scheduling of LFCF placement with MSE retaining wall erection, on site manufacturer representative, specialized equipment to mix, transport, and place LFCF, geotextile fabric, groundwater control and temporary shoring, and include all associated costs such as materials, labor, equipment and incidentals necessary to complete the work in accordance with the contract.

RAILROAD DATA SHEET

COUNTY: POTTAWATTAMIE
PROJECT NUMBER: IM-NHS-080-1(372)4--03-78
ROUTE: I 80
LOCATION: WB I-80 (Viaduct) Over NB I-29, Railroads and Harry Langdon Blvd.
WORK TYPE: Bridge New-Steel Girder

The following information is furnished to aid in the determination of a proper premium for the Railroad Highway Insurance Protection required of the Contractor.

RAILROAD: BNSF RAILWAY COMPANY
RAILROAD CONTACT: Calvin Nutt
TITLE: Manager of Public Projects
ADDRESS: 80 44th Ave NE
Minneapolis MN 55421
TELEPHONE NUMBER: 763-782-3495
EMAIL: calvin.nutt@bnsf.com

INSURANCE SUBMITTAL: Engineering Services, Insurance Approval
BNSF Railway Company
2500 Lou Menk Drive
Building AOB-1
Ft. Worth, Texas 76131
TELEPHONE NUMBER: 817-352-3485

Total number of trains/day: 2
Freight or Coal: 2 Speed: 10
Passenger: -- Speed: --
Number of Tracks: Mainline: 1 Branchline:

Number of railroad crossings within or near project limits with potential railroad traffic interference: 1 FRA Number: 378238C

This information is the most current FRA crossing inventory data supplied to the Iowa DOT by the Railroad Company. Actual conditions may vary at the time of construction. It shall be the contractor's responsibility to contact the railroad for additional information needed to fully provide required Railroad Highway Insurance Protection.

GENERAL REQUIREMENTS

1. The cost of railroad flagging and temporary grade crossings will be the responsibility of the Contractor, UNLESS other arrangements are specifically outlined elsewhere in the contract documents

RAILROAD DATA SHEET

COUNTY: POTTAWATTAMIE
PROJECT NUMBER: IM-NHS-080-1(374)4--03-78
ROUTE: I 80
LOCATION: I-29/80 from E of S Expressway to Ramp A/Viaduct (NB/WB)
WORK TYPE: Unknown Pavement - Grade and Replace

The following information is furnished to aid in the determination of a proper premium for the Railroad Highway Insurance Protection required of the Contractor.

RAILROAD: BNSF RAILWAY COMPANY
RAILROAD CONTACT: Calvin Nutt
TITLE: Manager of Public Projects
ADDRESS: 80 44th Ave NE
Minneapolis MN 55421
TELEPHONE NUMBER: 763-782-3495
EMAIL: calvin.nutt@bnsf.com

INSURANCE SUBMITTAL: Engineering Services, Insurance Approval
BNSF Railway Company
2500 Lou Menk Drive
Building AOB-1
Ft. Worth, Texas 76131
TELEPHONE NUMBER: 817-352-3485

Total number of trains/day: 2
Freight or Coal: 2 Speed: 10
Passenger: -- Speed: --
Number of Tracks: Mainline: 1 Branchline: 2

Number of railroad crossings within or near project limits with potential railroad traffic interference: 1 FRA Number: 084230h

This information is the most current FRA crossing inventory data supplied to the Iowa DOT by the Railroad Company. Actual conditions may vary at the time of construction. It shall be the contractor's responsibility to contact the railroad for additional information needed to fully provide required Railroad Highway Insurance Protection.

GENERAL REQUIREMENTS

1. The cost of railroad flagging and temporary grade crossings will be the responsibility of the Contractor, UNLESS other arrangements are specifically outlined elsewhere in the contract documents

RAILROAD DATA SHEET

COUNTY: POTTAWATTAMIE
PROJECT NUMBER: IM-NHS-080-1(377)4--03-78
ROUTE: I 80
LOCATION: Westbound I-80 to Southbound I-29, Ramp G over I-80, I-29, Ramps, CBEC
RR, IAIS RR and BNSF RR.
WORK TYPE: Bridge New-Steel Girder

The following information is furnished to aid in the determination of a proper premium for the Railroad Highway Insurance Protection required of the Contractor.

RAILROAD: BNSF RAILWAY COMPANY
RAILROAD CONTACT: Calvin Nutt
TITLE: Manager of Public Projects
ADDRESS: 80 44th Ave NE
Minneapolis MN 55421
TELEPHONE NUMBER: 763-782-3495
EMAIL: calvin.nutt@bnsf.com

INSURANCE SUBMITTAL: Engineering Services, Insurance Approval
BNSF Railway Company
2500 Lou Menk Drive
Building AOB-1
Ft. Worth, Texas 76131
TELEPHONE NUMBER: 817-352-3485

Total number of trains/day: 2
Freight or Coal: 2 Speed: 10
Passenger: -- Speed: --
Number of Tracks: Mainline: 1 Branchline:

Number of railroad crossings within or near project limits with potential railroad traffic interference: 1 FRA Number: 378238C

This information is the most current FRA crossing inventory data supplied to the Iowa DOT by the Railroad Company. Actual conditions may vary at the time of construction. It shall be the contractor's responsibility to contact the railroad for additional information needed to fully provide required Railroad Highway Insurance Protection.

GENERAL REQUIREMENTS

1. The cost of railroad flagging and temporary grade crossings will be the responsibility of the Contractor, UNLESS other arrangements are specifically outlined elsewhere in the contract documents

[illegible]



108-23A
08-01-08

TRAFFIC CONTROL PLAN

1. All I-29 / I-80 lanes, ramps and local roadways will be maintained at all times except as provided for in the following. Large construction projects, such as bridge or interchange reconstruction, will be scheduled in advance of the construction season. The contractor will be provided 10 weeks advance notice of any planned lane closures. The contractor will generate traffic volumes exceeding lane closure thresholds. Two week notification to the contractor will be provided so lane closures can be coordinated with the engineer. For areas that overlap, the more restrictive time period shall govern.

2. A. The contractor will be allowed to close one lane of traffic except for the following:

I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (June, July, August, September, and October):

Monday through Thursday - No Lane Closures allowed 5:30 AM - 7:00 PM

Friday - No Lane Closures allowed 6:00 AM - 8:00 PM

Saturday - No Lane Closures allowed 8:00 AM - 7:00 PM

Sunday - No Lane Closures allowed 9:30 AM - 7:00 PM

I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (November through May excluding Thanksgiving week, Christmas week and Memorial Day week):

Monday through Thursday - No Lane Closures allowed 5:30 AM - 9:30 AM and 2:00 PM - 7:00 PM

Friday - No Lane Closures allowed 6:00 AM - 8:00 PM

Saturday - No Lane Closures allowed 8:00 AM - 7:00 PM

Sunday - No Lane Closures allowed 9:30 AM - 7:00 PM

I-80 eastbound (east of the I-29 southbound diverge in the east system interchange) as follows:

Monday through Friday - No Lane Closures allowed 7:00 AM - 8:00 PM

Saturday - No Lane Closures allowed 9:00 AM - 7:00 PM

Sunday - No Lane Closures allowed 10:00 AM - 7:00 PM

I-29 northbound (south of the I-80 westbound merge in the east system interchange) as follows:

Monday through Thursday - No Lane Closures allowed 6:00 AM - 9:00 AM and 3:00 PM - 7:00 PM

Friday - No Lane Closures allowed 6:00 AM - 9:00 AM and 2:00 PM - 7:00 PM

Saturday and Sunday - No time restrictions

I-29 southbound (south of the I-80 eastbound diverge in the east system interchange) as follows:

Monday through Thursday - No Lane Closures allowed from 11:00 AM - 7:00 PM

Friday - No Lane Closures allowed from 11:00 AM - 7:00 PM

Saturday and Sunday - No time restrictions

Combined I-29 northbound / I-80 westbound as follows:

Monday through Thursday - No Lane Closures allowed 5:00 AM - 10:30 PM

Friday - No Lane Closures allowed 5:00 AM - 11:00 PM

Saturday - No Lane Closures allowed 6:30 AM - 11:30 PM

Sunday - No Lane Closures allowed 8:00 AM - 10:30 PM

Combined I-29 southbound / I-80 eastbound as follows:

Monday through Thursday - No Lane Closures allowed 6:30 AM - 7:30 PM

Friday - No Lane Closures allowed 9:00 AM - 6:30 PM

Saturday - No Lane Closures allowed 10:00 AM - 6:00 PM

Sunday - No Lane Closures allowed 9:30 PM

B. The Contractor will be allowed to close two lanes of traffic for Combined I-29 southbound / I-80 eastbound except as follows:

Monday through Friday - No Lane Closures allowed 5:30 AM - 11:00 PM

Saturday - No Lane Closures allowed 7:00 AM - 11:30 PM

Sunday - No Lane Closures allowed 7:00 AM - 9:30 PM

C. Traffic will be maintained on 29th Avenue at all times.

D. Nighttime road closures of an interstate segment will be permitted to set bridge beams and shall be in accordance with the following:

12:00 Midnight to 4:00 AM except on Saturdays and Sundays. The Contractor shall notify the Engineer two weeks advance of the closure time for approval.

E. Nighttime road closures of Harry Langdon Boulevard will be permitted to set bridge beams. Short duration closures will be allowed daily from 10:00 PM - 6:00 AM.

F. Ramp closures shall be in accordance with the layouts outlined in the plans or allowed daily from 10:00 PM - 6:00 AM.

G. Shoulder Closures will be allowed during non-peak hours. Peak Hours are 6 AM to 9 AM and 3 PM to 6 PM, Monday thru Saturday. The Contractor shall be allowed to close the shoulder during the shoulder closure time, then the shoulder closure will be allowed during the less restrictive lane closure time.

108-23A
08-01-08

TRAFFIC CONTROL PLAN

3. The Contractor shall submit any traffic control plan modifications to the Engineer for review and approval 2 weeks prior to any changes being made.

4. All shy distance to TBR shall be 3' minimum from the travel lane unless otherwise noted in the plans.

5. The Contractor shall notify the Engineer at least 5 calendar days in advance of all lane closures, lane shifts, traffic pattern changes, and transition between traffic control stages.

6. The Contractor shall provide notification to the Statewide Traffic Operations Center (315-237-3300) immediately prior to deployment and upon removal of lane closures. If a planned lane closure does not occur at the scheduled time immediately contact the Statewide Traffic Operations Center

111-01
04-17-12

COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
IM-NHS-080-1(372)4--03-78	Bridge Replacement
IM-NHS-080-1(377)4--03-78	Bridge Replacement
IM-NHS-080-1(378)4--03-78	Bridge Replacement
IM-NHS-080-1(384)3--03-78	Bridge Replacement
IM-NHS-080-1(374)4--03-78	Grade and Pave
IM-NHS-080-1(375)4--03-78	Lighting
IM-NHS-080-1(376)4--03-78	Traffic Signs
IM-NHS-080-1(420)4--03-78	Noise Wall
IM-NHS-080-1(103)48--03-78	Ballroad Grading
IM-NHS-080-1(103)48--03-78	Grade and Pave
IM-029-3(103)48--03-78	Traffic Signs
IM-029-3(104)48--03-78	Traffic Signals
IM-029-3(110)48--03-78	Lighting
IM-NHS-029-3(122)48--03-78	Culvert Replacement
IM-029-3(105)48--13-78	Bridge Replacement
NHS-029-3(106)48--11-78	Bridge Replacement

108-25
10-21-14

511 TRAVEL RESTRICTIONS

Route

Direction

County

Location Description

Feature Crossed

Maint. Bridge No., Structure ID, or FHWA No.

Type of Restriction

Existing Measurement

Construction Measurement as Signed

Projected Measurement As Built

Remarks

FILE NO. 30169

ENGLISH

DESIGN TEAM Strum\Nading

POTAWATTAMIE COUNTY

PROJECT NUMBER IM-NHS-080-1(373)4--03-78

SHEET NUMBER J.1


7:29:22 AM

8/1/2012

C:\p_w\p\pawattamie\08024157\178080873\01.xls

Includes Addenda: a01

[illegible]



105-234 08-01-08				111-01 04-17-12			
TRAFFIC CONTROL PLAN				COORDINATED OPERATIONS			
1. All I-29 / I-80 lanes, ramps and local roadways will be maintained at all times except as provided for in the following. Large venue entertainment events at the CenturyLink Center, TD Ameritrade Ballpark, MAC Center, casinos, Tom Hanafan Park, Westfair, retail outlets, and other locations will generate traffic volumes exceeding lane closure thresholds. Two week notification to the contractor will be provided so lane closures can be coordinated with the engineer. For areas that overlap, the more restrictive time period shall govern. 2. A. The contractor will be allowed to close one lane of traffic except for the following: I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (June, July, August, September and October): - Monday through Thursday - No lane closures allowed 5:30 AM - 7:00 PM - Friday - No lane closures allowed 6:00 AM - 8:00 PM - Saturday - No lane closures allowed 6:00 AM - 7:00 PM - Sunday - No lane closures allowed 9:30 AM - 7:00 PM I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (November through May excluding Thanksgiving week, Christmas week and Memorial Day week): - Monday through Thursday - No lane closures allowed 5:30 AM - 9:30 AM and 2:00 PM - 7:00 PM - Friday - No lane closures allowed 6:00 AM - 8:00 PM - Saturday - No lane closures allowed 6:00 AM - 7:00 PM - Sunday - No lane closures allowed 9:30 AM - 7:00 PM I-80 eastbound (east of the I-29 southbound diverge in the east system interchange) as follows: - Monday through Friday - No lane closures allowed 7:00 AM - 8:00 PM - Saturday - No lane closures allowed 9:00 AM - 7:00 PM - Sunday - No lane closures allowed 10:00 AM - 7:00 PM I-29 northbound (south of the I-80 westbound merge in the east system interchange) as follows: - Monday through Thursday - No lane closures allowed 6:00 AM - 9:00 AM and 3:00 PM - 7:00 PM - Friday - No lane closures allowed 6:00 AM - 9:00 AM and 2:00 PM - 7:00 PM - Saturday and Sunday - No time restrictions I-29 southbound (south of the I-80 eastbound diverge in the east system interchange) as follows: - Monday through Thursday - No lane closures allowed from 2:00 PM - 7:00 PM - Friday - No lane closures allowed from 11:00 AM - 7:00 PM - Saturday and Sunday - No time restrictions Combined I-29 northbound / I-80 westbound as follows: - Monday through Thursday - No lane closures allowed 5:00 AM - 10:30 PM - Friday - No lane closures allowed 5:00 AM - 11:00 PM - Saturday - No lane closures allowed 6:30 AM - 11:30 PM - Sunday - No lane closures allowed 8:00 AM - 10:30 PM Combined I-29 southbound / I-80 eastbound as follows: - Monday through Friday - No lane closures allowed 7:00 AM - 7:30 PM - Saturday - No lane closures allowed 9:00 AM - 6:30 PM - Sunday - No lane closures allowed 10:00 AM - 6:00 PM B. The Contractor will be allowed to close two lanes of traffic for Combined I-29 southbound / I-80 eastbound except as follows: - Monday through Friday - No lane closures allowed 5:30 AM - 11:00 PM - Saturday - No lane closures allowed 7:00 AM - 11:30 PM - Sunday - No lane closures allowed 7:00 AM - 9:30 PM C. Traffic will be maintained on 29th Avenue at all times. D. Nighttime road closures of an interstate segment will be permitted to set bridge beams and shall be in accordance with the layouts outlined in the plans. Short duration closures will be allowed daily from 12:00 Midnight to 4:00 AM except on Saturdays and Sundays. The Contractor shall submit the layout of the closures in advance of the closure time. E. Nighttime road closures of Harry Warden Boulevard will be permitted to set bridge beams. Short duration closures will be allowed daily from 10:00 PM - 6:00 AM. The Contractor shall submit the traffic control plan two weeks in advance of the closure time for approval. F. Ramp closures shall be in accordance with the layouts outlined in the plans or allowed daily from 10:00 PM - 6:00 AM. The Contractor shall notify the Engineer two weeks in advance of the closure time for approval. G. Shoulder Closures will be allowed during non-peak hours. Peak hours are 6 AM to 9 AM and 3 PM to 6 PM, Monday thru Saturday. If the shoulder closure time is less restrictive than the shoulder closure time, then the shoulder closure will be allowed during the less restrictive lane closure time. 3. The Contractor shall submit any traffic control plan modifications to the Engineer for review and approval 2 weeks prior to any changes being made. 4. Any distances to TBB shall be 37' minimum from travel lane unless otherwise noted in the plans. 5. The Contractor shall notify the Engineer at least 5 calendar days in advance of all lane closures, lane shifts, traffic pattern changes, and transition between traffic control stages. 6. The Contractor shall provide notification to the Statewide Traffic Operations Center (515-237-3300) immediately prior to deployment and upon removal of lane closures. If a planned lane closure does not occur at the scheduled time immediately contact the Statewide Traffic Operations Center.				Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.			

111-001 04-17-12	108-231 08-01-08	COORDINATED OPERATIONS Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.	TRAFFIC CONTROL PLAN 1. All I-29 / I-80 lanes, ramps and local roadways will be maintained at all times except as provided for in the following. Large venue entertainment events at the CenturyLink Center, TD Ameritrade Ballpark, MAC Center, casinos, Tom Hanafan Park, Westfair, retail outlets, and other locations will generate traffic volumes exceeding lane closure thresholds. Two week notification to the contractor will be provided so lane closures can be coordinated with the engineer. For areas that overlap, the more restrictive time period shall govern. 2. The contractor will be allowed to close one lane of traffic except for the following: 1-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (June, July, August, September and October): - Monday through Thursday - No lane closures allowed 5:30 AM - 7:00 PM - Friday - No lane closures allowed 6:00 AM - 8:00 PM - Saturday - No lane closures allowed 8:00 AM - 7:00 PM - Sunday - No lane closures allowed 9:30 AM - 7:00 PM 1-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (November through May excluding Thanksgiving Week, Christmas week and Memorial Day week): - Monday through Thursday - No lane closures allowed 5:30 AM - 9:30 AM and 2:00 PM - 7:00 PM - Friday - No lane closures allowed 6:00 AM - 8:00 PM - Saturday - No lane closures allowed 8:00 AM - 7:00 PM - Sunday - No lane closures allowed 9:30 AM - 7:00 PM 1-80 eastbound (east of the I-29 southbound diverge in the east system interchange) as follows: - Monday through Friday - No lane closures allowed 7:00 AM - 8:00 PM - Saturday - No lane closures allowed 9:00 AM - 7:00 PM - Sunday - No lane closures allowed 10:00 AM - 7:00 PM I-29 northbound (south of the I-80 westbound merge in the east system interchange) as follows: - Monday through Thursday - No lane closures allowed 6:00 AM - 9:00 AM and 2:00 PM - 7:00 PM - Friday - No lane closures allowed 6:00 AM - 9:00 AM and 3:00 PM - 7:00 PM - Saturday and Sunday - No time restrictions I-29 southbound (south of the I-80 eastbound diverge in the east system interchange) as follows: - Monday through Thursday - No lane closures allowed from 2:00 PM - 7:00 PM - Friday - No lane closures allowed from 2:00 PM - 7:00 PM - Saturday and Sunday - No time restrictions Combined I-29 northbound / I-80 westbound as follows: - Monday through Thursday - No lane closures allowed 5:00 AM - 10:30 PM - Friday - No lane closures allowed 5:00 AM - 11:00 PM - Saturday - No lane closures allowed 6:00 AM - 10:30 PM - Sunday - No lane closures allowed 8:00 AM - 10:30 PM Combined I-29 southbound / I-80 eastbound as follows: - Monday through Friday - No lane closures allowed 7:00 AM - 7:30 PM - Saturday - No lane closures allowed 9:00 AM - 6:30 PM - Sunday - No lane closures allowed 10:00 AM - 6:00 PM B. The Contractor will be allowed to close two lanes of traffic for Combined I-29 southbound / I-80 eastbound except as follows: - Monday through Friday - No lane closures allowed 5:30 AM - 11:00 PM - Saturday - No lane closures allowed 7:00 AM - 11:30 PM - Sunday - No lane closures allowed 7:00 AM - 9:30 PM C. Traffic will be maintained on 29th Avenue at all times. D. Nighttime road closures of an interstate segment will be permitted to set bridge beams and shall be in accordance with the layouts outlined in the plans. Short duration closures will be allowed daily from 12:00 Midnight to 4:00 AM except on Saturdays and Sundays. The Contractor shall notify the Engineer two weeks in advance of the closure time for approval. E. Nighttime road closures of Harry Langdon Boulevard will be permitted to set bridge beams. Short duration closures will be allowed daily from 10:00 PM - 6:00 AM. The Contractor shall submit the traffic control plan two weeks in advance of the closure time for approval. F. Rain closures shall be in accordance with the layouts outlined in the plans or allowed daily from 10:00 PM - 6:00 AM. The Contractor shall notify the Engineer two weeks in advance of the closure time for approval. G. Shoulder Closures will be allowed during non-peak hours. Peak Hours are 6 AM to 9 AM and 3 PM to 6 PM, Monday thru Saturday. If the lane closure time is less restrictive than the shoulder closure time, then the shoulder closure will be allowed during the less restrictive lane closure time. 3. The Contractor shall submit any traffic control plan modifications to the Engineer for review and approval 2 weeks prior to any changes being made. 4. All shy distances to TBR shall be 3' minimum from travel lane unless otherwise noted in the plans. 5. The Contractor shall notify the Engineer at least 5 calendar days in advance of all lane closures, lane shifts, traffic pattern changes, and transition between traffic control stages. The Contractor shall notify the Statewide Traffic Operations Center (515-237-3300) immediately prior to deployment and upon removal of lane closures. If a planned lane closure does not occur at the scheduled time immediately contact the Statewide Traffic Operations Center.
--	--	--	--

FILE NO.

30169

ENGLISH

DESIGN TEAM

Strum\Nading

POTAWATTAMIE COUNTY PROJECT NUMBERIM-NHS-080-1(377)4--03-78SHEET NUMBERJ.1

7:48:48 AM

C:\Users\jvannan\Documents\08524138\08524138\78808377\01.xls

Includes Addenda : a01

TRAFFIC CONTROL PLAN		
1. All I-29 / I-80 lanes, ramps and local roadways will be maintained at all times except as provided for in the following. Large closures are prohibited during peak hours or periods of inclement weather. The Contractor shall submit any traffic control plan modifications to the Engineer for review and approval 2 weeks prior to any construction activities. Traffic volumes exceeding lane closure thresholds. Two week notification to the contractor will be provided so lane closures can be coordinated with the engineer. For areas that overlap, the more restrictive time period shall govern. 2. A. The contractor will be allowed to close one lane of traffic except for the following: I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (June, July, August, September, and October): Monday through Thursday - No Lane Closures allowed 5:30 AM – 7:00 PM Friday - No Lane Closures allowed 6:00 AM – 8:00 PM Saturday - No Lane Closures allowed 8:00 AM – 7:00 PM Sunday - No Lane Closures allowed 9:30 AM – 7:00 PM I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (November through May excluding Thanksgiving Week, Christmas Week and Memorial Day Week): Monday through Thursday - No Lane Closures allowed 5:30 AM – 9:30 AM and 2:00 PM – 7:00 PM Friday - No Lane Closures allowed 6:00 AM – 8:00 PM Saturday - No Lane Closures allowed 8:00 AM – 7:00 PM Sunday - No Lane Closures allowed 9:30 AM – 7:00 PM I-80 eastbound (east of the I-29 southbound diverge in the east system interchange) as follows: Monday through Friday - No Lane Closures allowed 7:00 AM – 8:00 PM Saturday - No Lane Closures allowed 9:00 AM – 7:00 PM Sunday - No Lane Closures allowed 10:00 AM – 7:00 PM I-29 northbound (south of the I-80 westbound merge in the east system interchange) as follows: Monday through Thursday - No Lane Closures allowed 6:00 AM – 9:00 AM and 3:00 PM – 7:00 PM Friday - No Lane Closures allowed 6:00 AM – 9:00 AM and 2:00 PM – 7:00 PM Saturday and Sunday - No time restrictions I-29 southbound (south of the I-80 eastbound diverge in the east system interchange) as follows: Monday through Thursday - No Lane Closures allowed from 11:00 AM – 7:00 PM Friday - No Lane Closures allowed from 11:00 AM – 7:00 PM Saturday and Sunday - No time restrictions Combined I-29 northbound / I-80 westbound as follows: Monday through Friday - No Lane Closures allowed 6:00 AM – 5:00 AM – 10:30 PM Saturday - No Lane Closures allowed 6:00 AM – 11:00 PM Sunday - No Lane Closures allowed 6:30 AM – 11:30 PM Saturday - No Lane Closures allowed 8:00 AM – 10:30 PM Combined I-29 southbound / I-80 eastbound as follows: Sunday through Friday - No Lane Closures allowed 7:00 AM – 7:30 PM Saturday - No Lane Closures allowed 8:00 AM – 8:30 PM Sunday - No Lane Closures allowed 10:00 AM – 6:00 PM B. The Contractor will be allowed to close two lanes of traffic for Combined I-29 southbound / I-80 eastbound except as follows: Monday through Friday - No Lane Closures allowed 6:30 AM – 11:00 PM Saturday - No Lane Closures allowed 7:00 AM – 9:30 PM Sunday - No Lane Closures allowed 10:00 AM – 6:00 PM C. Traffic will be maintained on 29th Avenue at all times. D. Nighttime road closures of an interstate segment will be permitted to set bridge beams and shall be in accordance with the following schedule. Road closures must begin no later than 12:00 Midnight to 4:00 AM except on Saturdays and Sundays. The Contractor shall notify the Engineer two weeks advance of the Closure time for approval. E. Nighttime road closures of Harry Langdon Boulevard will be permitted to set bridge beams. Short duration closures will be allowed daily from 10:00 PM – 6:00 AM. The Contractor shall submit the traffic control plan two weeks in advance of the Closure time for approval. F. Ramp closures shall be in accordance with the layouts outlined in the plans or allowed daily from 10:00 PM - 6:00 AM. The Contractor shall notify the Engineer two weeks in advance of the Closure time for approval. G. Shoulder Closures will be allowed during non-peak hours. Peak Hours are 6 AM to 9 AM and 3 PM to 6 PM, Monday thru Saturday. If the lane closure time is less restrictive than the shoulder closure time, then the shoulder closure will be allowed during the less restrictive lane closure time.		

TRAFFIC CONTROL PLAN		
3. The Contractor shall submit any traffic control plan modifications to the Engineer for review and approval 2 weeks prior to any construction activities. Traffic volumes exceeding lane closure thresholds. Two week notification to the contractor will be provided so lane closures can be coordinated with the engineer. For areas that overlap, the more restrictive time period shall govern. 4. All shy distance to TBR shall be 3' minimum from the travel lane unless otherwise noted in the plans. 5. The Contractor shall notify the Engineer at least 5 calendar days in advance of all lane closures, lane shifts, traffic pattern changes, and transition between traffic control stages. 6. The Contractor shall provide notification to the Statewide Traffic Operations Center (515-237-3300) immediately prior to deployment and upon removal of lane closures. If a planned lane closure does not occur at the scheduled time immediately contact the Statewide Traffic Operations Center		

COORDINATED OPERATIONS		
Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.		
Project	Type of Work	
IM-NHS-080-1(377)4--03-78	Bridge Replacement	
IM-NHS-080-1(377)4--03-78	Bridge Replacement	
IM-NHS-080-1(377)4--03-78	Bridge Replacement	
IM-NHS-080-1(377)4--03-78	Traffic Signals	
IM-NHS-080-1(377)4--03-78	Lighting	
IM-NHS-080-1(376)4--03-78	Noise Wall	
IM-NHS-080-1(420)4--03-78	Railroad Grading	
IM-NHS-080-1(420)4--03-78	Grade and Pave	
IM-NHS-080-1(420)4--03-78	Traffic Signals	
IM-NHS-080-1(420)4--03-78	Traffic Signals	
IM-NHS-080-1(420)4--03-78	Lighting	
IM-NHS-080-1(420)4--03-78	Culvert Replacement	
IM-NHS-080-1(420)4--03-78	Bridge Replacement	
IM-NHS-080-1(420)4--03-78	Bridge Replacement	

511 TRAVEL RESTRICTIONS						
Route	Direction	County	Location Description	Feature Crossed	Object Type	Maint. Bridge No., Structure ID, or FHWA No.
NONE						
Projected As Built Measurement as Signed Construction Measurement as Signed Existing Measurement as Signed						
Remarks						

108-23A
08-01-08

108-23B
08-01-08

108-23C
08-01-08

108-23A 08-01-08				TRAFFIC CONTROL PLAN				108-23A 08-01-08			
1. All I-29 / I-80 lanes, ramps and local roadways will be maintained 24/7 times except as provided for in the following. Large commercial vehicles will be prohibited from the I-29 / I-80 system. The contractor shall submit a traffic control plan to the engineer for review and approval 2 weeks prior to any project start. The contractor shall submit any traffic control plan modifications to the engineer for review and approval 2 weeks prior to any changes being made.				TRAFFIC CONTROL PLAN				TRAFFIC CONTROL PLAN			
2. A. The contractor will be allowed to close one lane of traffic except for the following: I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (June, July, August, September, and October): Monday through Thursday - No lane closures allowed 5:30 AM - 7:00 PM Friday - No lane closures allowed 6:00 AM - 8:00 PM Saturday - No lane closures allowed 8:00 AM - 7:00 PM Sunday - No lane closures allowed 9:30 AM - 7:00 PM I-80 westbound (east of the I-29 northbound merge in the east system interchange) as follows (November through May excluding Thanksgiving Week, Christmas Week and Memorial Day Week): Monday through Thursday - No lane closures allowed 5:30 AM - 9:30 AM and 2:00 PM - 7:00 PM Friday - No lane closures allowed 6:00 AM - 8:00 PM Saturday - No lane closures allowed 8:00 AM - 7:00 PM Sunday - No lane closures allowed 9:30 AM - 7:00 PM I-80 eastbound (east of the I-29 southbound diverge in the east system interchange) as follows: Monday through Friday - No lane closures allowed 7:00 AM - 8:00 PM Saturday - No lane closures allowed 9:00 AM - 7:00 PM Sunday - No lane closures allowed 10:00 AM - 7:00 PM I-29 northbound (south of the I-80 westbound merge in the east system interchange) as follows: Monday through Thursday - No lane closures allowed 6:00 AM - 9:00 AM and 3:00 PM - 7:00 PM Friday - No lane closures allowed 6:00 AM - 9:00 AM and 2:00 PM - 7:00 PM Saturday and Sunday - No time restrictions I-29 southbound (south of the I-80 eastbound diverge in the east system interchange) as follows: Monday through Thursday - No lane closures allowed from 2:00 PM - 7:00 PM Saturday and Sunday - No time restrictions Combined I-29 northbound / I-80 westbound as follows: Monday through Thursday - No lane closures allowed 5:00 AM - 10:30 PM Friday - No lane closures allowed 5:00 AM - 11:00 PM Saturday - No lane closures allowed 6:30 AM - 11:30 PM Sunday - No lane closures allowed 8:00 AM - 10:30 PM Combined I-29 southbound / I-80 eastbound as follows: Monday through Thursday - No lane closures allowed 7:00 AM - 7:30 PM Friday - No lane closures allowed 9:00 AM - 6:30 PM Saturday - No lane closures allowed 10:00 AM - 6:00 PM Sunday - No lane closures allowed 10:00 AM - 6:00 PM				3. The Contractor shall submit any traffic control plan modifications to the engineer for review and approval 2 weeks prior to any changes being made.				3. The Contractor shall submit any traffic control plan modifications to the engineer for review and approval 2 weeks prior to any changes being made.			
4. All shifts between to BTR shall be 3' minimum from the travel lane unless otherwise noted in the plans.				4. All shifts between to BTR shall be 3' minimum from the travel lane unless otherwise noted in the plans.				4. All shifts between to BTR shall be 3' minimum from the travel lane unless otherwise noted in the plans.			
5. The Contractor shall notify the Engineer at least 5 calendar days in advance of all lane closures, lane shifts, traffic pattern changes, and transition between traffic control stages.				5. The Contractor shall notify the Engineer at least 5 calendar days in advance of all lane closures, lane shifts, traffic pattern changes, and transition between traffic control stages.				5. The Contractor shall notify the Engineer at least 5 calendar days in advance of all lane closures, lane shifts, traffic pattern changes, and transition between traffic control stages.			
6. The Contractor shall provide notification to the Statewide Traffic Operations Center (515-237-3300) immediately prior to deployment and upon removal of lane closures. If a planned lane closure does not occur at the scheduled time immediately contact the Statewide Traffic Operations Center				6. The Contractor shall provide notification to the Statewide Traffic Operations Center (515-237-3300) immediately prior to deployment and upon removal of lane closures. If a planned lane closure does not occur at the scheduled time immediately contact the Statewide Traffic Operations Center				6. The Contractor shall provide notification to the Statewide Traffic Operations Center (515-237-3300) immediately prior to deployment and upon removal of lane closures. If a planned lane closure does not occur at the scheduled time immediately contact the Statewide Traffic Operations Center			
111-01 04-17-12				COORDINATED OPERATIONS				COORDINATED OPERATIONS			
Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.				Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.				Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.			
Project				Type of Work				Type of Work			
IM-NHS-080-1 (372)A--03-78				Bridge Replacement				Bridge Replacement			
IM-NHS-080-1 (377)A--03-78				Bridge Replacement				Bridge Replacement			
IM-NHS-080-1 (371)3--03-78				Bridge Replacement				Bridge Replacement			
IM-NHS-080-1 (372)A--03-78				Bridge Replacement				Bridge Replacement			
IM-NHS-080-1 (374)A--03-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (375)A--03-78				Lighting				Lighting			
IM-NHS-080-1 (376)A--03-78				Traffic Signs				Traffic Signs			
IM-NHS-080-1 (373)A--03-78				Bridge Replacement				Bridge Replacement			
IM-NHS-080-1 (365)A--0E-78				Railroad Grading				Railroad Grading			
IM-NHS-080-1 (366)A--0E-78				Grade and Pave				Grade and Pave			
IM-NHS-080-1 (367)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (368)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (369)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (370)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (371)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (372)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (373)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (374)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (375)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (376)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (377)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (378)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (379)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (380)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (381)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (382)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (383)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (384)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (385)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (386)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (387)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (388)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (389)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (390)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (391)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (392)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (393)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (394)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (395)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (396)A--0E-78				Grading and Pave				Grading and Pave			
IM-NHS-080-1 (397)A--0E-78											

100-10 10-18-05	
PROJECT DESCRIPTION	
This project includes grading and paving portion of I-896B.	

ESTIMATED PROJECT QUANTITIES (1 DIVISION PROJECT)			
Item No.	Item Code	Unit	As Built Qty.
1	2101-0850001	ACRE	6.3
2	2102-0100000	TON	23,450.8
3	2102-0100000	CV	116,782.0
4	2102-0100000	CV	56.0
5	2105-8425015	CV	22,450.0
6	2107-0875100	CV	29,780.0
7	2111-8714100	CV	15,970.3
8	2113-0001100	CV	15,975.2
9	2113-0001100	CV	3,896.7
10	2122-5100011	CV	22.0
11	2122-5100005	CV	128.04
12	2123-7450000	STA	10,908.3
13	2301-1004115	STA	616.8
14	2301-1033100	CV	4,830.8
15	2304-0100000	CV	5,124.5
16	2304-0100000	CV	6,597.5
17	2304-0100000	CV	1,959.1
18	2304-0100000	CV	976.7
19	2402-0425031	TON	584.0
20	2402-0425040	CV	4,282.0
21	2402-2728100	CV	740.0
22	2402-2728100	CV	1
23	2416-0100015	EACH	9
24	2416-0100024	EACH	1
25	2416-0100030	EACH	1
26	2416-0100060	EACH	1
27	2416-1100024	LF	461
28	2416-1100024	LF	160
29	2416-1100024	LF	9427
30	2432-0000100	EA	2
31	2435-0140310	EACH	17
32	2435-0251224	EACH	7
33	2435-0251310	EACH	7
34	2435-0254900	EACH	1
35	2435-0254902	EACH	1
36	2435-0254902	EACH	1
37	2501-8400172	EA	1.00
38	2502-8212034	LF	7,133.8
39	2502-8221304	EA	32
40	2503-0114215	LF	32.0
41	2503-0114218	LF	1,034.0
42	2503-0114224	LF	895.0
43	2503-0114230	LF	134.0
44	2503-0114260	LF	302.0
45	2503-0144660	LF	394
46	2503-0200036	LF	138
47	2505-4000120	LF	525.0
48	2505-4000300	LF	362.5
49	2505-4000400	EA	3
50	2505-4021010	EA	3
51	2505-4021010	EA	3
52	2506-4000000	CV	48.4
53	2507-3250005	CV	55.7
54	2507-8029000	TON	30.6
55	2510-6745850	CV	18,303.6
56	2513-0001020	LF	762.0
57	2513-0001050	EACH	1
58	2513-0001050	EACH	1
59	2516-8725000	CV	0.6
60	2518-6910000	EACH	2
61	2519-1001000	LF	2,777.0
62	2519-4200120	LF	3,026.0
63	2526-8205000	LF	1.00
64	2527-9563100	STA	531.31

100-1A 07-15-97	
ESTIMATED PROJECT QUANTITIES (1 DIVISION PROJECT)	
Item No.	Item Code
65	2527-9263131
66	2527-9263180
67	2528-3800000
68	2528-8400000
69	2528-8400055
70	2528-9200050
71	2528-9200050
72	2533-4000005
73	2533-4000005
74	2533-4000005
75	2533-4000005
76	2533-4000005
77	2533-4000005
78	2533-4000005
79	2533-4000005
80	2533-4000005
81	2533-4000005
82	2533-4000005
83	2533-4000005
84	2533-4000005
85	2533-4000005
86	2533-4000005
87	2533-4000005
88	2533-4000005
89	2533-4000005
90	2533-4000005
91	2533-4000005
92	2533-4000005
93	2533-4000005
94	2533-4000005
95	2533-4000005
96	2533-4000005
97	2533-4000005
98	2533-4000005
99	2533-4000005
100	2533-4000005

Item No.	Item Code	Item	Unit	Total	As Built Qty.
65	2527-9263131	NET RETROREFLECTIVE REMOVABLE TAPE MARKINGS	STA	97.26	
66	2527-9263180	PAVEMENT MARKINGS REMOVED	STA	149.29	
67	2528-3800000	MODULAR GLARE SCREEN SYSTEM	LF	20,212.5	
68	2528-8400000	TEMPORARY BARRIER RAIL, CONCRETE	LF	20,212.5	
69	2528-8400055	TEMPORARY TO PERMANENT BARRIER CONNECTION	EACH	1	
70	2528-9200050	PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	CDAY	1	
71	2528-9200050	PORTABLE DYNAMIC MESSAGE SIGN (PDMS)	CDAY	1	
72	2533-4000005	MOBILIZATION	LS	1.00	
73	2533-4000005	TEMP CRASH CUSHION	EACH	13	
74	2533-4000005	PROJECT MANAGEMENT	LS	1.00	
75	2533-4000005	(CUBIC YARDS' ITEM) CLASS B LIGHTWEIGHT FORMED CONCRETE FILL	CV	8,313.0	
76	2533-4000005	(CUBIC YARDS' ITEM) GRANULAR BACKFILL, WORKING PAD STONE	CV	1,200.0	
77	2533-4000005	(LINEAR FEET' ITEM) RIGID INCLUSIONS	LF	20,000.0	
78	2533-4000005	(LUMP SUM' ITEM) INSTRUMENTATION	LS	1.00	
79	2533-4000005	(LUMP SUM' ITEM) LOAD TEST	LS	1.00	
80	2533-4000005	(LUMP SUM' ITEM) PROGRESS SCHEDULING	TON	132.9	
81	2533-4000005	(LUMP SUM' ITEM) CRUSHED LIMESTONE	ACRE	10.9	
82	2533-4000005	MULCHING	ACRE	11.9	
83	2533-4000005	SEEDING AND FERTILIZING (RURAL)	ACRE	11.9	
84	2533-4000005	SEEDING AND FERTILIZING (RURAL)	ACRE	11.9	
85	2533-4000005	SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	MGAL	22.40	
86	2533-4000005	WATERING FOR SOO, SPECIAL DITCH CONTROL, OR SLOPE PROTECTION	EACH	3	
87	2533-4000005	SILT FENCE	LF	11,500.0	
88	2533-4000005	SILT BASINS	EACH	3,470.0	
89	2533-4000005	MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	LF	1,395.0	
90	2533-4000005	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	LF	800.0	
91	2533-4000005	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 20 IN. DIA.	LF	1,600.0	
92	2533-4000005	REMOVAL OF PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE	LF	1	
93	2533-4000005	MOBILIZATIONS, EMERGENCY EROSION CONTROL	EACH	1	
94	2533-4000005	ALTERNATE AA OPTION 1	TON	31.9	
95	2533-4000005	SPECIAL BACKFILL	SY	77.8	
96	2533-4000005	PAVED SHOULDER, P.C. CONCRETE, 7 IN.	TON	26.8	
97	2533-4000005	ALTERNATE AA OPTION 2	SY	77.8	
98	2533-4000005	PAVED SHOULDER, HOT MIX ASPHALT MIXTURE, 8 IN.	TON	26.8	
99	2533-4000005	PAVED SHOULDER, HOT MIX ASPHALT MIXTURE, 8 IN.	SY	77.8	


SEE V SHEETS FOR ADDITIONAL BID ITEMS AND QUANTITIES


ESTIMATE REFERENCE INFORMATION			100-4A 10-29-02
Item No.	Item Code	Description	
1	2101-0050001	CLEARING AND GRUBBING Refer to Sheet U.13.	
2	2102-0425070	SPECIAL BACKFILL Refer to Tab. 100-24 on sheet C.7 and Tab. 112-9 on Sheet C.9 and Typicals I-80MB PAVING and E029G PAVING on Sheets B.2 to B.3.	
-	-	Refer to Tab. 100-24M0D on Sheet C.8 and Typicals on Sheets B.5-B.11.	
3	2102-2710070	EXCAVATION, CLASS 10, ROADWAY AND BORROW Refer to "I" sheets.	
-	-	Overhaul will not be measured or paid for, but shall be considered incidental to roadway excavation on this project.	
-	-	Includes 92,975 CY of template cut and 23,307 CY from optional borrow. Refer to Sheet R.1-R.4 for borrow details.	
-	-	79,035 CY of template cut to be wasted per Article 1106.07 of the current specifications.	
-	-	Includes 3 settlement plates. Refer to Tab 103-5 for locations.	
-	-	Refer to "Special Provision for Alternate Borrows (Loess Hills)" for the Contractor's responsibilities for locating alternate borrow areas in the Loess Hills Region of Western Iowa.	
4	2102-2712015	EXCAVATION, CLASS 12, Boulders or Rock Fragments Refer to Tab. 103-7 on Sheet CS.1. Dispose of excess material according to Article 1106.07 of the current specifications.	
-	-	Includes 3 settlement plates. Refer to Tab 103-5 for locations.	
5	2105-0425015	TOPSOIL, STRIP, SALVAGE AND SPREAD Refer to Tab. 103-4 on Sheet C.11.	
6	2107-0075100	COMPACTION WITH MOISTURE CONTROL Refer to Tab. 103-6 on Sheet CS.1. Shrinkage is not included in the moisture control quantity.	
7	2111-0174100	GRANULAR SUBBASE Refer to Tab. 100-24 on sheet C.7 and Tab. 112-9 on Sheet C.9 and Typicals I-80MB PAVING and E029G PAVING on Sheets B.2 to B.3.	
-	-	SUBGRADE STABILIZATION MATERIAL, POLYMER GRID Refer to Tab. 103-6 on Sheet CS.1.	
8	2113-0001100	Refer to Typicals I-80MB PAVING and E029G PAVING on Sheets B.2 to B.3.	
9	2115-0100000	MODIFIED SUBBASE Refer to Typical MDVAEC PAVING on Sheet B.4 and Tab 100-24 on Sheet C.7.	
-	-	PAVED SHOULDER, P.C. CONCRETE, 11.5 IN. Refer to Tab. 112-9 on Sheet C.9.	
10	2122-5190115	Refer to Typicals I-80MB PAVING and E029G PAVING on Sheets B.2-B.3.	
-	-	REINFORCED PAVED SHOULDER FOR CONCRETE BARRIER Refer to Tab. 112-9 on Sheet C.9.	
11	2122-5191005	SHOULDER CONSTRUCTION, EARTH Refer to Tab. 112-9 on Sheet C.9 and Typicals on Sheet B.1-B.4.	
12	2123-7450000	Refer to Detour Typicals on Sheets B.5-B.11 for additional location and quantities.	
-	-	STANDARD OR SLIP-FORM PORTLAND CEMENT CONCRETE PAVEMENT, QN-C, CLASS 31 DURABILITY, 11.5 IN. Refer to Tab. 100-24 on Sheet C.7 and Typicals I-80MB PAVING and E029G PAVING on Sheets B.2 to B.3.	
13	2301-1004115	STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN. Refer to Typical MDVAEC PAVING on Sheet B.4 and Tab 100-24 on Sheet C.7.	
14	2301-1033100	Refer to Tab. 100-24M0D on Sheet C.8.	
-	-	DETOUR PAVEMENT 8 IN PCC OR 11 IN HMA Refer to Typical DET 303300 on Sheet B.7 , and Typical DET 304000 on Sheet B.8, Typical DET 309000 on Sheet B.9.	
15	2304-0100000	DETOUR PAVEMENT 8 IN PCC OR 11 IN HMA	
16	2304-0100000	DETOUR PAVEMENT 8.5 IN PCC OR 12 IN HMA	
17	2304-0100000	DETOUR PAVEMENT 9 IN PCC 13 HMA	
18	2304-0101000	TEMPORARY PAVEMENT Refer to Tab. 100-24M0D on Sheet C.8.	
-	-	DETOUR PAVEMENT 8 IN PCC OR 11 IN HMA	
-	-	Refer to Typical DET 303300 on Sheet B.7 , and Typical DET 304000 on Sheet B.8, Typical DET 309000 on Sheet B.9.	
-	-	DETOUR PAVEMENT 8.5 IN PCC OR 12 IN HMA	
-	-	Refer to Typical DET 300100 on Sheet B.5.	
2304-0100000	DETOUR PAVEMENT 9 IN PCC 13 HMA	Refer to Typical DET 300400 on Sheet B.5, and Typical DET 300500 on Sheet B.6, and Refer to Typical DET 309100 on Sheet B.10.	
2304-0101000	TEMPORARY PAVEMENT		

ESTIMATE REFERENCE INFORMATION			100-4A 10-29-02
Item No.	Item Code	Description	
		Refer to Typical TEMP on Sheet B.11.	
		Type A quality coarse aggregate for HMA must meet the requirements in Standard Specification 4127 with the exception of the A-freeze limit of 1%.	
19	2402-0425031	GRANULAR BACKFILL Item is for backfill between Noise Wall and Barrier. Refer to typical I-80 PAVING on Sheet B.2 and retaining wall detail on Sheet U.1. Includes Engineering Fabric to be placed over all buried joints of the Noise Wall.	
20	2402-0425040	FLOODED BACKFILL	
21	2402-2720100	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT Refer to Tab. 104-3 on Sheet CD.1.	
22	2414-0444100	EXCAVATION, CLASS 20, FOR ROADWAY PIPE CULVERT Includes 1020 CY for excavation of the soil and CLSM in front of the Soldier-Pile Wall to install the timber lagging. This does not include the excavation quantity for the roadway earthwork.	
23	2416-0100015	STEEL PIPE PEDESTRIAN HAND RAILING Refer to sheet U.15 and tab 100-7 on sheet C.16 for location and details.	
24	2416-0100024	APRONS, CONCRETE, 15 IN. DIA. Refer to tab 104-5B on sheet M.1.	
25	2416-0100030	APRONS, CONCRETE, 24 IN. DIA. Refer to Tab. 104-3 on Sheet CD.1.	
26	2416-0100060	3 aprons - Refer to tab 104-5B on sheet M.1.	
27	2416-1100024	APRONS, CONCRETE, 30 IN. DIA.	
28	2416-1263024	APRONS, CONCRETE, 60 IN. DIA. Refer to M Sheets and Tab 104-5B on sheet M.1 for location and details.	
29	2417-5895018	CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	
30	2432-0000100	CULVERT, CONCRETE PIPE, 30000, TRENCHLESS, 24 IN. DIA. Refer to Tab. 104-3 on Sheet CD.1.	
31	2435-01040310	CULVERT, CONCRETE PIPE, 30000, TRENCHLESS, 24 IN. DIA. The Contractor shall take special care to avoid trenchless operations during any rain event or take measures to protect the installation area to avoid any damaging effects to the existing pavement, subbase, and embankment.	
32	2435-0251224	BEVELED PIPE AND GUARD, 18 INCH Refer to M sheets and Standard Road Plan DR-212 for location and details.	
33	2435-0251310	MECHANICALLY STABILIZED EARTH RETAINING WALL Includes 6581 SF for RM 3050 and 2846 SF for RM3150 Refer to Sheet V.1, V.2, V.11 and Q sheets for details.	
34	2435-0254900	MANHOLE, STORM SEWER, SW-403 MODIFIED Refer to M Sheets and Tab. 104-5B on sheet M.1 for locations and details.	
35	2435-0254902	INTAKE, SW-512, 24 IN. Refer to M Sheets for locations and details. Requires SW-604 - Type 4 casting.	
36	2435-0256210	INTAKE, SW-513 MODIFIED Refer to M Sheets for locations and details.	
37	2501-8400172	TEMPORARY SHORING Includes 6581 SF for RM 3050 and 2846 SF for RM3150 Refer to Sheet V.1, V.2, V.11 and Q sheets for details.	
		TEMPORARY SHORING Temporary shoring (sheet pile or other) shall be required as necessary to prevent the earth under the traffic lane from sloughing in during construction of Detour 300500 from STA 3004+25 to STA 3007+60. The Contractor shall submit a Temporary Shoring Plan. The Temporary Shoring Plan shall be designed and certified by a Professional Engineer licensed in the State of Iowa. The Contractor shall not proceed with installation of the Temporary Shoring without notice to proceed from the Engineer.	
		The temporary Shoring submittal shall include: - Design calculations (including a global stability analysis) - Soil properties - Shoring material properties - Shoring plan layout (showing location of traffic) - Shoring details	
		Temporary Shoring shall be paid as a lump sum including all cost for designing and furnishing, installing and removal. All material used for shoring shall remain the property of the Contractor. Shoring is to be removed after backfilling has been completed. In addition to the requirements noted above Article 1107.07 of the Standard Specifications still applies.	

FILE NO.	DESIGN TEAM	COUNTY	PROJECT NUMBER	SHEET NUMBER
10/1/2015	Strum\Brinkman\Janus	POTTAWATTAMIE	IM-NHS-080-1(462)4--03-78	C.2
11:56:04 AM	ajjanus2		Includes Addenda:	a01


[illegible]





TIMBER LAGGING CONNECTION DETAIL

NOTE: THIS DETAIL OR AN APPROVED EQUIVALENT SHOULD BE USED.
N.T.S.




SECTION A-A

N.T.S.

REQUIRED CONSTRUCTION SEQUENCE

DUE TO THE CONSIDERABLE INTERACTION OF THE PROPOSED RETAINING WALL, EXISTING EMBANKMENT LEADING UP TO THE WOODBURY AVENUE BRIDGE, AND FUTURE GRADING OF PROPOSED I-80, THE FOLLOWING CONSTRUCTION SEQUENCE IS REQUIRED. SEE SPECIAL PROVISIONS FOR FURTHER DETAILS. THE CONTRACTOR MUST ATTAIN APPROVAL FROM THE ENGINEER BEFORE DEVIATING FROM THIS SEQUENCE.

1. DRILL HOLE FOR SOLDIER PILE AND IMMEDIATELY PLACE SOLDIER PILE IN HOLE.
2. POUR STRUCTURAL CONCRETE FROM TIP ELEVATION TO SPECIFIED ELEVATION FOR THE TOP OF CONCRETE ENCASMENT ON THE PLANS. THEN POUR CLSM FROM THE TOP OF ENCASMENT ELEVATION TO THE EXISTING GROUND SURFACE ELEVATION. DO NOT ALLOW HOLE TO STAND UNSUPPORTED WITHOUT STRUCTURAL CONCRETE AND CLSM FOR MORE THAN 3 HOURS.
3. EXCAVATE ALONG THE FACE OF THE WALL AND PLACE TIMBER LAGGING ALLOWING NO MORE THAN 5 FEET OF EXPOSED/UNSUPPORTED EXCAVATION PRIOR TO SUBSEQUENT EXCAVATION.
4. OVEREXCAVATION RESULTING IN ANY GAP BETWEEN THE TIMBER LAGGING AND RETAINED FILL MUST BE FILLED WITH GRANULAR BACKFILL SPECIFIED IN THE SPECIAL PROVISIONS.
5. A WALER IS PLACED ACROSS PILES 13, 14, 15, AND 16 AT ELEVATION 1,030 FEET. ADD STEEL SHIMS WHERE NEEDED.



CANTILEVER SPL WALL

N.T.S.

DETAIL

N.T.S.

DESIGN FOR 400'-0\"/>

STATION 7625+74.31, 12.51' LEFT
POTTAWATTAMIE COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 3 OF 3 FILE NO. 30169 DESIGN NO. 3116

PROJECT NUMBER IN-NIS-080-146234-03-78 POTTAWATTAMIE COUNTY SHEET NUMBER V.6