MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 05-0714-048

Proposed Contract Period: Late Start Date of 05/31/16 with 100 WORK DAYS

Project(s):

Project No: NHSN-071-4(48)--2R-05

2303-0101000 HMA WEDGE/LEVEL/STRENGTH

County: AUDUBON

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT Route: U.S. 71 Length: 0.00 miles

Location: US 71 OVER E NISHNABOTNA RIVER

1.0 MILES SOUT OF IA 44

Item No. Item Description Quantity/Unit

SECTION NO. 0001

DESIGN NO. 0215;240'-0 X 32'-0 CONTINOUS WELDED GIRDER
BRIDGE

2403-0100010 STRUCT CONC (BRIDGE)

2404-7775005 REINFORC STEEL, EPOXY COATED
SECTION NO. 0002

ROADWAY ITEMS

2102-2625000 EMBANKMENT-IN-PLACE

148 CY

394 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 07-C007-138

Proposed Contract Period: Late Start Date of 08/29/16 with 35 WORK DAYS

Project(s):

Project No: BROS-C007(138)--8J-07

County: BLACK HAWK

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: BURTON AVE Length: 0.00 miles Location: BURTON AVE: 0.25 MILES NORTH OF DUNKERTON RD

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 10' X 6' X 28' REINFORCED CONCRETE BOX CULVERT

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 115 CY 2403-0100020 STRUCT CONC (RCB CULV) 106 CY 2404-7775000 REINFORC STEEL 16,090 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 14-C014-155

Proposed Contract Period: Late Start Date of 08/08/16 with 55 WORK DAYS

Project(s):

Project No: BRS-C014(155)--60-14

County: CARROLL

Type of Work: BRIDGE REPLACEMENT - CCS

Route: E46 Length: 0.00 miles Location: E46: NW QUARTER SECTION 16 WASHINGTON

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR 70' X 30' CONTINUOUS CONCRETE SLAB BRIDGE

2403-0100010 STRUCT CONC (BRIDGE) 160 CY 2404-7775000 REINFORC STEEL 40,767 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 16-C016-092

Proposed Contract Period: Late Start Date of 07/05/16 with 75 WORK DAYS

Project(s):

Project No: BROS-C016(92)--8J-16

County: CEDAR

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 210TH ST Length: 0.00 miles Location: 1420 210TH ST. BRIDGE: OVER SUGAR CREEK

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 130' X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 2,502 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 330 CY

 2404-7775000
 REINFORC STEEL
 76,314 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 16-C016-093

Proposed Contract Period: Late Start Date of 07/05/16 with 75 WORK DAYS

Project(s):

Project No: BROS-C016(93)--5F-16

County: CEDAR

Type of Work: BRIDGE REPLACEMENT - CCS

Route: CHARLES AVE Length: 0.00 miles

Location: 410 CHARLES AVE.: OVER BR CLEAR CR

Item No. Item Description Quantity/Unit ______

SECTION NO. 0001

ITEMS FOR A 150' X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 3,388 CY 473 CY

91,140 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 17-C017-073

Proposed Contract Period: Late Start Date of 08/08/16 with 55 WORK DAYS

Project(s):

Project No: BRS-C017(73)--60-17

County: CERRO GORDO

Type of Work: RCB CULVERT REPLACEMENT - TRIPLE BOX

Route: S56 Length: 0.00 miles

Location: ON S56, OVER COLD WATER CREEK, 3,500 FEET NORTH OF THE SW CO

RNER OF S17 T94 R19

Item No. Item Description Quantity/Unit .-----

SECTION NO. 0001

ITEMS FOR A TRIPLE 12' X 8' X 48'-8" REINFORCED CONCRETE

BOX CULVERT

2301-1033070 STD/S-F PCC PAV'T, CL C CL 3, 7" 176 SY 2403-0100020 STRUCT CONC (RCB CULV) 306 CY

2404-7775000 REINFORC STEEL 47,554 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 24-0303-509

Proposed Contract Period: Late Start Date of 07/18/16 with 55 WORK DAYS

Project(s):

Project No: MB-030-3(509)47--77-24

County: CRAWFORD

Type of Work: DECK JOINT REPAIR

Route: U.S. 30 Length: 0.00 miles Location: OVER BOYER RIVER, 0.6 MILE EAST OF M14.

Item No. Item Description ______

Quantity/Unit

SECTION NO. 0001

DESIGN NO. 0116; REPAIRS TO A 320'-0 X 30' CONTINUOUS

WELDED GIRDER BRIDGE

2403-0100000 STRUCT CONC (MISCELLANEOUS) 2404-7775005 REINFORC STEEL, EPOXY COATED

9 CY

1,376 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 26-C026-087

Proposed Contract Period: Late Start Date of 07/05/16 with 80 WORK DAYS

Project(s):

Project No: BROS-C026(87)--5F-26

County: DAVIS

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: KEY BOULEVARD Length: 0.10 miles

Location: ON KEY BLVD, OVER WYACONDAH CREEK, FROM 0.3 MILES EAST OF 24

OTH ST, IN S2 T68 R14

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 120'-0 X 24'-0 PRETENSIONED PRESTRESSED

CONCRETE BEAMM BRIDGE

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 736 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 162 CY

 2404-7775000
 REINFORC STEEL
 38,430 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 39-0444-042

Proposed Contract Period: Late Start Date of 04/18/16 with 125 WORK DAYS

Project(s):

Project No: BRFN-044-4(42)--39-39

County: GUTHRIE

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: IOWA 44 Length: 0.00 miles Location: OVER SEELY CREEK 1.3 MILE W. OF CO. RD. N-70

Item No. Item Description	Quantity/Unit
SECTION NO. 0001	
DESIGN NO. 0116; TWIN 12' X 12' X 183' REINFORCED	
CONCRETE BOX CULVERT	
2403-0100020 STRUCT CONC (RCB CULV)	960 CY
2404-7775000 REINFORC STEEL	129,851 LB
SECTION NO. 0002	
ROADWAY ITEMS	
2102-2625000 EMBANKMENT-IN-PLACE	9,604 CY
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	1,980 CY
2303-0041500 HMA (3M ESAL) BASE, 1/2"	178 TON
2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC	181 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 43-C043-077

Proposed Contract Period: Late Start Date of 07/05/16 with 80 WORK DAYS

Project(s):

Project No: BRS-C043(77)--60-43

County: HARRISON

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: 296TH ST (F58) Length: 0.00 miles

Location: ON 296TH ST., OVER MOSQUITO CREEK, ALONG NLINE S09 T78 R41

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 176'-4 X 24' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

 2102-2625000
 EMBANKMENT-IN-PLACE
 821 CY

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 1,611 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 313 CY

 2404-7775000
 REINFORC STEEL
 61,358 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 48-0806-324

Proposed Contract Period: Late Start Date of 05/23/16 with 85 WORK DAYS

Project(s):

Project No: IMN-080-6(324)212--0E-48

County: IOWA

Type of Work: BRIDGE DECK OVERLAY

Length: 0.00 miles

Route: I-80 Location: I-80 OVER SR V-52

Location: I-80 OVER SR V-52 (EBL/WBL)		
Item No. Item Description (uantity	 /Unit
SECTION NO. 0001 DESIGN NO. 0116; REPAIRS TO A 121'-8 X 40' PRETENSICE PRESTRESSED CONCRETE BEAM BRIDGE (WBL)	NED	
2403-0100000 STRUCT CONC (MISCELLANEOUS)	25	CY
2404-7775005 REINFORC STEEL, EPOXY COATED	3,223	LB
2413-0698074 DECK REPAIR, CL A	108	SY
SECTION NO. 0002		
DESIGN NO. 0116; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN 2413-0698066 DECK OVERLAY (CL O PCC)		SY
SECTION NO. 0003	DGG.	
DESIGN NO. 0116; ALTERNATE 'AA' OPTION 2: CLASS HPC-C BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		QV.
2413-0698067 DECK OVERLAY (CL HPC-O PCC) SECTION NO. 0004	537	SI
	MED	
DESIGN NO. 0216; REPAIRS TO A 121'-8 X 40.0 PRETENSION	MED	
PRESTRESSED CONCRETE BEAM BRIDGE (EBL)	2.5	CV
2403-0100000 STRUCT CONC (MISCELLANEOUS)	3,223	CY
2404-7775005 REINFORC STEEL, EPOXY COATED 2413-0698074 DECK REPAIR, CL A	108	
	108	SI
SECTION NO. 0005	,	
DESIGN NO. 0216; ALTERNATE 'BB' OPTION 1: CLASS O PCC		
BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN 2413-0698066 DECK OVERLAY (CL O PCC)	, ,	CV
, ,	537	SI
SECTION NO. 0006 DESIGN NO. 0216; ALTERNATE 'BB' OPTION 2: CLASS HPC-C	DCC	
BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN		
2413-0698067 DECK OVERLAY (CL HPC-O PCC)	537	CV
SECTION NO. 0007	337	51
ROADWAY ITEMS		
(WBL)		
2102-2625000 EMBANKMENT-IN-PLACE	193	CV
2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC	1,364	
SECTION NO. 0008	1,304	ION
ROADWAY ITEMS		
(EBL)		
2102-2625000 EMBANKMENT-IN-PLACE	195	CY
2102 202000 Didiminidi III LDNOD	195	O 1

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 51-C051-060

Proposed Contract Period: Late Start Date of 04/04/16 with 120 WORK DAYS

Project(s):

Project No: BROS-C051(60)--5F-51

County: JEFFERSON

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 218TH Length: 0.10 miles

Location: ON 218TH WAY, OVER TRIB TO ROCK CREEK, FROM ASH AVE EAST 0.7

4 MILES TO ON 218TH WY, AT SW S32 T72 R11

Project No: BROS-C051(61)--5F-51

County: JEFFERSON

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX
Route: 220TH Length: 0.10 miles
Location: 220TH ST: OVER STODDARD CREEK

Project No: BROS-C051(62)--5F-51
County: JEFFERSON
Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 220TH Length: 0.10 miles

Location: ON 220TH ST., OVER BONELL CREEK, FROM EPISCIA AVE. EAST 0.21

MILES TO ON 220TH ST., AT NLINE S2 T71 R11

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
	ITEMS FOR A TWIN 10' X 8' X 118'-0 REINFORCED	CONCRETE BOX
(CULVERT BROS-C051(60)5F-51	
2102-2625000	EMBANKMENT-IN-PLACE	416 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	684 CY
2403-0100020	STRUCT CONC (RCB CULV)	396 CY
2404-7775000	REINFORC STEEL	57,626 LB
SECTION	NO. 0002	
	ITEMS FOR A TWIN 10' X 10' X 62'-0 REINFORCED	CONCRETE BOX

X 62'-0 REINFORCED CONCRETE BOX CULVERT BROS-C051(61)--5F-51

2102-2625000	EMBANKMENT-IN-PLACE	915 CY	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	70 CY	
2403-0100020	STRUCT CONC (RCB CULV)	259 CY	
2404-7775000	REINFORC STEEL	39,502 LB	

SECTION NO. 0003

ITEMS FOR A TWIN 10' X 8' X 50'-0 REINFORCED CONCRETE BOX CULVERT BROS-C051(62)--5F-51

2102-2625000	EMBANKMENT-IN-PLACE	155 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	25 CY
2403-0100020	STRUCT CONC (RCB CULV)	187 CY
2404-7775000	REINFORC STEEL	29,206 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 51-0348-156

Proposed Contract Period: Late Start Date of 04/04/16 with 120 WORK DAYS

Project(s):

Project No: BRF-034-8(156)--38-51

County: JEFFERSON

2122-5190007 PAVED SHLD, PCC, 7"

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: U.S. 34 Length: 0.00 miles

Location: US 34 OVER BIG CEDAR CREEK (EBL)

1.5 MILES WEST OF JCT. WITH CO. RD. V63

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
]	DESIGN NO. 0116; 214'-0 X 40'-0 PRESTRESSED	PRETENSIONED
(CONCRETE BEAM BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	819 CY
2404-7775000	REINFORC STEEL	82,519 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	101,593 LB
SECTION	NO. 0002	
I	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	2,006 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,023 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	1,063 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	1,222 TON
SECTION	NO. 0004	
Ž	ALTERNATE 'AA' OPTION 2: PCC SHOULDERS	

BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN

218 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 52-0806-326

Proposed Contract Period: Late Start Date of 05/08/16 with 90 WORK DAYS

Project(s):

Project No: IMN-080-6(326)244--0E-52

County: JOHNSON

Type of Work: BRIDGE DECK OVERLAY Route: I-80

Length: 0.00 miles

Location: DUBUQUE ST. OVER I-80

(SBL/NBL)

(SDL/NDL)		
	Quantity/	/Unit
SECTION NO. 0001		
DESIGN NO. 2117; REPAIRS TO A 236'-0 X 30' CONTINUOU BRIDGE (SBL)	S I-BEAM	
2403-0100000 STRUCT CONC (MISCELLANEOUS)	11	CY
2404-7775005 REINFORC STEEL, EPOXY COATED	1,451	LB
2413-0698074 DECK REPAIR, CL A	156	SY
SECTION NO. 0002		
DESIGN NO. 2117; ALTERNATE 'AA' OPTION 1: CLASS O PC	C	
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSE	N	
2413-0698066 DECK OVERLAY (CL O PCC)	778	SY
SECTION NO. 0003		
DESIGN NO. 2117; ALTERNATE 'AA' OPTION 2: CLASS HPC-) PCC	
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSE	N	
2413-0698067 DECK OVERLAY (CL HPC-O PCC)	778	SY
SECTION NO. 0004		
DESIGN NO. 2217; REPAIRS TO A 236'-0 X 30' CONTINUOU	S I-BEAM	
BRIDGE (NBL)		
2403-0100000 STRUCT CONC (MISCELLANEOUS)	11	
2404-7775005 REINFORC STEEL, EPOXY COATED	1,445	
2413-0698074 DECK REPAIR, CL A SECTION NO. 0005	156	SY
DESIGN NO. 2217; ALTERNATE 'BB' OPTION 1: CLASS O PC		
BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSE		
2413-0698066 DECK OVERLAY (CL O PCC)	778	CV
SECTION NO. 0006	770	31
DESIGN NO. 2217; ALTERNATE 'BB' OPTION 2: CLASS HPC-) PCC	
BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSE		
2413-0698067 DECK OVERLAY (CL HPC-O PCC)	778	SY
2110 00000. Phot overthem (of file of foc)	, , ,	J 1

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 54-C054-105

Proposed Contract Period: Late Start Date of 08/01/16 with 60 WORK DAYS

Project(s):

Project No: FM-C054(105)--55-54

County: KEOKUK

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: V5G Length: 0.09 miles

Location: ON V5G, OVER STREAM, FROM 200' NORTH OF 220TH AVE SOUTHEAST

400 FEET TO 200' EAST OF 220TH AVE, S30 T75 R11

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 8' X 8' X 94'REINFORCED CONCRETE BOX CULVERT

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 1,959 CY

 2301-1034080
 STD/S-F PCC PAV'T, CL C CL 3I, 8"
 207 SY

 2403-0100020
 STRUCT CONC (RCB CULV)
 147 CY

 2404-7775000
 REINFORC STEEL
 23,190 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 64-C064-031

Proposed Contract Period: Late Start Date of 07/05/16 with 70 WORK DAYS

Project(s):

Project No: BROS-C064(31)--5F-64

County: MARSHALL

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 105TH ST Length: 0.00 miles

Location: 105TH ST & HART AVE OVER HONEY CREEK: SEC 6-85-19

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 120' X 30'-6 CONTINUOUS CONCRETE BRIDGE

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 23 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 293 CY

 2404-7775000
 REINFORC STEEL
 69,193 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 67-C067-074

Proposed Contract Period: Late Start Date of 06/27/16 with 80 WORK DAYS

Project(s):

Project No: BROS-C067(74)--8J-67

County: MONONA

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 245TH ST Length: 0.00 miles

Location: 245TH ST: OVER JORDAN CREEK

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2625000 EMBANKMENT-IN-PLACE

305 CY

SECTION NO. 0002

ITEMS FOR A110'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE

2403-0100010 STRUCT CONC (BRIDGE)

211 CY

2404-7775000 REINFORC STEEL

54,630 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 018 Proposal ID: 67-C067-075

Proposed Contract Period: Late Start Date of 08/01/16 with 50 WORK DAYS

Project(s):

Project No: BROS-C067(75)--8J-67

County: MONONA

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 170TH ST Length: 0.00 miles Location: 170TH ST: OVER TRIBUTARY TO SOLDIER RIVER

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 10' X 10' X 43' REINFORCED CONCRETE BOX

CULVERT

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 70 CY 2403-0100020 STRUCT CONC (RCB CULV) 307 CY

2404-7775000 REINFORC STEEL 52,535 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 019 Proposal ID: 77-0803-198

Proposed Contract Period: Late Start Date of 04/04/16 with 140 WORK DAYS

Project(s):

Project No: NHS-080-3(198)128--11-77

County: POLK

Type of Work: BRIDGE AND APPROACHES - STEEL GIRDER

Route: I-80 Length: 0.21 miles

Location: IN THE CITY OF URBANDALE, 100TH ST: 100TH ST. AT I-35/I-80

Project No: IN-080-3(207)128--15-77

County: POLK

Type of Work: RCB CULVERT EXTENSION - TWIN BOX

Route: I-80 Length: 0.00 miles Location: IN THE CITY OF URBANDALE, ON 100TH ST, CULVERT EXTENSIONS AS

SOCIATED WITH NEW I-80 INTERCHANGE

-----Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

NHS-080-3 (198) 128--11-77

2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	95 , 576 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	15,137 CY
2122-5190125	PAVED SHLD, PCC, 12.5"	336 SY
2301-1033085	STD/S-F PCC PAV'T, CL C CL 3, 8.5"	9,267 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	1,002 SY

SECTION NO. 0002

ITEMS FOR A 330'-0 X 101'-0 CONTINUOUS WELDED GIRDER

BRIDGE NHS-080-3(198)128--11-77

2403-0100010	STRUCT CONC (BRIDGE)	148 CY
2404-7775000	REINFORC STEEL	31,028 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	378,830 LB

SECTION NO. 0003

ITEMS FOR A TWIN 12' X 10' REINFORCED CONCRETE BOX

CULVERT EXTENSION IN-080-3(207)128--15-77

2403-0100020	STRUCT CONC (RCB CULV)	1,150 CY
2404-7775000	REINFORC STEEL	133,965 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 020 Proposal ID: 78-0294-507

Proposed Contract Period: Late Start Date of 08/29/16 with 45 WORK DAYS

Project(s):

Project No: MBIN-029-4(507)57--0M-78

County: POTTAWATTAMIE Type of Work: DECK JOINT REPAIR

Route: I-29 Length: 0.00 miles

2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH

Location: IN THE CITY OF COUNCIL BLUFFS OVER IA. 192

Item Description Quantity/Unit Item No. ______ SECTION NO. 0001 DESIGN NO. 0416; REPAIRS TO A 222' X 39' CONTINUOUS COMPOSITE STEEL BEAM BRIDGE 2403-0100000 STRUCT CONC (MISCELLANEOUS) 2404-7775005 REINFORC STEEL, EPOXY COATED 19 CY 986 LB SECTION NO. 0002 ROADWAY ITEMS 237 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 021 Proposal ID: 82-0741-230

Proposed Contract Period: Late Start Date of 05/16/16 with 90 WORK DAYS

Project(s):

Project No: IMN-074-1(230)0--0E-82

County: SCOTT

Length: 0.00 miles

Type of Work: BRIDGE DECK OVERLAY
Route: I-74 Leng
Location: WESTBOUND I-74 OVER I-80

Item No.	Item Description	Quantity,	/Unit
SECTION	NO. 0001		
D	DESIGN NO. 0316; REPAIRS TO 251'-0 X 30'-0 CONTINUOU	S WELDED	
G	IRDER BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	5	CY
	REINFORC STEEL, EPOXY COATED	517	LB
2413-0698074	DECK REPAIR, CL A	167	SY
SECTION	NO. 0002		
D	ESIGN NO. 0316; ALTERNATE 'AA' OPTION 1: CLASS O PC	С	
В	ID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSE	N	
2413-0698066	DECK OVERLAY (CL O PCC)	839	SY
SECTION	NO. 0003		
D	ESIGN NO. 0316; ALTERNATE 'AA' OPTION 2: CLASS HPC-	O PCC	
В	ID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSE	N	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	839	SY
SECTION	NO. 0004		
R	COADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	69	SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4	EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 022 Proposal ID: 82-0808-283

Proposed Contract Period: Late Start Date of 05/09/16 with 90 WORK DAYS

Project(s):

Project No: IMN-080-8(283)303--0E-82

County: SCOTT

Type of Work: BRIDGE DECK OVERLAY

Route: I-80 Length: 0.00 miles

Location: I-80 OVER SR Z-30

3.5 MILES W. OF US 67 (EBL/WBL)

______ Item No. Item Description Quantity/Unit SECTION NO. 0001 DESIGN NO. 0416; REPAIRS TO A 150-10 X 30' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE (EBL) 2403-0100000 STRUCT CONC (MISCELLANEOUS) 21 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 2,739 LB 2413-0698074 DECK REPAIR, CL A 125 SY SECTION NO. 0002 DESIGN NO. 0416; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (EBL) 2413-0698066 DECK OVERLAY (CL O PCC) SECTION NO. 0003 DESIGN NO. 0416; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (EBL) 2413-0698067 DECK OVERLAY (CL HPC-O PCC) SECTION NO. 0004 DESIGN NO. 0516; REPAIR TO A 150'-10 X 30' PRESTRESSED PRETENSIONED CONCRETE BEAM BRIDGE (WBL) 2403-0100000 STRUCT CONC (MISCELLANEOUS) 21 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 2,739 LB 2413-0698074 DECK REPAIR, CL A 125 SY SECTION NO. 0005 DESIGN NO. 0516; ALTERNATE 'BB' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN (WBL) 2413-0698066 DECK OVERLAY (CL O PCC) SECTION NO. 0006 DESIGN NO. 0516; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN (WBL) 2413-0698067 DECK OVERLAY (CL HPC-O PCC) 499 SY SECTION NO. 0007 ROADWAY ITEMS (EBL) 2102-2625000 EMBANKMENT-IN-PLACE 710 CY SECTION NO. 0008 ROADWAY ITEMS (WBL) 2102-2625000 EMBANKMENT-IN-PLACE 178 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 023 Proposal ID: 84-6550-605

Proposed Contract Period: Late Start Date of 04/04/16 with 135 WORK DAYS

Project(s):

Project No: BRS-6550(605)--60-84

County: SIOUX

Type of Work: BRIDGE AND APPROACHES - PPCB

2301-1032090 STD/S-F PCC PAV'T, CL C CL 2, 9"

Route: ELMWOOD AVENUE Length: 0.00 miles

Location: ELMWOOD AVE.: NEAR ROCK VALLEY, IA

Item No.	Item Description	Quantity	/Unit
SECTION	 NO. 0001		
I	TEMS FOR A 409'-0 X 32'-0 PRETENSIONED PRESTRESSED	CONCRETE	
В	EAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	1,065	CY
2404-7775000	REINFORC STEEL	51,955	LB
2404-7775005	REINFORC STEEL, EPOXY COATED	172,980	LB
SECTION	NO. 0002		
R	OADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,955	CY

834 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 024 Proposal ID: 85-C085-134

Proposed Contract Period: Late Start Date of 08/08/16 with 30 WORK DAYS

Project(s):

Project No: FM-C085(131)--55-85

County: STORY

Type of Work: BRIDGE DECK OVERLAY

Route: S14 Length: 0.10 miles

Location: ON S14, OVER BRANCH OF INDIAN CREEK, WLINE S31 T83 R22

Project No: FM-C085(134)--55-85

County: STORY

Type of Work: BRIDGE DECK OVERLAY

Route: 660TH AVE Length: Location: S27: OVER EAST INDIAN CREEK Length: 0.10 miles

Item Description ______

SECTION NO. 0001

ITEMS FOR REPAIRS TO A 50'-0 X 28'-0 STEEL BEAM BRIDGE

FM-C085(131)--55-85

2413-0698067 DECK OVERLAY (CL HPC-O PCC) 165 SY

2413-0698074 DECK REPAIR, CL A 40 SY

SECTION NO. 0002

ITEMS FOR REPAIRS TO A 55'-0 X 28'-0 STEEL BEAM BRIDGE

FM-C085(134)--55-85

175 SY 2413-0698067 DECK OVERLAY (CL HPC-O PCC)

2413-0698074 DECK REPAIR, CL A 44 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 025 Proposal ID: 85-0695-098

Proposed Contract Period: Late Start Date of 07/05/16 with 70 WORK DAYS

Project(s):

Project No: BRFN-069-5(98)--39-85

County: STORY

Type of Work: BRIDGE REPLACEMENT - CCS

Route: U.S. 69 Length: 0.00 miles

Location: US 69 OVER KEIGLEY BRANCH 1.1 MILES S OF CO RD E18

Item No.	Item Description	Quantity	/Unit
SECTION	NO. 0001		
Ι	DESIGN NO. 0116; A 120'-0 X 44'-0 CONTINUOUS CONCRET	E SLAB	
E	BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	423	CY
2404-7775005	REINFORC STEEL, EPOXY COATED	97 , 899	LB
SECTION	NO. 0002		
F	ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	4,073	CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,648	CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	3,207	SY
SECTION	NO. 0004		
I	ALTERNATE 'AA ' OPTION 2: PCC SHOULDER		

BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN

2122-5190007 PAVED SHLD, PCC, 7" 1,253 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 026 Proposal ID: 86-0635-052

Proposed Contract Period: Late Start Date of 08/15/16 with 40 WORK DAYS

Project(s):

Project No: BRFN-063-5(52)--39-86

County: TAMA

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT Route: U.S. 63 Length: 0.00 miles

Location: US 63 OVER TWELVE MILE CREEK 1.1 MI. S. OF S. JCT. SR D65

Item No. Item Description Quantity/Unit

SECTION NO. 0001

DESIGN NO. 0216; A 180'-0 X 30'-0 CONTINUOUS I-BEAM BRIDGE

2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 185 CY

64,870 LB

SECTION NO. 0002

ROADWAY ITEMS

2102-2625000 EMBANKMENT-IN-PLACE 148 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 027 Proposal ID: 87-C087-051

Proposed Contract Period: Late Start Date of 07/05/16 with 80 WORK DAYS

Project(s):

Project No: BROS-C087(51)--8J-87

County: TAYLOR

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: IDAHO AVE Length: 0.00 miles Location: ON IDAHO AVE. 0.2 MI. NORTH OF 110TH ST.

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 12' X 12' X 74' REINFORCED CONCRETE BOX

CULVERT

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 905 CY 2403-0100020 STRUCT CONC (RCB CULV) 512 CY 2404-7775000 REINFORC STEEL 71,513 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 028 Proposal ID: 92-C092-083

Proposed Contract Period: Late Start Date of 05/30/16 with 105 WORK DAYS

Project(s):

Project No: BRS-C092(83)--60-92

County: WASHINGTON

Type of Work: BRIDGE AND APPROACHES - PPCB

Route: G38 Length: 0.20 miles

Location: G38: OVER DUTCH CREEK

Item No.	Item Description	Quantity/Unit
	NO. 0001	
I	TTEMS FOR A 163'-10 X 30'-6 PRETENSIONED PRESTRESSE	D
C	CONCRETE BEAM BRIDGE	
2102-2625000	EMBANKMENT-IN-PLACE	1,972 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,572 CY
2301-1034080	STD/S-F PCC PAV'T, CL C CL 31, 8"	228 SY
2403-0100010	STRUCT CONC (BRIDGE)	248 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	61,920 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 029 Proposal ID: 93-C093-077

Proposed Contract Period: Late Start Date of 08/01/16 with 60 WORK DAYS

Project(s):

Project No: BROS-C093(77)--8J-93

County: WAYNE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: CEDAR Length: 0.10 miles

Location: ON CEDAR, OVER MEDICINE CREEK, FROM NW1/4 OF SECTION 16 EAST

0.5 MILES TO 95TH STREET AT S16 T67 R22

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 120'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE

2403-0100010 STRUCT CONC (BRIDGE) 314 CY 2404-7775000 REINFORC STEEL 70,080 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 030 Proposal ID: 93-0651-027

Proposed Contract Period: Late Start Date of 08/15/16 with 50 WORK DAYS

Proposal Note:

PAVEMENT CORRECTION-MOBILIZATION AND TRAFFIC CONTROL THE CONTRACTOR MAY BE REQUIRED TO CORRECT PAVEMENT SETTLEMENT THAT OCCURS WITHIN THE FIRST NINETY DAYS FOLLOWING INITIAL COMPLETION OF APPROACH PAVEMENT. THE PROJECT ENGINEER WILL PROVIDE A FOURTEEN DAY CALENDAR NOTICE TO BEGIN THIS WORK. WORK WILL BE WILL BE PAID AT CONTRACT UNIT PRICES.

Project(s):

Project No: BRFN-065-1(27)--39-93

County: WAYNE

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX
Route: U.S. 65 Length: 0.00 miles
Location: OVER SMALL STREAM 0.1 MILE S. OF CO. RD. J-46

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001

DESIGN NO. 0115; TWIN 12'-0 X 10'-0 X 82'-0 REINFORCED CONCRETE BOX CULVERT

2403-0100020	STRUCT CONC (RCB CULV)	364 CY
2404-7775000	REINFORC STEEL	55,556 LB
OF OF TON	370 0000	

SECTION NO. 0002 ROADWAY ITEMS

10	OADWAI IIEMS	
2102-2625000	EMBANKMENT-IN-PLACE	720 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	289 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	39 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	32 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	16 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 031 Proposal ID: 99-0034-038

Proposed Contract Period: Late Start Date of 07/11/16 with 65 WORK DAYS

Project(s):

Project No: BRFN-003-4(38)--39-99

County: WRIGHT

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: IOWA 3 Length: 0.00 miles

Location: IOWA 3 OVER LITTLE EAGLE CREEK 2.9 MILES W. OF CO. RD. R-38

Item No. Item Description Quantity/Unit

SECTION NO. 0001

DESIGN NO. 0115; ALTERNATE 'AA' OPTION 1: CAST IN PLACE RCB

BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN

2403-0100020 STRUCT CONC (RCB CULV) 416 CY 2404-7775000 REINFORC STEEL 63,579 LB

SECTION NO. 0003

ROADWAY ITEMS

2102-2625000 EMBANKMENT-IN-PLACE 1,283 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 1,913 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 00-000S-655

Proposed Contract Period: Completion Date of 08/19/16

Project(s):

Project No: NHSN-000-S(655)--2R-00

County: STATEWIDE

Type of Work: PCC SIDEWALK/TRAIL

Route: VARIOUS LOCATIONS Length: 0.00 miles

Location: IN AFTON AND LOGAN (ADA - DIST 4)

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2301-1012090 STD/S-F PCC PAV'T, CL A CL 2, 9"

34 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT

Proposed Bid Order: 102 Proposal ID: 00-000S-656

Proposed Contract Period: Completion Date of 08/19/16

Project(s):

Project No: NHSN-000-S(656)--2R-00

County: STATEWIDE

Type of Work: PCC SIDEWALK/TRAIL

Route: VARIOUS LOCATIONS Length: 0.00 miles

Location: IN CONESVILLE / HUMESTON / KINROSS / SOUTH ENGLISH /

WAYLAND / WEST LIBERTY (ADA - DIST 5)

 Item No.
 Item Description
 Quantity/Unit

 SECTION NO. 0001

 ROADWAY ITEMS

 2403-0100000
 STRUCT CONC (MISCELLANEOUS)
 4 CY

 2404-7775000
 REINFORC STEEL
 268 LB

 2529-5070110
 PATCH, FULL-DEPTH FINISH, BY AREA
 1,023 SY

84 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 00-000S-657

Proposed Contract Period: Completion Date of 08/19/16

Project(s):

Project No: NHSN-000-S(657)--2R-00

County: STATEWIDE

Type of Work: PCC SIDEWALK/TRAIL

Route: VARIOUS LOCATIONS Length: 0.00 miles Location: IN ANDREW AND RIVERDALE (ADA - DIST 6)

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW

4 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 07-0202-708

Proposed Contract Period: Late Start Date of 09/19/16 with 20 WORK DAYS

Project(s):

Project No: MP-020-2(708)230--76-07

County: BLACK HAWK

Type of Work: BRIDGE APPROACH REPAIR

Route: U.S. 20 Length: 0.00 miles

Location: AT KIMBALL AVE,, 0.5 MILE WEST OF IOWA 21 IN WATERLOO.

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 16-C016-094

Proposed Contract Period: Late Start Date of 07/11/16 with 65 WORK DAYS

Project(s):

Project No: STP-S-C016(94)--5E-16

County: CEDAR

Type of Work: PCC OVERLAY - UNBONDED

Route: X64 Length: 5.05 miles

Location: ON X64, FROM CLARENCE CITY LIMITS NORTH 5 MILES TO JONES COU

NTY LINE, S12 T82 R02

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
]	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	27 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	401 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	4,518 SY
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	13 TON
2310-5151040	PCC OVERLAY, FURN ONLY	13,131 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	67,534 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 23-1415-625

Proposed Contract Period: Late Start Date of 04/04/16 with 130 WORK DAYS

Project(s):

Project No: STP-U-1415(625)--70-23

County: CLINTON

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: 19TH AVE Length: 0.00 miles

Location: IN THE CITY OF CLINTON, 19TH AVE NORTH PHASE III: FROM APPRO

X. 1100' WEST OF RANDALL TO N. 2ND STREET

______ Item No. Item Description

Quantity/Unit -----SECTION NO. 0001 ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 56,972 CY 20,591 SY 3,428 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 31-1147-605

Proposed Contract Period: Late Start Date of 08/29/16 with 30 WORK DAYS

Project(s):

Project No: STP-E-1147(605)--8V-31

County: DUBUQUE

Type of Work: PCC SIDEWALK/TRAIL

Route: NEW TRAIL CONST. Length: 0.67 miles

Location: IN THE CITY OF CASCADE, 1 ST AVE: FROM MONROE STREET TO NIXO

2,869 SY

N STREET

Item No. Item Description Quantity/Unit SECTION NO. 0001 PEDESTRIAN TRAIL ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 750 CY 1,750 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 44-C044-077

Proposed Contract Period: Late Start Date of 08/08/16 with 55 WORK DAYS

Project(s):

Project No: STP-S-C044(77)--5E-44

County: HENRY

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: H38 (220TH STREET) Length: 8.18 miles

Location: H38 FROM HWY 218 AND HWY 34 OVERPASS TO X23 (RACINE AVENUE)

Quantity/Unit Item No. Item Description ______ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1013080 STD/S-F PCC PAV'T, CL A CL 3, 8" 14,763 CY

94,192 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 51-2465-623

Proposed Contract Period: Late Start Date of 08/29/16 with 40 WORK DAYS

Project(s):

Project No: STP-U-2465(623)--70-51

County: JEFFERSON

Type of Work: PCC PAVEMENT - REPLACE

Route: KIRKWOOD AVE Length: 0.10 miles

Location: IN THE CITY OF FAIRFIELD, ON KIRKWOOD AV, FROM 9TH STREET TO

7TH STREET AND PROJECT RELATED IMPROVEMENTS ON SIDE STREETS

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 636 CY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 2,434 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 110 Proposal ID: 52-5557-619

Proposed Contract Period: Late Start Date of 04/04/16 with 105 WORK DAYS

Project(s):

Project No: STP-A-5557(619)--86-52

County: JOHNSON

Type of Work: PCC PAVEMENT WIDENING

Route: PENN ST Length: 0.63 miles

Location: ON PENN STREET, FROM I-380 NB ON-RAMP EAST .63 MILES TO ALEX

ANDER WAY

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 5,865 CY 2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10" 8,600 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 111 Proposal ID: 60-C060-107

Proposed Contract Period: Late Start Date of 05/31/16 with 85 WORK DAYS

Project(s):

Project No: L-(A-22)--73-60

County: LYON

Type of Work: PCC OVERLAY - UNBONDED

Route: A22 Length: 1.65 miles Location: 170TH ST: FROM JCT OF US 75 TO CO RD K-52

Project No: STP-S-C060(107)--5E-60

County: LYON

Type of Work: PCC OVERLAY - UNBONDED

Length: 8.08 miles

Route: L26 Length: Location: L-26: FROM INT OF A46 TO HWY 9

Project No: FM-C060(108)--55-60 County: LYON Type of Work: PCC OVERLAY - UNBONDED

Route: L26 Length: 0.99 miles Location: A22: FROM INT. OF L-26 TO OSCEOLA COUNTY LINE

Item No. Item Description Quantity/Unit ______ SECTION NO. 0001 ROADWAY ITEMS L-(A22)--73-60 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8"
2310-5151040 PCC OVERLAY, FURN ONLY
2310-5151251 PCC OVERLAY PLACE ONLY (UNBONDED) 2,508 SY 3,313 CY 20,578 SY SECTION NO. 0002 ROADWAY ITEMS STP-S-C060(107--5E-60 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 3,827 SY 2310-5151040 PCC OVERLAY, FURN ONLY 18,494 CY 2310-5151551 PCC OVERLAY PLACE ONLY (WHITE TOPPING) 109,561 SY SECTION NO. 0003

ROADWAY ITEMS

FM-C060(108)--55-60

2301-1033050 STD/S-F PCC PAV'T, CL C CL 3, 5" 503 SY 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8"
2310-5151040 PCC OVERLAY, FURN ONLY
2310-5151551 PCC OVERLAY PLACE ONLY (WHITE TOPPING) 512 SY 2,342 CY 13,139 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 112 Proposal ID: 77-7875-638

Proposed Contract Period: Late Start Date of 04/04/16 with 130 WORK DAYS

Project(s):

Project No: STP-U-7875(638)--70-77

County: POLK

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: 100TH ST Length: 0.00 miles

Location: IN THE CITY OF URBANDALE, NW 100TH STREET: AT NW 54TH AVENUE

INTERSECTION WITH GRIMES AND URBANDALE

Item No.	Item Description	Quantity,	/Unit
SECTION	NO. 0001		
I	ROADWAY ITEMS		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	31,993	CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	20,638	CY
2301-1033085	STD/S-F PCC PAV'T, CL C CL 3, 8.5"	38,788	SY
2303-0041500	HMA (3M ESAL) BASE, 1/2"	40	TON
2303-0143500	HMA (3M ESAL) SURF, 1/2", NO FRIC	832	SY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1	CY
2404-7775000	REINFORC STEEL	24	LB
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	4,259	SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	527	SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 113 Proposal ID: 82-1827-665

Proposed Contract Period: Late Start Date of 04/04/16 with 130 WORK DAYS

Project(s):

Project No: STP-U-1827(665)--70-82

County: SCOTT

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: FOREST GROVE RD Length: 0.51 miles

Location: ON FOREST GROVE RD, FROM UTICA RIDGE RD. (DAVENPORT) TO ~650

' E OF EAGLE RIDGE RD. (BETTENDORF)

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
F	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	85,253 CY
2301-1032070	STD/S-F PCC PAV'T, CL C CL 2, 7"	2,836 SY
2301-1032100	STD/S-F PCC PAV'T, CL C CL 2, 10"	34,048 SY
2303-0013500	HMA (100K ESAL) B-I-S, 1/2", NO FRIC	154 TON
2403-0100020	STRUCT CONC (RCB CULV)	424 CY
2404-7775000	REINFORC STEEL	68,605 LB
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	4,912 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 114 Proposal ID: 85-3630-091-A

Proposed Contract Period: Late Start Date of 08/15/16 with 45 WORK DAYS

Project(s):

Project No: TAP-U-3630(91)--8I-85

County: STORY

Type of Work: PCC SIDEWALK/TRAIL

Route: HEART OF IOWA TRAIL Length: 0.00 miles

Location: HEART OF IOWA NATURE TRAIL, FROM HIGHWAY 69 TO TRAILRIDGE PA

RK

Item No. Item Description Quantity/Unit

SECTION NO. 0001

PCC TRAIL ITEMS

2511-0302500 RECREATIONAL TRAIL, PCC, 5"

5,410 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 115 Proposal ID: 97-0201-123

Proposed Contract Period: Late Start Date of 04/04/16 with 20 WORK DAYS

Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.

Completion Date of 12/01/18

Site 02: TO COMPLETE THE OBLITERATION OF 165TH STREET.

Completion Date of 11/23/16

Site 03: SEE SITE NUMBER 03 DESCRIPTION BELOW.

Approx Start Date of 05/16/16 with 60 WORK DAYS

Proposal Note:

*** SITE NUMBER CONTRACT ***

THIS IS FOR ALL WORK NOT COVERED BY SITE 01. THIS IS FOR EROSION CONTROL AND SEEDING.

*** SITE NUMBER 01 ***

THIS SITE IS FOR THE COMPLETION OF STAGES 1A, 1B AND 2, COMPLETED SO THAT ALL OF US 20 MAINLINE, US 20 SHOULDERS, AND COUNTY ROADS ARE OPEN TO TRAFFIC. THIS INCLUDES THE COMPLETION OF ALL SAFETY ITEMS NEEDED TO OPEN THE ROADWAY TO TRAFFIC. THESE SAFETY ITEMS INCLUDE ITEMS SUCH AS GUARDRAIL, PAINT LINES, REGULATORY SIGNING.

SITE NUMBER 01 ALSO HAS A ROAD OPENING BONUS AS FOLLOWS:

THE CONTRACTOR WILL BE PAID THE PREDETERMINED AMOUNT SHOWN IN THE PROPOSAL SCHEDULE FOR 'ROAD OPENING BONUS' FOR COMPLETING CONSTRUCTION SO THAT NEW US 20 MAINLINE, US 20 SHOULDERS AND COUNTY ROAD CONNECTIONS ARE OPEN TO TRAFFIC. COMPLIANCE REQUIRES THAT ALL SAFETY ITEMS ARE COMPLETED. THIS INCLUDES ITEMS SUCH AS GUARDRAIL, PAINT LINES AND REGULATORY SIGNING. FAILURE TO OPEN US 20 TO TRAFFIC DUE TO WEATHER, CHANGE ORDERS, CHANGE IN QUANTITIES, UTILITY DELAYS OR ANY OTHER DELAYS WILL NOT BE CONSIDERED AS A JUSTIFICATION TO MODIFY THE DATE OR JUSTIFY PAYMENT OF THE BONUS.

SCHEDULE FOR ROAD OPENING BONUS:

OPENING DATE / BONUS

ON OR BEFORE 11/16/18 --- \$1,500,000

11/17/18 --- \$1,400,000

11/18/18 --- \$1,300,000

11/19/18 --- \$1,200,000

11/20/18 --- \$1,100,000

11/21/18 --- \$1,000,000

11/22/18 --- \$900,000

11/23/18 --- \$800,000

11/24/18 --- \$700,000

11/25/18 --- \$600,000

11/26/18 --- \$500,000

11/27/18 --- \$400,000

Project(s):

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Project No: NHSN-020-2(123)--2R-47

County: IDA

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Length: 12.40 miles

Route: U.S. 20 Length: 12 Location: APPROX 3 MI E OF CORRECTIONVILLE

Project No: NHSN-020-2(125)--2R-47

County: IDA

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: U.S. 20 Length: 12.40 miles

Location: 1 MI W OF CO RD L43

Project No: NHSN-020-2(127)--2R-47

County: IDA

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: U.S. 20 Length: 12.40 miles

Location: 0.3 MI W OF CO RD L43

Project No: NHSN-020-2(129)--2R-47

County: IDA

Type of Work: RCB CULVERT EXTENSION - SINGLE BOX
Route: U.S. 20 Length: 12.40
Location: 1 MI E OF CO RD L43

Length: 12.40 miles

Project No: NHSN-020-2(131)--2R-47

County: IDA

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: U.S. 20 Length: 12.40 miles

Location: 0.2 MI W OF CO RD L51

Project No: NHSN-020-2(133)--2R-47

County: IDA

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX
Route: U.S. 20 Length: 12.40 miles
Location: 1 MI E OF CO RD L43

Project No: NHSN-020-1(123)--2R-97

County: WOODBURY

Type of Work: PCC PAVEMENT - GRADE AND NEW

Route: U.S. 20 Length: 11.25 miles

Location: E OF CORRECTIONVILLE TO W JCT US 59

Project No: NHSN-020-1(138)--2R-97

County: WOODBURY Type of Work: TRAFFIC SIGNS

Route: U.S. 20 Length: 12.40 miles

Location: E OF CORRECTIONVILLE TO W JCT US 59

Project No: NHSN-020-1(155)--2R-97
County: WOODBURY

Type of Work: RCB CULVERT NEW - SINGLE BOX
Route: U.S. 20 Length: 12.40 miles
Location: APPROX 2 MI E OF CORRECTIONVILLE

Item No. Item Description

Ouantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

(101 Information only)	
SECTION NO. 0001	
BID ITEMS FOR A 6' X 5' REINFORCED CONCRETE	
3:1 FLUME AND BASIN FOR 54" RCP PIPE NHSN-020-2(123)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 38	
2404-7775000 REINFORC STEEL 6,407	
SECTION NO. 0002	
BID ITEMS FOR A 4' X 4' REINFORCED CONCRETE	
3:1 FLUME FOR 30" RCP NHSN-020-2(123)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 35	
2404-7775000 REINFORC STEEL 4,913	LB
SECTION NO. 0003	
DESIGN NO. 0315; ITEMS FOR A 10' X 8' X 263' REINFORCED	
CONCRETE BOX CULVERT NHSN-020-2(123)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 253	CY
2404-7775000 REINFORC STEEL 46,280	LB
SECTION NO. 0004	
DESIGN NO. 0118; ITEMS FOR A 10' X 8' X 263' REINFORCED	
CONCRETE BOX CULVERT NHSN-020-2(123)2R-47 2403-0100020 STRUCT CONC (RCB CULV) 175	
2403-0100020 STRUCT CONC (RCB CULV) 175	CY
2404-7775000 REINFORC STEEL 31,831	LB
SECTION NO. 0005	
BID ITEMS FOR A 8' X 5' REINFORCED CONCRETE	
4:1 FLUME AND BASIN FOR 60" RCP NHSN-020-2(123)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 57	CY
2404-7775000 REINFORC STEEL 10,601	LB
SECTION NO. 0006	
BID ITEMS FOR A 8' X 8' REINFORCED CONCRETE	
DROP INLET FOR A 60" PIPE NHSN-020-2(123)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 21	
2404-7775000 REINFORC STEEL 2,783	LB
SECTION NO. 0007	
BID ITEMS FOR A 8' X 5' REINFORCED 3:1 CONCRETE	
FLUME FOR 60" RCP NHSN-020-2(125)2R-47 2403-0100020 STRUCT CONC (RCB CULV) 52	~
2404-7775000 REINFORC STEEL 9,446	TR
SECTION NO. 0008 DESIGN NO. 0615; ITEMS FOR A 8' X 8' X 294' REINFORCED	
CONCRETE BOX CULVERT WITH FLUME NHSN-020-2(125)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 267	CV
2404-7775000 REINFORC STEEL 49,444	
SECTION NO. 0009	шБ
DESIGN NO. 0318; ITEMS FOR A 8' X 8' X 294' REINFORCED	
CONCRETE BOX CULVERT NHSN-020-2(125)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 159	CY
2404-7775000 REINFORC STEEL 29,616	
SECTION NO. 0010	
DESIGN NO. 0715; ITEMS FOR A 6' X 6' X 287' REINFORCED	
CONCRETE BOX CULVERT WITH 3:1 FLUME NHSN-020-2(125)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 213	CY
2404-7775000 REINFORC STEEL 31,039	
SECTION NO. 0011	
DESIGN NO. 0418; 6' X 6' X 287' REINFORCED CONCRETE	
BOX CULVERT NHSN-020-2(125)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 116	CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

()	
SECTION NO. 0011	
DESIGN NO. 0418; 6' X 6' X 287' REINFOR	RCED CONCRETE
·	NHSN-020-2(125)2R-47
2404-7775000 REINFORC STEEL	16,666 LB
SECTION NO. 0012	10,000 LB
BID ITEMS FOR A 5' X 4' REINFORCED CONC	CDEME 2.1
FLUME AND BASIN FOR 42" PIPE	NHSN-U2U-2 (125)2R-4/
2403-0100020 STRUCT CONC (RCB CULV)	25 CY
2404-7775000 REINFORC STEEL	3,929 LB
SECTION NO. 0013	
DESIGN NO. 0915; ITEMS FOR A 10' X 8' X	
CONCRETE BOX CULVERT WITH 3:1 FLUME N	
2403-0100020 STRUCT CONC (RCB CULV)	450 CY
2404-7775000 REINFORC STEEL	79,744 LB
SECTION NO. 0014	
BID ITEMS FOR A 5' X 4' REINFORCED CONC	
FLUME WITH 42" RCP 12403-0100020 STRUCT CONC (RCB CULV)	NHSN-020-2(127)2R-47
2403-0100020 STRUCT CONC (RCB CULV)	93 CY
2404-7775000 REINFORC STEEL	12 , 671 LB
SECTION NO. 0015	
DESIGN NO. 0518; ITEMS FOR A 10' X 8'	X 130' REINFORCED
CONCRETE BOX CULVERT EXTENSION NHSN-02	20-2(127)2R-47
2403-0100020 STRUCT CONC (RCB CULV)	256 CY
2404-7775000 REINFORC STEEL	44,525 LB
SECTION NO. 0016	
DESIGN NO. 1115; ITEMS FOR A 12' X 8' >	K 474' REINFORCED
CONCRETE BOX CULVERT	NHSN-020-2(129)2R-47
2403-0100020 STRUCT CONC (RCB CULV)	791 CY
2404-7775000 REINFORC STEEL	116,530 LB
SECTION NO. 0017	,
DESIGN NO. 0618; ITEMS FOR A 12' X 8' X	X 474' CONCRETE BOX
CHIVED EVERICION	NHSN-020-2(129)2R-47
2403-0100020 STRUCT CONC (RCB CULV)	560 CY
2404-7775000 REINFORC STEEL	82,449 LB
SECTION NO. 0018	02,113 22
DESIGN NO. 1215; ITEMS FOR A 10' X 12'	X 514' REINFORCED
CONCRETE BOX CULVERT	NHSN-020-2(129)2R-47
CONCRETE BOX CULVERT 12403-0100020 STRUCT CONC (RCB CULV)	861 CY
2404-7775000 REINFORC STEEL	126,140 LB
SECTION NO. 0019	
DESIGN NO. 0718; ITEMS FOR A 10' X 12'	X 514' REINFORCED
	NHSN-020-2(129)2R-47
2403-0100020 STRUCT CONC (RCB CULV)	613 CY
2404-7775000 REINFORC STEEL	90,439 LB
SECTION NO. 0020	30 , 133 EB
DESIGN NO. 1318; ALTERNATE 'AA' OPTION	1. CAST IN DIACE
BID THIS SECTION IF ALTERNATE 'AA' OPTI	
2403-0100020 STRUCT CONC (RCB CULV)	216 CY
2404-7775000 REINFORC STEEL	39,980 LB
SECTION NO. 0022	39,900 LB
DESIGN NO. 1315; ITEMS FOR A 10' X 10'	V 2/12! DETNEODOED
CONCRETE BOX CULVERT	NHSN-020-(131)2R-47
	/
2403-0100020 STRUCT CONC (RCB CULV) 2404-7775000 REINFORC STEEL	606 CY 96,614 LB
	90,014 LB
SECTION NO. 0023	

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

(for information only)	
DESIGN NO. 1415; ALTERNATE 'CC' OPTION 1: CAST IN PLACE	
BID THIS SECTION IF ALTERNATE 'CC' OPTION 1 IS CHOSEN (131)	
2403-0100020 STRUCT CONC (RCB CULV) 293	CY
2404-7775000 REINFORC STEEL 53,067	LB
SECTION NO. 0024	
DESIGN NO. 1415; ALTERNATE 'CC' OPTION 2: PRECAST CULVERT	
BID THIS SECTION IF ALTERNATE 'CC' OPTION 2 IS CHOSEN (131)	
· · · · · · · · · · · · · · · · · · ·	CY
2404-7775000 REINFORC STEEL 8,303	LB
SECTION NO. 0025	
DESIGN NO. 1515; ITEMS FOR A 8' X 6' X 142 REINFORCED	
CONCRETE BOX CULVERT NHSN-020-2(131)2R-47 2403-0100020 STRUCT CONC (RCB CULV) 166	
2404-7775000 REINFORC STEEL 27,752	LB
SECTION NO. 0026	
DESIGN NO. 0818; ITEMS FOR A 10' X 10' X 168' REINFORCED	
CONCRETE BOX CULVERT NHSN-020-2(131)2R-47 2403-0100020 STRUCT CONC (RCB CULV) 379	CV
2403-0100020 STRUCT CONC (RCB CULV) 379 2404-7775000 REINFORC STEEL 66,239	
SECTION NO. 0027	ПЪ
DESIGN NO. 0918; ALTERNATE 'BB' OPTION 1: CAST IN PLACE	
BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN (131)	
2403-0100020 STRUCT CONC (RCB CULV) 186	CY
2404-7775000 REINFORC STEEL 33,742	
SECTION NO. 0028	
DESIGN NO. 0918; ALTERNATE 'BB' OPTION 2: CAST IN PLACE	
BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN (131)	
2403-0100020 STRUCT CONC (RCB CULV) 66	CY
2404-7775000 REINFORC STEEL 11,821	LB
SECTION NO. 0029	
DESIGN NO. 1018; ITEMS FOR A 8' X 6' X 102' REINFORCED	
CONCRETE BOX CULVERT NHSN-020-2(131)2R-47 2403-0100020 STRUCT CONC (RCB CULV) 129	~
2404-7775000 REINFORC STEEL 21,628	TR
SECTION NO. 0030 DESIGN NO. 1118; ALTERNATE 'DD' OPTION 1: CAST IN PLACE	
BID THIS SECTION IF ALTERNATE 'DD' OPTION 1 IS CHOSEN (133)	
2403-0100020 STRUCT CONC (RCB CULV) 124	CY
2404-7775000 REINFORC STEEL 18,703	
SECTION NO. 0032	
DESIGN NO. 1218; ALTERNATE 'EE' OPTION 1: CAST IN PLACE	
BID THIS SECTION IF ALTERNATE 'EE' OPTION 1 IS CHOSEN (133)	
2403-0100020 STRUCT CONC (RCB CULV) 91	CY
2404-7775000 REINFORC STEEL 13,302	LB
SECTION NO. 0034	
ROADWAY ITEMS	
NHSN-020-1(123)2R-97	
2102-2624980 CONTRACTOR FURNISH SELECT TREATMENT 393,667	
2102-2625000 EMBANKMENT-IN-PLACE 1,300	
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 4,576,241	
2301-1003100 STD/S-F PCC PAV'T, QM-C CL 3, 10" 391,979	
2303-0043502 HMA (3M ESAL) SURF, 1/2", FRIC L-2 159 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 320	TON
·	EACH
SECTION NO. 0035	TACH
ODOTION NO. 0000	

ALTERNATE 'FF' OPTION 1: PCC PAVED SHOULDERS

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

(for information only)			
BID THIS SECTION IF ALTERNATE 'FF' OPTION 1 IS CHOS	EN (123)		
2122-5190006 PAVED SHLD, PCC, 6"	94,838 SY		
SECTION NO. 0040			
BID ITEMS FOR A 6' X 4' REINFORCED CONCRETE			
3:1 FLUME AND BASIN NHSN-020-1(15	5)2R-97		
2403-0100020 STRUCT CONC (RCB CULV)	27 CY		
2404-7775000 REINFORC STEEL	4,623 LB		
SECTION NO. 0041			
DESIGN NO. 0515; ITEMS FOR A 14' X 18'-6 DISSIPATIO	N BASIN		
REINFORCED CONCRETE PIPE NHSN-020-1(15	5)2R-97		
2403-0100020 STRUCT CONC (RCB CULV)	46 CY		
2404-7775000 REINFORC STEEL	5,677 LB		
SECTION NO. 0042			
DESIGN NO. 0615; ITEMS FOR A 12' X 12' X 332' REINF	ORCED		
CONCRETE BOX CULVERT NHSN-020-1(15	5)2R-97		
2403-0100020 STRUCT CONC (RCB CULV)	649 CY		
2404-7775000 REINFORC STEEL	107,951 LB		
SECTION NO. 0043			
DESIGN NO. 0118; ITEMS FOR A 12' X 12' X 332' REINF	ORCED		
CONCRETE BOX CULVERT - STAGE 2 140'-0	(155)		
2403-0100020 STRUCT CONC (RCB CULV)	403 CY		
2404-7775000 REINFORC STEEL	64,632 LB		

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 67-1751-043

Proposed Contract Period: Late Start Date of 05/16/16 with 100 WORK DAYS

Project(s):

Project No: STPN-175-1(43)--2J-67

County: MONONA

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: IOWA 175 Length: 5.63 miles

Location: IA 175 FROM MISSOURI RIVER TO I-29

Item No.	Item Description	Quantity,	/Unit
	NO. 0001		
2102-2625000 2303-0031500 2303-0032500 2303-0033383 2529-5070110	EMBANKMENT-IN-PLACE HMA (1M ESAL) BASE, 1/2" HMA (1M ESAL) INTERMEDIATE, 1/2" HMA (1M ESAL) SURF, 3/8", FRIC L-3 PATCH, FULL-DEPTH FINISH, BY AREA	710 79 7,952 7,894 265	TON TON TON
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT		EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 81-1103-703

Proposed Contract Period: Late Start Date of 09/19/16 with 15 WORK DAYS

Project(s):

Project No: MP-110-3(703)2--76-81

County: SAC

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 110 Length: 0.47 miles

Location: IN SCHALLER, FROM 250 FT. SOUTH OF KLING ST., NORTH TO

NORTH OF 1ST STREET.

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 85-C085-133

Proposed Contract Period: Late Start Date of 08/29/16 with 30 WORK DAYS

Project(s):

Project No: STP-S-C085(133)--5E-85

County: STORY

Type of Work: HMA RESURFACING

Route: 320TH ST Length: 3.50 miles

Location: ON E63, FROM R38 EAST APPROX. 3.5 MILES TO N. 5TH AVE. IN HU

XLEY

Project No: STP-S-C085(135)--5E-85

County: STORY

Type of Work: HMA RESURFACING
Route: E63
Location: ON E63, FROM A POINT 870 FEET NE OF THE CAMBRIDGE CITY LIMIT

S EAST 3.25 MILES TO S14

Item Description Item No. Quantity/Unit ______

SECTION NO. 0001

ROADWAY ITEMS

STP-S-C085(133)--5E-85

2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 8,883 TON

SECTION NO. 0002

ROADWAY ITEMS

STP-S-C085(135)--5E-85

2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 7,241 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 91-0653-078

Proposed Contract Period: Late Start Date of 09/19/16 with 20 WORK DAYS

Project(s):

Project No: NHSN-065-3(78)--2R-91

County: WARREN

Type of Work: HMA RESURFACING

Route: U.S. 65 Length: 1.20 miles Location: S OF 17TH AVE TO 3RD AVE IN INDIANOLA

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 06-1512-010

Proposed Contract Period: Late Start Date of 07/05/16 with 25 WORK DAYS

Project(s):

Project No: NHSN-151-2(10)--2R-06

County: BENTON

Type of Work: SLURRY SEAL

Route: U.S. 151 Length: 5.30 miles

Location: CO RD E66 TO FAIRFAX

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 16-0306-707

Proposed Contract Period: Late Start Date of 06/13/16 with 60 WORK DAYS

Project(s):

Project No: MP-030-6(707)285--76-16

County: CEDAR

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 30 Length: 24.83 miles Location: FROM NEAR ECL OF CLARENCE TO WEST OF U.S. 61.

Project No: MP-022-6(706)92--76-82

County: SCOTT

Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 22 Length: 4.80 miles
Location: FROM WEST OF Y48, NORTHESTERLY TO IOWA 461.

Project No: MP-067-6(721)23--76-82
County: SCOTT
Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 67 Length: 10.87 miles

Location: FROM F33, NORTHEASTERLY TO WASHINGTON BLVD. IN CAMANCHE.

Project No: MP-461-6(702)120--76-82

County: SCOTT

Type of Work: HMA JOINT & CRACK SEALING

Route: IOWA 461 Length: 1.80 miles Location: IN DAVENPORT, FROM 35TH ST TO 59TH ST.

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 22-0762-706

Proposed Contract Period: Late Start Date of 08/08/16 with 30 WORK DAYS

Project(s):

Project No: MP-076-2(706)5--76-22 County: CLAYTON

Type of Work: HMA PATCHING

Route: IOWA 76 Length: 0.00 miles

Location: FROM MARQUETTE TO X52.

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001 OADWAY ITEMS	
= -	PATCH, FULL-DEPTH FINISH, BY AREA	323 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	1,447 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	47 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 35-0352-721

Proposed Contract Period: Late Start Date of 06/27/16 with 30 WORK DAYS

Project(s):

Project No: MPIN-035-2(721)172--0N-35

County: FRANKLIN

Type of Work: MICROSURFACING

Route: I-35 Length: 0.00 miles

Location: 1.5 MI NORTH OF C25, NORTH TO 2.0 MI SOUTH OF C13.

Project No: MPIN-035-2(722)175--0N-35

County: FRANKLIN

Type of Work: HMA PAVED SHOULDER - FOG SEAL
Route: I-35 Length: 0.00 miles
Location: FROM 2.0 MI SOUTH OF C13, NORTH TO THE MINNESOTA STATE LINE.

(VARIOUS LOCATIONS)

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 36-0294-702

Proposed Contract Period: Late Start Date of 06/13/16 with 70 WORK DAYS

Project(s):

Project No: MPIN-029-4(700)0--0N-36

County: FREMONT Type of Work: SLURRY SEAL

Route: I-29 Length: 17.35 miles

Location: MISSOURI STATE LINE EAST TO 1.8 MI NORTH OF J26 (NBL)

Project No: MPIN-029-4(701)21--0N-36

County: FREMONT

Type of Work: SLURRY SEAL
Route: I-29 Length: 17.65 miles
Location: FROM 1.2 MI NORTH OF J24, NORTH TO NORTH OF THE REST AREA

(NBL).

Project No: MPIN-029-4(702)0--0N-36 County: FREMONT Type of Work: SLURRY SEAL

Route: I-29 Length: 25.50 miles

Location: FROM MISSOURI STATE LINE, NORTH TO MILLS COUNTY (SBL).

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 52-0016-715

Proposed Contract Period: Late Start Date of 06/06/16 with 75 WORK DAYS

Project(s):

Project No: MP-030-6(708)218--76-06

County: BENTON

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 30 Length: 13.91 miles Location: FROM IOWA 21, EAST TO WEST JCT. U.S. 218.

Project No: MP-003-6(708)278--76-28

County: DELAWARE

Type of Work: HMA JOINT & CRACK SEALING

Route: IOWA 3 Length: 6.60 miles Location: FROM THE EAST JCT IOWA 13, EAST TO IOWA 38.

Project No: MP-013-6(711)53--76-28
County: DELAWARE

Type of Work: HMA JOINT & CRACK SEALING

Route: IOWA 13 Length: 5.35 miles

Location: FROM THE SOUTH JCT. IOWA 3, NORTHWESTERLY TO INSIDE THE SCL

OF STRAWBERRY POINT.

Project No: MP-052-6(717)48--76-31

County: DUBUQUE

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 52 Length: 1.23 miles

Location: IN DUBUQUE, FROM 21ST ST TO 32ND ST.

Project No: MP-001-6(715)98--76-52

County: JOHNSON
Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 1 Length

Length: 20.98 miles

Location: FROM E ROCK ST IN SOLON, NORTHEASTERLY TO U.S. 151

Project No: MP-100-6(713)0--76-57

County: LINN

Type of Work: HMA JOINT & CRACK SEALING

Route: IOWA 100 Length: 2.13 miles

Location: IN CEDAR RAPIDS, FROM EDGEWOOD RD, EAST TO W OF COUNCIL AVE.

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 75-0753-718

Proposed Contract Period: Late Start Date of 08/22/16 with 20 WORK DAYS

Project(s):

Project No: MP-075-3(718)100--76-75

County: PLYMOUTH

Type of Work: LONGITUDINAL JOINT REPAIR

Route: U.S. 75 Length: 14.15 miles

Location: FROM THE WOODBURY CO LINE NORTH TO SOUTH OF C38 (SB).

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 97-0293-713

Proposed Contract Period: Late Start Date of 06/13/16 with 45 WORK DAYS

Project(s):

Project No: MPIN-029-3(713)127--0N-97

County: WOODBURY

Type of Work: MICROSURFACING

Route: I-29 Length: 13.84 miles

Location: MONONA CO TO SERGEANT BLUFF (SBL)

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 07-3802-508

Proposed Contract Period: Late Start Date of 08/01/16 with 20 WORK DAYS

Project(s):

Project No: MBIN-380-2(508)73--0M-07

County: BLACK HAWK

Type of Work: SLOPE PROTECTION

Route: I-380 Length: 0.00 miles Location: E SAN MARNAN DR 1.0 MI NORTH OF U.S. 20

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 61-1693-046

Proposed Contract Period: Late Start Date of 07/11/16 with 70 WORK DAYS

Project(s):

Project No: ER-169-3(46)--28-61

County: MADISON

Type of Work: SLIDE REPAIR

Route: U.S. 169 Length: 0.00 miles

Location: APPROX 3 MI N OF WINTERSET

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 63-0055-502

Proposed Contract Period: Late Start Date of 08/01/16 with 20 WORK DAYS

Project(s):

Project No: MB-005-5(502)62--77-63

County: MARION

Type of Work: SLOPE PROTECTION

Route: IOWA 5 Length: 0.00 miles

Location: SB IOWA 5/EB IOWA. 92/NB IOWA. 5 AT JCT. IOWA. 14

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-819

Proposed Contract Period: Late Start Date of 04/04/16 with 120 WORK DAYS

Project(s):

Project No: NHSN-000-S(819)--2R-00

County: STATEWIDE
Type of Work: TRAFFIC SIGNS

Route: STATEWIDE Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 4

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 29-0612-105

Proposed Contract Period: Approx Start Date of 02/22/16 with 15 WORK DAYS

Project(s):

Project No: NHSN-061-2(105)--2R-29

County: DES MOINES

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 61 Length: 0.00 miles Location: PARCEL 48A, 15295 U.S. 61, BURLINGTON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 402 Proposal ID: 48-0066-055

Proposed Contract Period: Approx Start Date of 02/22/16 with 15 WORK DAYS

Project(s):

Project No: STPN-006-6(55)--2J-48

County: IOWA

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 6 Length: 0.00 miles

Location: PARCEL 5, 500 PACIFIC ST, LADORA

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 403 Proposal ID: 57-0307-194

Proposed Contract Period: Approx Start Date of 02/22/16 with 15 WORK DAYS

Project(s):

Project No: NHSN-030-7(194)--2R-57

County: LINN

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 30 Length: 6.03 miles Location: PARCEL 44, 653 GREEN RIDGE RD, LISBON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 404 Proposal ID: 57-1001-114

Proposed Contract Period: Approx Start Date of 02/22/16 with 10 WORK DAYS

Project(s):

Project No: NHSN-100-1(114)--2R-57

County: LINN

Type of Work: SALVAGE AND REMOVAL

Route: IOWA 100 Length: 4.50 miles Location: PARCEL 46, 912 80TH ST, CEDAR RAPIDS

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 43-1834-706

Proposed Contract Period: Late Start Date of 03/21/16 with 5 WORK DAYS

Project(s):

Project No: MP-183-4(706)34--76-43

County: HARRISON

Type of Work: CLEARING AND GRUBBING

Route: IOWA 183 Length: 9.00 miles

Location: FROM IOWA 127 NORTH TO PISGAH.

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 502 Proposal ID: 82-0808-294

Proposed Contract Period: Late Start Date of 02/15/16 with 30 WORK DAYS

Project(s):

Project No: IMN-080-8(294)300--0E-82

County: SCOTT

Type of Work: LANDSCAPING

Route: I-80 Length: 0.00 miles

Location: REST AREAS WEST OF MIDDLE ROAD.

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 503 Proposal ID: 97-0296-273

Proposed Contract Period: Late Start Date of 03/21/16 with 70 WORK DAYS

Project(s):

Project No: IMN-029-6(273)143--0E-97

County: WOODBURY
Type of Work: LANDSCAPING

Route: I-29 Length: 0.00 miles

Location: IA 376 / SINGING HILLS BLVD AND IA 12 INTERCHANGES

IN SIOUX CITY

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: December 15, 2015 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 40-0201-502

Proposed Contract Period: Late Start Date of 07/25/16 with 80 WORK DAYS

Project(s):

Project No: MB-020-1(502)142--77-40

County: HAMILTON

Type of Work: BRIDGE PAINTING

Route: U.S. 20 Length: 0.00 miles

Location: OVER BOONE RIVER, 1.2 MILES E. OF E. JCT. IOWA 17 (EBL/WBL)

Project No: MB-330-1(501)11--77-64

County: MARSHALL

Type of Work: BRIDGE PAINTING
Route: IOWA 330 Length: 0.00 miles
Location: OVER NORTH SKUNK RIVER, 1 MILE NORTH OF S52.

Item Description