

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: December 15, 2015
Date of Addendum: December 9, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
601	40-0201-502	Bridge Painting	Hamilton	MB-020-1(502)142--77-40 MB-330-1(501)11--77-64	15DEC601.A01

Make the following changes to the PROPOSAL PLAN ATTACHMENTS:

Replace Page 2 of 4 with the attached Page 2 of 4.

ESTIMATE REFERENCE INFORMATION	
Data listed below is for informational purposes only and shall not constitute a basis for any extra work orders.	
ITEM NO.	DESCRIPTION
	<p>All steel to be painted shall be blasted to SP-10. The paint system shall be the Epoxy system. This includes a Zinc-rich Epoxy, an Aluminum Epoxy Mastic intermediate coat, and an Aliphatic Polyurethane topcoat.</p> <p>BRIDGE # 4041.6R020 This bridge is to be painted. . Painting includes the bottom of the top flange, the exterior of the exterior girder, the exterior top of the bottom flange, the exterior of the bottom flange, and the bottom of the bottom flange of the Exterior Girders. Also, paint all steel within 10' of the abutments.</p> <p>The total area of structural steel in the zones designated to be painted is estimated to be 8,050 sq. ft. This estimate is given only for the contractor's information. There will be no additional payment if the actual areas in the zones vary from the estimated amounts shown. The contractor may obtain a copy of the original construction plans for the bridge from the Office of Contracts, Iowa Department of Transportation, 800 Lincoln Way, Ames, IA 50010 (Phone: 515-239-1414).</p> <p>BRIDGE # 4041.6L020 This bridge is to be painted. . Painting includes the bottom of the top flange, the exterior of the exterior girder, the exterior top of the bottom flange, the exterior of the bottom flange, and the bottom of the bottom flange of the Exterior Girders. Also, paint all steel within 10' of the abutments.</p> <p>The total area of structural steel in the zones designated to be painted is estimated to be 8,050 sq. ft. This estimate is given only for the contractor's information. There will be no additional payment if the actual areas in the zones vary from the estimated amounts shown. The contractor may obtain a copy of the original construction plans for the bridge from the Office of Contracts, Iowa Department of Transportation, 800 Lincoln Way, Ames, IA 50010 (Phone: 515-239-1414).</p> <p>NOTE: Abrasives shall be steel shot and/or grit, aluminum oxide, or garnet abrasives. Do not use sand or coal slag.</p>