

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: December 15, 2015
Date of Addendum: December 9, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
108	44-C044-077	PCC PAVEMENT - GRADE & REPLACE	HENRY	STP-S-C044(77)--5E-44	15DEC108.A03

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the ESTIMATE REFERENCE INFORMATION:

Add note to Item No. 34 2510-67550501 REMOVAL AND CRUSHING OF PAVEMENT:

1965 original 6 inch pcc was placed with #4 REBAR at 48 inch centers at centerline
1987 overlay #4 REBAR was placed at 36 inch centers at centerline
Additionally approximately 10 percent of overlay was reinforced with a combination of full width transverse bars at two foot spacing or single lane transverse bars. All reinforcing was #4 bar. No documentation of locations known.

If the above changes are not made, they will be made as shown here.